



BLM LIBRARY



88071566

Department of  
Agriculture

Soil  
Conservation  
Service

In cooperation with United  
States Department of the  
Interior, Bureau of Land  
Management; University  
of Idaho, College of  
Agriculture; and Idaho  
Soil Conservation  
Commission

# Soil Survey of Blaine County Area, Idaho

LIBRARY

AUG 22 1991

Bureau of Reclamation  
Denver Office

BLM Library  
Denver Federal Center  
Bldg. 50, OC-521  
P.O. Box 25047  
Denver, CO 80225



DEPOSITORY

A 57.38 : B 57/4

0102-B-12



## SEP 4 1991

Bureau of Reclamation  
Denver Office

PLM Library  
Denver Federal Center  
Bldg. 50, OC-521  
P.O. Box 25047  
Denver, CO 80225

DATE DUE

GAYLORD

PRINTED IN U.S.A.



# How To Use This Soil Survey

## General Soil Map



The general soil map, which is the color map preceding the detailed soil maps, shows the survey area divided into groups of associated soils called general soil map units. This map is useful in planning the use and management of large areas.

To find information about your area of interest, locate that area on the map, identify the name of the map unit in the area on the color-coded map legend, then refer to the section **General Soil Map Units** for a general description of the soils in your area.



## Detailed Soil Maps

The detailed soil maps follow the general soil map. These maps can be useful in planning the use and management of small areas.

To find information about your area of interest, locate that area on the **Index to Map Sheets**, which precedes the soil maps. Note the number of the map sheet, and turn to that sheet.



Locate your area of interest on the map sheet. Note the map unit symbols that are in that area. Turn to the **Index to Map Units** (see Contents), which lists the map units by symbol and name and shows the page where each map unit is described.



NOTE: Map unit symbols in a soil survey may consist only of numbers or letters, or they may be a combination of numbers and letters.

The **Summary of Tables** shows which table has data on a specific land use for each detailed soil map unit. See **Contents** for sections of this publication that may address your specific needs.



---

This soil survey is a publication of the National Cooperative Soil Survey, a joint effort of the United States Department of Agriculture and other federal agencies, state agencies including the Agricultural Experiment Stations, and local agencies. The Soil Conservation Service has leadership for the federal part of the National Cooperative Soil Survey.

Major fieldwork for this soil survey was completed in 1984. Soil names and descriptions were approved in 1985. Unless otherwise indicated, statements in this publication refer to conditions in the survey area in 1985. This survey was made cooperatively by the Soil Conservation Service; the Bureau of Land Management; the University of Idaho, College of Agriculture; and the Idaho Soil Conservation Commission. It is part of the technical assistance furnished to the Blaine Soil Conservation District.

Soil maps in this survey may be copied without permission. Enlargement of these maps, however, could cause misunderstanding of the detail of mapping. If enlarged, maps do not show the small areas of contrasting soils that could have been shown at a larger scale.

All programs and services of the Soil Conservation Service are offered on a nondiscriminatory basis, without regard to race, color, national origin, religion, sex, age, marital status, or handicap.

**Cover: Picabo, Hapur, and Bickett soils on flood plains and stream terraces along Silver Creek. Vitale, Milligan, Elksel, and Starhope soils are on foothills and mountainsides in the background.**



# Contents

---

|  |      |                          |     |
|--|------|--------------------------|-----|
| <b>Index to map units</b> .....              | v    | Earcree series .....     | 135 |
| <b>Summary of tables</b> .....               | viii | Elkcreek series .....    | 135 |
| <b>Foreword</b> .....                        | xi   | Elksel series .....      | 136 |
| General nature of the survey area .....      | 1    | Friedman series .....    | 137 |
| How this survey was made .....               | 3    | Furshur series .....     | 138 |
| <b>General soil map units</b> .....          | 5    | Gaib series .....        | 139 |
| Map unit descriptions .....                  | 6    | Gimlett series .....     | 140 |
| <b>Detailed soil map units</b> .....         | 13   | Gooding series .....     | 141 |
| Map unit descriptions .....                  | 14   | Goodington series .....  | 142 |
| <b>Prime farmland</b> .....                  | 101  | Hamrub series .....      | 143 |
| <b>Use and management of the soils</b> ..... | 103  | Hapur series .....       | 144 |
| Crops and pasture .....                      | 103  | Hutton series .....      | 145 |
| Rangeland .....                              | 105  | Hutton Variant .....     | 146 |
| Windbreaks and environmental plantings ..... | 106  | Isknat series .....      | 147 |
| Recreation .....                             | 106  | Justesen series .....    | 149 |
| Wildlife habitat .....                       | 107  | Ketchum series .....     | 150 |
| Engineering .....                            | 108  | Laurentzen series .....  | 151 |
| <b>Soil properties</b> .....                 | 113  | Lavacreek series .....   | 152 |
| Engineering index properties .....           | 113  | Little Wood series ..... | 153 |
| Physical and chemical properties .....       | 114  | Lockman series .....     | 154 |
| Soil and water features .....                | 115  | Manard series .....      | 155 |
| <b>Classification of the soils</b> .....     | 119  | Marshdale series .....   | 156 |
| Soil series and their morphology .....       | 120  | McBiggam series .....    | 156 |
| Adamson series .....                         | 120  | McCarey series .....     | 157 |
| Adios series .....                           | 121  | Milligan series .....    | 158 |
| Balaam series .....                          | 122  | Molyneux series .....    | 159 |
| Bancroft series .....                        | 123  | Moonstone series .....   | 160 |
| Bauscher series .....                        | 124  | Muldoon series .....     | 160 |
| Bickett series .....                         | 125  | Mulshoe series .....     | 161 |
| Blackspar series .....                       | 126  | Pagari series .....      | 162 |
| Blackspot series .....                       | 126  | Pedleford series .....   | 163 |
| Bostrum series .....                         | 127  | Peevywell series .....   | 164 |
| Bringmee series .....                        | 128  | Picabo series .....      | 165 |
| Bruneel series .....                         | 129  | Polecreek series .....   | 167 |
| Carey Lake series .....                      | 130  | Povey series .....       | 168 |
| Cinderhurst series .....                     | 131  | Prudy series .....       | 168 |
| Cox series .....                             | 132  | Rehfield series .....    | 170 |
| Deerhorn series .....                        | 132  | Rockybar series .....    | 170 |
| Dollarhide series .....                      | 133  | Simonton series .....    | 171 |
| Drage series .....                           | 134  | Smelter series .....     | 172 |



---

|                      |     |                                     |     |
|----------------------|-----|-------------------------------------|-----|
| Starhope series..... | 173 | Yuttrue series.....                 | 178 |
| Trevino series.....  | 174 | <b>Formation of the soils</b> ..... | 181 |
| Vitale series.....   | 175 | <b>References</b> .....             | 189 |
| Wildors series.....  | 176 | <b>Glossary</b> .....               | 191 |
| Winridge series..... | 177 | <b>Tables</b> .....                 | 201 |
| Winu series.....     | 177 |                                     |     |

Issued May 1991



# Index to Map Units

---

|  |    |  |    |
|--|----|--|----|
| 1—Adamson loam, 0 to 2 percent slopes.....                                 | 14 | 27—Dollarhide-Rock outcrop complex, 60 to 75<br>percent slopes .....       | 35 |
| 2—Adios-Gooding-Bostrum complex, 4 to 20<br>percent slopes .....           | 14 | 28—Drage gravelly loam, 4 to 8 percent slopes .....                        | 35 |
| 3—Adios association, 8 to 25 percent slopes .....                          | 15 | 29—Drage gravelly loam, 8 to 12 percent slopes ....                        | 36 |
| 4—Balaam gravelly sandy loam, 0 to 2 percent<br>slopes.....                | 16 | 30—Drage gravelly loam, cool, 2 to 15 percent<br>slopes.....               | 37 |
| 5—Balaam very gravelly sandy loam, 2 to 4<br>percent slopes .....          | 17 | 31—Drage very gravelly loam, cool, 0 to 3<br>percent slopes .....          | 37 |
| 6—Balaam-Adamson complex, 0 to 2 percent<br>slopes.....                    | 18 | 32—Earcree-Lockman complex, 30 to 60 percent<br>slopes.....                | 38 |
| 7—Balaam-Adamson complex, cool, 0 to 2<br>percent slopes .....             | 19 | 33—Earcree-Moonstone association, 8 to 30<br>percent slopes .....          | 39 |
| 8—Balaam-Adamson-Riverwash complex, 0 to 2<br>percent slopes .....         | 20 | 34—Earcree-Moonstone association, 30 to 60<br>percent slopes .....         | 40 |
| 9—Bancroft silt loam, 1 to 4 percent slopes.....                           | 21 | 35—Elkcreek-Gaib complex, 30 to 60 percent<br>slopes.....                  | 40 |
| 10—Bancroft silt loam, 4 to 8 percent slopes .....                         | 22 | 36—Elkcreek-Polecreek complex, 4 to 30 percent<br>slopes.....              | 41 |
| 11—Bickett mucky peat, 0 to 2 percent slopes .....                         | 23 | 37—Elksel-Friedman-Starhope complex, 30 to 60<br>percent slopes .....      | 42 |
| 12—Blackspar-Rock outcrop complex, 45 to 75<br>percent slopes .....        | 23 | 38—Elksel-Peevywell-Furshur complex, 30 to 60<br>percent slopes .....      | 43 |
| 13—Blackspot-Prudy association, 30 to 60<br>percent slopes .....           | 24 | 39—Elksel-Starhope-Rock outcrop complex,<br>30 to 60 percent slopes.....   | 44 |
| 14—Bostrum-Yuttrue-Hamrub complex, 2 to 12<br>percent slopes .....         | 24 | 40—Friedman-Elksel-Winridge complex, 30 to 60<br>percent slopes .....      | 45 |
| 15—Bringmee loam, 0 to 2 percent slopes.....                               | 26 | 41—Gaib-Rock outcrop complex, 30 to 60<br>percent slopes .....             | 46 |
| 16—Bringmee loam, 2 to 4 percent slopes.....                               | 26 | 42—Gimlett very gravelly sandy loam, 0 to 2<br>percent slopes .....        | 47 |
| 17—Bringmee loam, 4 to 8 percent slopes.....                               | 27 | 43—Gooding-Gooding, eroded-Hamrub complex,<br>2 to 12 percent slopes ..... | 48 |
| 18—Bringmee-Hutton complex, 1 to 4 percent<br>slopes.....                  | 27 | 44—Goodington silt loam, 2 to 4 percent slopes.....                        | 49 |
| 19—Bringmee-Little Wood complex, 1 to 4<br>percent slopes .....            | 28 | 45—Goodington-Manard complex, 2 to 8 percent<br>slopes.....                | 50 |
| 20—Bruneel loam, 0 to 2 percent slopes .....                               | 29 | 46—Hapur silt loam, 0 to 2 percent slopes.....                             | 51 |
| 21—Carey Lake loam, 0 to 2 percent slopes.....                             | 30 | 47—Hapur-Bickett complex, 0 to 2 percent slopes...                         | 52 |
| 22—Carey Lake loam, 2 to 4 percent slopes.....                             | 30 | 48—Hapur-Picabo silt loams, 0 to 2 percent<br>slopes.....                  | 53 |
| 23—Cox-Rehfield-Rock outcrop complex, 2 to 15<br>percent slopes .....      | 31 | 49—Hutton clay loam, 0 to 2 percent slopes .....                           | 54 |
| 24—Deerhorn-Rehfield-Rock outcrop complex,<br>2 to 15 percent slopes ..... | 32 |  |    |
| 25—Deerhorn-Wildors complex, 2 to 8 percent<br>slopes.....                 | 32 |  |    |
| 26—Deerhorn-Wildors-Trevino complex, 2 to 15<br>percent slopes .....       | 33 |  |    |

|  |    |   |    |
|--|----|---|----|
| 50—Hutton Variant clay loam, 0 to 2 percent slopes.....                              | 55 | 75—McCarey-Justesen-Rock outcrop complex, 2 to 15 percent slopes..... | 73 |
| 51—Isknat gravelly clay loam, 0 to 2 percent slopes.....                             | 55 | 76—McCarey-Molyneux loams, 2 to 8 percent slopes.....                 | 74 |
| 52—Justesen loam, 2 to 4 percent slopes.....   | 56 | 77—McCarey-Pedleford complex, 2 to 30 percent slopes.....             | 75 |
| 53—Justesen loam, 4 to 8 percent slopes.....   | 57 | 78—Molyneux loam, 2 to 4 percent slopes.....                          | 76 |
| 54—Justesen loam, 8 to 12 percent slopes.....  | 57 | 79—Molyneux loam, 4 to 8 percent slopes.....                          | 76 |
| 55—Justesen loam, 12 to 30 percent slopes.....                                       | 58 | 80—Molyneux loam, cool, 2 to 15 percent slopes...                     | 77 |
| 56—Ketchum-Dollarhide complex, 30 to 60 percent slopes.....                          | 58 | 81—Moonstone-Bauscher complex, 8 to 30 percent slopes.....            | 78 |
| 57—Ketchum-Povey complex, 30 to 60 percent slopes.....                               | 59 | 82—Moonstone-Earcree association, 30 to 60 percent slopes.....        | 79 |
| 58—Laurentzen-Mulshoe complex, 4 to 30 percent slopes.....                           | 60 | 83—Muldoon-Peevywell loams, 2 to 15 percent slopes.....               | 79 |
| 59—Lava flows.....   | 61 | 84—Mulshoe-Gaib-Rock outcrop complex, 4 to 30 percent slopes.....     | 80 |
| 60—Lava flows-Cinderhurst complex, 2 to 15 percent slopes.....                       | 61 | 85—Mulshoe-Gaib-Winu complex, 30 to 60 percent slopes.....            | 81 |
| 61—Lavacreek-Dollarhide very gravelly silt loams, 30 to 60 percent slopes.....       | 62 | 86—Pagari-Rehfield complex, 2 to 15 percent slopes.....               | 82 |
| 62—Lavacreek-Dollarhide very gravelly silt loams, cold, 15 to 60 percent slopes..... | 63 | 87—Peevywell-Simonton loams, 2 to 8 percent slopes.....               | 83 |
| 63—Lavacreek-Vitale association, 30 to 60 percent slopes.....                        | 64 | 88—Peevywell-Simonton complex, 8 to 30 percent slopes.....            | 84 |
| 64—Little Wood gravelly loam, 0 to 2 percent slopes.....                             | 65 | 89—Picabo silt loam, 0 to 2 percent slopes.....                       | 85 |
| 65—Little Wood gravelly loam, 2 to 4 percent slopes.....                             | 66 | 90—Picabo gravelly loam, 0 to 2 percent slopes...                     | 85 |
| 66—Little Wood very gravelly loam, 0 to 2 percent slopes.....                        | 66 | 91—Pits, gravel.....  | 86 |
| 67—Little Wood very gravelly loam, 2 to 4 percent slopes.....                        | 67 | 92—Povey-Dollarhide complex, 30 to 60 percent slopes.....             | 86 |
| 68—Little Wood very gravelly loam, cool, 1 to 4 percent slopes.....                  | 68 | 93—Povey-Rock outcrop complex, 30 to 60 percent slopes.....           | 87 |
| 69—Little Wood-Balaam complex, 0 to 2 percent slopes.....                            | 69 | 94—Povey association, cold, 15 to 60 percent slopes.....              | 88 |
| 70—Manard silt loam, 1 to 4 percent slopes.....                                      | 70 | 95—Povey-Vitale association, 30 to 60 percent slopes.....             | 89 |
| 71—Marshdale loam, 0 to 2 percent slopes.....  | 71 | 96—Rehfield-Gooding complex, 2 to 15 percent slopes.....              | 89 |
| 72—Marshdale-Bruneel loams, 0 to 2 percent slopes.....                               | 71 | 97—Riverwash.....   | 90 |
| 73—McBiggam silt loam, 2 to 8 percent slopes.....                                    | 72 | 98—Rock outcrop-Adios complex, 25 to 60 percent slopes.....           | 90 |
| 74—McCarey-Justesen loams, 2 to 8 percent slopes.....                                | 73 |   |    |



---

|   |    |  |    |
|---|----|--|----|
| 99—Rockybar extremely cobbly loam, 2 to 30 percent slopes ..... | 91 | 106—Starhope-Peevywell-Smelter loams, 4 to 30 percent slopes ..... | 95 |
| 100—Rubbleland.....   | 92 | 107—Vitale-Blackspar complex, 30 to 60 percent slopes.....         | 96 |
| 101—Rubbleland-Milligan complex, 60 to 75 percent slopes .....  | 92 | 108—Vitale-Milligan complex, 30 to 60 percent slopes.....          | 97 |
| 102—Simonton loam, 2 to 4 percent slopes.....                   | 92 | 109—Vitale-Povey association, 30 to 60 percent slopes.....         | 98 |
| 103—Simonton loam, 4 to 8 percent slopes.....                   | 93 | 110—Winu-Rock outcrop complex, 30 to 60 percent slopes .....       | 99 |
| 104—Simonton-Bauscher complex, 4 to 15 percent slopes .....     | 94 | 111—Winu-Gaib association, 30 to 60 percent slopes.....            | 99 |
| 105—Starhope-Furshur complex, 4 to 15 percent slopes.....       | 94 |  |    |

# Summary of Tables

---

|   |     |
|---|-----|
| Temperature and precipitation (table 1) .....   | 202 |
| Freeze dates in spring and fall (table 2).....  | 203 |
| <i>Probability. Temperature.</i>  |     |
| Growing season (table 3).....   | 204 |
| <i>Probability. Daily minimum temperature during growing season.</i>  |     |
| Acreage and proportionate extent of the soils (table 4) .....   | 205 |
| <i>Acres. Percent.</i>  |     |
| Yields per acre of crops and pasture (table 5) .....  | 207 |
| <i>Wheat. Barley. Oats. Alfalfa hay. Grass hay. Pasture.</i>  |     |
| Rangeland productivity and characteristic plant communities (table 6).....  | 210 |
| <i>Range site. Total production. Characteristic vegetation. Composition.</i>  |     |
| Windbreaks and environmental plantings (table 7) .....  | 232 |
| Recreational development (table 8).....   | 236 |
| <i>Camp areas. Picnic areas. Playgrounds. Paths and trails. Golf fairways.</i>  |     |
| Building site development (table 9) .....   | 250 |
| <i>Shallow excavations. Dwellings without basements. Dwellings with basements. Small commercial buildings. Local roads and streets. Lawns and landscaping.</i>              |     |
| Sanitary facilities (table 10) .....  | 264 |
| <i>Septic tank absorption fields. Sewage lagoon areas. Trench sanitary landfill. Area sanitary landfill. Daily cover for landfill.</i>                                      |     |
| Construction materials (table 11) .....   | 279 |
| <i>Roadfill. Sand. Gravel. Topsoil.</i>   |     |
| Water management (table 12).....  | 292 |
| <i>Limitations for—Pond reservoir areas; Embankments, dikes, and levees; Aquifer-fed excavated ponds. Features affecting—Drainage, Irrigation, Terraces and diversions.</i> |     |



---

|   |     |
|---|-----|
| Engineering index properties (table 13) .....                       | 305 |
| <i>Depth. USDA texture. Classification—Unified, AASHTO.</i>         |     |
| <i>Fragments greater than 3 inches. Percentage passing</i>          |     |
| <i>sieve number—4, 10, 40, 200. Liquid limit. Plasticity index.</i> |     |
| Physical and chemical properties of the soils (table 14) .....      | 337 |
| <i>Depth. Clay. Permeability. Available water capacity. Soil</i>    |     |
| <i>reaction. Salinity. Shrink-swell potential. Erosion factors.</i> |     |
| <i>Wind erodibility group. Organic matter.</i>                      |     |
| Water features (table 15) .....                                     | 352 |
| <i>Hydrologic group. Flooding. High water table.</i>                |     |
| Soil features (table 16) .....                                      | 360 |
| <i>Bedrock. Cemented pan. Subsidence. Potential frost</i>           |     |
| <i>action. Risk of corrosion.</i>                                   |     |
| Classification of the soils (table 17) .....                        | 367 |
| <i>Family or higher taxonomic class.</i>                            |     |





# Foreword


---

This soil survey contains information that can be used in land-planning programs in the survey area. It contains predictions of soil behavior for selected land uses. The survey also highlights limitations and hazards inherent in the soil, improvements needed to overcome the limitations, and the impact of selected land uses on the environment.

This soil survey is designed for many different users. Farmers, ranchers, foresters, and agronomists can use it to evaluate the potential of the soil and the management needed for maximum food and fiber production. Planners, community officials, engineers, developers, builders, and home buyers can use the survey to plan land use, select sites for construction, and identify special practices needed to ensure proper performance. Conservationists, teachers, students, and specialists in recreation, wildlife management, waste disposal, and pollution control can use the survey to help them understand, protect, and enhance the environment.

Great differences in soil properties can occur within short distances. Some soils are seasonally wet or subject to flooding. Some are shallow to bedrock. Some are too unstable to be used as a foundation for buildings or roads. Clayey or wet soils are poorly suited to use as septic tank absorption fields. A high water table makes a soil poorly suited to basements or underground installations.

These and many other soil properties that affect land use are described in this soil survey. Broad areas of soils are shown on the general soil map. The location of each soil is shown on the detailed soil maps. Each soil in the survey area is described. Information on specific uses is given for each soil. Help in using this publication and additional information are available at the local office of the Soil Conservation Service or the Cooperative Extension Service.

A handwritten signature in black ink, reading "Paul H. Calverley". The signature is fluid and cursive, with a large initial "P" and "C".

Paul H. Calverley  
State Conservationist  
Soil Conservation Service



Location of the Blaine County area in Idaho.



5  
591.1  
458  
F2  
B55  
1991

1

# Soil Survey of Blaine County Area, Idaho

---

By Mark E. Johnson, Soil Conservation Service

Fieldwork by Mark E. Johnson, William D. Harrison, Peter F. Biggam, Jr.,  
Glenn A. Hoffman, and Karen R. Langersmith, Soil Conservation Service

United States Department of Agriculture, Soil Conservation Service,  
in cooperation with

United States Department of the Interior, Bureau of Land Management; University of Idaho,  
College of Agriculture; and Idaho Soil Conservation Commission

BLAINE COUNTY AREA is in the south-central part of Idaho. It includes all of Blaine County, except for an area in the southern part adjacent to Lincoln and Minidoka Counties extending to the Snake River and an area in the extreme northern part, in the Salmon River drainageway. Also excluded is land administered by the Forest Service. The survey area includes private land and land that is administered by the state and by the Bureau of Land Management. The total area is about 807,529 acres, or 1,262 square miles. The population of Hailey, the county seat of Blaine County, was 2,109 in 1980.

The northern part of the survey area consists of steep, rugged mountains. The Big Wood River, the Little Wood River, and Fish Creek flow in a southerly direction from the mountains. Silver Creek originates south of Bellevue. The southern and eastern parts of the survey area consist of lava flows, which extend from the Craters of the Moon area to the southern boundary of the survey area.

The lowest point in the survey area, about 4,600 feet in elevation, is the area where the Big Wood River crosses the boundary line between Blaine and Lincoln Counties. Hailey, located in the center of Wood River Valley, is at an elevation of about 5,329 feet, and Sun Valley, in the northern part of Wood River Valley, is at about 5,960 feet. Blizzard Mountain, the highest point in the survey area, has an elevation of 9,250 feet. It is in

the mountainous northeastern area.

Two older unpublished surveys, "Wood River Soil Survey," completed in 1974 (20), and "Soil Survey of Blaine Soil Conservation District," completed in 1961 (19), cover most of the present survey. The present survey, however, updates the earlier surveys and provides additional information.

The descriptions, names, and delineations of the soils in this survey area do not fully agree with those of the soils in adjacent survey areas. Differences are the result of a better knowledge of soils, modifications in series concepts, or variations in the intensity of mapping or the extent of the soils in the survey areas.

## General Nature of the Survey Area

This section gives general information about the survey area. It describes history and development, natural resources, farming, and climate.

## History and Development

In 1824, Alexander Ross led an expedition into the Blaine County region. The first permanent settlers in the Wood River Valley arrived in 1879. They mined galena, which is a combination of silver, zinc, and lead. Some gold was also mined.

Alturas County, which was later renamed Logan

County and then Alta County, was established on February 4, 1864. Part of this county became Blaine County on March 5, 1895, and Hailey became the county seat. Other communities in the county are Ketchum, Sun Valley, Carey, Picabo, Bellevue, and Gannett.

Mining influenced the establishment of mail and freight routes in Blaine County. In 1883, the first railroad line in the area was established. The mining boom was over by the early 1900's, and the amount of mining done became dependent on fluctuating mineral prices.

In 1935, the Union Pacific Railroad hired an Austrian alpine ski expert to locate a site for a ski resort that would attract tourists to travel to the west on the company's streamlined trains. In January 1936, a 3,400-acre ranch just 1 mile east of Ketchum became the Sun Valley ski area. In 1939, the Union Pacific Railroad leased Bald Mountain from the Forest Service, and the first chair lift was installed on the mountain the following summer.

The first farming community in the area was established along Spring Creek near Carey in 1879. The population of the early farming communities fluctuated with the boom and decline of the mining industry. Also contributing to the instability of the agricultural communities was the cool climate, which limited the number of suitable crops.

## Natural Resources

Soil and water are the most important natural resources in the survey area. Livestock, crops, and timber are marketable products that are dependent on these resources. Only a small acreage of timber, which is on federally administered land, is harvested and marketed in the area.

The survey area has abundant water resources. The deep snowpack and large amount of precipitation received in the high mountains are the main sources of water for the Big Wood River, the Little Wood River, and Fish Creek. Silver Creek, a major tributary of the Little Wood River, gets its water from springs and from the high water table that is a result of irrigation in the higher areas.

Water for irrigation comes from many sources, including the Big Wood River, the Little Wood River, Fish Creek, Silver Creek, and wells. The distribution of irrigation water from the Big Wood River and Silver Creek to individual farms is handled by irrigation districts and cooperative ditch groups. The Little Wood River drainageway in Carey Valley provides water for a 312-square-mile area. Water from the Little Wood

Reservoir, which was enlarged in 1955 to its present capacity of 30,000 acre-feet, irrigates about 12,000 acres. Fish Creek Reservoir, which was built in 1917, has a capacity of 14,000 acre-feet, and water from it irrigates about 6,000 acres. Ground-water wells are used to irrigate most of the rest of the agricultural acreage in the survey area. Water from artesian wells is used to irrigate crops near the community of Picabo.

Most of the mining done in the area is for sand and gravel, which are plentiful along the Big Wood and Little Wood Rivers. A few metallic ore mines are in operation, but work is restricted to exploration.

## Farming

In 1980, about 79,000 acres of cultivated land was in the survey area, most of which was used for alfalfa, barley, wheat, oats, or pasture. Irrigation is needed for maximum production of all crops; however, some dryland wheat and barley is grown in the western part of the survey area. Areas of wet soils scattered throughout the area support wet meadow hay and pasture. Malting barley is a specialty crop grown in the survey area.

Grazing by sheep and cattle is important to the economy of the survey area. Cow-calf operations are dominant.

There are about 220 farms in the survey area. The average farm size in 1978 was 1,415 acres, of which about 270 acres was used as cropland.

The Blaine Soil Conservation District was established on January 29, 1954. Originally the district included only the Gannett, Picabo, Carey, Fish Creek, and Little Wood River areas, but on May 22, 1958, it was expanded to include the rest of Blaine County.

## Climate

Prepared by the National Climatic Data Center, Asheville, North Carolina.

Table 1 gives data on temperature and precipitation for the survey area as recorded at Hailey and Picabo in the period 1951 to 1981. Table 2 shows probable dates of the first freeze in fall and the last freeze in spring. Table 3 provides data on length of the growing season.

In winter, the average temperature is 22 degrees F at Hailey and 21 degrees at Picabo and the average daily minimum temperature is 11 degrees at Hailey and 10 degrees at Picabo. The lowest temperature on record, which occurred at Picabo on January 24, 1962, is -33 degrees. In summer, the average temperature is 64 degrees at both Hailey and Picabo and the average



daily maximum temperature is about 81 degrees. The highest recorded temperature, which occurred at Picabo on July 21, 1960, is 101 degrees.

Growing degree days are shown in table 1. They are equivalent to "heat units." During the month, growing degree days accumulate by the amount that the average temperature each day exceeds a base temperature (40 degrees F). The normal monthly accumulation is used to schedule single or successive plantings of a crop between the last freeze in spring and the first freeze in fall.

The total annual precipitation is about 17 inches at Hailey and 13 inches at Picabo. Of this, about 40 percent usually falls in April through September. The heaviest 1-day rainfall during the period of record was 2.68 inches at Hailey on December 22, 1964. Thunderstorms occur on about 15 days each year.

The average seasonal snowfall is 86 inches at Hailey and 47 inches at Picabo. The greatest snow depth at any one time during the period of record was 54 inches at Hailey. On an average, at least 1 inch of snow is on the ground 86 days of the year at Hailey and 64 days at Picabo. The number of such days varies greatly from year to year.

The average relative humidity in midafternoon is about 50 percent. Humidity is higher at night, and the average at dawn is about 70 percent. The sun shines 80 percent of the time possible in summer and 40 percent in winter. The prevailing wind is from the southeast. Average windspeed is highest, 11 miles per hour, in spring.

## How This Survey Was Made

This survey was made to provide information about the soils and miscellaneous areas in the survey area. The information includes a description of the soils and miscellaneous areas and their location and a discussion of their suitability, limitations, and management for specified uses. Soil scientists observed the steepness, length, and shape of the slopes; the general pattern of drainage; the kinds of crops and native plants growing on the soils; and the kinds of bedrock. They dug many holes to study the soil profile, which is the sequence of natural layers, or horizons, in a soil. The profile extends from the surface down into the unconsolidated material in which the soil formed. The unconsolidated material is devoid of roots and other living organisms and has not been changed by other biological activity.

The soils and miscellaneous areas in the survey area occur in an orderly pattern that is related to the geology, landforms, relief, climate, and natural

vegetation of the area. Each kind of soil and miscellaneous area is associated with a particular kind of landscape or with a segment of the landscape. By observing the soils and miscellaneous areas in the survey area and relating their position to specific segments of the landscape, a soil scientist develops a concept, or model, of how the soils and miscellaneous areas were formed. Thus, during mapping, this model enables the soil scientist to predict with a considerable degree of accuracy the kind of soil or miscellaneous area at a specific location on the landscape.

Commonly, individual soils on the landscape merge into one another as their characteristics gradually change. To construct an accurate soil map, however, soil scientists must determine the boundaries between the soils. They can observe only a limited number of soil profiles. Nevertheless, these observations, supplemented by an understanding of the soil-vegetation-landscape relationship, are sufficient to verify predictions of the kinds of soil in an area and to determine the boundaries.

Soil scientists recorded the characteristics of the soil profiles that they studied. They noted color, texture, size and shape of soil aggregates, kind and amount of rock fragments, distribution of plant roots, reaction, and other features that enable them to identify soils. After describing the soils in the survey area and determining their properties, the soil scientists assigned the soils to taxonomic classes (units). Taxonomic classes are concepts. Each taxonomic class has a set of soil characteristics with precisely defined limits. The classes are used as a basis for comparison to classify soils systematically. The system of taxonomic classification used in the United States is based mainly on the kind and character of soil properties and the arrangement of horizons within the profile. After the soil scientists classified and named the soils in the survey area, they compared the individual soils with similar soils in the same taxonomic class in other areas so that they could confirm data and assemble additional data based on experience and research.

While a soil survey is in progress, samples of some of the soils in the area generally are collected for laboratory analyses and for engineering tests. Soil scientists interpret the data from these analyses and tests as well as the field-observed characteristics and the soil properties to determine the expected behavior of the soils under different uses. Interpretations for all of the soils are field tested through observation of the soils in different uses and under different levels of management. Some interpretations are modified to fit local conditions, and some new interpretations are



developed to meet local needs. Data are assembled from other sources, such as research information, production records, and field experience of specialists.

Predictions about soil behavior are based not only on soil properties but also on such variables as climate and biological activity. Soil conditions are predictable over long periods of time, but they are not predictable from year to year. For example, soil scientists can predict with a fairly high degree of accuracy that a given soil will have a high water table within certain depths in most years, but they cannot assure that a high water table will always be at a specific level in the soil on a specific date.

Special remote sensing techniques were used in this survey to aid in determining the composition and location of map units. Satellite imagery and large-scale aerial photographs were used to help soil scientists identify and quantify soils in remote and inaccessible areas.

Computer-generated maps were developed from satellite multispectral scanner imagery of the southeastern part of the survey area. The special

symbols, or "pixels," on the maps portray various soil-vegetation-landscape characteristics important in the survey area. These maps combined with the field maps were used to help identify map units in remote areas (3).

Aerial observations were also conducted to determine the composition of map units affected by soil wetness. Computerized scanning of aerial photographs was used to determine the percentage of wet areas within specific map units. Digital maps depicting significant tonal changes due to wetness were used to help determine the composition of map units in areas that were not easily accessible (4, 7).

Helicopters were also used to observe some areas that were otherwise inaccessible.

After soil scientists located and identified the significant natural bodies of soil in the survey area, they drew the boundaries of these bodies on aerial photographs and identified each as a specific map unit. Aerial photographs show trees, buildings, fields, roads, and rivers, all of which help in locating boundaries accurately.

# General Soil Map Units

The general soil map at the back of this publication shows broad areas that have a distinctive pattern of soils, relief, and drainage. Each unit on this map is a unique natural landscape. Typically, it consists of one or more major soils or miscellaneous areas and some minor soils or miscellaneous areas. It is named for the major soils or miscellaneous areas. The soils or miscellaneous areas making up one unit can occur in another but in a different pattern.

The general soil map can be used to compare the

suitability of large areas for general land uses. Areas of suitable soils can be identified on the map. Likewise, areas where the soils are not suitable can be identified.

Because of its small scale, the map is not suitable for planning the management of a farm or field or for selecting a site for a road or building or other structure. The soils in any one map unit differ from place to place in slope, depth, drainage, and other characteristics that affect management.

The general map units in this survey have been




Figure 1.—Typical pattern of soils and underlying material in general soil map unit 1.




Figure 2.—Typical pattern of Lava flows, soils, and underlying material in general soil map unit 6.

grouped into general kinds of landscape for broad interpretive purposes. Each of the broad groups and the map units in each group are described in the following pages.

## Map Unit Descriptions

### Well Drained Soils on Mountainsides and Foothills

*Number of map units:* 5

*Percentage of survey area:* 58

#### 1. Povey-Vitale-Milligan

Moderately deep and deep soils that formed in colluvium derived from metasedimentary rock (fig. 1); on slopes of 15 to 75 percent

*Percentage of survey area:* 22

*Landscape position:* Povey soils—north- and east-facing

mountainsides; Vitale and Milligan soils—south- and west-facing mountainsides

*Elevation:* 5,000 to 9,250 feet

*Frost-free period:* 30 to 90 days

*Average annual precipitation:* 12 to 24 inches

*Minor components:* Drage, Dollarhide, and Ketchum soils; Rock outcrop; Rubbleland; Blackspot and Prudy soils

*Major uses:* Rangeland, wildlife habitat

#### 2. Friedman-Elksel-Starhope

Moderately deep and deep soils that formed in colluvium and residuum derived from volcanic rock; on slopes of 4 to 60 percent

*Percentage of survey area:* 19

*Landscape position:* Friedman soils—north- and east-facing mountainsides; Elksel and Starhope soils—



south- and west-facing mountainsides and foothills  
*Elevation:* 4,700 to 8,000 feet  
*Frost-free period:* 30 to 90 days  
*Average annual precipitation:* 12 to 22 inches  
*Minor components:* Smelter and Winridge soils; Rock outcrop; Furshur, Peevywell, Molyneux, and Justesen soils  
*Major uses:* Rangeland, wildlife habitat

### 3. Moonstone-Earcree

Moderately deep and very deep soils that formed in colluvium, alluvium, and residuum derived from granite; on slopes of 8 to 60 percent  
*Percentage of survey area:* 6  
*Landscape position:* Moonstone soils—south- and west-facing mountainsides and foothills; Earcree soils—north- and east-facing mountainsides and foothills  
*Elevation:* 4,800 to 8,200 feet  
*Frost-free period:* 30 to 90 days  
*Average annual precipitation:* 12 to 22 inches  
*Minor components:* Lockman, Bauscher, and Marshdale soils

*Major uses:* Rangeland, wildlife habitat

### 4. Vitale-Lavacreek-Blackspar

Shallow to deep soils that formed in colluvium and in tephra over colluvium; on slopes of 15 to 75 percent  
*Percentage of survey area:* 6  
*Landscape position:* Vitale and Blackspar soils—south- and west-facing mountainsides; Lavacreek soils—north- and east-facing mountainsides  
*Elevation:* 5,000 to 9,250 feet  
*Frost-free period:* 30 to 90 days  
*Average annual precipitation:* 12 to 24 inches  
*Minor components:* Rock outcrop, Rubbleland, Dollarhide soils  
*Major uses:* Rangeland, wildlife habitat

### 5. Elkcreek-Gaib-Winu

Shallow and moderately deep soils that formed in colluvium and residuum derived from volcanic rock; on slopes of 4 to 60 percent  
*Percentage of survey area:* 5  
*Landscape position:* Elkcreek and Gaib soils—south-




Figure 3.—Typical pattern of soils and underlying material in general soil map unit 8.




Figure 4.—Typical pattern of soils and underlying material in general soil map unit 11.

and west-facing mountainsides and foothills; Winu soils—north- and east-facing mountainsides and foothills

*Elevation:* 4,800 to 8,500 feet

*Frost-free period:* 30 to 90 days

*Average annual precipitation:* 12 to 20 inches

*Minor components:* Rock outcrop; Mulshoe, Polecreek, Molyneux, and Laurentzen soils

*Major uses:* Rangeland, wildlife habitat

#### **Well Drained Soils on Basalt Plains**

*Number of map units:* 5

*Percentage of survey area:* 26

#### **6. Lava flows-Cinderhurst**

Lava flows, and very shallow soils that formed in tephra (fig. 2); on slopes of 2 to 15 percent

*Percentage of survey area:* 12

*Landscape position:* Cinderhurst soils—gently sloping areas of basalt plains; Lava flows—basalt plains

*Elevation:* 4,800 to 6,000 feet

*Frost-free period:* 60 to 90 days

*Average annual precipitation:* 12 to 16 inches

*Minor components:* Soils that are similar to the

Cinderhurst soils but are 20 to 40 inches deep

*Major use:* Wildlife habitat

#### **7. Deerhorn-Rehfield-Rock outcrop**

Moderately deep and very deep soils that formed in eolian material over basalt and in eolian-influenced alluvium, and Rock outcrop; on slopes of 2 to 15 percent

*Percentage of survey area:* 5

*Landscape position:* Deerhorn soils—convex tops and side slopes of undulating basalt plains; Rehfield soils—drainageways; Rock outcrop—convex areas

*Elevation:* 4,600 to 5,000 feet

*Frost-free period:* 90 to 120 days

*Average annual precipitation:* 11 to 13 inches

*Minor components:* Cox, Wildors, and Trevino soils; Playas; Pagari soils

*Major uses:* Rangeland, wildlife habitat



### 8. Gooding-Hamrub

Deep soils that formed in alluvium over basalt and in loess over alluvium (fig. 3); on slopes of 2 to 20 percent

*Percentage of survey area:* 4

*Landscape position:* Gooding soils—intermounds, drainageways; Hamrub soils—mounds

*Elevation:* 4,600 to 5,300 feet

*Frost-free period:* 90 to 120 days

*Average annual precipitation:* 11 to 13 inches

*Minor components:* Yutruie soils, Rock outcrop, Adios and Bostrum soils

*Major uses:* Rangeland, wildlife habitat

loess over residuum and in silty alluvium; on slopes of 1 to 30 percent

*Percentage of survey area:* 3

*Landscape position:* McCarey soils—convex tops and side slopes of undulating basalt plains; McBiggam and Bancroft soils—drainageways

*Elevation:* 4,800 to 5,600 feet

*Frost-free period:* 60 to 90 days

*Average annual precipitation:* 12 to 16 inches

*Minor components:* Pedleford soils, soils that are similar to the McCarey soils but are 10 to 20 inches deep, Molyneux soils

*Major use:* Rangeland

*Minor uses:* Cropland, hayland, pasture

### 9. McCarey-McBiggam-Bancroft

Moderately deep and very deep soils that formed in

### 10. McCarey-Justesen-Rock outcrop

Moderately deep and very deep soils that formed in




Figure 5.—Typical pattern of soils and underlying material in general soil map unit 13.






Figure 6.—Typical pattern of soils and underlying material in general soil map unit 14.

loess over residuum and in alluvium, and Rock outcrop; on slopes of 2 to 15 percent

*Percentage of survey area:* 2

*Landscape position:* McCarey soils—convex tops and side slopes of undulating basalt plains; Justesen soils—drainageways, depressions

*Elevation:* 4,700 to 5,000 feet

*Frost-free period:* 60 to 90 days

*Average annual precipitation:* 12 to 16 inches

*Minor components:* Soils that are similar to the McCarey soils but are 10 to 20 inches deep and have a very stony upper layer

*Major uses:* Rangeland, wildlife habitat

#### **Well Drained and Somewhat Excessively Drained Soils on Fan Terraces and Stream Terraces**

*Number of map units:* 3

*Percentage of survey area:* 14

#### **11. Little Wood-Balaam-Adamson**

Very deep, well drained and somewhat excessively drained soils that formed in alluvium (fig. 4); on slopes of 0 to 4 percent

*Percentage of survey area:* 7

*Landscape position:* Stream terraces along the major streams and rivers

*Elevation:* 4,700 to 6,000 feet

*Frost-free period:* 60 to 90 days

*Average annual precipitation:* 12 to 18 inches

*Minor components:* Drage, Marshdale, Bruneel, Hutton Variant, Isknot, and Gimlett soils; Riverwash

*Major uses:* Irrigated cropland, hayland, and pasture; rangeland; wildlife habitat

#### **12. Peevywell-Muldoon-Simonton**

Moderately deep to very deep, well drained soils that formed in alluvium; on slopes of 2 to 30 percent

*Percentage of survey area:* 4

*Landscape position:* Peevywell soils—convex areas of fan terraces; Muldoon and Simonton soils—drainageways and depressions on fan terraces

*Elevation:* 4,800 to 6,000 feet

*Frost-free period:* 60 to 90 days

*Average annual precipitation:* 12 to 16 inches

*Minor components:* Manard, Goodington, Marshdale, Molyneux, Bruneel, and Rockybar soils

*Major uses:* Irrigated and nonirrigated cropland,

hayland, and pasture; rangeland; wildlife habitat; watershed

**13. Carey Lake-Bringmee**

Very deep, well drained soils that formed in alluvium (fig. 5); on slopes of 0 to 8 percent

*Percentage of survey area:* 3

*Landscape position:* Fan terraces, stream terraces

*Elevation:* 4,700 to 6,000 feet

*Frost-free period:* 60 to 90 days

*Average annual precipitation:* 12 to 16 inches

*Minor components:* Hutton, Little Wood, Adamson, Balaam, Bruneel, Marshdale, Bancroft, Molyneux, and Justesen soils

*Major uses:* Irrigated and nonirrigated cropland, hayland, and pasture; rangeland; wildlife habitat

**Somewhat Poorly Drained to Very Poorly Drained Soils on Stream Terraces and Flood Plains**

*Number of map units:* 1

*Percentage of survey area:* 2

**14. Picabo-Hapur-Bickett**

Very deep, somewhat poorly drained to very poorly drained soils that formed in alluvium (fig. 6); on slopes of 0 to 2 percent

*Percentage of survey area:* 2

*Landscape position:* Flood plains and stream terraces in the vicinity of the community of Picabo

*Elevation:* 4,700 to 5,500 feet

*Frost-free period:* 60 to 90 days

*Average annual precipitation:* 12 to 16 inches

*Minor components:* Bruneel soils, soils that are similar to the Picabo soils but are shallower to lime nodules

*Major uses:* Nonirrigated cropland, hayland, and pasture





## Detailed Soil Map Units

---

The map units on the detailed soil maps at the back of this survey represent the soils or miscellaneous areas in the survey area. The map unit descriptions in this section, along with the soil maps, can be used to determine the suitability and potential of a unit for specific uses. They also can be used to plan the management needed for those uses. More information on each map unit is given under "Use and Management of the Soils."

A map unit delineation on a map represents an area dominated by one or more major kinds of soil or miscellaneous areas. A map unit is identified and named according to the taxonomic classification of the dominant soils or miscellaneous areas. Within a taxonomic class there are precisely defined limits for the properties of the soils. On the landscape, however, the soils and miscellaneous areas are natural phenomena, and they have the characteristic variability of all natural phenomena. Thus, the range of some observed properties may extend beyond the limits defined for a taxonomic class. Areas of soils of a single taxonomic class rarely, if ever, can be mapped without including areas of other taxonomic classes. Consequently, every map unit is made up of the soils or miscellaneous areas for which it is named and some included areas that belong to other taxonomic classes.

Most included soils have properties similar to those of the dominant soil or soils in the map unit, and thus they do not affect use and management. These are called noncontrasting, or similar, inclusions. They may or may not be mentioned in the map unit description. Other included soils and miscellaneous areas, however, have properties and behavior divergent enough to affect use or to require different management. These are called contrasting, or dissimilar, inclusions. They generally are in small areas and could not be mapped separately because of the scale used. Some small areas of strongly contrasting soils or miscellaneous areas are identified by a special symbol on the maps. The included areas of contrasting soils or miscellaneous areas are mentioned in the map unit descriptions. A few

included areas may not have been observed, and consequently they are not mentioned in the descriptions, especially where the pattern was so complex that it was impractical to make enough observations to identify all the soils and miscellaneous areas on the landscape.

The presence of included areas in a map unit in no way diminishes the usefulness or accuracy of the data. The objective of mapping is not to delineate pure taxonomic classes but rather to separate the landscape into segments that have similar use and management requirements. The delineation of such landscape segments on the map provides sufficient information for the development of resource plans, but if intensive use of small areas is planned, onsite investigation is needed.

An identifying symbol precedes the map unit name in the map unit descriptions. Each description includes general facts about the unit and gives the principal hazards and limitations to be considered in planning for specific uses.

Soils that have profiles that are almost alike make up a *soil series*. Except for differences in texture of the upper layer or of the underlying material, all the soils of a series have major horizons that are similar in composition, thickness, and arrangement.

Soils of one series can differ in texture of the upper layer or of the underlying material. They also can differ in slope, stoniness, salinity, wetness, degree of erosion, and other characteristics that affect their use. On the basis of such differences, a soil series is divided into *soil phases*. Most of the areas shown on the detailed soil maps are phases of soil series. The name of a soil phase commonly indicates a feature that affects use or management. For example, Little Wood gravelly loam, 0 to 2 percent slopes, is a phase of the Little Wood series.

Some map units are made up of two or more major soils or miscellaneous areas. These map units are called complexes or associations.

A *complex* consists of two or more soils or



miscellaneous areas in such an intricate pattern or in such small areas that they cannot be shown separately on the maps. The pattern and proportion of the soils or miscellaneous areas are somewhat similar in all areas. Goodington-Manard complex, 2 to 8 percent slopes, is an example.

An *association* is made up of two or more geographically associated soils or miscellaneous areas that are shown as one unit on the maps. Because of present or anticipated uses of the map units in the survey area, it was not considered practical or necessary to map the soils or miscellaneous areas separately. The pattern and relative proportion of the soils or miscellaneous areas are somewhat similar. Lavacreek-Vitale association, 30 to 60 percent slopes, is an example.

This survey includes *miscellaneous areas*. Such areas have little or no soil material and support little or no vegetation. Rubbleland is an example.

Table 4 gives the acreage and proportionate extent of each map unit. Other tables (see "Summary of Tables") give properties of the soils and the limitations, capabilities, and potentials for many uses. The Glossary defines many of the terms used in describing the soils or miscellaneous areas.

## Map Unit Descriptions

### 1—Adamson loam, 0 to 2 percent slopes

#### *Composition*

Adamson loam, 0 to 2 percent slopes, and similar inclusions—90 percent

Contrasting inclusions—10 percent

#### *Characteristics of the Adamson Soil*

*Position on landscape:* Stream terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 19 inches—grayish brown loam

19 to 28 inches—grayish brown fine sandy loam

28 to 61 inches—light brownish gray very gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate in the upper 28 inches; very rapid below this depth

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 28 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Frequency of flooding:* Rare

#### *Inclusions*

*Similar inclusions:* Soils that have a fine sandy loam upper layer

*Contrasting inclusions:* Balaam gravelly sandy loam in convex areas (5 percent); Bruneel loam in depressions and drainageways (5 percent)

#### *Major Uses*

##### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Barley, oats, wheat, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Border and corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

#### *Capability Classification*

III<sub>s</sub>, irrigated

### 2—Adios-Gooding-Bostrum complex, 4 to 20 percent slopes

#### *Composition*

Adios stony loam, 8 to 20 percent slopes—35 percent

Gooding silt loam, 4 to 12 percent slopes—25 percent

Bostrum cobbly silt loam, 4 to 12 percent slopes—20 percent

Contrasting inclusions—20 percent

#### *Characteristics of the Adios Soil*

*Position on landscape:* Convex tops and side slopes of basalt plains

*Parent material:* Residuum, slope alluvium

*Elevation:* 4,600 to 4,900 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 100 days

*Typical profile:*

0 to 5 inches—brown stony loam

5 to 23 inches—yellowish brown, light yellowish brown, and very pale brown clay and clay loam

23 to 27 inches—white, indurated duripan

27 inches—fractured rhyolite that has silica and lime in the fractures

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Low

*Potential rooting depth:* 22 to 31 inches

*Restriction affecting rooting depth:* Duripan at a depth of 23 inches

*Runoff:* Rapid

*Hazard of water erosion:* Severe

### **Characteristics of the Gooding Soil**

*Position on landscape:* Intermounds and convex side slopes of basalt plains

*Parent material:* Alluvium over basalt or rhyolite

*Elevation:* 4,600 to 4,900

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 100 days

*Typical profile:*

0 to 9 inches—brown and pale brown silt loam

9 to 49 inches—yellowish brown, pale brown, and very pale brown silty clay and silty clay loam

49 to 62 inches—very pale brown, weakly cemented duripan

62 inches—basalt that has a silica cap

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* High

*Potential rooting depth:* 40 to 60 inches

*Restriction affecting rooting depth:* Duripan at a depth of 49 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Characteristics of the Bostrum Soil**

*Position on landscape:* Drainageways on basalt plains

*Parent material:* Residuum derived from basalt

*Elevation:* 4,600 to 4,800 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 100 days

*Typical profile:*

0 to 4 inches—grayish brown and pale brown cobbly silt loam

4 to 28 inches—yellowish brown and brown silty clay

28 to 32 inches—light yellowish brown silty clay loam

32 inches—lime-coated basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Moderate

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Contrasting Inclusions**

Furshur very channery loam on toe slopes (10 percent);

Rock outcrop in convex areas (10 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Adios soil—Wyoming big sagebrush, bluebunch wheatgrass; Gooding soil—Wyoming big sagebrush, bluebunch wheatgrass; Bostrum soil—alkali sagebrush, bluebunch wheatgrass

*Main limitations:* Adios soil—stony upper layer, hazard of erosion, low available water capacity; Bostrum soil—cobbly upper layer, hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by stones and cobbles on the surface of the Adios and Bostrum soils. Prescribed burning is limited on the Bostrum soil by the inability of the alkali sagebrush to carry fire.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

VIs, nonirrigated

## **3—Adios association, 8 to 25 percent slopes**

### **Composition**

Adios stony loam, 8 to 25 percent slopes—50 percent



Adios loam, cool, 8 to 25 percent slopes—30 percent  
Contrasting inclusions—20 percent

### ***Characteristics of the Stony Adios Soil***

*Position on landscape:* South- and west-facing sides of buttes

*Parent material:* Residuum, slope alluvium

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 5 inches—brown stony loam

5 to 23 inches—yellowish brown, light yellowish brown, and very pale brown clay and clay loam

23 to 27 inches—white, indurated duripan

27 inches—fractured rhyolite that has silica and lime in the fractures

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Low

*Potential rooting depth:* 22 to 31 inches

*Restriction affecting rooting depth:* Duripan at a depth of 23 inches

*Runoff:* Rapid

*Hazard of water erosion:* Severe

### ***Characteristics of the Cool Adios Soil***

*Position on landscape:* North- and east-facing sides of buttes

*Parent material:* Residuum, slope alluvium

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 46 degrees F

*Frost-free period:* About 100 days

*Typical profile:*

0 to 7 inches—dark grayish brown and dark brown loam

7 to 25 inches—yellowish brown, light yellowish brown, and very pale brown clay and clay loam

25 to 28 inches—white, indurated duripan

28 inches—fractured rhyolite that has silica and lime in the fractures

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Low

*Potential rooting depth:* 22 to 31 inches

*Restriction affecting rooting depth:* Duripan at a depth of 25 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### ***Contrasting Inclusions***

Furshur very channery loam on toe slopes (10 percent);

Gooding silt loam in concave areas (5 percent);

Rock outcrop in convex areas (5 percent)

### ***Major Use***

#### ***Rangeland***

*Dominant vegetation in potential natural plant community:*

Stony Adios soil—Wyoming big sagebrush,

bluebunch wheatgrass; cool Adios soil—Wyoming big sagebrush, bluebunch wheatgrass

*Main limitations:* Stony upper layer, hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.

- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment of brush is limited by stones on the surface.

- Range seeding is suitable on this unit. Drilling is the best suited method.

### ***Capability Classification***

Vlc, nonirrigated

## **4—Balaam gravelly sandy loam, 0 to 2 percent slopes**

### ***Composition***

Balaam gravelly sandy loam, 0 to 2 percent slopes—90 percent

Contrasting inclusions—10 percent

### ***Characteristics of the Balaam Soil***

*Position on landscape:* Stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 14 inches—grayish brown gravelly sandy loam

14 to 21 inches—light brownish gray very gravelly coarse sandy loam

21 to 61 inches—grayish brown extremely gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Somewhat excessively drained

*Permeability:* Moderately rapid in the upper 21 inches; very rapid below this depth  
*Available water capacity:* Very low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 21 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* Slight

**Contrasting Inclusions**

Adamson loam in concave areas (5 percent); Bruneel loam in drainageways and depressions (5 percent)

**Major Uses**

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Barley, oats, wheat, alfalfa hay, pasture (fig. 7)  
*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Border systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Rangeland**

*Dominant vegetation in potential natural plant community:* Basin big sagebrush, bluebunch wheatgrass  
*Main limitation:* Very low available water capacity  
*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.
- Plants that can tolerate droughtiness are suitable for seeding.

**Capability Classification**

IIIc, irrigated; IVs, nonirrigated

**5—Balaam very gravelly sandy loam, 2 to 4 percent slopes**

**Composition**

Balaam very gravelly sandy loam, 2 to 4 percent slopes—90 percent  
Contrasting inclusions—10 percent

**Characteristics of the Balaam Soil**

*Position on landscape:* Stream terraces  
*Parent material:* Alluvium derived from various kinds of rock  
*Elevation:* 4,700 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 42 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*

- 0 to 21 inches—grayish brown very gravelly sandy loam
- 21 to 35 inches—light brownish gray very gravelly coarse sandy loam
- 35 to 63 inches—grayish brown extremely gravelly coarse sand

*Depth class:* Very deep  
*Drainage class:* Somewhat excessively drained  
*Permeability:* Moderately rapid in the upper 35 inches; very rapid below this depth  
*Available water capacity:* Very low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 35 inches  
*Runoff:* Slow  
*Hazard of water erosion:* Slight

**Contrasting Inclusions**

Bruneel loam in drainageways (5 percent); Adamson loam in concave areas (5 percent)

**Major Uses**

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Barley, oats, wheat, alfalfa hay, pasture  
*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled





Figure 7.—Irrigated pasture in an area of Balaam gravelly sandy loam, 0 to 2 percent slopes.

application of water, reduces the rate of runoff, and minimizes the risk of water erosion.

- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*Main limitation:* Very low available water capacity

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.
- Plants that can tolerate droughtiness are suitable for seeding.

#### **Capability Classification**

IVs, irrigated and nonirrigated

### **6—Balaam-Adamson complex, 0 to 2 percent slopes**

#### **Composition**

Balaam very gravelly sandy loam, 0 to 2 percent slopes, and similar inclusions—60 percent

Adamson fine sandy loam, 0 to 2 percent slopes, and similar inclusions—35 percent

Contrasting inclusions—5 percent

#### **Characteristics of the Balaam Soil**

*Position on landscape:* Stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 21 inches—grayish brown very gravelly sandy loam

21 to 35 inches—light brownish gray very gravelly coarse sandy loam



35 to 63 inches—multicolored extremely gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Somewhat excessively drained

*Permeability:* Moderately rapid in the upper 35 inches; very rapid below this depth

*Available water capacity:* Very low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 35 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Shrink-swell potential:* Low

### **Characteristics of the Adamson Soil**

*Position on landscape:* Stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 5 inches—grayish brown fine sandy loam

5 to 19 inches—grayish brown loam

19 to 28 inches—grayish brown fine sandy loam

28 to 61 inches—light grayish brown very gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate in the upper 28 inches; very rapid below this depth

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 28 inches

*Runoff:* Slow

*Hazard of water erosion:* Slight

*Frequency of flooding:* Rare

*Shrink-swell potential:* Low

### **Inclusions**

*Similar inclusions:* Balaam gravelly sandy loam, Adamson loam in concave areas

*Contrasting inclusions:* Soils that are similar to the Balaam soil but are shallower to loose sand and gravel and are in convex areas (5 percent)

### **Major Uses**

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Barley, oats, wheat, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Border systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*Main limitations:* Very low and low available water capacity

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.
- Plants that can tolerate droughtiness are suitable for seeding.

### **Capability Classification**

IVs, irrigated and nonirrigated

## **7—Balaam-Adamson complex, cool, 0 to 2 percent slopes**

### **Composition**

Balaam gravelly sandy loam, 0 to 2 percent slopes—50 percent

Adamson fine sandy loam, 0 to 2 percent slopes—35 percent

Contrasting inclusions—15 percent

### **Characteristics of the Balaam Soil**

*Position on landscape:* Convex areas of stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 5,200 to 6,000 feet

*Average annual precipitation:* About 16 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 65 days

*Typical profile:*

0 to 10 inches—grayish brown gravelly sandy loam

10 to 17 inches—brown very gravelly sandy loam

17 to 60 inches—multicolored extremely cobbly coarse sand

*Depth class:* Very deep

*Drainage class:* Somewhat excessively drained

*Permeability:* Moderately rapid in the upper 17 inches; very rapid below this depth

*Available water capacity:* Very low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and rock fragments at a depth of 17 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Frequency of flooding:* Rare

*Shrink-swell potential:* Low

### **Characteristics of the Adamson Soil**

*Position on landscape:* Concave areas of stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 5,200 to 6,000 feet

*Average annual precipitation:* About 16 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 65 days

*Typical profile:*

0 to 9 inches—grayish brown fine sandy loam

9 to 22 inches—brown very fine sandy loam

22 to 48 inches—brown extremely cobbly coarse sand

48 to 60 inches—multicolored extremely stony coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate in the upper 22 inches; very rapid below this depth

*Available water capacity:* Low

*Potential rooting depth:* More than 60 inches

*Restriction affecting rooting depth:* Loose sand and rock fragments at a depth of 22 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Frequency of flooding:* Rare

*Shrink-swell potential:* Low

### **Contrasting Inclusions**

Balaam very cobbly sandy loam (10 percent); Adamson

gravelly fine sandy loam (5 percent)

### **Major Uses**

#### **Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa, pasture

*General management considerations:*

- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IVs, irrigated and nonirrigated

## **8—Balaam-Adamson-Riverwash complex, 0 to 2 percent slopes**

### **Composition**

Balaam gravelly sandy loam, flooded, 0 to 2 percent slopes—35 percent

Adamson fine sandy loam, flooded, 0 to 2 percent slopes—25 percent

Riverwash—20 percent

Contrasting inclusions—20 percent

### **Characteristics of the Balaam Soil**

*Position on landscape:* Flood plains

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 15 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 70 days

*Typical profile:*

0 to 10 inches—grayish brown gravelly sandy loam

10 to 17 inches—brown very gravelly sandy loam

17 to 60 inches—multicolored extremely cobbly coarse sand

*Depth class:* Very deep

*Drainage class:* Somewhat excessively drained

*Permeability:* Moderately rapid in the upper 17 inches; very rapid below this depth

*Available water capacity:* Very low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and rock



fragments at a depth of 17 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Depth to water table:* 60 to 84 inches

*Frequency of flooding:* Occasional

*Shrink-swell potential:* Low

### **Characteristics of the Adamson Soil**

*Position on landscape:* Flood plains

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 9 inches—grayish brown fine sandy loam

9 to 22 inches—brown very fine sandy loam

22 to 48 inches—brown extremely cobbly coarse sand

48 to 60 inches—multicolored extremely stony coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate in the upper 22 inches; very rapid below this depth

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and rock fragments at a depth of 22 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Depth to water table:* 48 to 60 inches

*Frequency of flooding:* Occasional

*Shrink-swell potential:* Low

### **Characteristics of the Riverwash**

*Position on landscape:* Commonly in braided channels of major rivers and streams

*Kind of material:* Sandy, gravelly, or cobbly sediment, commonly occurring as gravel bars or sand bars

*Vegetation:* Little, if any

*Special features:* Frequently flooded, washed, and reworked by rivers and streams

### **Contrasting Inclusions**

Bruneel loam in drainageways and depressions (10 percent); soils that are similar to the Balaam soil but are shallower to loose sand, gravel, and cobbles and are in convex areas (10 percent)

### **Major Use**

#### **Wildlife habitat**

*General management consideration:*

- This unit provides important habitat for wildlife; therefore, it should be managed and protected for this use.

### **Capability Classification**

IVs, irrigated and nonirrigated

## **9—Bancroft silt loam, 1 to 4 percent slopes**

### **Composition**

Bancroft silt loam, 1 to 4 percent slopes—90 percent

Contrasting inclusions—10 percent

### **Characteristics of the Bancroft Soil**

*Position on landscape:* Basalt plains

*Parent material:* Silty alluvium

*Elevation:* 4,800 to 5,200 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 11 inches—brown silt loam

11 to 33 inches—yellowish brown and dark yellowish brown silty clay loam

33 to 42 inches—very pale brown silt loam

42 to 80 inches—very pale brown gravelly loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow

*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

McCarey loam on side slopes (5 percent); Goodington silt loam in depressions (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.



- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Threetip sagebrush, Idaho fescue

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the inherent ability of threetip sagebrush to sprout from its roots.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

IIIe, irrigated and nonirrigated

## **10—Bancroft silt loam, 4 to 8 percent slopes**

### **Composition**

Bancroft silt loam, 4 to 8 percent slopes—90 percent  
Contrasting inclusions—10 percent

### **Characteristics of the Bancroft Soil**

*Position on landscape:* Basalt plains

*Parent material:* Silty alluvium

*Elevation:* 4,800 to 5,200 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 11 inches—brown silt loam

11 to 33 inches—yellowish brown and dark  
yellowish brown silty clay loam

33 to 42 inches—very pale brown silt loam

42 to 80 inches—very pale brown gravelly loamy  
sand and gravelly loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Medium

*Hazard of water erosion:* Moderate

### **Contrasting Inclusions**

McCarey loam and Manard very stony silt loam on  
convex side slopes (5 percent); Goodington silt  
loam in depressions (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats,  
alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Threetip sagebrush, Idaho fescue

*Main limitation:* Moderate hazard of water erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the inherent ability of threetip sagebrush to sprout from its roots.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

IIIe, irrigated and nonirrigated

**11—Bickett mucky peat, 0 to 2 percent slopes**

***Composition***

Bickett mucky peat, 0 to 2 percent slopes—90 percent  
Contrasting inclusions—10 percent

***Characteristics of the Bickett Soil***

*Position on landscape:* Flood plains  
*Parent material:* Herbaceous plants over silty alluvium  
*Elevation:* 4,700 to 5,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 42 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
    0 to 6 inches—black mucky peat  
    6 to 11 inches—black muck  
    11 to 40 inches—light brownish gray silty clay loam  
    40 to 61 inches—dark gray loam  
*Depth class:* Very deep  
*Drainage class:* Very poorly drained  
*Permeability:* Moderately slow  
*Available water capacity:* Very high  
*Potential rooting depth:* 60 inches or more for water-tolerant plants  
*Runoff:* Pondered  
*Hazard of water erosion:* None  
*Water table:* 6 inches above the surface to 6 inches below  
*Frequency of flooding:* Frequent

***Contrasting Inclusions***

Hapur silt loam in the higher lying areas (5 percent);  
Bickett mucky peat that has strata of sand and gravel between depths of 40 and 60 inches (5 percent)

***Major Use***

**Wetland wildlife habitat**

*Dominant vegetation in potential natural plant community:*  
Rushes, sedges, cattails, other wetland herbaceous plants  
*General management considerations:*  
• This unit provides open, marshy or swampy, shallow water areas that should be maintained in their natural state.  
• Wildlife attracted to areas of this unit include ducks, geese, sandhill cranes, shore birds, muskrat, beaver, and songbirds.

***Capability Classification***

Vw, nonirrigated

**12—Blackspar-Rock outcrop complex, 45 to 75 percent slopes**

***Composition***

Blackspar very cobbly loam, 45 to 75 percent slopes—50 percent  
Rock outcrop—25 percent  
Contrasting inclusions—25 percent

***Characteristics of the Blackspar Soil***

*Position on landscape:* South- and west-facing mountainsides  
*Parent material:* Colluvium derived dominantly from quartzitic sandstone and conglomerate  
*Elevation:* 5,200 to 8,500 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
    0 to 3 inches—brown very cobbly loam  
    3 to 7 inches—yellowish brown very cobbly loam  
    7 to 17 inches—light yellowish brown extremely cobbly loam  
    17 inches—quartzitic sandstone  
*Depth class:* Shallow  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Very low  
*Potential rooting depth:* 10 to 20 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

***Characteristics of the Rock Outcrop***

*Position on landscape:* Ridges  
*Kind of material:* Exposed bedrock

***Contrasting Inclusions***

Vitale very gravelly loam on south- and west-facing side slopes (15 percent); Lavacreek very gravelly silt loam on north- and east-facing slopes at elevations below 7,500 feet and on all aspects at elevations above 7,500 feet (5 percent); Dollarhide very gravelly silt loam on north- and east-facing slopes (5 percent)

***Major Use***

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Low sagebrush, bluebunch wheatgrass  
*General management considerations:*  
• Brush management and proper distribution of livestock are needed.



- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope and the hazard of erosion.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **13—Blackspot-Prudy association, 30 to 60 percent slopes**

### **Composition**

Blackspot very gravelly loam, 30 to 60 percent slopes—45 percent

Prudy loam, 30 to 60 percent slopes—35 percent

Contrasting inclusions—20 percent

### **Characteristics of the Blackspot Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Mixed colluvium over calcareous quartzitic residuum

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 7 inches—grayish brown and brown very gravelly loam

7 to 14 inches—pale brown very gravelly loam

14 to 19 inches—white, indurated duripan

19 inches—fractured, calcareous quartzite

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Very low

*Potential rooting depth:* 13 to 17 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Prudy Soil**

*Position on landscape:* North- and east-facing mountainsides

*Parent material:* Mixed colluvium over calcareous quartzitic residuum

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 10 inches—dark grayish brown and dark brown loam

10 to 42 inches—brown and pale brown loam and gravelly loam

42 to 50 inches—white, indurated duripan

50 inches—fractured, calcareous quartzite

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Moderate

*Potential rooting depth:* 40 to 48 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Soils that are similar to the Blackspot soil but are 20 to 40 inches deep to a duripan and are in convex areas (10 percent); soils that are similar to the Prudy soil but are more than 35 percent rock fragments, are 20 to 40 inches deep to a duripan, and are on convex, north- and east-facing slopes (10 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Blackspot soil—black sagebrush, bluebunch wheatgrass; Prudy soil—mountain big sagebrush, mountain snowberry, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.
- Installation of pipelines and fences is limited by the slope and by the shallow depth of the Blackspot soil.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **14—Bostrum-Yuttrue-Hamrub complex, 2 to 12 percent slopes**

### **Composition**

Bostrum cobbly silt loam, 2 to 8 percent slopes—40 percent

Yuttrue silty clay, 2 to 8 percent slopes—30 percent  
Hamrub silt loam, 2 to 12 percent slopes—20 percent  
Contrasting inclusions—10 percent

**Characteristics of the Bostrum Soil**

*Position on landscape:* Drainageways on basalt plains  
*Parent material:* Residuum derived from basalt  
*Elevation:* 4,600 to 4,800 feet  
*Average annual precipitation:* About 12 inches  
*Average annual air temperature:* About 47 degrees F  
*Frost-free period:* About 110 days  
*Typical profile:*  
    0 to 4 inches—grayish brown and pale brown  
        cobbly silt loam  
    4 to 28 inches—yellowish brown and brown silty  
        clay  
    28 to 32 inches—light yellowish brown silty clay  
        loam  
    32 inches—lime-coated basalt  
*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Very slow  
*Available water capacity:* Moderate  
*Potential rooting depth:* 20 to 40 inches  
*Runoff:* Medium  
*Hazard of water erosion:* Slight or moderate

**Characteristics of the Yuttrue Soil**

*Position on landscape:* Intermounds on basalt plains  
*Parent material:* Fine-textured alluvium  
*Elevation:* 4,600 to 4,800 feet  
*Average annual precipitation:* About 12 inches  
*Average annual air temperature:* About 47 degrees F  
*Frost-free period:* About 110 days  
*Typical profile:*  
    0 to 7 inches—pale brown silty clay  
    7 to 35 inches—pale brown and yellowish brown  
        silty clay  
    35 to 63 inches—light yellowish brown silty clay  
        loam and white clay loam  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Very slow  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Runoff:* Medium  
*Hazard of water erosion:* Slight or moderate

**Characteristics of the Hamrub Soil**

*Position on landscape:* Mounds on basalt plains  
*Parent material:* Loess over alluvium

*Elevation:* 4,600 to 4,800 feet  
*Average annual precipitation:* About 12 inches  
*Average annual air temperature:* About 47 degrees F  
*Frost-free period:* About 110 days  
*Typical profile:*  
    0 to 10 inches—brown and yellowish brown silt  
        loam  
    10 to 41 inches—yellowish brown silty clay loam  
    41 to 43 inches—very pale brown silt loam  
    43 to 48 inches—white, indurated duripan  
    48 inches—fractured rhyolitic bedrock  
*Depth class:* Deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* High  
*Potential rooting depth:* 40 to 50 inches  
*Restriction affecting rooting depth:* Duripan at a depth of  
    43 inches  
*Runoff:* Medium or rapid  
*Hazard of water erosion:* Moderate or severe

**Contrasting Inclusions**

Yuttrue silty clay that has slopes of 0 to 2 percent and is  
    in areas southeast of Magic Reservoir (5 percent);  
    Rock outcrop in convex areas (5 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
    Bostrum and Yuttrue soils—alkali sagebrush,  
    bluebunch wheatgrass; Hamrub soil—Wyoming big  
    sagebrush, bluebunch wheatgrass  
*Main limitations:* Bostrum soil—cobbly upper layer,  
    hazard of erosion; Yuttrue soil—silty clay upper  
    layer, hazard of erosion; Hamrub soil—hazard of  
    erosion  
*General management considerations:*  
    • Brush management, proper distribution of livestock,  
    and range seeding are needed.  
    • Suitable methods of brush management are chemical  
    spraying and mechanical treatment. Prescribed burning  
    is limited on the Bostrum and Yuttrue soils by the  
    inability of alkali sagebrush to carry fire.  
    • Range seeding is suitable on this unit. Drilling is the  
    best suited method.  
    • Plants that can tolerate shrinking and swelling of the  
    Yuttrue soil are suitable for seeding.

**Capability Classification**

VIs, nonirrigated



## 15—Bringmee loam, 0 to 2 percent slopes

### **Composition**

Bringmee loam, 0 to 2 percent slopes—85 percent  
Contrasting inclusions—15 percent

### **Characteristics of the Bringmee Soil**

*Position on landscape:* Fan terraces, stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 7 inches—dark grayish brown loam

7 to 47 inches—grayish brown, brown, and dark grayish brown clay loam, sandy clay loam, and loam

47 to 61 inches—light yellowish brown gravelly sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow in the upper 47 inches; moderately rapid or rapid below this depth

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Sand and gravel at a depth of 47 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

Little Wood gravelly loam in convex areas (5 percent);  
Marshdale loam and Bruneel loam in depressions and drainageways (10 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Border and

corrugation systems are also suitable.

- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IIIc, irrigated and nonirrigated

## 16—Bringmee loam, 2 to 4 percent slopes

### **Composition**

Bringmee loam, 2 to 4 percent slopes—85 percent  
Contrasting inclusions—15 percent

### **Characteristics of the Bringmee Soil**

*Position on landscape:* Fan terraces, stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 7 inches—dark grayish brown loam

7 to 47 inches—grayish brown, brown, and dark grayish brown clay loam, sandy clay loam, and loam

47 to 61 inches—light yellowish brown gravelly sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow in the upper 47 inches; moderately rapid or rapid below this depth

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Sand and gravel at a depth of 47 inches

*Runoff:* Slow

*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

Little Wood gravelly loam in convex areas (5 percent);  
Marshdale loam and Bruneel loam in drainageways and depressions (10 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue

- management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
  - The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Corrugation systems are also suitable.
  - Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Capability Classification**

IIIe, irrigated and nonirrigated

**17—Bringmee loam, 4 to 8 percent slopes**

**Composition**

Bringmee loam, 4 to 8 percent slopes—90 percent  
Contrasting inclusions—10 percent

**Characteristics of the Bringmee Soil**

- Position on landscape:* Fan terraces, stream terraces  
*Parent material:* Alluvium derived from various kinds of rock  
*Elevation:* 4,800 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*
- 0 to 7 inches—dark grayish brown loam
  - 7 to 47 inches—grayish brown, brown, and dark grayish brown clay loam, sandy clay loam, and loam
  - 47 to 61 inches—light yellowish brown gravelly sandy loam
- Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow in the upper 47 inches; moderately rapid or rapid below this depth  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Sand and gravel at a depth of 47 inches  
*Runoff:* Medium  
*Hazard of water erosion:* Moderate

**Contrasting Inclusions**

Molyneux loam in concave areas (5 percent); Little Wood gravelly loam along streams (5 percent)

**Major Uses**

**Cropland, hayland, and pasture**

- Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture  
*General management considerations:*
- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
  - Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
  - The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
  - Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Capability Classification**

IIIe, irrigated and nonirrigated

**18—Bringmee-Hutton complex, 1 to 4 percent slopes**

**Composition**

Bringmee loam, 1 to 4 percent slopes—50 percent  
Hutton clay loam, 1 to 2 percent slopes—30 percent  
Contrasting inclusions—20 percent

**Characteristics of the Bringmee Soil**

- Position on landscape:* Fan terraces, stream terraces  
*Parent material:* Alluvium derived from various kinds of rock  
*Elevation:* 4,800 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*
- 0 to 7 inches—dark grayish brown loam
  - 7 to 47 inches—grayish brown, brown, and dark grayish brown clay loam, sandy clay loam, and loam
  - 47 to 61 inches—light yellowish brown gravelly coarse sandy loam



*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow in the upper 47 inches; moderately rapid or rapid below this depth  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Sand and gravel at a depth of 47 inches  
*Runoff:* Slow  
*Hazard of water erosion:* Slight

### **Characteristics of the Hutton Soil**

*Position on landscape:* Flood plains  
*Parent material:* Mixed alluvium  
*Elevation:* 4,800 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 42 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
 0 to 19 inches—dark gray clay loam  
 19 to 62 inches—gray clay  
*Depth class:* Very deep  
*Drainage class:* Poorly drained  
*Permeability:* Very slow  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Water table at a depth of 12 to 30 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* None  
*Depth to water table:* 12 to 30 inches  
*Frequency of flooding:* Frequent

### **Contrasting Inclusions**

Marshdale loam and Bruneel loam in drainageways and depressions (20 percent)

### **Major Uses**

#### **Hayland and pasture**

*Currently grown nonirrigated crops:* Pasture, grass-legume hay  
*Dominant vegetation in potential natural plant community:*  
 Bringmee soil—basin big sagebrush, Idaho fescue;  
 Hutton soil—tufted hairgrass, sedges, rushes, willow  
*General management considerations:*  
 • Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.  
 • Wetness in areas of the Hutton soil limits the choice of plants and the period of cutting or grazing and increases the risk of winterkill.

- Plants that can tolerate wetness are suitable for seeding on the Hutton soil.
- Grazing on the Hutton soil should be deferred until the water table lowers and the upper part of the soil is firm.
- Irrigation is needed on the Bringmee soil. A sprinkler system is the best suited method.

### **Capability Classification**

IVw, irrigated and nonirrigated

## **19—Bringmee-Little Wood complex, 1 to 4 percent slopes**

### **Composition**

Bringmee gravelly loam, 1 to 4 percent slopes—45 percent  
 Little Wood very gravelly loam, 1 to 4 percent slopes—35 percent  
 Contrasting inclusions—20 percent

### **Characteristics of the Bringmee Soil**

*Position on landscape:* Fan terraces  
*Parent material:* Alluvium derived from various kinds of rock  
*Elevation:* 4,800 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
 0 to 11 inches—dark grayish brown gravelly loam  
 11 to 22 inches—grayish brown clay loam  
 22 to 33 inches—grayish brown sandy clay loam  
 33 to 42 inches—grayish brown gravelly sandy loam  
 42 to 61 inches—light olive brown very gravelly loamy coarse sand  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow in the upper 33 inches; moderately rapid or rapid below this depth  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Sand and gravel at a depth of 42 inches  
*Runoff:* Slow  
*Hazard of water erosion:* Slight

### **Characteristics of the Little Wood Soil**

*Position on landscape:* Stream terraces  
*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,800 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
    0 to 13 inches—dark brown and brown very gravelly loam  
    13 to 26 inches—brown and yellowish brown very gravelly sandy clay loam  
    26 to 32 inches—yellowish brown extremely gravelly coarse sandy loam  
    32 to 42 inches—brown extremely gravelly loamy coarse sand  
    42 to 61 inches—pale brown extremely gravelly coarse sand  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate in the upper 32 inches; very rapid below this depth  
*Available water capacity:* Low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Sand and gravel at a depth of 32 inches  
*Runoff:* Slow  
*Hazard of water erosion:* Slight

**Contrasting Inclusions**

Bruneel gravelly loam and Hutton clay loam in depressions and drainageways (15 percent); Bringmee loam that has slopes of more than 4 percent (5 percent)

**Major Uses**

**Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa, pasture  
*General management considerations:*  
• Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.  
• The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Border and corrugation systems are also suitable.  
• Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Capability Classification**

IVs, irrigated and nonirrigated

**20—Bruneel loam, 0 to 2 percent slopes**  
**Composition**

Bruneel loam, 0 to 2 percent slopes—90 percent  
Contrasting inclusions—10 percent

**Characteristics of the Bruneel Soil**

*Position on landscape:* Flood plains  
*Parent material:* Recent alluvium derived from various kinds of rock  
*Elevation:* 4,700 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 42 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
    0 to 14 inches—grayish brown loam  
    14 to 23 inches—light gray loam  
    23 to 27 inches—grayish brown very gravelly loamy sand  
    27 to 61 inches—multicolored extremely gravelly coarse sand  
*Depth class:* Very deep  
*Drainage class:* Poorly drained  
*Permeability:* Moderate in the upper 23 inches; very rapid below this depth  
*Available water capacity:* Low  
*Potential rooting depth:* 60 inches or more for water-tolerant plants  
*Restrictions affecting rooting depth:* Loose sand and gravel at a depth of 27 inches; water table at a depth of 12 to 18 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* None  
*Depth to water table:* 12 to 18 inches  
*Frequency of flooding:* Occasional

**Contrasting Inclusions**

Marshdale loam in drainageways (5 percent); Bringmee loam in the higher lying areas (5 percent)

**Major Uses**

**Hayland and pasture**

*Currently grown nonirrigated crops:* Pasture, grass-legume hay  
*Dominant vegetation in potential natural plant community:*  
    Tufted hairgrass, sedges, rushes  
*General management considerations:*  
• Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.  
• Wetness limits the choice of plants and the period of cutting or grazing.



- Plants that can tolerate wetness are suitable for seeding.
- Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

### **Capability Classification**

IVw, nonirrigated

## **21—Carey Lake loam, 0 to 2 percent slopes**

### **Composition**

Carey Lake loam, 0 to 2 percent slopes—90 percent  
Contrasting inclusions—10 percent

### **Characteristics of the Carey Lake Soil**

*Position on landscape:* Fan terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 12 inches—grayish brown loam

12 to 20 inches—grayish brown clay loam

20 to 42 inches—grayish brown and brown fine sandy loam

42 to 72 inches—grayish brown and brown fine sandy loam and loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Very slow

*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

Bringmee loam on the higher lying stream terraces (5 percent); Hutton clay loam along drainageways and in depressions (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water

management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.

- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Border and corrugation systems are also suitable.

- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IIIc, irrigated and nonirrigated

## **22—Carey Lake loam, 2 to 4 percent slopes**

### **Composition**

Carey Lake loam, 2 to 4 percent slopes—90 percent  
Contrasting inclusions—10 percent

### **Characteristics of the Carey Lake Soil**

*Position on landscape:* Fan terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 12 inches—grayish brown loam

12 to 20 inches—grayish brown clay loam

20 to 42 inches—grayish brown and brown fine sandy loam

42 to 72 inches—grayish brown and brown fine sandy loam and loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow

*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

Bringmee loam on the higher lying stream terraces (5 percent); Hutton clay loam along drainageways and in depressions (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IIIc, irrigated; IIle, nonirrigated

## **23—Cox-Rehfield-Rock outcrop complex, 2 to 15 percent slopes**

### **Composition**

Cox very stony sandy loam, 2 to 15 percent slopes—35 percent

Rehfield loamy sand, 2 to 8 percent slopes—30 percent

Rock outcrop—20 percent

Contrasting inclusions—15 percent

### **Characteristics of the Cox Soil**

*Position on landscape:* Convex tops and side slopes of basalt plains

*Parent material:* Eolian material derived from various kinds of rock

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 3 inches—dark brown very stony sandy loam

3 to 12 inches—dark yellowish brown very cobbly fine sandy loam

12 inches—basalt

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### **Characteristics of the Rehfield Soil**

*Position on landscape:* Depressions and drainageways on basalt plains

*Parent material:* Eolian-influenced alluvium derived from various kinds of rock

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 3 inches—brown loamy sand

3 to 11 inches—brown sandy loam

11 to 42 inches—yellowish brown sandy loam and sandy clay loam

42 to 67 inches—light yellowish brown loamy sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow

*Hazard of water erosion:* Slight

*Hazard of wind erosion:* Severe

### **Characteristics of the Rock Outcrop**

*Kind of material:* Exposed basalt

### **Contrasting Inclusions**

Soils that are similar to the Rehfield soil but are 20 to 40 inches deep to bedrock and are in depressions (10 percent); Pagari very cobbly sandy loam in convex areas (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Cox soil—basin big sagebrush, bluebunch

wheatgrass; Rehfield soil—basin big sagebrush, needleandthread, Indian ricegrass

*Main limitations:* Very stony sandy loam upper layer in the Cox soil; areas of Rock outcrop; loamy sand upper layer, droughtiness, and hazard of wind erosion on the Rehfield soil

*General management considerations:*

- Brush management, proper distribution of livestock,



and range seeding are needed.

- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the very stony sandy loam upper layer in the Cox soil and by the areas of Rock outcrop.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

Vls, nonirrigated

## **24—Deerhorn-Rehfield-Rock outcrop complex, 2 to 15 percent slopes**

### **Composition**

Deerhorn fine sandy loam, 2 to 15 percent slopes—40 percent  
 Rehfield sandy loam, 2 to 8 percent slopes—30 percent  
 Rock outcrop—20 percent  
 Contrasting inclusions—10 percent

### **Characteristics of the Deerhorn Soil**

*Position on landscape:* Convex tops and side slopes of basalt plains

*Parent material:* Eolian material over basalt

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

- 0 to 9 inches—dark grayish brown fine sandy loam
- 9 to 17 inches—brown sandy clay loam
- 17 to 21 inches—very pale brown loam
- 21 to 24 inches—very pale brown, indurated duripan
- 24 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 30 inches

*Restriction affecting rooting depth:* Duripan at a depth of 21 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Characteristics of the Rehfield Soil**

*Position on landscape:* Depressions and drainageways on basalt plains

*Parent material:* Eolian-influenced alluvium derived from various kinds of rock

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

- 0 to 11 inches—brown sandy loam
- 11 to 23 inches—yellowish brown sandy loam
- 23 to 42 inches—yellowish brown sandy clay loam
- 42 to 67 inches—light yellowish brown loamy sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### **Characteristics of the Rock Outcrop**

*Kind of material:* Exposed basalt

### **Contrasting Inclusions**

Wildors very stony sandy loam on convex tops and playas in depressions (10 percent)

### **Major Use**

### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the areas of Rock outcrop and the areas of included Wildors very stony sandy loam.
- Range seeding is suitable on this unit. It is limited by the areas of Rock outcrop, the hazard of erosion, and the areas of included Wildors very stony sandy loam. Drilling is the best suited method.

### **Capability Classification**

Vle, nonirrigated

## **25—Deerhorn-Wildors complex, 2 to 8 percent slopes**

### **Composition**

Deerhorn fine sandy loam, 2 to 8 percent slopes—45 percent

Wildors very stony sandy loam, 2 to 8 percent slopes—30 percent

Contrasting inclusions—25 percent

### **Characteristics of the Deerhorn Soil**

*Position on landscape:* Concave side slopes of basalt plains

*Parent material:* Eolian material over basalt

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 9 inches—dark grayish brown fine sandy loam

9 to 17 inches—brown sandy clay loam

17 to 21 inches—very pale brown loam

21 to 24 inches—very pale brown, indurated duripan

24 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 30 inches

*Restriction affecting rooting depth:* Duripan at a depth of 21 inches

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### **Characteristics of the Wildors Soil**

*Position on landscape:* Flat ridgetops and convex side slopes of basalt plains

*Parent material:* Eolian material over basalt

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 9 inches—brown and yellowish brown very stony sandy loam

9 to 15 inches—yellowish brown extremely stony loam

15 to 21 inches—light yellowish brown extremely stony loam

21 to 24 inches—very pale brown, indurated duripan

24 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Very low

*Potential rooting depth:* 21 to 28 inches

*Restriction affecting rooting depth:* Duripan at a depth of 21 inches

*Runoff:* Slow

*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

Rehfield sandy loam in depressions (10 percent); soils that are similar to the Wildors soil but are 10 to 20 inches deep to a duripan (10 percent); Rock outcrop on ridges and playas in depressions (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the areas of Rock outcrop and the very stony sandy loam upper layer in the Wildors soil.
- Range seeding is suitable on this unit. It is limited by the areas of Rock outcrop, the very stony sandy loam upper layer and very low available water capacity of the Wildors soil, and the hazard of erosion on the Deerhorn soil. Drilling is the best suited method of seeding.
- Seeding late in fall produces the best results.
- Plants that can tolerate droughtiness are suitable for seeding.

### **Capability Classification**

VIs, nonirrigated

## **26—Deerhorn-Wildors-Trevino complex, 2 to 15 percent slopes**

### **Composition**

Deerhorn fine sandy loam, 2 to 15 percent slopes—40 percent

Wildors very stony sandy loam, 2 to 15 percent slopes—30 percent

Trevino extremely stony silt loam, 2 to 15 percent slopes—20 percent

Contrasting inclusions—10 percent

### **Characteristics of the Deerhorn Soil**

*Position on landscape:* Concave side slopes of buttes and basalt plains



*Parent material:* Eolian material over basalt

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 8 inches—dark grayish brown and brown fine sandy loam

8 to 15 inches—brown loam

15 to 21 inches—yellowish brown loam

21 to 28 inches—white, indurated duripan

28 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 30 inches

*Restriction affecting rooting depth:* Duripan at a depth of 21 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Characteristics of the Wildors Soil**

*Position on landscape:* Flat ridges and convex side slopes of buttes and basalt plains

*Parent material:* Eolian material over basalt

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 10 inches—brown very stony sandy loam

10 to 15 inches—brown and yellowish brown very stony sandy loam

15 to 18 inches—light yellowish brown very stony loam

18 to 22 inches—very pale brown very stony sandy loam

22 to 24 inches—very pale brown, indurated duripan

24 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Very low

*Potential rooting depth:* 21 to 28 inches

*Restriction affecting rooting depth:* Duripan at a depth of 22 inches

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### **Characteristics of the Trevino Soil**

*Position on landscape:* Eroded drainageways on the sides of buttes and basalt plains

*Parent material:* Eolian-influenced slope alluvium

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* About 11 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 5 inches—brown extremely stony silt loam

5 to 9 inches—pale brown extremely stony silt loam

9 to 12 inches—light yellowish brown extremely stony silt loam

12 inches—basalt

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### **Contrasting Inclusions**

Rehfield sandy loam on playas in depressions (5 percent); Rock outcrop on ridges (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Deerhorn and Wildors soils—basin big sagebrush, bluebunch wheatgrass; Trevino soil—Wyoming big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the areas of Rock outcrop and the stones in the upper layer of the Wildors and Trevino soils.
- Range seeding is suitable on this unit. It is limited by the hazard of erosion, the areas of Rock outcrop, the stones in the upper layer of the Wildors and Trevino soils, and the restricted available water capacity.
- Drilling is the best suited method of seeding.
- Seeding late in fall produces the best results.
- Plants that can tolerate droughtiness are suitable for seeding.

### **Capability Classification**

VIs, nonirrigated

**27—Dollarhide-Rock outcrop complex, 60 to 75 percent slopes****Composition**

Dollarhide very gravelly fine sandy loam, 60 to 75 percent slopes—50 percent  
 Rock outcrop—25 percent  
 Contrasting inclusions—25 percent

**Characteristics of the Dollarhide Soil**

*Position on landscape:* North- and east-facing mountainsides and ridges at elevations below 7,500 feet; all aspects of mountainsides and ridges at elevations above 7,500 feet

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 5,700 to 9,250 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 7 inches—brown very gravelly fine sandy loam

7 to 13 inches—yellowish brown extremely cobbly fine sandy loam

13 inches—quartzite

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

**Characteristics of the Rock Outcrop**

*Position on landscape:* Ridges

*Kind of material:* Exposed bedrock

**Contrasting Inclusions**

Povey gravelly loam in drainageways (10 percent);  
 Rubbleland on toe slopes (10 percent); Ketchum very gravelly loam in forested areas (5 percent)

**Major Use****Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*Main limitations:* Slope, hazard of erosion

*General management consideration:*

- Proper distribution of livestock is needed.

**Capability Classification**

VIIIe, nonirrigated

**28—Drage gravelly loam, 4 to 8 percent slopes****Composition**

Drage gravelly loam, 4 to 8 percent slopes—90 percent  
 Contrasting inclusions—10 percent

**Characteristics of the Drage Soil**

*Position on landscape:* Fan terraces

*Parent material:* Alluvium derived from mixed igneous and metamorphic rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 8 inches—dark grayish brown gravelly loam

8 to 14 inches—brown gravelly loam

14 to 20 inches—yellowish brown very gravelly clay loam

20 to 61 inches—very pale brown extremely gravelly sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow

*Hazard of water erosion:* Slight

**Contrasting Inclusions**

Justesen loam on toe slopes (5 percent); Rockybar extremely cobbly loam on the steeper side slopes (5 percent)

**Major Uses**

*Current uses:* Hayland, pasture, rangeland

*Potential use:* Cropland

**Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa, pasture

*General management considerations:*

- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage.
- The best suited method of irrigation is a sprinkler system.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.



**Rangeland**

*Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*Main limitation:* Low available water capacity

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.
- Plants that can tolerate droughtiness are suitable for seeding.

**Cropland**

*Currently grown irrigated crops:* Wheat, barley, oats

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Capability Classification**

IIIe, irrigated and nonirrigated

**29—Drage gravelly loam, 8 to 12 percent slopes****Composition**

Drage gravelly loam, 8 to 12 percent slopes—85 percent

Contrasting inclusions—15 percent

**Characteristics of the Drage Soil**

*Position on landscape:* Fan terraces

*Parent material:* Alluvium derived from mixed igneous and metamorphic rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 8 inches—dark grayish brown gravelly loam

8 to 14 inches—brown gravelly loam

14 to 20 inches—yellowish brown very gravelly clay loam

20 to 61 inches—very pale brown extremely gravelly sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Runoff:* Medium

*Hazard of water erosion:* Moderate

**Contrasting Inclusions**

Justesen loam (5 percent), Povey gravelly loam (5 percent), and Vitale very gravelly loam (5 percent) on toe slopes

**Major Uses****Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa, pasture

*General management considerations:*

- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Rangeland**

*Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*Main limitation:* Low available water capacity

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.
- Plants that can tolerate droughtiness are suitable for seeding.

**Capability Classification**

IVe, irrigated; IIIe, nonirrigated

### 30—Drage gravelly loam, cool, 2 to 15 percent slopes

#### **Composition**

Drage gravelly loam, cool, 2 to 15 percent slopes—80 percent

Contrasting inclusions—20 percent

#### **Characteristics of the Drage Soil**

*Position on landscape:* Stream terraces, fan terraces

*Parent material:* Mixed alluvium

*Elevation:* 5,500 to 6,100 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 65 days

*Typical profile:*

0 to 14 inches—dark grayish brown and brown gravelly loam

14 to 30 inches—yellowish brown very gravelly clay loam

30 to 61 inches—very pale brown extremely gravelly sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Sand and gravel at a depth of 30 inches

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

#### **Contrasting Inclusions**

Little Wood very gravelly loam on stream terraces (10 percent); Molyneux loam in concave areas (10 percent)

#### **Major Uses**

*Current use:* Rangeland

*Potential uses:* Hayland, pasture

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

#### **Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa, pasture

*General management considerations:*

- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system, but corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

#### **Capability Classification**

Ive, irrigated; IIle, nonirrigated

### 31—Drage very gravelly loam, cool, 0 to 3 percent slopes

#### **Composition**

Drage very gravelly loam, cool, 0 to 3 percent slopes—85 percent

Contrasting inclusions—15 percent

#### **Characteristics of the Drage Soil**

*Position on landscape:* Stream terraces, fan terraces

*Parent material:* Mixed alluvium

*Elevation:* 5,000 to 6,100 feet

*Average annual precipitation:* About 16 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 65 days

*Typical profile:*

0 to 16 inches—very dark grayish brown and dark grayish brown very gravelly loam

16 to 41 inches—dark brown and brown very gravelly sandy clay loam and very gravelly clay loam

41 to 61 inches—yellowish brown and light yellowish brown extremely gravelly sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Sand and gravel at a depth of 41 inches

*Runoff:* Slow

*Hazard of water erosion:* Slight

*Shrink-swell potential:* Moderate



### ***Contrasting Inclusions***

Isknat gravelly clay loam (5 percent); Bringmee loam (5 percent); Hutton Variant clay loam (5 percent)

### ***Major Uses***

#### **Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa, pasture

*General management considerations:*

- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system, but corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### ***Capability Classification***

IVs, irrigated and nonirrigated

## **32—Earcree-Lockman complex, 30 to 60 percent slopes**

### ***Composition***

Earcree gravelly coarse sandy loam, 30 to 60 percent slopes—50 percent

Lockman sandy loam, 30 to 60 percent slopes—30 percent

Contrasting inclusions—20 percent

### ***Characteristics of the Earcree Soil***

*Position on landscape:* North- and east-facing mountainsides at elevations below 7,500 feet; all aspects of mountainsides at elevations above 7,500 feet

*Parent material:* Colluvium and alluvium over residuum derived from granite

*Elevation:* 6,000 to 8,200 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

- 0 to 37 inches—dark grayish brown and brown gravelly coarse sandy loam
- 37 to 52 inches—pale brown gravelly coarse sandy loam
- 52 to 70 inches—pale brown very gravelly loamy coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### ***Characteristics of the Lockman Soil***

*Position on landscape:* North- and east-facing mountainsides

*Parent material:* Colluvium derived from granite

*Elevation:* 6,000 to 8,200 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

- 0 to 15 inches—brown sandy loam
- 15 to 23 inches—pale brown gravelly sandy loam
- 23 to 44 inches—pale brown gravelly loamy sand
- 44 to 58 inches—partially weathered granitic rock
- 58 inches—granitic rock

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### ***Contrasting Inclusions***

Soils that are similar to the Earcree soil but receive supplemental moisture in the lower part of the profile from springs and support quaking aspen (10 percent); soils that are 10 to 20 inches deep to bedrock and Rock outcrop in convex areas (10 percent)

### ***Major Uses***

#### **Rangeland (Earcree Soil)**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, mountain snowberry, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope and the hazard of erosion.
- Range seeding generally is not suitable on this unit because of the slope and the hazard of erosion.



- Fences and stock water pipelines are limited by the slope.

#### **Woodland (Lockman Soil)**

*Dominant vegetation in potential natural plant community:*

Douglas fir, mountain snowberry

*Average site index for Douglas fir (50-year site curve):* 50

*Maximum average annual growth for Douglas fir:* 68

cubic feet per acre from a stand of trees 45 years old

*Main limitations:* Hazard of erosion, slope, low available water capacity, hazard of windthrow

#### **Grazable understory (Lockman Soil)**

*Common forest understory plants:* Elk sedge, heartleaf arnica, pine reedgrass, mountain snowberry

*General management considerations:*

- Where the canopy cover is more than 40 percent, the understory is sparse and has low value as forage. Where the canopy is less dense, the understory provides good forage.
- Forage production can be increased by seeding disturbed areas to suitable plants and deferring grazing until seedlings are well established.

#### **Capability Classification**

VIIe, nonirrigated

### **33—Earcree-Moonstone association, 8 to 30 percent slopes**

#### **Composition**

Earcree gravelly coarse sandy loam, 8 to 30 percent slopes—50 percent

Moonstone gravelly coarse sandy loam, 8 to 30 percent slopes—30 percent

Contrasting inclusions—20 percent

#### **Characteristics of the Earcree Soil**

*Position on landscape:* North- and east-facing slopes of foothills

*Parent material:* Colluvium and slope alluvium over residuum derived from granite

*Elevation:* 5,200 to 6,500 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 37 inches—dark grayish brown and brown gravelly coarse sandy loam

37 to 52 inches—pale brown gravelly coarse sandy loam

52 to 70 inches—pale brown very gravelly loamy coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Runoff:* Rapid or very rapid

*Hazard of water erosion:* Severe or very severe

#### **Characteristics of the Moonstone Soil**

*Position on landscape:* South- and west-facing slopes of foothills

*Parent material:* Colluvium and residuum derived from granite

*Elevation:* 5,200 to 6,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 26 inches—dark grayish brown and brown gravelly coarse sandy loam

26 to 34 inches—pale brown gravelly coarse sandy loam

34 inches—partially weathered granitic rock

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Rapid or very rapid

*Hazard of water erosion:* Severe or very severe

#### **Contrasting Inclusions**

Marshdale loam in drainageways (15 percent);

Bauscher loam on fan terraces and toe slopes (5 percent)

#### **Major Use**

##### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.



- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

Ive, nonirrigated

## **34—Earcree-Moonstone association, 30 to 60 percent slopes**

### **Composition**

Earcree gravelly coarse sandy loam, 30 to 60 percent slopes—45 percent

Moonstone gravelly coarse sandy loam, 30 to 60 percent slopes—30 percent

Contrasting inclusions—25 percent

### **Characteristics of the Earcree Soil**

*Position on landscape:* North- and east-facing mountainsides at elevations below 7,500 feet; all aspects of mountainsides at elevations above 7,500 feet

*Parent material:* Colluvium and slope alluvium over residuum derived from granite

*Elevation:* 5,200 to 7,800 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 37 inches—dark grayish brown and brown gravelly coarse sandy loam

37 to 52 inches—pale brown gravelly coarse sandy loam

52 to 70 inches—pale brown very gravelly loamy coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Moonstone Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Colluvium and residuum derived from granite

*Elevation:* 5,200 to 7,800 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 21 inches—dark grayish brown and brown gravelly coarse sandy loam

21 to 32 inches—grayish brown gravelly coarse sandy loam

32 inches—granitic rock

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Bauscher loam on toe slopes (10 percent); soils that are similar to the Earcree soil but receive supplemental moisture in the lower part of the profile from springs and support quaking aspen (10 percent); soils that are similar to the Moonstone soil but are 10 to 20 inches deep to bedrock and are on ridges (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope and the hazard of erosion.
- Range seeding generally is not suitable on this unit because of the slope and the hazard of erosion.
- Fences and stock water pipelines are limited by the slope and the hazard of erosion.

### **Capability Classification**

Vlle, nonirrigated

## **35—Elkcreek-Gaib complex, 30 to 60 percent slopes**

### **Composition**

Elkcreek loam, 30 to 60 percent slopes—50 percent

Gaib very gravelly loam, 30 to 60 percent slopes—30 percent

Contrasting inclusions—20 percent

### **Characteristics of the Elkcreek Soil**

*Position on landscape:* Concave areas on south- and west-facing mountainsides

*Parent material:* Residuum derived from andesite and basalt

*Elevation:* 5,000 to 6,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 11 inches—grayish brown and brown loam

11 to 28 inches—yellowish brown and light yellowish brown clay loam

28 to 34 inches—yellowish brown sandy clay loam

34 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 26 to 40 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Gaib Soil**

*Position on landscape:* Convex areas on south- and west-facing mountainsides

*Parent material:* Residuum derived from andesite, latite, and basalt

*Elevation:* 5,000 to 6,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 4 inches—brown very gravelly loam

4 to 12 inches—dark yellowish brown very cobbly clay loam

12 inches—basalt

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Winu stony loam on north- and east-facing slopes (10 percent); Rock outcrop in convex areas (10 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*  
Mountain big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope, the hazard of erosion, and the areas of Rock outcrop.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.
- Fences and stock water pipelines are limited by the slope, the depth to bedrock, and the areas of Rock outcrop.

### **Capability Classification**

VIIe, nonirrigated

### **36—Elkcreek-Polecreek complex, 4 to 30 percent slopes**

#### **Composition**

Elkcreek loam, 4 to 30 percent slopes—55 percent

Polecreek very stony loam, 4 to 15 percent slopes—30 percent

Contrasting inclusions—15 percent

### **Characteristics of the Elkcreek Soil**

*Position on landscape:* Side slopes of foothills

*Parent material:* Residuum derived from andesite and basalt

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 11 inches—grayish brown and brown loam

11 to 28 inches—yellowish brown and light yellowish brown clay loam

28 to 34 inches—yellowish brown loam

34 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 26 to 40 inches

*Runoff:* Rapid or very rapid

*Hazard of water erosion:* Severe or very severe

### **Characteristics of the Polecreek Soil**

*Position on landscape:* Ridges and eroded drainageways on foothills

*Parent material:* Residuum derived from andesite and basalt



*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 4 inches—dark brown very stony loam

4 to 6 inches—brown very cobbly clay

6 to 13 inches—brown very gravelly clay

13 inches—basalt

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Contrasting Inclusions**

Mulshoe very stony loam in convex areas (10 percent);

Laurentzen silt loam in drainageways (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Elkcreek soil—mountain big sagebrush, Idaho fescue; Polecreek soil—alkali sagebrush, Idaho fescue

*Main limitations:* Very stony loam upper layer in the Polecreek soil, hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the very stony loam upper layer in the Polecreek soil and by the hazard of erosion. Prescribed burning is limited by the inability of alkali sagebrush to carry fire and by the hazard of erosion.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

VIs, nonirrigated

## **37—Elksel-Friedman-Starhope complex, 30 to 60 percent slopes**

### **Composition**

Elksel very cobbly loam, 30 to 60 percent slopes—45 percent

Friedman cobbly loam, 30 to 60 percent slopes—20 percent

Starhope very cobbly clay loam, 30 to 60 percent slopes—20 percent

Contrasting inclusions—15 percent

### **Characteristics of the Elksel Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Colluvium and residuum derived from andesite, latite, and basalt

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 10 inches—grayish brown and dark grayish brown very cobbly loam

10 to 17 inches—brown very cobbly clay

17 to 33 inches—yellowish brown extremely cobbly clay

33 to 45 inches—yellowish brown extremely cobbly sandy clay

45 inches—andesite

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Friedman Soil**

*Position on landscape:* North- and east-facing mountainsides

*Parent material:* Colluvium derived from andesite, latite, and welded tuff

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 5 inches—dark brown cobbly loam

5 to 17 inches—dark brown gravelly loam

17 to 24 inches—brown gravelly clay loam

24 to 36 inches—dark yellowish brown very gravelly clay

36 to 47 inches—yellowish brown very gravelly clay loam

47 to 54 inches—brown very gravelly sandy clay loam

54 inches—partially weathered latite

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Moderate

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Starhope Soil**

*Position on landscape:* Eroded areas on south- and west-facing mountainsides

*Parent material:* Residuum derived from andesite, latite, and welded tuff

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

- 0 to 3 inches—grayish brown very cobbly clay loam
- 3 to 19 inches—brown clay loam
- 19 to 22 inches—pale brown gravelly clay loam
- 22 inches—welded tuff

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Winridge clay loam on ridges (5 percent); Starhope loam in gently sloping areas (5 percent); Rock outcrop in convex areas (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

- Elksel soil—mountain big sagebrush, bluebunch wheatgrass; Friedman soil—mountain big sagebrush, Idaho fescue; Starhope soil—low sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope and the hazard of erosion.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.
- Fences and stock water pipelines are limited by the

slope and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **38—Elksel-Peevywell-Furshur complex, 30 to 60 percent slopes**

### **Composition**

Elksel gravelly loam, 30 to 60 percent slopes—35 percent

Peevywell cobbly loam, 30 to 60 percent slopes—30 percent

Furshur very channery loam, 30 to 60 percent slopes—20 percent

Contrasting inclusions—15 percent

### **Characteristics of the Elksel Soil**

*Position on landscape:* Convex areas on mountainsides

*Parent material:* Colluvium over residuum derived from rhyolite and andesite

*Elevation:* 4,700 to 5,600 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 90 days

*Typical profile:*

- 0 to 12 inches—grayish brown and yellowish brown gravelly loam
- 12 to 42 inches—yellowish brown and brownish yellow very gravelly clay and extremely gravelly clay
- 42 to 54 inches—white duripan
- 54 inches—fractured andesite

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 40 to 50 inches

*Restriction affecting rooting depth:* Duripan at a depth of 42 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Peevywell Soil**

*Position on landscape:* Concave areas on mountainsides

*Parent material:* Colluvium and alluvium derived from rhyolite and andesite

*Elevation:* 4,700 to 5,600 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 90 days



*Typical profile:*

- 0 to 5 inches—brown and yellowish brown cobbly loam
- 5 to 13 inches—yellowish brown gravelly clay loam
- 13 to 31 inches—yellowish brown and brown gravelly clay
- 31 to 40 inches—reddish yellow, indurated duripan
- 40 inches—weathered andesite

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 24 to 35 inches

*Restriction affecting rooting depth:* Duripan at a depth of 31 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Furshur Soil**

*Position on landscape:* Undulating convex areas on mountainsides

*Parent material:* Residuum and slope alluvium derived from rhyolite

*Elevation:* 4,700 to 5,600 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 90 days

*Typical profile:*

- 0 to 2 inches—dark grayish brown very channery loam
- 2 to 5 inches—brown clay loam
- 5 to 15 inches—yellowish brown and brownish yellow clay and gravelly clay
- 15 to 20 inches—very pale brown duripan
- 20 inches—fractured, layered rhyolitic bedrock that has lime and silica in the fractures

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Very low

*Potential rooting depth:* 14 to 20 inches

*Restriction affecting rooting depth:* Duripan at a depth of 15 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Smelter loam in gently sloping areas (5 percent); Friedman cobbly loam on north- and east-facing slopes (5 percent); Rock outcrop on ridges (5 percent)

## **Major Use**

### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Elksel and Peevywell soils—Wyoming big sagebrush, bluebunch wheatgrass; Furshur soil—low sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope and by the inability of low sagebrush to carry fire.
- Fences and stock water pipelines are limited by the slope and by the depth to bedrock in the Furshur soil.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **39—Elksel-Starhope-Rock outcrop complex, 30 to 60 percent slopes**

### **Composition**

Elksel very cobbly loam, 30 to 60 percent slopes—45 percent

Starhope very cobbly clay loam, 30 to 60 percent slopes—25 percent

Rock outcrop—20 percent

Contrasting inclusions—10 percent

### **Characteristics of the Elksel Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Colluvium and residuum derived from andesite, latite, and basalt

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

- 0 to 10 inches—grayish brown and dark grayish brown very cobbly loam
- 10 to 17 inches—brown very cobbly clay
- 17 to 33 inches—yellowish brown extremely cobbly clay
- 33 to 45 inches—yellowish brown extremely cobbly sandy clay
- 45 inches—andesite

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Starhope Soil**

*Position on landscape:* Eroded areas on south- and west-facing mountainsides

*Parent material:* Residuum derived from andesite, latite, and welded tuff

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 40 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 3 inches—grayish brown very cobbly clay loam

3 to 19 inches—brown clay loam

19 to 22 inches—pale brown gravelly clay loam

22 inches—welded tuff

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Rock Outcrop**

*Position on landscape:* Ridges

*Kind of material:* Exposed bedrock

### **Contrasting Inclusions**

Friedman cobbly loam on north- and east-facing slopes (5 percent); Starhope loam in gently sloping areas (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Elksel soil—mountain big sagebrush, bluebunch wheatgrass; Starhope soil—low sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.

- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope and the hazard of erosion.

- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

- Fences and stock water pipelines are limited by the slope and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **40—Friedman-Elksel-Winridge complex, 30 to 60 percent slopes**

### **Composition**

Friedman cobbly loam, 30 to 60 percent slopes—40 percent

Elksel very cobbly loam, 30 to 60 percent slopes—25 percent

Winridge clay loam, 30 to 60 percent slopes—20 percent

Contrasting inclusions—15 percent

### **Characteristics of the Friedman Soil**

*Position on landscape:* North- and east-facing mountainsides

*Parent material:* Colluvium derived from andesite, latite, and welded tuff

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 5 inches—dark brown cobbly loam

5 to 17 inches—dark brown gravelly loam

17 to 24 inches—brown gravelly clay loam

24 to 36 inches—dark yellowish brown very gravelly clay

36 to 47 inches—yellowish brown very gravelly clay loam

47 to 54 inches—brown very gravelly sandy clay loam

54 inches—weathered latite

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Moderate

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Elksel Soil**

*Position on landscape:* South- and west-facing mountainsides



*Parent material:* Colluvium and residuum derived from andesite, latite, and basalt

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 10 inches—grayish brown and dark grayish brown very cobbly loam

10 to 17 inches—brown very cobbly clay

17 to 33 inches—yellowish brown extremely cobbly clay

33 to 45 inches—yellowish brown extremely cobbly sandy clay

45 inches—andesite

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### ***Characteristics of the Winridge Soil***

*Position on landscape:* Convex and eroded areas on north- and east-facing mountainsides

*Parent material:* Colluvium and residuum derived from andesite, latite, and welded tuff

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 4 inches—dark grayish brown clay loam

4 to 16 inches—dark grayish brown and brown gravelly clay and clay

16 to 23 inches—olive brown sandy clay loam

23 inches—partially weathered andesite

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### ***Contrasting Inclusions***

Smelter loam in gently sloping areas (5 percent); soils that are similar to the Friedman soil but receive supplemental moisture in the middle part of the profile from springs, support trees, and are on concave north- and east-facing slopes (5 percent);

Rock outcrop on ridges and in convex areas (5 percent)

### ***Major Use***

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Friedman soil—mountain big sagebrush, Idaho fescue; Elksel soil—mountain big sagebrush, bluebunch wheatgrass; Winridge soil—low sagebrush, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope and the hazard of erosion.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.
- Fences and stock water pipelines are limited by the slope and the hazard of erosion.

### ***Capability Classification***

VIIe, nonirrigated

## **41—Gaib-Rock outcrop complex, 30 to 60 percent slopes**

### ***Composition***

Gaib very gravelly loam, 30 to 60 percent slopes—50 percent

Rock outcrop—30 percent

Contrasting inclusions—20 percent

### ***Characteristics of the Gaib Soil***

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Residuum derived from andesite, latite, and basalt

*Elevation:* 5,000 to 7,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 5 inches—brown very gravelly loam

5 to 13 inches—dark yellowish brown very cobbly clay loam

13 inches—basalt

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Very low  
*Potential rooting depth:* 10 to 20 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

**Characteristics of the Rock Outcrop**

*Position on landscape:* Convex areas, ridgetops  
*Kind of material:* Exposed basalt

**Contrasting Inclusions**

Elkcreek loam in concave areas (10 percent); Winu stony loam on north- and east-facing slopes (10 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Gaib soil—mountain big sagebrush, bluebunch wheatgrass  
*General management considerations:*  
• Brush management and proper distribution of livestock are needed.  
• Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope, the hazard of erosion, and the areas of Rock outcrop.  
• Range seeding is not suitable on this unit because of the slope and the hazard of erosion.  
• Fences and stock water pipelines are limited by the slope, the depth to bedrock, the areas of Rock outcrop, and the hazard of erosion.

**Capability Classification**

Vlle, nonirrigated

**42—Gimlett very gravelly sandy loam, 0 to 2 percent slopes**

**Composition**

Gimlett very gravelly sandy loam, 0 to 2 percent slopes—95 percent  
Contrasting inclusions—5 percent

**Characteristics of the Gimlett Soil**

*Position on landscape:* Stream terraces  
*Parent material:* Mixed alluvium  
*Elevation:* 5,300 to 6,000 feet  
*Average annual precipitation:* About 17 inches  
*Average annual air temperature:* About 40 degrees F  
*Frost-free period:* About 65 days

*Typical profile:*  
0 to 3 inches—very dark grayish brown very gravelly sandy loam  
3 to 9 inches—very dark grayish brown very gravelly loam  
9 to 18 inches—dark grayish brown very gravelly loam  
18 to 27 inches—dark brown very gravelly sandy loam  
27 to 33 inches—yellowish brown extremely cobbly sandy loam  
33 to 38 inches—yellowish brown extremely cobbly loamy coarse sand  
38 to 63 inches—brown extremely cobbly coarse sand  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate in the upper 33 inches; very rapid below this depth  
*Available water capacity:* Very low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 27 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* Slight  
*Shrink-swell potential:* Low

**Contrasting Inclusions**

Isknat gravelly clay loam; Little Wood very gravelly loam; Gimlett soils that have a very cobbly loam upper layer

**Major Uses**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Mountain big sagebrush, Idaho fescue (fig. 8)  
*General management considerations:*  
• Brush management, proper distribution of livestock, and range seeding are needed.  
• Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.  
• Drilling is the best suited method of range seeding.

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture  
*General management considerations:*  
• A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.





Figure 8.—Typical area of Gimlett very gravelly sandy loam, 0 to 2 percent slopes. The dominant vegetation is mountain big sagebrush and Idaho fescue.

- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

#### ***Capability Classification***

IVs, irrigated and nonirrigated

### **43—Gooding-Gooding, eroded-Hamrub complex, 2 to 12 percent slopes**

#### ***Composition***

Gooding silt loam, 2 to 12 percent slopes—40 percent  
 Gooding very cobbly clay loam, 2 to 8 percent slopes, eroded—30 percent  
 Hamrub silt loam, 2 to 12 percent slopes—20 percent  
 Contrasting inclusions—10 percent

#### ***Characteristics of the Noneroded Gooding Soil***

*Position on landscape:* Intermounds on basalt plains

*Parent material:* Alluvium over basalt and rhyolite

*Elevation:* 4,600 to 4,800 feet

*Average annual precipitation:* About 12 inches



*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 100 days

*Typical profile:*

- 0 to 9 inches—brown and pale brown silt loam
- 9 to 49 inches—yellowish brown, pale brown, and very pale brown silty clay and silty clay loam
- 49 to 62 inches—very pale brown, weakly cemented duripan
- 62 inches—basalt that has a silica cap

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* High

*Potential rooting depth:* 40 to 60 inches

*Restriction affecting rooting depth:* Duripan at a depth of 49 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

**Characteristics of the Eroded Gooding Soil**

*Position on landscape:* Drainageways on basalt plains

*Parent material:* Alluvium over basalt and rhyolite

*Elevation:* 4,600 to 4,800 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 100 days

*Typical profile:*

- 0 to 2 inches—grayish brown very cobbly clay loam
- 2 to 42 inches—dark brown, dark yellowish brown, pale brown, and light yellowish brown silty clay and silty clay loam
- 42 to 62 inches—very pale brown, weakly cemented duripan
- 62 inches—basalt that has a silica cap

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* High

*Potential rooting depth:* 40 to 60 inches

*Restriction affecting rooting depth:* Duripan at a depth of 42 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

**Characteristics of the Hamrub Soil**

*Position on landscape:* Mounds on basalt plains

*Parent material:* Loess over alluvium

*Elevation:* 4,600 to 4,800 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 100 days

*Typical profile:*

- 0 to 10 inches—brown and yellowish brown silt loam
- 10 to 41 inches—yellowish brown silty clay loam
- 41 to 43 inches—very pale brown silt loam
- 43 to 48 inches—white, indurated duripan
- 48 inches—fractured rhyolitic bedrock

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 40 to 50 inches

*Restriction affecting rooting depth:* Duripan at a depth of 43 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

**Contrasting Inclusions**

Bostrum cobbly silt loam and Gooding very stony clay loam in eroded drainageways (5 percent); Rock outcrop in convex areas (5 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*

- Noneroded Gooding soil and Hamrub soil—Wyoming big sagebrush, bluebunch wheatgrass;
- eroded Gooding soil—alkali sagebrush, bluebunch wheatgrass

*Main limitations:* Hazard of erosion; very cobbly upper layer in the eroded Gooding soil

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Prescribed burning is limited by the inability of alkali sagebrush to carry fire.
- Range seeding is suitable on this unit. Drilling is the best suited method.

**Capability Classification**

VIs, nonirrigated

**44—Goodington silt loam, 2 to 4 percent slopes**

**Composition**

Goodington silt loam, 2 to 4 percent slopes—90 percent  
Contrasting inclusions—10 percent



### ***Characteristics of the Goodington Soil***

*Position on landscape:* Basalt plains

*Parent material:* Loess over residuum derived dominantly from basalt

*Elevation:* 4,800 to 6,200 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 10 inches—dark grayish brown and dark brown silt loam

10 to 26 inches—brown silty clay

26 to 34 inches—brown silty clay loam

34 to 56 inches—light yellowish brown silty clay loam

56 inches—basalt

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* High

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Slow

*Hazard of water erosion:* Moderate

### ***Contrasting Inclusions***

Manard very stony silt loam and Manard silt loam in convex areas (5 percent); soils that are similar to Manard very stony silt loam but are less than 20 inches deep to basalt and are in eroded, convex areas (5 percent)

### ***Major Uses***

*Current uses:* Cropland, hayland, pasture

*Potential use:* Rangeland

### ***Cropland, hayland, and pasture***

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied

to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### ***Rangeland***

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, bluebunch wheatgrass

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### ***Capability Classification***

IIIe, irrigated and nonirrigated

## **45—Goodington-Manard complex, 2 to 8 percent slopes**

### ***Composition***

Goodington silt loam, 2 to 4 percent slopes—45 percent

Manard very stony silt loam, 2 to 8 percent slopes—40 percent

Contrasting inclusions—15 percent

### ***Characteristics of the Goodington Soil***

*Position on landscape:* Concave areas on basalt plains

*Parent material:* Loess over residuum derived dominantly from basalt

*Elevation:* 4,800 to 6,200 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 5 inches—dark grayish brown silt loam

5 to 15 inches—dark brown silt loam

15 to 28 inches—brown silty clay

28 to 38 inches—brown silty clay loam

38 to 46 inches—light yellowish brown silt loam

46 to 48 inches—very pale brown silt loam

48 inches—basalt

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* High

*Potential rooting depth:* 40 to 60 inches

*Restriction affecting rooting depth:* Bedrock at a depth of 48 inches

Runoff: Slow  
Hazard of water erosion: Moderate

**Characteristics of the Manard Soil**

*Position on landscape:* Convex areas on basalt plains  
*Parent material:* Residuum derived from basalt  
*Elevation:* 4,800 to 6,200 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
0 to 11 inches—dark grayish brown very stony silt loam  
11 to 20 inches—brown silty clay  
20 to 26 inches—brown clay  
26 to 28 inches—very pale brown, indurated duripan  
28 inches—basalt  
*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Very slow  
*Available water capacity:* Low  
*Potential rooting depth:* 20 to 37 inches  
*Restriction affecting rooting depth:* Duripan at a depth of 26 inches  
*Runoff:* Slow or medium  
*Hazard of water erosion:* Slight or moderate

**Contrasting Inclusions**

Manard silt loam in gently sloping areas (5 percent); soils that are similar to the Manard soil but are 10 to 20 inches deep to bedrock and are in eroded, convex areas (5 percent); Rock outcrop in convex areas (5 percent)

**Major Uses**

**Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa, pasture  
*General management considerations:*  
• Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.  
• Because of the hazard of erosion, sprinkler irrigation is best suited to this unit.  
• Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Rangeland  
(Goodington Soil)**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, bluebunch wheatgrass  
*Main limitation:* Hazard of erosion  
*General management considerations:*  
• Brush management, proper distribution of livestock, and range seeding are needed.  
• Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.  
• Range seeding is suitable on this soil. Drilling is the best suited method.

**(Manard Soil)**

*Dominant vegetation in potential natural plant community:*  
Alkali sagebrush, Idaho fescue  
*General management considerations:*  
• Brush management, proper distribution of livestock, and range seeding are needed.  
• Suitable methods of brush management are chemical spraying and mechanical treatment. Prescribed burning is limited by the inability of alkali sagebrush to carry fire.  
• Range seeding is not suitable on this soil because of the stoniness of the upper layer and the hazard of erosion.

**Capability Classification**

VIs, nonirrigated

**46—Hapur silt loam, 0 to 2 percent slopes**

**Composition**

Hapur silt loam, 0 to 2 percent slopes—85 percent  
Contrasting inclusions—15 percent

**Characteristics of the Hapur Soil**

*Position on landscape:* Flood plains  
*Parent material:* Silty alluvium  
*Elevation:* 4,700 to 5,500 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 42 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
0 to 3 inches—gray silt loam  
3 to 15 inches—gray silty clay loam  
15 to 30 inches—light gray clay loam  
30 to 44 inches—light gray fine sandy loam  
44 to 51 inches—light gray loamy fine sand  
51 to 63 inches—light gray very gravelly loamy sand  
*Depth class:* Very deep  
*Drainage class:* Poorly drained  
*Permeability:* Moderately slow



*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Restrictions affecting rooting depth:* Loose sand and gravel at a depth of 51 inches; water table at a depth of 6 to 12 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* None  
*Depth to water table:* 6 to 12 inches  
*Frequency of flooding:* Frequent

### **Contrasting Inclusions**

Bruneel loam and Picabo silt loam in the higher lying areas (10 percent); Bickett mucky peat in the lower lying areas (5 percent)

### **Major Uses**

#### **Hayland and pasture**

*Dominant vegetation in potential natural plant community:*

Tufted hairgrass, sedges, rushes, shrubby cinquefoil

*Currently grown nonirrigated crops:* Grass-legume hay, pasture

*General management considerations:*

- Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- Wetness limits the choice of plants and the production of deep-rooted crops.
- Plants that can tolerate wetness are suitable for seeding.
- Providing drainage is difficult because most areas have poor outlets and are subject to seasonal flooding.
- Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

### **Capability Classification**

Vw, nonirrigated

## **47—Hapur-Bickett complex, 0 to 2 percent slopes**

### **Composition**

Hapur silt loam, 0 to 2 percent slopes—55 percent  
 Bickett mucky peat, 0 to 2 percent slopes—35 percent  
 Contrasting inclusions—10 percent

### **Characteristics of the Hapur Soil**

*Position on landscape:* Flood plains  
*Parent material:* Silty alluvium  
*Elevation:* 4,700 to 5,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 3 inches—gray silt loam  
 3 to 15 inches—gray silty clay loam  
 15 to 30 inches—light gray clay loam  
 30 to 44 inches—light gray fine sandy loam  
 44 to 51 inches—light gray loamy fine sand  
 51 to 63 inches—light gray very gravelly loamy sand

*Depth class:* Very deep

*Drainage class:* Poorly drained

*Permeability:* Moderately slow

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Restrictions affecting rooting depth:* Loose sand and gravel at a depth of 51 inches; water table at a depth of 6 to 12 inches

*Runoff:* Very slow

*Hazard of water erosion:* None

*Depth to water table:* 6 to 12 inches

*Frequency of flooding:* Frequent

### **Characteristics of the Bickett Soil**

*Position on landscape:* Flood plains

*Parent material:* Material derived from herbaceous plants over silty alluvium

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 6 inches—black mucky peat  
 6 to 11 inches—black muck  
 11 to 40 inches—light brownish gray silty clay loam  
 40 to 61 inches—dark gray loam

*Depth class:* Very deep

*Drainage class:* Very poorly drained

*Permeability:* Moderately slow

*Available water capacity:* Very high

*Potential rooting depth:* 60 inches or more for water-tolerant plants

*Runoff:* Pondered

*Hazard of water erosion:* None

*Water table:* 6 inches above the surface to 6 inches below

*Frequency of flooding:* Frequent

### **Contrasting Inclusions**

Soils that are similar to the Hapur soil but are calcareous throughout and are in the lower lying areas (10 percent)

**Major Uses**

**Hayland and pasture  
(Hapur Soil)**

*Dominant vegetation in potential natural plant community:*

Tufted hairgrass, sedges, rushes, shrubby cinquefoil

*Currently grown nonirrigated crops:* Grass-legume hay, pasture

*General management considerations:*

- Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- Wetness limits the choice of plants and the production of deep-rooted crops.
- Providing drainage is difficult because most areas have poor outlets and are subject to seasonal flooding.
- Plants that can tolerate wetness are suitable for seeding.
- Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

**Wetland wildlife habitat  
(Bickett Soil)**

*Dominant vegetation in potential natural plant community:*

Rushes, sedges, cattails, other wetland herbaceous plants

*General management considerations:*

- This soil provides open, marshy or swampy, shallow water areas that should be maintained in their natural state.
- Wildlife attracted to areas of this soil include ducks, geese, sandhill cranes, shore birds, muskrat, beaver, and songbirds.

**Capability Classification**

Vw, nonirrigated

**48—Hapur-Picabo silt loams, 0 to 2 percent slopes**

**Composition**

Hapur silt loam, 0 to 2 percent slopes—50 percent  
Picabo silt loam, 0 to 2 percent slopes—40 percent  
Contrasting inclusions—10 percent

**Characteristics of the Hapur Soil**

*Position on landscape:* Depressions on flood plains

*Parent material:* Silty alluvium

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 3 inches—gray silt loam

3 to 15 inches—gray silty clay loam

15 to 30 inches—light gray clay loam

30 to 44 inches—light gray fine sandy loam

44 to 51 inches—light gray loamy fine sand

51 to 63 inches—light gray very gravelly loamy sand

*Depth class:* Very deep

*Drainage class:* Poorly drained

*Permeability:* Moderately slow

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Restrictions affecting rooting depth:* Loose sand and gravel at a depth of 51 inches; water table at a depth of 6 to 12 inches

*Runoff:* Very slow

*Hazard of water erosion:* None

*Depth to water table:* 6 to 12 inches

*Frequency of flooding:* Frequent

**Characteristics of the Picabo Soil**

*Position on landscape:* Convex areas on stream terraces

*Parent material:* Silty alluvium

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 9 inches—grayish brown silt loam

9 to 16 inches—light brownish gray silt loam

16 to 23 inches—light gray loam

23 to 39 inches—light gray silt loam

39 to 51 inches—white gravelly silt loam

51 to 53 inches—white silt loam

53 to 55 inches—gray silt loam

55 to 61 inches—gray very fine sandy loam

61 to 72 inches—dark gray extremely gravelly loamy sand

*Depth class:* Very deep

*Drainage class:* Somewhat poorly drained

*Permeability:* Moderate

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Restrictions affecting rooting depth:* Water table at a depth of 24 to 48 inches; lime nodules at a depth of 36 to 50 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Depth to water table:* 24 to 48 inches

*Frequency of flooding:* Occasional



### ***Contrasting Inclusions***

Bickett mucky peat in the lower lying areas (5 percent);  
Picabo gravelly loam (5 percent)

### ***Major Uses***

#### **Hayland and pasture (Hapur Soil)**

*Dominant vegetation in potential natural plant community:*

Tufted hairgrass, sedges, rushes

*Currently grown nonirrigated crops:* Grass-legume hay, pasture

*General management considerations:*

- Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- Wetness limits the choice of plants and the production of deep-rooted crops.
- Providing drainage is difficult because most areas have poor outlets and are subject to seasonal flooding.
- Plants that can tolerate wetness are suitable for planting.
- Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

#### **(Picabo Soil)**

*Dominant vegetation in potential natural plant community:*

Shrubby cinquefoil, sedges, tufted hairgrass

*Currently grown nonirrigated crops:* Grass-legume hay, pasture

*General management considerations:*

- Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- Supplemental irrigation may be needed during the growing season to ensure adequate moisture for crop production. The best suited method is a sprinkler system.
- Plants that can tolerate a fluctuating water table and seasonal wetness are suitable for planting.
- Grazing should be deferred until the water table lowers and the soil is firm.

#### **Cropland**

#### **(Picabo Soil)**

*Currently grown nonirrigated crops:* Wheat, barley, oats

*General management considerations:*

- Providing drainage is difficult because most areas have poor outlets and are subject to seasonal flooding.
- A suitable cropping system, crop residue management, and applications of fertilizer help to minimize the risk of erosion.
- Supplemental irrigation may be needed during the

growing season to ensure adequate moisture for crop production.

- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### ***Capability Classification***

Vw, nonirrigated

## **49—Hutton clay loam, 0 to 2 percent slopes**

### ***Composition***

Hutton clay loam, 0 to 2 percent slopes—90 percent  
Contrasting inclusions—10 percent

### ***Characteristics of the Hutton Soil***

*Position on landscape:* Flood plains

*Parent material:* Mixed alluvium

*Elevation:* 4,700 to 5,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 19 inches—dark gray clay loam

19 to 62 inches—gray clay

*Depth class:* Very deep

*Drainage class:* Poorly drained

*Permeability:* Very slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Water table at a depth of 12 to 30 inches

*Runoff:* Very slow

*Hazard of water erosion:* None

*Depth to water table:* 12 to 30 inches

*Frequency of flooding:* Frequent

### ***Contrasting Inclusions***

Carey Lake loam in the steeper areas (5 percent);  
Marshdale loam in drainageways and depressions (5 percent)

### ***Major Uses***

#### **Hayland and pasture**

*Dominant vegetation in potential natural plant community:*

Tufted hairgrass, sedges, rushes, willow

*Currently grown nonirrigated crops:* Pasture, grass-legume hay

*General management considerations:*

- Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- Wetness limits the choice of plants and the period of cutting or grazing and increases the risk of winterkill.
- Plants that can tolerate wetness are suitable for planting.
- Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

### **Capability Classification**

IVw, irrigated and nonirrigated

## **50—Hutton Variant clay loam, 0 to 2 percent slopes**

### **Composition**

Hutton Variant clay loam, 0 to 2 percent slopes—90 percent

Contrasting inclusions—10 percent

### **Characteristics of the Hutton Variant Soil**

*Position on landscape:* Stream terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,950 to 6,000 feet

*Average annual precipitation:* About 16 inches

*Average annual air temperature:* About 40 degrees F

*Frost-free period:* About 65 days

*Typical profile:*

- 0 to 8 inches—very dark gray clay loam
- 8 to 13 inches—dark gray clay
- 13 to 17 inches—dark grayish brown clay
- 17 to 24 inches—grayish brown gravelly clay
- 24 to 39 inches—grayish brown very gravelly sandy clay loam
- 39 to 52 inches—brown extremely gravelly sandy loam
- 52 to 66 inches—multicolored extremely gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Very slow in the upper 39 inches; very rapid below this depth

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 39 inches

*Runoff:* Slow

*Hazard of water erosion:* Slight

*Shrink-swell potential:* High

### **Contrasting Inclusions**

Soils that are similar to the Hutton Variant soil but have 35 to 60 percent coarse fragments between depths of 2 and 35 inches (10 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Border and corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

III<sub>s</sub>, irrigated and nonirrigated

## **51—Isknot gravelly clay loam, 0 to 2 percent slopes**

### **Composition**

Isknot gravelly clay loam, 0 to 2 percent slopes—95 percent

Contrasting inclusions—5 percent

### **Characteristics of the Isknot Soil**

*Position on landscape:* Stream terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,950 to 6,100 feet

*Average annual precipitation:* About 16 inches

*Average annual air temperature:* About 40 degrees F

*Frost-free period:* About 65 days

*Typical profile:*

- 0 to 11 inches—very dark gray and very dark grayish brown gravelly clay loam
- 11 to 26 inches—dark grayish brown very gravelly clay loam and very gravelly sandy clay loam



26 to 35 inches—brown very gravelly sandy clay loam

35 to 61 inches—brown and pale brown extremely gravelly sandy loam and extremely gravelly loamy sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Slow in the upper 35 inches; rapid or very rapid below this depth

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 35 inches

*Runoff:* Slow

*Hazard of water erosion:* Slight

*Shrink-swell potential:* Moderate

### **Contrasting Inclusions**

Hutton Variant clay loam (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Border and corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

III<sub>s</sub>, irrigated and nonirrigated

## **52—Justesen loam, 2 to 4 percent slopes**

### **Composition**

Justesen loam, 2 to 4 percent slopes—90 percent

Contrasting inclusions—10 percent

### **Characteristics of the Justesen Soil**

*Position on landscape:* Fan terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 2 inches—brown loam

2 to 7 inches—yellowish brown loam

7 to 15 inches—brown clay loam

15 to 24 inches—pale brown loam

24 to 42 inches—light brownish gray and light gray loam

42 to 62 inches—white fine sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow

*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

Manard silt loam in convex areas (5 percent);

Goodington silt loam in depressions (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

III<sub>e</sub>, irrigated; III<sub>c</sub>, nonirrigated

**53—Justesen loam, 4 to 8 percent slopes****Composition**

Justesen loam, 4 to 8 percent slopes—90 percent  
Contrasting inclusions—10 percent

**Characteristics of the Justesen Soil**

*Position on landscape:* Fan terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 2 inches—brown loam

2 to 7 inches—yellowish brown loam

7 to 15 inches—brown clay loam

15 to 24 inches—pale brown loam

24 to 42 inches—light brownish gray and light gray loam

42 to 62 inches—white fine sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Medium

*Hazard of water erosion:* Moderate

**Contrasting Inclusions**

Goodington silt loam in depressions (5 percent);

Bringmee loam along stream terraces (5 percent)

**Major Uses****Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.

- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.

- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent

overirrigating and the leaching of plant nutrients.

**Rangeland**

*Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*Main limitations:* Hazard of erosion, slope

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

**Capability Classification**

IIIe, irrigated and nonirrigated

**54—Justesen loam, 8 to 12 percent slopes****Composition**

Justesen loam, 8 to 12 percent slopes—90 percent  
Contrasting inclusions—10 percent

**Characteristics of the Justesen Soil**

*Position on landscape:* Fan terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 14 inches—very dark grayish brown loam

14 to 25 inches—pale brown clay loam

25 to 31 inches—very pale brown silty clay loam

31 to 64 inches—white loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Rapid

*Hazard of water erosion:* Severe

**Contrasting Inclusions**

Goodington silt loam in depressions (5 percent);

Elkcreek loam on toe slopes (5 percent)

**Major Uses****Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture



*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Rangeland***Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*Main limitations:* Hazard of erosion, slope*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

**Capability Classification**

IVe, irrigated; IIle, nonirrigated

**55—Justesen loam, 12 to 30 percent slopes****Composition**

Justesen loam, 12 to 30 percent slopes—85 percent  
Contrasting inclusions—15 percent

**Characteristics of the Justesen Soil**

*Position on landscape:* Fan terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

- 0 to 14 inches—very dark grayish brown loam
- 14 to 25 inches—pale brown clay loam
- 25 to 31 inches—very pale brown silty clay loam
- 31 to 64 inches—white loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

**Contrasting Inclusions**

Elkcreek loam on toe slopes (10 percent); Winu stony loam on toe slopes (5 percent)

**Major Use****Rangeland***Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*Main limitations:* Hazard of erosion, slope*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

**Capability Classification**

IVe, irrigated and nonirrigated

**56—Ketchum-Dollarhide complex, 30 to 60 percent slopes****Composition**

Ketchum very gravelly loam, 30 to 60 percent slopes—55 percent

Dollarhide very gravelly fine sandy loam, 30 to 60 percent slopes—30 percent

Contrasting inclusions—15 percent

**Characteristics of the Ketchum Soil**

*Position on landscape:* North- and east-facing mountainsides

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 6,000 to 8,500 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 38 degrees F

*Frost-free period:* Less than 60 days

*Organic layer on surface:* Forest litter 2 inches thick

*Typical profile:*

- 0 to 3 inches—brown very gravelly loam
- 3 to 32 inches—pale brown and light gray very gravelly fine sandy loam

32 to 48 inches—light yellowish brown and very pale brown very gravelly sandy loam

48 to 61 inches—light gray extremely gravelly coarse sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Dollarhide Soil**

*Position on landscape:* Ridges

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 6,000 to 8,500 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 7 inches—brown very gravelly fine sandy loam

7 to 13 inches—yellowish brown extremely cobbly fine sandy loam

13 inches—fractured quartzite

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Povey gravelly loam on open north- and east-facing slopes (10 percent); Rock outcrop on ridges (5 percent)

### **Major Uses**

#### **Woodland**

##### **(Ketchum Soil)**

*Dominant vegetation in potential natural plant community:*

Douglas fir, mountain snowberry

*Average site index for Douglas fir (50-year site curve):* 50

*Maximum average annual growth for Douglas fir:* 68

cubic feet per acre from a stand of trees 45 years old

*Main limitations:* Hazard of erosion, slope, low available water capacity, hazard of windthrow

#### **Grazable understory**

##### **(Ketchum Soil)**

*Common forest understory plants:* Elk sedge, heartleaf

arnica, pine reedgrass, mountain snowberry

#### *General management considerations:*

- Where the canopy cover is more than 40 percent, the understory is sparse and has low value as forage.

Where the canopy is less dense, the understory provides good forage.

- Forage production can be increased by seeding disturbed areas to suitable plants and deferring grazing until seedlings are well established.

#### **Rangeland**

##### **(Dollarhide Soil)**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

#### *General management considerations:*

- Brush management and proper distribution of livestock are needed.

- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope and the hazard of erosion.

- Range seeding is not suitable on this soil because of the slope, the very low available water capacity, and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **57—Ketchum-Povey complex, 30 to 60 percent slopes**

### **Composition**

Ketchum very gravelly loam, 30 to 60 percent slopes—50 percent

Povey gravelly loam, 30 to 60 percent slopes—30 percent

Contrasting inclusions—20 percent

### **Characteristics of the Ketchum Soil**

*Position on landscape:* North- and east-facing mountainsides

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 6,000 to 8,500 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 38 degrees F

*Frost-free period:* Less than 60 days

*Organic layer on surface:* Forest litter 2 inches thick

*Typical profile:*

0 to 3 inches—brown very gravelly loam

3 to 32 inches—pale brown and light gray very gravelly fine sandy loam



- 32 to 42 inches—very pale brown very gravelly sandy loam  
 42 to 48 inches—light yellowish brown very gravelly sandy loam  
 48 to 61 inches—light gray extremely gravelly coarse sandy loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Povey Soil**

*Position on landscape:* Open areas on north- and east-facing mountainsides

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 6,000 to 8,500 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 38 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

- 0 to 4 inches—dark grayish brown and brown gravelly loam  
 4 to 25 inches—brown very gravelly loam  
 25 to 50 inches—brown extremely cobbly loam  
 50 inches—quartzitic sandstone

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Dollarhide very gravelly fine sandy loam on ridges (10 percent); Vitale very gravelly loam on south- and west-facing slopes (5 percent); Rock outcrop on ridges (5 percent)

### **Major Uses**

#### **Woodland**

##### **(Ketchum soil)**

*Dominant vegetation in potential natural plant community:*

Douglas fir, mountain snowberry

*Average site index for Douglas fir (50-year site curve):* 50

*Maximum average annual growth for Douglas fir:* 68 cubic feet per acre from a stand of trees 45 years old

*Main limitations:* Hazard of erosion, slope, low available water capacity, hazard of windthrow

#### **Grazable understory**

##### **(Ketchum soil)**

*Common forest understory plants:* Elk sedge, heartleaf arnica, pine reedgrass, mountain snowberry

*General management considerations:*

- Where the canopy cover is more than 40 percent, the understory is sparse and has low value as forage. Where the overstory is less dense, the understory provides good forage.
- Forage production can be increased by seeding disturbed areas to suitable plants and deferring grazing until seedlings are well established.

#### **Rangeland**

##### **(Povey soil)**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, mountain snowberry, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope and the hazard of erosion.
- Range seeding is not suitable on this soil because of the slope, the low available water capacity, and the hazard of erosion.
- Fences and stock water pipelines are limited by the slope.

### **Capability Classification**

VIIe, nonirrigated

### **58—Laurentzen-Mulshoe complex, 4 to 30 percent slopes**

#### **Composition**

Laurentzen silt loam, 4 to 12 percent slopes—50 percent

Mulshoe very stony loam, 4 to 30 percent slopes—30 percent

Contrasting inclusions—20 percent

#### **Characteristics of the Laurentzen Soil**

*Position on landscape:* Depressions and swales on foothills

*Parent material:* Alluvium derived from basalt

*Elevation:* 5,000 to 6,000 feet

*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*

- 0 to 13 inches—dark brown silt loam
- 13 to 26 inches—dark brown clay loam
- 26 to 63 inches—yellowish brown clay loam
- 63 inches—basalt

*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Runoff:* Medium or rapid  
*Hazard of water erosion:* Moderate or severe

**Characteristics of the Mulshoe Soil**

*Position on landscape:* Concave areas on foothills  
*Parent material:* Residuum and colluvium derived from basalt  
*Elevation:* 5,000 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*

- 0 to 10 inches—brown very stony loam
- 10 to 23 inches—yellowish brown very stony clay loam
- 23 to 28 inches—very pale brown, weathered basalt that has yellowish brown clay loam in the cracks
- 28 inches—hard basalt

*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* Very low  
*Potential rooting depth:* 20 to 40 inches  
*Runoff:* Rapid or very rapid  
*Hazard of water erosion:* Severe or very severe

**Contrasting Inclusions**

Elkcreek loam on concave side slopes (10 percent);  
Polecreek very stony loam in eroded areas (5 percent); Rock outcrop on all aspects (5 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Mountain big sagebrush, Idaho fescue  
*Main limitations:* Very stony loam upper layer in the Mulshoe soil, hazard of erosion  
*General management considerations:*  
• Brush management, proper distribution of livestock,

and range seeding are needed.  
• Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the very stony loam upper layer in the Mulshoe soil.  
• Range seeding is suitable on the Laurentzen soil. Drilling is the best suited method.

**Capability Classification**

VIs, nonirrigated

**59—Lava flows**

*Location in survey area:* Craters of the Moon National Monument  
*Slope range:* 2 to 15 percent  
*Kind of material:* Barren basalt associated with recent volcanic activity  
*Common features:* Pressure ridges, fissures, sinkholes  
*Major use:* Wildlife habitat for small rodents, rabbits, marmots, bobcats, sage grouse, hawks, and falcons  
*Capability classification:* VIIIs, nonirrigated

**60—Lava flows-Cinderhurst complex, 2 to 15 percent slopes**

**Composition**

Lava flows—75 percent  
Cinderhurst extremely cobbly silt loam, 2 to 15 percent slopes—20 percent  
Contrasting inclusions—5 percent

**Characteristics of the Lava Flows**

*Location in survey area:* Craters of the Moon National Monument  
*Kind of material:* Barren basalt associated with recent volcanic activity  
*Common features:* Pressure ridges, fissures, sinkholes

**Characteristics of the Cinderhurst Soil**

*Position on landscape:* Depressions on basalt plains  
*Parent material:* Volcanic tephra  
*Elevation:* 4,800 to 6,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 42 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*

- 0 to 3 inches—brown extremely cobbly silt loam
- 3 to 8 inches—yellowish brown very cobbly silt loam
- 8 inches—basalt that has vertical fractures 2 to 5 centimeters wide



*Depth class:* Very shallow  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Very low  
*Potential rooting depth:* 4 to 10 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

Soils that are similar to the Cinderhurst soil but are 20 to 40 inches deep (5 percent)

### **Major Use**

#### **Wildlife habitat**

*Dominant vegetation in potential natural plant community:*  
 Big sagebrush, lava fernbush, antelope bitterbrush, Nevada bluegrass (fig. 9)  
*Common wildlife species:* Small rodents, rabbits, marmots, bobcats, sage grouse, hawks, falcons

### **Capability Classification**

VIIIs, nonirrigated

## **61—Lavacreek-Dollarhide very gravelly silt loams, 30 to 60 percent slopes**

### **Composition**

Lavacreek very gravelly silt loam, 30 to 60 percent slopes—65 percent  
 Dollarhide very gravelly silt loam, 30 to 60 percent slopes—20 percent  
 Contrasting inclusions—15 percent

### **Characteristics of the Lavacreek Soil**

*Position on landscape:* North- and east-facing mountainsides  
*Parent material:* Volcanic-tephra-influenced colluvium derived dominantly from quartzitic sandstone and related rock  
*Elevation:* 5,500 to 8,500 feet  
*Average annual precipitation:* About 20 inches  
*Average annual air temperature:* About 39 degrees F  
*Frost-free period:* Less than 60 days  
*Typical profile:*

0 to 4 inches—dark brown very gravelly silt loam  
 4 to 23 inches—brown very gravelly silt loam  
 23 to 36 inches—dark yellowish brown very cobbly loam  
 36 to 41 inches—yellowish brown extremely cobbly loam  
 41 to 49 inches—very pale brown extremely cobbly sandy loam

49 inches—fractured quartzitic sandstone  
*Depth class:* Deep  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Low  
*Potential rooting depth:* 40 to 60 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

### **Characteristics of the Dollarhide Soil**

*Position on landscape:* Ridges on mountainsides  
*Parent material:* Volcanic-tephra-influenced colluvium derived from quartzitic sandstone and conglomerate  
*Elevation:* 5,500 to 8,500 feet  
*Average annual precipitation:* About 20 inches  
*Average annual air temperature:* About 39 degrees F  
*Frost-free period:* Less than 60 days  
*Typical profile:*  
 0 to 7 inches—brown very gravelly silt loam  
 7 to 11 inches—light yellowish brown very gravelly silt loam  
 11 to 16 inches—yellowish brown extremely cobbly loam  
 16 inches—quartzitic sandstone

*Depth class:* Shallow  
*Drainage class:* Well drained  
*Permeability:* Moderately rapid  
*Available water capacity:* Very low  
*Potential rooting depth:* 10 to 20 inches  
*Restriction affecting rooting depth:* Bedrock at a depth of 16 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Ketchum very gravelly loam on forested north- and east-facing slopes (5 percent); Vitale very gravelly loam on south- and west-facing slopes (5 percent); Rock outcrop (5 percent) in concave areas

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*  
 Lavacreek soil—mountain big sagebrush, Idaho fescue; Dollarhide soil—hot springs sagebrush, Idaho fescue  
*General management considerations:*  
 • Brush management and proper distribution of livestock are needed.  
 • Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.





Figure 9.—Typical area of Lava flows-Cinderhurst complex, 2 to 15 percent slopes.

- Fences and stock water pipelines are limited by the slope and by the depth to bedrock in the Dollarhide soil.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

### ***Capability Classification***

VIIe, nonirrigated

### **62—Lavacreek-Dollarhide very gravelly silt loams, cold, 15 to 60 percent slopes**

#### ***Composition***

Lavacreek very gravelly silt loam, cold, 15 to 60 percent slopes—65 percent  
 Dollarhide very gravelly silt loam, cold, 15 to 60 percent slopes—25 percent  
 Contrasting inclusions—10 percent

### ***Characteristics of the Lavacreek Soil***

*Position on landscape:* North- and east-facing mountainsides

*Parent material:* Volcanic-tephra-influenced colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 7,000 to 9,250 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* About 30 days

*Typical profile:*

0 to 9 inches—grayish brown very gravelly silt loam  
 9 to 18 inches—brown very gravelly silt loam  
 18 to 38 inches—yellowish brown very gravelly loam  
 38 to 43 inches—very pale brown extremely cobbly sandy loam  
 43 inches—fractured quartzitic sandstone



*Depth class:* Deep  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Low  
*Potential rooting depth:* 40 to 60 inches  
*Runoff:* Medium to very rapid  
*Hazard of water erosion:* Severe or very severe

### **Characteristics of the Dollarhide Soil**

*Position on landscape:* Ridges  
*Parent material:* Volcanic-tephra-influenced colluvium derived dominantly from quartzitic sandstone and conglomerate  
*Elevation:* 7,000 to 9,250 feet  
*Average annual precipitation:* About 20 inches  
*Average annual air temperature:* About 39 degrees F  
*Frost-free period:* About 30 days  
*Typical profile:*  
 0 to 7 inches—brown very gravelly silt loam  
 7 to 11 inches—light yellowish brown very gravelly silt loam  
 11 to 16 inches—yellowish brown extremely cobbly loam  
 16 inches—quartzitic sandstone  
*Depth class:* Shallow  
*Drainage class:* Well drained  
*Permeability:* Moderately rapid  
*Available water capacity:* Very low  
*Potential rooting depth:* 10 to 20 inches  
*Restriction affecting rooting depth:* Bedrock at a depth of 16 inches  
*Runoff:* Medium to very rapid  
*Hazard of water erosion:* Severe or very severe

### **Contrasting Inclusions**

Blackspar very cobbly loam on south- and west-facing slopes (5 percent); Vitale very gravelly loam on south- and west-facing slopes (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*  
 Lavacreek soil—subalpine big sagebrush, Idaho fescue; Dollarhide soil—hot springs sagebrush, Idaho fescue  
*Main limitation:* Hazard of erosion  
*General management considerations:*  
 • Brush management, proper distribution of livestock, and range seeding are needed.  
 • Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. In areas that have slopes of more than 30

percent, however, brush control is limited to chemical spraying.

- Range seeding is suitable in areas that have slopes of less than 30 percent. Drilling is the best suited method.
- Fences and stock water pipelines are limited by the slope, the depth to bedrock in the Dollarhide soil, and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **63—Lavacreek-Vitale association, 30 to 60 percent slopes**

### **Composition**

Lavacreek very gravelly silt loam, 30 to 60 percent slopes—45 percent  
 Vitale very gravelly loam, 30 to 60 percent slopes—35 percent  
 Contrasting inclusions—20 percent

### **Characteristics of the Lavacreek Soil**

*Position on landscape:* North- and east-facing mountainsides at elevations below 7,500 feet; all aspects of mountainsides at elevations above 7,500 feet  
*Parent material:* Volcanic-tephra-influenced colluvium derived dominantly from quartzitic sandstone and related rock  
*Elevation:* 5,300 to 9,000 feet  
*Average annual precipitation:* About 20 inches  
*Average annual air temperature:* About 38 degrees F  
*Frost-free period:* Less than 60 days  
*Typical profile:*  
 0 to 4 inches—dark brown very gravelly silt loam  
 4 to 23 inches—brown very gravelly silt loam  
 23 to 36 inches—dark yellowish brown very cobbly loam  
 36 to 41 inches—yellowish brown extremely cobbly loam  
 41 to 49 inches—very pale brown extremely cobbly sandy loam  
 49 inches—fractured quartzitic sandstone

*Depth class:* Deep  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Low  
*Potential rooting depth:* 40 to 60 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

**Characteristics of the Vitale Soil**

*Position on landscape:* South- and west-facing mountainsides  
*Parent material:* Residuum and colluvium derived dominantly from quartzitic sandstone and related rock  
*Elevation:* 5,300 to 9,000 feet  
*Average annual precipitation:* About 16 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
    0 to 6 inches—dark grayish brown very gravelly loam  
    6 to 15 inches—brown very gravelly clay loam  
    15 to 23 inches—light brownish gray very gravelly loam  
    23 inches—quartzitic sandstone  
*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Low  
*Potential rooting depth:* 20 to 40 inches  
*Restriction affecting rooting depth:* Bedrock at a depth of 23 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

**Contrasting Inclusions**

Dollarhide very gravelly silt loam on north- and east-facing slopes (10 percent); Blackspar very cobbly loam on south- and west-facing slopes (5 percent); Rock outcrop on ridges (5 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
    Lavacreek soil—mountain big sagebrush, Idaho fescue; Vitale soil—mountain big sagebrush, bluebunch wheatgrass  
*General management considerations:*  
• Brush management and proper distribution of livestock are needed.  
• Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.  
• Range seeding is not suitable on this unit because of the slope and the hazard of erosion.  
• Fences and stock water pipelines are limited by the slope and by the depth to bedrock in the Vitale soil.

**Capability Classification**

Vlle, nonirrigated

**64—Little Wood gravelly loam, 0 to 2 percent slopes**

**Composition**

Little Wood gravelly loam, 0 to 2 percent slopes—90 percent  
Contrasting inclusions—10 percent

**Characteristics of the Little Wood Soil**

*Position on landscape:* Stream terraces  
*Parent material:* Mixed alluvium  
*Elevation:* 4,700 to 5,300 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 80 days  
*Typical profile:*  
    0 to 8 inches—dark brown gravelly loam  
    8 to 13 inches—brown gravelly loam  
    13 to 26 inches—brown and yellowish brown very gravelly sandy clay loam  
    26 to 32 inches—yellowish brown extremely gravelly coarse sandy loam  
    32 to 42 inches—brown extremely gravelly loamy coarse sand  
    42 to 61 inches—pale brown extremely gravelly coarse sand  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate in the upper 26 inches; rapid or very rapid below this depth  
*Available water capacity:* Low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 32 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* Slight  
*Shrink-swell potential:* Moderate

**Contrasting Inclusions**

Bringmee loam in concave areas (5 percent); Bruneel loam in drainageways (5 percent)

**Major Uses**

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture  
*General management considerations:*  
• A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.  
• Proper grazing practices, irrigation water management, seeding of suitable forage plants, and



applications of fertilizer improve the quality of forage on pastures.

- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IIIc, irrigated and nonirrigated

## **65—Little Wood gravelly loam, 2 to 4 percent slopes**

### **Composition**

Little Wood gravelly loam, 2 to 4 percent slopes—95 percent

Contrasting inclusions—5 percent

### **Characteristics of the Little Wood Soil**

*Position on landscape:* Stream terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,700 to 5,300 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

- 0 to 8 inches—dark brown gravelly loam
- 8 to 13 inches—brown gravelly loam
- 13 to 26 inches—brown and yellowish brown very gravelly sandy clay loam
- 26 to 32 inches—yellowish brown extremely gravelly coarse sandy loam
- 32 to 42 inches—brown extremely gravelly loamy coarse sand
- 42 to 61 inches—pale brown extremely gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate in the upper 26 inches; rapid or very rapid below this depth

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 32 inches

*Runoff:* Slow

*Hazard of water erosion:* Slight

*Shrink-swell potential:* Moderate

### **Contrasting Inclusions**

Bringmee loam in concave areas (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IIIe, irrigated; IIIc, nonirrigated

## **66—Little Wood very gravelly loam, 0 to 2 percent slopes**

### **Composition**

Little Wood very gravelly loam, 0 to 2 percent slopes—90 percent

Contrasting inclusions—10 percent

### **Characteristics of the Little Wood Soil**

*Position on landscape:* Stream terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,700 to 5,300 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

- 0 to 10 inches—grayish brown very gravelly loam
- 10 to 21 inches—yellowish brown and brown very gravelly sandy clay loam
- 21 to 25 inches—yellowish brown very gravelly loam
- 25 to 35 inches—brown extremely gravelly loamy coarse sand
- 35 to 61 inches—pale brown extremely gravelly coarse sand



*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate in the upper 25 inches; rapid or very rapid below this depth  
*Available water capacity:* Low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 25 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* Slight  
*Shrink-swell potential:* Moderate

**Contrasting Inclusions**

Bringmee gravelly loam in convex areas (5 percent); Adamson fine sandy loam in concave areas (5 percent)

**Major Uses**

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay (fig. 10), pasture  
*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Capability Classification**

IVs, irrigated and nonirrigated

**67—Little Wood very gravelly loam, 2 to 4 percent slopes**

**Composition**

Little Wood very gravelly loam, 2 to 4 percent slopes—90 percent  
Contrasting inclusions—10 percent

**Characteristics of the Little Wood Soil**

*Position on landscape:* Stream terraces

*Parent material:* Mixed alluvium  
*Elevation:* 4,700 to 5,300 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 80 days

*Typical profile:*

- 0 to 10 inches—grayish brown very gravelly loam
- 10 to 18 inches—yellowish brown and brown very gravelly sandy clay loam
- 18 to 22 inches—yellowish brown very gravelly loam
- 22 to 32 inches—brown extremely gravelly loamy coarse sand
- 32 to 61 inches—pale brown extremely gravelly coarse sand

*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate in the upper 22 inches; rapid or very rapid below this depth  
*Available water capacity:* Low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 22 inches  
*Runoff:* Slow  
*Hazard of water erosion:* Slight  
*Shrink-swell potential:* Moderate

**Contrasting Inclusions**

Bringmee gravelly loam in convex areas (5 percent); Adamson fine sandy loam in concave areas (5 percent)

**Major Uses**

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture  
*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.





Figure 10.—Irrigated alfalfa hay in an area of Little Wood very gravelly loam, 0 to 2 percent slopes. An area of Vitale-Milligan complex, 30 to 60 percent slopes, is in the background.

### Rangeland

*Dominant vegetation in potential natural plant community:*

Basin big sagebrush, bluebunch wheatgrass

*Main limitation:* Low available water capacity

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.
- Plants that can tolerate droughtiness are suitable for seeding.

### **Capability Classification**

IVs, irrigated and nonirrigated

### **68—Little Wood very gravelly loam, cool, 1 to 4 percent slopes**

#### **Composition**

Little Wood very gravelly loam, cool, 1 to 4 percent slopes—95 percent

Contrasting inclusions—5 percent

#### **Characteristics of the Little Wood Soil**

*Position on landscape:* Stream terraces

*Parent material:* Mixed alluvium

*Elevation:* 5,200 to 6,200 feet

*Average annual precipitation:* About 16 inches

*Average annual air temperature:* About 40 degrees F

*Frost-free period:* About 60 days

*Typical profile:*

0 to 2 inches—very dark grayish brown very gravelly loam



2 to 12 inches—brown very gravelly loam  
12 to 16 inches—dark yellowish brown very gravelly sandy clay loam  
16 to 24 inches—yellowish brown extremely cobbly sandy clay loam  
24 to 31 inches—yellowish brown extremely cobbly sandy loam  
31 to 43 inches—yellowish brown extremely cobbly loamy coarse sand  
43 to 60 inches—multicolored extremely cobbly coarse sand  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate in the upper 31 inches; very rapid below this depth  
*Available water capacity:* Low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and rock fragments at a depth of 31 inches  
*Runoff:* Slow  
*Hazard of water erosion:* Slight  
*Shrink-swell potential:* Moderate

**Contrasting Inclusions**

Isknat gravelly loam and Balaam gravelly sandy loam (5 percent)

**Major Uses**

**Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa hay, pasture  
*General management considerations:*  
• Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.  
• The best suited method of irrigation is a sprinkler system. Corrugation systems are also suitable, but their use is restricted by the rapid or very rapid permeability of the included areas.

**Capability Classification**

IVs, irrigated and nonirrigated

**69—Little Wood-Balaam complex, 0 to 2 percent slopes**

**Composition**

Little Wood very gravelly loam, 0 to 2 percent slopes—50 percent  
Balaam very gravelly sandy loam, 0 to 2 percent slopes—35 percent

Contrasting inclusions—15 percent

**Characteristics of the Little Wood Soil**

*Position on landscape:* Stream terraces  
*Parent material:* Mixed alluvium  
*Elevation:* 4,800 to 5,100 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 80 days  
*Typical profile:*  
0 to 10 inches—grayish brown very gravelly loam  
10 to 21 inches—yellowish brown very gravelly sandy clay loam  
21 to 25 inches—yellowish brown very gravelly loam  
25 to 35 inches—brown extremely gravelly loamy coarse sand  
35 to 61 inches—pale brown extremely gravelly coarse sand  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate in the upper 25 inches; rapid or very rapid below this depth  
*Available water capacity:* Low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and gravel at a depth of 25 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* Slight  
*Shrink-swell potential:* Moderate

**Characteristics of the Balaam Soil**

*Position on landscape:* Stream terraces  
*Parent material:* Mixed alluvium  
*Elevation:* 4,800 to 5,100 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 80 days  
*Typical profile:*  
0 to 10 inches—grayish brown very gravelly sandy loam  
10 to 24 inches—brown very gravelly sandy loam  
24 to 42 inches—pale brown extremely gravelly loamy coarse sand  
42 to 63 inches—extremely gravelly coarse sand  
*Depth class:* Very deep  
*Drainage class:* Somewhat excessively drained  
*Permeability:* Moderately rapid in the upper 24 inches; very rapid below this depth  
*Available water capacity:* Very low  
*Potential rooting depth:* 60 inches or more  
*Restriction affecting rooting depth:* Loose sand and rock



fragments at a depth of 24 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Shrink-swell potential:* Low

### **Contrasting Inclusions**

Balaam very cobbly sandy loam (10 percent); Isknot gravelly clay loam (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IVs, irrigated and nonirrigated

## **70—Manard silt loam, 1 to 4 percent slopes**

### **Composition**

Manard silt loam, 1 to 4 percent slopes—85 percent

Contrasting inclusions—15 percent

### **Characteristics of the Manard Soil**

*Position on landscape:* Basalt plains

*Parent material:* Residuum derived from basalt

*Elevation:* 4,700 to 5,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 11 inches—dark brown silt loam

11 to 30 inches—brown clay

30 to 36 inches—pale brown clay

36 to 38 inches—white, indurated duripan

38 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 37 inches

*Restriction affecting rooting depth:* Duripan at a depth of 36 inches

*Runoff:* Slow

*Hazard of water erosion:* Moderate

### **Contrasting Inclusions**

Goodington silt loam in depressions (5 percent); Manard very stony silt loam in convex areas (5 percent); Gaib very gravelly loam in eroded drainageways (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

#### **Rangeland**

*Dominant vegetation in potential natural plant community*

Alkali sagebrush, Idaho fescue

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are chemical spraying and mechanical treatment. Prescribed burning is limited by the inability of alkali sagebrush to carry fire.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

IIIe, irrigated and nonirrigated



**71—Marshdale loam, 0 to 2 percent slopes****Composition**

Marshdale loam, 0 to 2 percent slopes—85 percent  
Contrasting inclusions—15 percent

**Characteristics of the Marshdale Soil**

*Position on landscape:* Flood plains, drainageways  
*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 9 inches—dark grayish brown loam

9 to 14 inches—dark grayish brown sandy clay loam

14 to 37 inches—light brownish gray sandy clay loam

37 to 52 inches—light brownish gray loam

52 to 62 inches—light gray gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Poorly drained

*Permeability:* Moderate

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more for water-tolerant plants

*Restrictions affecting rooting depth:* Loose sand and gravel at a depth of 52 inches, water table at a depth of 6 to 18 inches

*Runoff:* Very slow

*Hazard of water erosion:* None

*Depth to water table:* 6 to 18 inches

*Frequency of flooding:* Frequent

**Contrasting Inclusions**

Bruneel loam and Hutton clay loam (15 percent)

**Major Uses****Hayland and pasture**

*Dominant vegetation in potential natural plant community:*

Tufted hairgrass, sedges, rushes, willow

*Currently grown nonirrigated crops:* Pasture, grass hay

*General management considerations:*

- Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- Wetness limits the choice of plants and the period of cutting or grazing and increases the risk of winterkill.
- Plants that can tolerate wetness are suitable for seeding.

- Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

**Capability Classification**

Vw, irrigated and nonirrigated

**72—Marshdale-Bruneel loams, 0 to 2 percent slopes****Composition**

Marshdale loam, 0 to 2 percent slopes—50 percent

Bruneel loam, 0 to 2 percent slopes—30 percent

Contrasting inclusions—20 percent

**Characteristics of the Marshdale Soil**

*Position on landscape:* Flood plains, drainageways

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 27 inches—dark grayish brown loam

27 to 50 inches—light brownish gray loam

50 to 65 inches—light gray gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Poorly drained

*Permeability:* Moderate

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more for water-tolerant plants

*Restrictions affecting rooting depth:* Loose sand and gravel at a depth of 50 inches, water table at a depth of 6 to 18 inches

*Runoff:* Very slow

*Hazard of water erosion:* None

*Depth to water table:* 6 to 18 inches

*Frequency of flooding:* Frequent

**Characteristics of the Bruneel Soil**

*Position on landscape:* Flood plains

*Parent material:* Recent alluvium derived from various kinds of rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 14 inches—grayish brown loam

14 to 23 inches—light gray loam



23 to 27 inches—grayish brown very gravelly loamy sand

27 to 61 inches—multicolored extremely gravelly coarse sand

*Depth class:* Very deep

*Drainage class:* Poorly drained

*Permeability:* Moderate in the upper 23 inches; very rapid below this depth

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more for water-tolerant plants

*Restrictions affecting rooting depth:* Loose sand and gravel at a depth of 27 inches, water table at a depth of 12 to 18 inches

*Runoff:* Very slow

*Hazard of water erosion:* None

*Depth to water table:* 12 to 18 inches

*Frequency of flooding:* Occasional

### **Contrasting Inclusions**

Little Wood gravelly loam on stream terraces (10 percent); Bruneel gravelly loam (5 percent); Riverwash (5 percent)

### **Major Uses**

#### **Hayland and pasture**

*Dominant vegetation in potential natural plant community:*

Tufted hairgrass, sedges, rushes, willows

*Currently grown nonirrigated crops:* Pasture, grass-legume hay

*General management considerations:*

- Proper grazing practices, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- Wetness limits the choice of plants and the period of cutting or grazing and increases the risk of winterkill.
- Plants that can tolerate wetness are suitable for seeding.
- Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

### **Capability Classification**

Vw, irrigated and nonirrigated

## **73—McBiggam silt loam, 2 to 8 percent slopes**

### **Composition**

McBiggam silt loam, 2 to 8 percent slopes—90 percent  
Contrasting inclusions—10 percent

### **Characteristics of the McBiggam Soil**

*Position on landscape:* Basalt plains

*Parent material:* Loess over residuum

*Elevation:* 5,300 to 5,600 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 10 inches—very dark grayish brown and dark brown silt loam

10 to 26 inches—dark brown and light yellowish brown silty clay loam

26 to 46 inches—brown silty clay

46 to 80 inches—brown silty clay loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow or medium

*Hazard of water erosion:* Moderate or severe

### **Contrasting Inclusions**

McCarey loam on convex ridges and Molyneux loam in drainageways (10 percent)

### **Major Uses**

*Current use:* Rangeland

*Potential uses:* Cropland, hayland, pasture

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and



applications of fertilizer improve the quality of forage on pastures.

- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Corrugation systems are suitable in areas that have slopes of less than 4 percent.

- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IVe, irrigated; IIle, nonirrigated

## **74—McCarey-Justesen loams, 2 to 8 percent slopes**

### **Composition**

McCarey loam, 2 to 8 percent slopes—50 percent

Justesen loam, 2 to 8 percent slopes—30 percent

Contrasting inclusions—20 percent

### **Characteristics of the McCarey Soil**

*Position on landscape:* Convex tops and side slopes of basalt plains

*Parent material:* Loess over residuum

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 11 inches—brown loam

11 to 18 inches—brown clay loam

18 to 23 inches—pale brown silt loam

23 to 28 inches—white silt loam

28 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Moderate

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### **Characteristics of the Justesen Soil**

*Position on landscape:* Drainageways and concave areas on basalt plains

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 14 inches—very dark grayish brown loam

14 to 25 inches—pale brown clay loam

25 to 31 inches—very pale brown silty clay loam

31 to 64 inches—white loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### **Contrasting Inclusions**

Soils that are similar to the McCarey soil but are 10 to 20 inches deep, have a very stony upper layer, and are on ridges (10 percent); Rock outcrop (10 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

McCarey soil—threetip sagebrush, bluebunch wheatgrass; Justesen soil—basin big sagebrush, bluebunch wheatgrass

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.

- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. On the McCarey soil, prescribed burning and mechanical treatment are limited by the inherent ability of threetip sagebrush to sprout from its roots and by the hazard of erosion.

- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

IIle, irrigated and nonirrigated

## **75—McCarey-Justesen-Rock outcrop complex, 2 to 15 percent slopes**

### **Composition**

McCarey loam, 2 to 15 percent slopes—40 percent

Justesen loam, 2 to 8 percent slopes—30 percent



Rock outcrop—20 percent  
Contrasting inclusions—10 percent

### ***Characteristics of the McCarey Soil***

*Position on landscape:* Convex tops and side slopes of basalt plains

*Parent material:* Loess over residuum

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 11 inches—brown loam

11 to 18 inches—brown clay loam

18 to 23 inches—pale brown silt loam

23 to 28 inches—white silt loam

28 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Moderate

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### ***Characteristics of the Justesen Soil***

*Position on landscape:* Drainageways and concave areas on basalt plains

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,700 to 5,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 14 inches—very dark grayish brown loam

14 to 25 inches—pale brown clay loam

25 to 31 inches—very pale brown silty clay loam

31 to 64 inches—white loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### ***Characteristics of the Rock Outcrop***

*Kind of rock:* Exposed basalt

### ***Contrasting Inclusions***

Soils that are similar to the McCarey soil but are 10 to 20 inches deep to bedrock, have a very stony upper

layer, and are on convex side slopes (5 percent); soils that are similar to the Justesen soil but are 40 to 60 inches deep to bedrock and are on concave side slopes (5 percent)

### ***Major Use***

#### ***Rangeland***

*Dominant vegetation in potential natural plant community:*

McCarey soil—threetip sagebrush, bluebunch wheatgrass; Justesen soil—basin big sagebrush, bluebunch wheatgrass

*Main limitations:* Areas of Rock outcrop, hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. On the McCarey soil, prescribed burning and mechanical treatment are limited by the inherent ability of threetip sagebrush to sprout from its roots and by the hazard of erosion.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### ***Capability Classification***

IVe, irrigated; IIle, nonirrigated

## **76—McCarey-Molyneux loams, 2 to 8 percent slopes**

### ***Composition***

McCarey loam, 2 to 8 percent slopes—45 percent  
Molyneux loam, 2 to 8 percent slopes—30 percent  
Contrasting inclusions—25 percent

### ***Characteristics of the McCarey Soil***

*Position on landscape:* Side slopes of basalt plains

*Parent material:* Loess over residuum derived from basalt

*Elevation:* 4,800 to 5,400 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 10 inches—dark grayish brown and dark brown loam

10 to 22 inches—yellowish brown clay loam

22 to 25 inches—very pale brown loam

25 to 37 inches—white silt loam

37 inches—basalt



*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* Moderate  
*Potential rooting depth:* 20 to 40 inches  
*Runoff:* Slow or medium  
*Hazard of water erosion:* Slight or moderate

### **Characteristics of the Molyneux Soil**

*Position on landscape:* Drainageways on basalt plains  
*Parent material:* Alluvium derived from various kinds of rock  
*Elevation:* 4,800 to 5,400 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
 0 to 8 inches—dark grayish brown loam  
 8 to 13 inches—brown loam  
 13 to 50 inches—yellowish brown clay loam  
 50 to 75 inches—yellowish brown gravelly sandy clay loam

*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Runoff:* Slow or medium  
*Hazard of water erosion:* Slight or moderate

### **Contrasting Inclusions**

Pedleford very stony loam in convex areas (10 percent);  
 Bancroft silt loam on toe slopes (10 percent); Rock outcrop in convex areas and on playas in depressions (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*  
 McCarey soil—threetip sagebrush, bluebunch wheatgrass; Molyneux soil—threetip sagebrush, Idaho fescue  
*Main limitation:* Hazard of erosion  
*General management considerations:*  
 • Brush management, proper distribution of livestock, and range seeding are needed.  
 • Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Prescribed burning and mechanical treatment are limited by the inherent ability of threetip sagebrush to sprout from its roots.

• Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

IIIe, irrigated and nonirrigated

## **77—McCarey-Pedleford complex, 2 to 30 percent slopes**

### **Composition**

McCarey loam, 2 to 30 percent slopes—50 percent  
 Pedleford very stony loam, 2 to 30 percent slopes—30 percent  
 Contrasting inclusions—20 percent

### **Characteristics of the McCarey Soil**

*Position on landscape:* Concave areas on sides of buttes and basalt plains  
*Parent material:* Loess over residuum derived from basalt  
*Elevation:* 4,800 to 5,400 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
 0 to 10 inches—dark brown and dark grayish brown loam  
 10 to 22 inches—yellowish brown clay loam  
 22 to 25 inches—very pale brown loam  
 25 to 37 inches—white silt loam  
 37 inches—basalt

*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* Moderate  
*Potential rooting depth:* 20 to 40 inches  
*Runoff:* Medium to very rapid  
*Hazard of water erosion:* Moderate to very severe

### **Characteristics of the Pedleford Soil**

*Position on landscape:* Convex areas on sides of buttes and basalt plains  
*Parent material:* Alluvium derived from loess and eolian material over basalt  
*Elevation:* 4,800 to 5,400 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
 0 to 5 inches—grayish brown very stony loam  
 5 to 13 inches—brown very stony loam



13 to 29 inches—very pale brown very stony silt loam

29 to 33 inches—very pale brown very cobbly loam  
33 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Very low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Slow to rapid

*Hazard of water erosion:* Slight to severe

### **Contrasting Inclusions**

Molyneux loam in drainageways (10 percent); Bancroft silt loam in drainageways (5 percent); Rock outcrop on ridges and convex side slopes and on playas in depressions (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

McCarey soil—Wyoming big sagebrush, bluebunch wheatgrass; Pedleford soil—basin big sagebrush, bluebunch wheatgrass

*Main limitations:* Very stony loam upper layer in the Pedleford soil, hazard of erosion, areas of Rock outcrop

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the very stony loam upper layer in the Pedleford soil and by the hazard of erosion.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

Vls, nonirrigated

## **78—Molyneux loam, 2 to 4 percent slopes**

### **Composition**

Molyneux loam, 2 to 4 percent slopes—85 percent  
Contrasting inclusions—15 percent

### **Characteristics of the Molyneux Soil**

*Position on landscape:* Fan terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 12 inches—grayish brown loam

12 to 35 inches—brown clay loam

35 to 61 inches—dark yellowish brown clay loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow

*Hazard of water erosion:* Slight

### **Contrasting Inclusions**

Bringmee loam (5 percent); Hutton clay loam in drainageways (5 percent); Molyneux loam that has slopes of less than 2 percent (5 percent)

### **Major Uses**

#### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion. Corrugation systems are also suitable.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

IIIe, irrigated; IIlc, nonirrigated

## **79—Molyneux loam, 4 to 8 percent slopes**

### **Composition**

Molyneux loam, 4 to 8 percent slopes—90 percent  
Contrasting inclusions—10 percent



**Characteristics of the Molyneux Soil**

*Position on landscape:* Fan terraces

*Parent material:* Mixed alluvium

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 43 degrees F

*Frost-free period:* About 80 days

*Typical profile:*

0 to 12 inches—grayish brown loam

12 to 35 inches—brown clay loam

35 to 61 inches—dark yellowish brown clay loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Medium

*Hazard of water erosion:* Moderate

**Contrasting Inclusions**

Bringmee loam (5 percent); Hutton clay loam in depressions (5 percent)

**Major Uses****Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

**Capability Classification**

IIIe, irrigated and nonirrigated

**80—Molyneux loam, cool, 2 to 15 percent slopes****Composition**

Molyneux loam, cool, 2 to 15 percent slopes—85 percent

Contrasting inclusions—15 percent

**Characteristics of the Molyneux Soil**

*Position on landscape:* Fan terraces

*Parent material:* Alluvium derived from various kinds of rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 13 inches—dark grayish brown and brown loam

13 to 50 inches—yellowish brown clay loam

50 to 75 inches—yellowish brown gravelly sandy clay loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow to rapid

*Hazard of water erosion:* Slight to severe

**Contrasting Inclusions**

Drage very gravelly loam in convex areas (10 percent); Little Wood very gravelly loam on stream terraces (5 percent)

**Major Uses**

*Current use:* Rangeland

*Potential uses:* Hayland, pasture

**Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are



prescribed burning, chemical spraying, and mechanical treatment.

- Range seeding is suitable on this unit. Drilling is the best suited method.

#### **Hayland and pasture**

*Currently grown irrigated crops:* Alfalfa hay, pasture

*General management considerations:*

- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Corrugation systems are suitable in areas that have slopes of less than 4 percent.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

#### **Capability Classification**

Ive, irrigated; IIle, nonirrigated

### **81—Moonstone-Bauscher complex, 8 to 30 percent slopes**

#### **Composition**

Moonstone gravelly coarse sandy loam, 8 to 30 percent slopes—50 percent

Bauscher loam, 8 to 15 percent slopes—30 percent

Contrasting inclusions—20 percent

#### **Characteristics of the Moonstone Soil**

*Position on landscape:* South- and west-facing foothills

*Parent material:* Colluvium and residuum derived from granite

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 26 inches—dark grayish brown and brown gravelly coarse sandy loam

26 to 34 inches—pale brown gravelly coarse sandy loam

34 inches—weathered granitic bedrock

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Rapid or very rapid

*Hazard of water erosion:* Severe or very severe

#### **Characteristics of the Bauscher Loam**

*Position on landscape:* Concave areas, depressions, and toe slopes of foothills

*Parent material:* Alluvium and colluvium derived from granite

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 14 inches—dark grayish brown and dark brown loam

14 to 37 inches—brown and yellowish brown sandy clay loam

37 to 42 inches—light yellowish brown coarse sandy loam

42 inches—weathered granitic bedrock

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Moderate

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Rapid

*Hazard of water erosion:* Severe

#### **Contrasting Inclusions**

Soils that are similar to the Moonstone soil but are 10 to 20 inches deep to bedrock and are on ridges (10 percent); Earcree gravelly coarse sandy loam on north- and east-facing slopes (10 percent)

#### **Major Use**

##### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

#### **Capability Classification**

Ive, nonirrigated



## 82—Moonstone-Earcree association, 30 to 60 percent slopes

### **Composition**

Moonstone gravelly coarse sandy loam, 30 to 60 percent slopes—50 percent  
 Earcree gravelly coarse sandy loam, 30 to 60 percent slopes—30 percent  
 Contrasting inclusions—20 percent

### **Characteristics of the Moonstone Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Colluvium and residuum derived from granite

*Elevation:* 5,000 to 7,800 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 21 inches—dark grayish brown and brown gravelly coarse sandy loam

21 to 32 inches—grayish brown gravelly coarse sandy loam

32 inches—granitic bedrock

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Earcree Soil**

*Position on landscape:* North- and east-facing mountainsides at elevations below 7,500 feet; all aspects of mountainsides at elevations above 7,500 feet

*Parent material:* Colluvium and slope alluvium over residuum

*Elevation:* 5,000 to 7,800 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 37 inches—dark grayish brown and brown gravelly coarse sandy loam

37 to 52 inches—pale brown gravelly coarse sandy loam

52 to 70 inches—pale brown very gravelly loamy coarse sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Bauscher loam on fan terraces (10 percent); soils that are similar to the Earcree soil but receive supplemental moisture in the lower part of the profile from springs and support quaking aspen (5 percent); soils that are less than 20 inches deep to bedrock and Rock outcrop (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Moonstone soil—mountain big sagebrush, bluebunch wheatgrass; Earcree soil—mountain big sagebrush, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope and the hazard of erosion.
- Range seeding generally is not suitable on this unit because of the slope and the hazard of erosion; however, it is suited to some gently sloping areas of the included Bauscher loam. Drilling is the best suited method.
- Fences and stock water pipelines are limited by the slope.

### **Capability Classification**

VIIe, nonirrigated

## 83—Muldoon-Peevywell loams, 2 to 15 percent slopes

### **Composition**

Muldoon loam, 2 to 15 percent slopes—60 percent  
 Peevywell loam, 2 to 15 percent slopes—30 percent  
 Contrasting inclusions—10 percent

### **Characteristics of the Muldoon Soil**

*Position on landscape:* Convex areas on fan terraces

*Parent material:* Alluvium derived from mixed igneous and metamorphic rock

*Elevation:* 4,800 to 6,500 feet



*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 7 inches—brown loam

7 to 45 inches—yellowish brown clay loam

45 inches—light yellowish brown, indurated duripan

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Moderate

*Potential rooting depth:* 40 to 60 inches

*Restriction affecting rooting depth:* Duripan at a depth of 45 inches

*Runoff:* Medium

*Hazard of water erosion:* Moderate

### ***Characteristics of the Peevywell Soil***

*Position on landscape:* Eroded areas and drainageways on fan terraces

*Parent material:* Alluvium derived from mixed igneous and metamorphic rock

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 12 inches—brown loam

12 to 22 inches—yellowish brown and brown clay loam

22 to 30 inches—brown clay

30 to 44 inches—light brown, indurated duripan

44 to 61 inches—yellowish brown very gravelly sandy loam

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 24 to 35 inches

*Restriction affecting rooting depth:* Duripan at a depth of 30 inches

*Runoff:* Slow to rapid

*Hazard of water erosion:* Slight to severe

### ***Contrasting Inclusions***

Hutton clay loam in depressions and drainageways (10 percent)

### ***Major Use***

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*  
Muldoon soil—mountain big sagebrush, bluebunch

wheatgrass; Peevywell soil—alkali sagebrush, Idaho fescue

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### ***Capability Classification***

IVs, nonirrigated

### **84—Mulshoe-Gaib-Rock outcrop complex, 4 to 30 percent slopes**

#### ***Composition***

Mulshoe very stony loam, 4 to 30 percent slopes—50 percent

Gaib stony loam, 4 to 30 percent slopes—25 percent

Rock outcrop—20 percent

Contrasting inclusions—5 percent

### ***Characteristics of the Mulshoe Soil***

*Position on landscape:* Concave areas on south- and west-facing foothills

*Parent material:* Residuum and colluvium derived from basalt

*Elevation:* 4,800 to 7,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 10 inches—brown very stony loam

10 to 23 inches—yellowish brown very stony clay loam

23 to 28 inches—very pale brown, weathered basalt that has yellowish brown clay loam in the cracks

28 inches—hard basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Very low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Slow to rapid

*Hazard of water erosion:* Slight to severe

### ***Characteristics of the Gaib Soil***

*Position on landscape:* Convex areas on south- and west-facing foothills

*Parent material:* Residuum derived from andesite, latite, and basalt

*Elevation:* 4,800 to 7,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 4 inches—brown stony loam

4 to 12 inches—dark yellowish brown very cobbly clay loam

12 inches—basalt

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Medium to very rapid

*Hazard of water erosion:* Moderate to very severe

**Characteristics of the Rock Outcrop**

*Position on landscape:* Convex areas, ridgetops

*Kind of material:* Exposed basalt

**Contrasting Inclusions**

Winu stony loam on north- and east-facing slopes (5 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*

Mulshoe soil—mountain big sagebrush, Idaho fescue; Gaib soil—low sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the very stony and stony upper layer in the Mulshoe and Gaib soils and by the hazard of erosion. Prescribed burning is limited on the Gaib soil by the inability of low sagebrush to carry fire.
- Range seeding is not suitable on this unit because of the very stony and stony upper layer in the Mulshoe and Gaib soils.

**Capability Classification**

Vls, nonirrigated

**85—Mulshoe-Gaib-Winu complex, 30 to 60 percent slopes**

**Composition**

Mulshoe very cobbly loam, 30 to 60 percent slopes—45 percent

Gaib very gravelly loam, 30 to 60 percent slopes—30 percent

Winu stony loam, 30 to 60 percent slopes—20 percent

Contrasting inclusions—5 percent

**Characteristics of the Mulshoe Soil**

*Position on landscape:* Concave areas on south- and west-facing mountainsides

*Parent material:* Residuum and colluvium derived from basalt

*Elevation:* 5,500 to 7,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 12 inches—brown very cobbly loam

12 to 21 inches—dark yellowish brown very cobbly clay loam

21 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Very low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

**Characteristics of the Gaib Soil**

*Position on landscape:* Convex areas on south- and west-facing mountainsides

*Parent material:* Residuum derived from andesite, latite, and basalt

*Elevation:* 5,500 to 7,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 5 inches—brown very gravelly loam

5 to 13 inches—dark yellowish brown very cobbly clay loam

13 inches—basalt

*Depth class:* Shallow

*Drainage class:* Well drained



*Permeability:* Moderately slow  
*Available water capacity:* Very low  
*Potential rooting depth:* 10 to 20 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

### **Characteristics of the Winu Soil**

*Position on landscape:* North- and east-facing mountainsides  
*Parent material:* Colluvium derived dominantly from latite, andesite, and basalt  
*Elevation:* 5,500 to 7,500 feet  
*Average annual precipitation:* About 18 inches  
*Average annual air temperature:* About 39 degrees F  
*Frost-free period:* Less than 60 days  
*Typical profile:*  
 0 to 13 inches—dark grayish brown and brown stony loam  
 13 to 21 inches—brown gravelly loam  
 21 to 35 inches—yellowish brown gravelly clay loam  
 35 inches—basalt  
*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* Low  
*Potential rooting depth:* 24 to 40 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Rock outcrop in convex areas (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*  
 Mulshoe and Gaib soils—mountain big sagebrush, bluebunch wheatgrass; Winu soil—mountain big sagebrush, Idaho fescue  
*General management considerations:*  
 • Brush management and proper distribution of livestock are needed.  
 • Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope and the hazard of erosion.  
 • Range seeding is not suitable on this unit because of the slope and the hazard of erosion.  
 • Fences and stock water pipelines are limited by the slope, the hazard of erosion, and the depth to bedrock in the Gaib soil.

### **Capability Classification**

VIIe, nonirrigated

## **86—Pagari-Rehfield complex, 2 to 15 percent slopes**

### **Composition**

Pagari very cobbly sandy loam, 2 to 15 percent slopes—45 percent  
 Rehfield loamy sand, 2 to 8 percent slopes—30 percent  
 Contrasting inclusions—25 percent

### **Characteristics of the Pagari Soil**

*Position on landscape:* Convex ridgetops and side slopes of basalt plains  
*Parent material:* Eolian-influenced alluvium over basalt  
*Elevation:* 4,600 to 4,800 feet  
*Average annual precipitation:* About 11 inches  
*Average annual air temperature:* About 47 degrees F  
*Frost-free period:* About 110 days  
*Typical profile:*  
 0 to 17 inches—brown and grayish brown very cobbly sandy loam  
 17 to 31 inches—yellowish brown extremely cobbly loam  
 31 to 46 inches—pale brown and very pale brown extremely cobbly loam  
 46 inches—fractured basalt  
*Depth class:* Deep  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Low  
*Potential rooting depth:* 40 to 60 inches  
*Runoff:* Slow or medium  
*Hazard of water erosion:* Slight or moderate

### **Characteristics of the Rehfield Soil**

*Position on landscape:* Depressions and drainageways on basalt plains  
*Parent material:* Eolian-influenced alluvium derived from various kinds of rock  
*Elevation:* 4,600 to 4,800 feet  
*Average annual precipitation:* About 11 inches  
*Average annual air temperature:* About 47 degrees F  
*Frost-free period:* About 110 days  
*Typical profile:*  
 0 to 11 inches—brown loamy sand  
 11 to 42 inches—yellowish brown sandy loam and sandy clay loam  
 42 to 67 inches—light yellowish brown loamy sand  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Moderate  
*Potential rooting depth:* 60 inches or more

*Runoff:* Slow  
*Hazard of water erosion:* Slight  
*Hazard of wind erosion:* Severe

**Contrasting Inclusions**

Rock outcrop in convex areas (15 percent); Cox very stony sandy loam on ridgetops and convex side slopes (10 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Pagari soil—basin big sagebrush, bluebunch wheatgrass; Rehfield soil—basin big sagebrush, needleandthread, Indian ricegrass  
*Main limitations:* Loamy sand upper layer in the Rehfield soil, very cobbly sandy loam upper layer in the Pagari soil, droughtiness, hazard of wind erosion  
*General management considerations:*  
• Brush management, proper distribution of livestock, and range seeding are needed.  
• Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the very cobbly sandy loam upper layer in the Pagari soil and by the included areas of Rock outcrop.  
• Range seeding is suited to this unit. It is limited by the very cobbly sandy loam upper layer in the Pagari soil and by the included areas of Rock outcrop. Drilling is the best suited method.

**Capability Classification**

VIs, nonirrigated

**87—Peevywell-Simonton loams, 2 to 8 percent slopes**

**Composition**

Peevywell loam, 2 to 8 percent slopes—50 percent  
Simonton loam, 2 to 8 percent slopes—30 percent  
Contrasting inclusions—20 percent

**Characteristics of the Peevywell Soil**

*Position on landscape:* Convex tops and side slopes on fan terraces  
*Parent material:* Mixed alluvium  
*Elevation:* 4,800 to 5,500 feet  
*Average annual precipitation:* About 13 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days

*Typical profile:*  
0 to 5 inches—brown loam  
5 to 10 inches—yellowish brown clay loam  
10 to 24 inches—yellowish brown and light yellowish brown clay  
24 to 46 inches—pale brown, indurated duripan  
46 to 61 inches—pale brown gravelly loamy sand  
*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Slow  
*Available water capacity:* Low  
*Potential rooting depth:* 24 to 35 inches  
*Restriction affecting rooting depth:* Duripan at a depth of 24 inches  
*Runoff:* Slow or medium  
*Hazard of erosion:* Slight or moderate

**Characteristics of the Simonton Soil**

*Position on landscape:* Drainageways and concave areas on fan terraces  
*Parent material:* Alluvium derived from granite  
*Elevation:* 4,800 to 5,500 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
0 to 12 inches—brown and yellowish brown loam  
12 to 52 inches—yellowish brown and light yellowish brown clay loam and sandy clay loam  
52 to 64 inches—pale brown sandy loam  
*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Runoff:* Slow or medium  
*Hazard of erosion:* Slight or moderate

**Contrasting Inclusions**

Manard very stony silt loam in convex areas (10 percent); Marshdale loam on flood plains (10 percent)

**Major Uses**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Peevywell soil—alkali sagebrush, Idaho fescue;  
Simonton soil—mountain big sagebrush, Idaho fescue  
*General management considerations:*  
• Brush management, proper distribution of livestock,



and range seeding are needed.

- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Prescribed burning is limited by the inability of alkali sagebrush to carry fire.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats, alfalfa hay, pasture

*Main limitation:* Hazard of erosion

*General management considerations:*

- A suitable cropping system, crop residue management, irrigation water management, and applications of fertilizer help to maintain fertility and tilth.
- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer improve the quality of forage on pastures.
- The best suited method of irrigation is a sprinkler system. Use of this method permits an even, controlled application of water, reduces the rate of runoff, and minimizes the risk of water erosion.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.

### **Capability Classification**

III<sub>s</sub>, irrigated; III<sub>e</sub>, nonirrigated

## **88—Peevywell-Simonton complex, 8 to 30 percent slopes**

### **Composition**

Peevywell loam, 8 to 30 percent slopes—50 percent  
Simonton silt loam, 8 to 15 percent slopes—35 percent  
Contrasting inclusions—15 percent

### **Characteristics of the Peevywell Soil**

*Position on landscape:* Convex and eroded areas on fan terraces

*Parent material:* Alluvium derived from mixed igneous and metamorphic rock

*Elevation:* 4,800 to 5,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 12 inches—brown loam

12 to 22 inches—yellowish brown and brown clay loam

22 to 30 inches—brown clay

30 to 44 inches—indurated duripan

44 to 61 inches—yellowish brown very gravelly sandy loam

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 24 to 35 inches

*Restriction affecting rooting depth:* Duripan at a depth of 30 inches

*Runoff:* Medium to very rapid

*Hazard of water erosion:* Severe or very severe

### **Characteristics of the Simonton Soil**

*Position on landscape:* Concave areas on fan terraces

*Parent material:* Alluvium derived from granite

*Elevation:* 4,800 to 5,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 11 inches—brown silt loam

11 to 43 inches—light yellowish brown clay loam

43 to 61 inches—light brown sandy clay loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Contrasting Inclusions**

Bauscher loam in depressions and on toe slopes (10 percent); Marshdale loam in drainageways (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Peevywell soil—alkali sagebrush, Idaho fescue;

Simonton soil—mountain big sagebrush, Idaho fescue

*Main limitations:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are

prescribed burning, chemical spraying, and mechanical treatment.

- Range seeding is suitable on this unit. Drilling is the best suited method.

**Capability Classification**

IVe, nonirrigated

**89—Picabo silt loam, 0 to 2 percent slopes**

**Composition**

Picabo silt loam, 0 to 2 percent slopes—90 percent  
Contrasting inclusions—10 percent

**Characteristics of the Picabo Soil**

- Position on landscape:* Stream terraces  
*Parent material:* Mixed alluvium  
*Elevation:* 4,700 to 5,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*
- 0 to 9 inches—grayish brown and light brownish gray silt loam
  - 9 to 16 inches—light brownish gray silt loam
  - 16 to 23 inches—light gray loam
  - 23 to 39 inches—light gray silt loam
  - 39 to 51 inches—white gravelly silt loam
  - 51 to 53—white silt loam
  - 53 to 55 inches—gray silt loam
  - 55 to 61 inches—gray very fine sandy loam
  - 61 to 72 inches—dark gray extremely gravelly loamy sand
- Depth class:* Very deep  
*Drainage class:* Somewhat poorly drained  
*Permeability:* Moderate  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more for water-tolerant plants  
*Restrictions affecting rooting depth:* Water table at a depth of 24 to 48 inches, lime concretions at a depth of 36 to 50 inches  
*Runoff:* Very slow  
*Hazard of water erosion:* Slight  
*Depth to water table:* 24 to 48 inches  
*Frequency of flooding:* Occasional

**Contrasting Inclusions**

Hapur silt loam and Bickett mucky peat in wet areas (5 percent); soils that are similar to the Picabo soil but are 20 to 30 inches deep to lime nodules and are in the higher lying areas (5 percent)

**Major Uses**

*Current uses:* Cropland, pasture  
*Potential uses:* Hayland, rangeland

**Cropland**

- Currently grown nonirrigated crops:* Wheat, barley, oats  
*General management considerations:*
- Providing drainage is difficult because most areas have poor outlets and are subject to seasonal flooding.
  - A suitable cropping system, crop residue management, and applications of fertilizer help to maintain fertility and tilth.
  - Supplemental irrigation may be needed during the growing season to ensure adequate moisture for crop production.
  - The best suited method of irrigation is a sprinkler system.

**Hayland and pasture**

- Dominant vegetation in potential natural plant community:*  
Shrubby cinquefoil, sedges, tufted hairgrass  
*Currently grown nonirrigated crops:* Grass-legume hay, pasture  
*General management considerations:*
- Providing drainage is difficult because most areas have poor outlets and are subject to seasonal flooding.
  - Supplemental irrigation may be needed during the growing season to ensure adequate moisture for crop production.
  - The best suited method of irrigation is a sprinkler system.
  - Plants that can tolerate wetness are suitable for seeding.
  - Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

**Capability Classification**

IIIw, irrigated and nonirrigated

**90—Picabo gravelly loam, 0 to 2 percent slopes**

**Composition**

Picabo gravelly loam, 0 to 2 percent slopes—95 percent  
Contrasting inclusions—5 percent

**Characteristics of the Picabo Soil**

- Position on landscape:* Stream terraces  
*Parent material:* Mixed alluvium  
*Elevation:* 4,700 to 5,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 43 degrees F



*Frost-free period:* About 75 days

*Typical profile:*

- 0 to 11 inches—very dark brown gravelly loam
- 11 to 31 inches—light gray and light brownish gray loam
- 31 to 40 inches—light gray silt loam
- 40 to 53 inches—white gravelly silt loam
- 53 to 61 inches—gray very fine sandy loam
- 61 to 72 inches—dark gray extremely gravelly loamy sand

*Depth class:* Very deep

*Drainage class:* Somewhat poorly drained

*Permeability:* Moderate

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more for water-tolerant plants

*Restrictions affecting rooting depth:* Water table at a depth of 24 to 48 inches, lime concretions at a depth of 36 to 50 inches

*Runoff:* Very slow

*Hazard of water erosion:* Slight

*Depth to water table:* 24 to 48 inches

*Frequency of flooding:* Occasional

### ***Contrasting Inclusions***

Bruneel loam along streams and Hapur silt loam in wet areas (5 percent)

### ***Major Uses***

*Current uses:* Cropland, pasture

*Potential use:* Hayland

#### **Cropland**

*Currently grown nonirrigated crops:* Wheat, barley, oats

*General management considerations:*

- Providing drainage is difficult because most areas have poor outlets and are subject to seasonal flooding.
- A suitable cropping system, crop residue management, and applications of fertilizer help to maintain fertility and tilth.
- Supplemental irrigation may be needed during the growing season to ensure adequate moisture for crop production.
- The best suited method of irrigation is a sprinkler system.

#### **Hayland and pasture**

*Dominant vegetation in potential natural plant community:*

Shrubby cinquefoil, sedges, tufted hairgrass

*Currently grown nonirrigated crops:* Grass-legume hay, pasture

*General management considerations:*

- Providing drainage is difficult because most areas

have poor outlets and are subject to seasonal flooding.

- Supplemental irrigation may be needed during the growing season to ensure adequate moisture for crop production.
- The best suited method of irrigation is a sprinkler system.
- Plants that can tolerate wetness are suitable for seeding.
- Grazing should be deferred until the water table lowers and the upper part of the soil is firm.

### ***Capability Classification***

III<sub>s</sub>, irrigated and nonirrigated

## **91—Pits, gravel**

*Position on landscape:* Areas along the Big Wood and Little Wood Rivers

*Kind of material:* Excavated cobbles, gravel, and sand

*Vegetation:* Little, if any

*Current use:* Wildlife habitat for small rodents, marmots, rabbits, and hawks and other small birds

*Capability classification:* VIII<sub>s</sub>

## **92—Povey-Dollarhide complex, 30 to 60 percent slopes**

### ***Composition***

Povey gravelly loam, 30 to 60 percent slopes—55 percent

Dollarhide very gravelly silt loam, 30 to 60 percent slopes—25 percent

Contrasting inclusions—20 percent

### ***Characteristics of the Povey Soil***

*Position on landscape:* North- and east-facing mountainsides at elevations below 7,500 feet; all aspects of mountainsides at elevations above 7,500 feet

*Parent material:* Colluvium derived dominantly from quartzitic sandstone, conglomerate, and related rock

*Elevation:* 5,200 to 8,600 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

- 0 to 14 inches—dark grayish brown and grayish brown gravelly loam
- 14 to 35 inches—brown very gravelly loam

35 to 60 inches—brown extremely cobbly loam  
60 inches—quartzitic sandstone

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Dollarhide Soil**

*Position on landscape:* North- and east-facing slopes of ridges

*Parent material:* Volcanic-ash-influenced colluvium derived dominantly from quartzitic sandstone and conglomerate

*Elevation:* 5,200 to 8,600 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 7 inches—dark grayish brown very gravelly silt loam

7 to 11 inches—light yellowish brown very gravelly silt loam

11 to 16 inches—yellowish brown extremely cobbly loam

16 inches—hard, quartzitic sandstone

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Rock outcrop on ridges (10 percent); Vitale very gravelly loam on south- and west-facing side slopes (5 percent); Blackspar very cobbly loam on south- and west-facing slopes of ridges (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Povey soil—mountain big sagebrush, Idaho fescue;

Dollarhide soil—mountain big sagebrush, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.

- Chemical spraying is a suitable method of brush

management. Mechanical treatment and prescribed burning are limited by the slope.

- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **93—Povey-Rock outcrop complex, 30 to 60 percent slopes**

### **Composition**

Povey gravelly loam, 30 to 60 percent slopes—55 percent

Rock outcrop—25 percent

Contrasting inclusions—20 percent

### **Characteristics of the Povey Soil**

*Position on landscape:* North- and east-facing mountainsides

*Parent material:* Colluvium derived dominantly from conglomerate, quartzitic sandstone, and related rock

*Elevation:* 5,200 to 8,600 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 14 inches—dark grayish brown and grayish brown gravelly loam

14 to 35 inches—brown very gravelly loam

35 to 60 inches—brown extremely cobbly loam

60 inches—quartzitic sandstone

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Rock Outcrop**

*Position on landscape:* Ridges

*Kind of material:* Exposed bedrock

### **Contrasting Inclusions**

Vitale very gravelly loam on south- and west-facing slopes (10 percent); Dollarhide very gravelly fine sandy loam on ridges (5 percent); Drage gravelly loam on fan terraces (5 percent)



### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.
- Fences and stock water pipelines are limited by the slope and the areas of Rock outcrop.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **94—Povey association, cold, 15 to 60 percent slopes**

### **Composition**

Povey very gravelly silt loam, cold, 15 to 60 percent slopes—45 percent

Povey gravelly loam, cold, 15 to 60 percent slopes—40 percent

Contrasting inclusions—15 percent

### **Characteristics of the Povey Very Gravelly Silt Loam**

*Position on landscape:* North- and east-facing mountaintops

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 7,000 to 9,250 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 37 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

- 0 to 12 inches—dark grayish brown very gravelly silt loam
- 12 to 28 inches—dark grayish brown very gravelly loam
- 28 to 44 inches—brown extremely gravelly fine sandy loam
- 44 to 52 inches—pale brown extremely cobbly sandy loam
- 52 inches—quartzitic sandstone

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Rapid or very rapid

*Hazard of water erosion:* Severe or very severe

### **Characteristics of the Povey Gravelly Loam**

*Position on landscape:* South- and west-facing mountaintops

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 7,000 to 9,250 feet

*Average annual precipitation:* About 20 inches

*Average annual air temperature:* About 37 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

- 0 to 14 inches—dark grayish brown and grayish brown gravelly loam
- 14 to 35 inches—brown very gravelly loam
- 35 to 60 inches—brown extremely cobbly loam
- 60 inches—quartzitic sandstone

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Rapid or very rapid

*Hazard of water erosion:* Severe or very severe

### **Contrasting Inclusions**

Dollarhide very gravelly loam on ridges (10 percent);

Rock outcrop on ridges (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

- Povey very gravelly silt loam—mountain big sagebrush, mountain snowberry, Idaho fescue;
- Povey gravelly loam—mountain big sagebrush, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.
- Fences and stock water pipelines are limited by the slope.
- Range seeding is not suitable in the steeper areas of this unit. In the less sloping areas, seeding is limited by the hazard of erosion and by restricted accessibility.

**Capability Classification**

VIIe, nonirrigated

**95—Povey-Vitale association, 30 to 60 percent slopes****Composition**

Povey gravelly loam, 30 to 60 percent slopes—50 percent

Vitale very gravelly loam, 30 to 60 percent slopes—30 percent

Contrasting inclusions—20 percent

**Characteristics of the Povey Soil**

*Position on landscape:* North- and east-facing mountainsides at elevations below 7,500 feet; all aspects of mountainsides at elevations above 7,500 feet

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 5,200 to 8,600 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 14 inches—dark grayish brown and grayish brown gravelly loam

14 to 35 inches—brown very gravelly loam

35 to 60 inches—brown extremely cobbly loam

60 inches—quartzitic sandstone

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

**Characteristics of the Vitale Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Residuum and colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 5,200 to 8,600 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 6 inches—dark grayish brown very gravelly loam

6 to 15 inches—brown very gravelly clay loam

15 to 23 inches—light brownish gray very gravelly loam

23 inches—quartzitic sandstone

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Restriction affecting rooting depth:* Bedrock at a depth of 23 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

**Contrasting Inclusions**

Rock outcrop on ridges (10 percent); Dollarhide very gravelly fine sandy loam on ridges and north- and east-facing convex slopes (5 percent); Rubbleland (5 percent)

**Major Use****Rangeland**

*Dominant vegetation in potential natural plant community:*

Povey soil—mountain big sagebrush, Idaho fescue;

Vitale soil—mountain big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.
- Fences and stock water pipelines are limited by the slope and by the depth to bedrock in the Vitale soil.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

**Capability Classification**

VIIe, nonirrigated

**96—Rehfield-Gooding complex, 2 to 15 percent slopes****Composition**

Rehfield sandy loam, 2 to 15 percent slopes—50 percent

Gooding silt loam, 2 to 15 percent slopes—30 percent

Contrasting inclusions—20 percent

**Characteristics of the Rehfield Soil**

*Position on landscape:* Concave areas on basalt plains



*Parent material:* Eolian-influenced alluvium  
*Elevation:* 4,600 to 4,800 feet  
*Average annual precipitation:* About 12 inches  
*Average annual air temperature:* About 47 degrees F  
*Frost-free period:* About 100 days

*Typical profile:*

0 to 11 inches—dark grayish brown and dark brown sandy loam

11 to 42 inches—yellowish brown and light yellowish brown sandy clay loam

42 to 67 inches—very pale brown loamy sand

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Moderate

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow to rapid

*Hazard of water erosion:* Slight to severe

### **Characteristics of the Gooding Soil**

*Position on landscape:* Convex areas on basalt plains

*Parent material:* Alluvium over basalt or rhyolite

*Elevation:* 4,600 to 4,800 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 100 days

*Typical profile:*

0 to 9 inches—brown and pale brown silt loam

9 to 49 inches—yellowish brown, pale brown, and very pale brown silty clay and silty clay loam

49 to 62 inches—very pale brown, weakly cemented duripan

62 inches—basalt that has a silica cap

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* High

*Potential rooting depth:* 40 to 60 inches

*Restriction affecting rooting depth:* Duripan at a depth of 49 inches

*Runoff:* Slow to rapid

*Hazard of water erosion:* Slight to severe

### **Contrasting Inclusions**

Yutru silty clay on playas (10 percent); Adios stony loam on toe slopes (5 percent); Rock outcrop (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*  
 Rehfield soil—basin big sagebrush, bluebunch

wheatgrass; Gooding soil—Wyoming big sagebrush, bluebunch wheatgrass

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

IVe, nonirrigated

## **97—Riverwash**

*Position on landscape:* Areas along braided channels of major rivers and streams

*Kind of material:* Unstabilized sandy, gravelly, or cobbly sediment that is frequently flooded, washed, and reworked by rivers and streams

*Vegetation:* Little, if any

*Contrasting inclusions:* Fluvents that support plants

*Capability classification:* VIIIs, nonirrigated

## **98—Rock outcrop-Adios complex, 25 to 60 percent slopes**

### **Composition**

Rock outcrop—45 percent

Adios stony loam, 25 to 60 percent slopes—35 percent

Contrasting inclusions—20 percent

### **Characteristics of the Rock Outcrop**

*Position on landscape:* Convex ridges and side slopes

*Kind of material:* Exposed basalt

### **Characteristics of the Adios Soil**

*Position on landscape:* Convex side slopes of buttes

*Parent material:* Residuum, slope alluvium

*Elevation:* 4,600 to 4,900 feet

*Average annual precipitation:* About 12 inches

*Average annual air temperature:* About 47 degrees F

*Frost-free period:* About 110 days

*Typical profile:*

0 to 5 inches—brown and yellowish brown stony loam

5 to 23 inches—yellowish brown, light yellowish brown, and very pale brown clay and clay loam

23 to 27 inches—white, indurated duripan



27 inches—fractured rhyolite that has silica and lime in the fractures

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Low

*Potential rooting depth:* 22 to 31 inches

*Restriction affecting rooting depth:* Duripan at a depth of 23 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### ***Contrasting Inclusions***

Furshur very channery loam in convex areas (10 percent); Rubbleland (10 percent)

### ***Major Use***

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Wyoming big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope, the areas of Rock outcrop, the included areas of Rubbleland, and the hazard of erosion.
- Range seeding is not suitable on this unit. It is limited by the slope, the areas of Rock outcrop, the hazard of erosion, and the stony upper layer in the Adios soil.
- Fences and stock water pipelines are limited by the slope and by depth to the duripan and to bedrock.

### ***Capability Classification***

Vlle, nonirrigated

## **99—Rockybar extremely cobbly loam, 2 to 30 percent slopes**

### ***Composition***

Rockybar extremely cobbly loam, 2 to 30 percent slopes—75 percent

Contrasting inclusions—25 percent

### ***Characteristics of the Rockybar Soil***

*Position on landscape:* Outwash terraces

*Parent material:* Glacial outwash derived from igneous and metamorphic rock

*Elevation:* 5,500 to 6,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 9 inches—yellowish brown extremely cobbly loam

9 to 20 inches—light yellowish brown extremely cobbly loam

20 to 31 inches—light yellowish brown extremely cobbly clay loam

31 to 47 inches—light yellowish brown extremely cobbly loam

47 to 62 inches—yellowish brown extremely cobbly loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 60 inches or more

*Runoff:* Slow to rapid

*Hazard of water erosion:* Slight to severe

### ***Contrasting Inclusions***

Soils that are similar to the Rockybar soil but are more than 35 percent clay between depths of 9 and 31 inches and are in depressions (15 percent); soils that are similar to the Rockybar soil but are poorly drained and are along streams and other drainageways (10 percent)

### ***Major Uses***

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, bluebunch wheatgrass

*Main limitations:* Extremely cobbly upper layer, hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the extremely cobbly upper layer.
- Range seeding is suitable on this unit. Drilling is the best suited method.

#### **Pasture**

*General management considerations:*

- Proper grazing practices, irrigation water management, seeding of suitable forage plants, and applications of fertilizer help to improve the quality of forage on pastures.



- The best suited method of irrigation is a sprinkler system.
- Adjusting the rate at which irrigation water is applied to the available water capacity, the water intake rate, and the needs of the crop helps to prevent overirrigating and the leaching of plant nutrients.
- Seeding and mechanical treatment of brush are limited by the extremely cobbly upper layer.

### **Capability Classification**

VIs, irrigated and nonirrigated

## **100—Rubbleland**

*Position on landscape:* Commonly at the base of steep slopes or escarpments along major drainageways

*Kind of material:* Areas covered by cobbles, stones, and boulders

*Vegetation:* Little, if any

*Major use:* Wildlife habitat for small rodents and marmots and for sage grouse, hawks, falcons, and other birds

*Capability classification:* VIIIs

## **101—Rubbleland-Milligan complex, 60 to 75 percent slopes**

### **Composition**

Rubbleland—40 percent

Milligan very cobbly loam, 60 to 75 percent slopes—35 percent

Contrasting inclusions—25 percent

### **Characteristics of the Rubbleland**

*Position on landscape:* South- and west-facing side slopes

*Kind of material:* Areas covered by stones, flagstones, and cobbles

*Vegetation:* Sparse woody shrubs and annual weeds

### **Characteristics of the Milligan Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 5,200 to 8,500 feet

*Average annual precipitation:* About 16 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 8 inches—brown very cobbly loam

8 to 18 inches—yellowish brown extremely cobbly loam

18 to 24 inches—gray, fractured, quartzitic sandstone that has brown loam between the fracture planes and in the cracks

24 inches—quartzitic sandstone

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid in the upper 18 inches; very rapid below this depth

*Available water capacity:* Very low

*Potential rooting depth:* 20 to 40 inches

*Restriction affecting rooting depth:* Bedrock at a depth of 24 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Rock outcrop on ridges (15 percent); Povey gravelly loam on north- and east-facing slopes at elevations below 7,500 feet and all aspects at elevations above 7,500 feet (10 percent)

### **Major Use**

### **Rangeland (Milligan soil)**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.
- Fences and stock water pipelines are limited by the slope and the depth to bedrock.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

### **Capability Classification**

VIIIe, nonirrigated

## **102—Simonton loam, 2 to 4 percent slopes**

### **Composition**

Simonton loam, 2 to 4 percent slopes—85 percent

Contrasting inclusions—15 percent

### **Characteristics of the Simonton Soil**

*Position on landscape:* Fan terraces

*Parent material:* Alluvium derived from granite

*Elevation:* 4,800 to 5,500 feet



*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days

*Typical profile:*  
0 to 12 inches—brown and yellowish brown loam  
12 to 52 inches—yellowish brown and light  
yellowish brown clay loam and sandy clay loam  
52 to 64 inches—pale brown sandy loam

*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Runoff:* Slow  
*Hazard of water erosion:* Slight

**Contrasting Inclusions**

Peevywell stony loam in convex areas (10 percent);  
Marshdale loam in drainageways and depressions  
(5 percent)

**Major Uses**

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats,  
alfalfa hay, pasture  
*General management considerations:*  
• A suitable cropping system, crop residue  
management, irrigation water management, and  
applications of fertilizer help to maintain fertility and tilth.  
• Proper grazing practices, irrigation water  
management, seeding of suitable forage plants, and  
applications of fertilizer improve the quality of forage on  
pastures.  
• The best suited method of irrigation is a sprinkler  
system. Use of this method permits an even, controlled  
application of water, reduces the rate of runoff, and  
minimizes the risk of water erosion. Corrugation  
systems are also suitable.  
• Adjusting the rate at which irrigation water is applied  
to the available water capacity, the water intake rate,  
and the needs of the crop helps to prevent  
overirrigating and the leaching of plant nutrients.

**Capability Classification**

IIIe, irrigated; IIIc, nonirrigated

**103—Simonton loam, 4 to 8 percent slopes**

**Composition**

Simonton loam, 4 to 8 percent slopes—85 percent  
Contrasting inclusions—15 percent

**Characteristics of the Simonton Soil**

*Position on landscape:* Fan terraces  
*Parent material:* Alluvium derived from granite  
*Elevation:* 4,800 to 5,500 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
0 to 12 inches—brown and yellowish brown loam  
12 to 52 inches—yellowish brown and light  
yellowish brown clay loam and sandy clay loam  
52 to 64 inches—pale brown sandy loam

*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* High  
*Potential rooting depth:* 60 inches or more  
*Runoff:* Medium  
*Hazard of water erosion:* Moderate

**Contrasting Inclusions**

Peevywell stony loam in convex areas (5 percent);  
Marshdale loam in drainageways and depressions  
(5 percent); soils that are similar to the Simonton  
soil but have more than 35 percent clay below the  
upper layer (5 percent)

**Major Uses**

**Cropland, hayland, and pasture**

*Currently grown irrigated crops:* Wheat, barley, oats,  
alfalfa hay, pasture  
*General management considerations:*  
• A suitable cropping system, crop residue  
management, irrigation water management, and  
applications of fertilizer help to maintain fertility and tilth.  
• Proper grazing practices, irrigation water  
management, seeding of suitable forage plants, and  
applications of fertilizer improve the quality of forage on  
pastures.  
• The best suited method of irrigation is a sprinkler  
system. Use of this method permits an even, controlled  
application of water, reduces the rate of runoff, and  
minimizes the risk of water erosion.  
• Adjusting the rate at which irrigation water is applied  
to the available water capacity, the water intake rate,  
and the needs of the crop helps to prevent  
overirrigating and the leaching of plant nutrients.

**Capability Classification**

IIIe, irrigated and nonirrigated



## 104—Simonton-Bauscher complex, 4 to 15 percent slopes

### **Composition**

Simonton silt loam, 4 to 15 percent slopes—50 percent  
Bauscher loam, 4 to 15 percent slopes—30 percent  
Contrasting inclusions—20 percent

### **Characteristics of the Simonton Soil**

*Position on landscape:* Convex areas on fan terraces

*Parent material:* Alluvium derived from granite

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 11 inches—brown silt loam

11 to 43 inches—light yellowish brown clay loam

43 to 61 inches—light brown sandy clay loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Characteristics of the Bauscher Soil**

*Position on landscape:* Concave areas, depressions, and toe slopes on fan terraces

*Parent material:* Colluvium and alluvium derived from granite

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 14 inches—dark grayish brown and dark brown loam

14 to 37 inches—brown and dark yellowish brown sandy clay loam

37 to 42 inches—light yellowish brown coarse sandy loam

42 inches—weathered granitic rock

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Moderate

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Contrasting Inclusions**

Peevywell loam on eroded fan terraces (10 percent);  
Marshdale loam in wet areas (10 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, Idaho fescue

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

IIIe, nonirrigated

## 105—Starhope-Furshur complex, 4 to 15 percent slopes

### **Composition**

Starhope loam, 4 to 15 percent slopes—50 percent  
Furshur very channery loam, 4 to 15 percent slopes—30 percent

Contrasting inclusions—20 percent

### **Characteristics of the Starhope Soil**

*Position on landscape:* Concave areas on ridgetops

*Parent material:* Residuum derived from rhyolite

*Elevation:* 5,000 to 5,600 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 85 days

*Typical profile:*

0 to 9 inches—grayish brown and brown loam

9 to 23 inches—brown clay loam

23 to 26 inches—light brown gravelly clay loam

26 inches—rhyolite

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

### **Characteristics of the Furshur Soil**

*Position on landscape:* Convex areas on ridgetops

*Parent material:* Residuum derived from rhyolite

*Elevation:* 5,000 to 5,600 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 42 degrees F

*Frost-free period:* About 85 days

*Typical profile:*

0 to 2 inches—dark grayish brown very channery loam

2 to 5 inches—brown clay loam

5 to 15 inches—yellowish brown and brownish yellow clay and gravelly clay

15 to 20 inches—very pale brown duripan

20 inches—fractured, layered rhyolite that has lime and silica in the fractures

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Very slow

*Available water capacity:* Very low

*Potential rooting depth:* 14 to 20 inches

*Restriction affecting rooting depth:* Duripan at a depth of 15 inches

*Runoff:* Slow or medium

*Hazard of water erosion:* Slight or moderate

### **Contrasting Inclusions**

Smelter loam in convex areas (10 percent); Furshur very channery loam on toe slopes (5 percent); Rock outcrop (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Starhope soil—mountain big sagebrush, bluebunch wheatgrass; Furshur soil—alkali sagebrush, Idaho fescue

*Main limitations:* Very channery loam upper layer and very low available water capacity of the Furshur soil, hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment. Mechanical treatment is limited by the very channery loam upper layer in the Furshur soil and by the hazard of erosion. Prescribed burning is limited on the Furshur soil by the inability of alkali sagebrush to carry fire.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

VI, nonirrigated

### **106—Starhope-Peevywell-Smelter loams, 4 to 30 percent slopes**

#### **Composition**

Starhope loam, 4 to 30 percent slopes—35 percent

Peevywell loam, 4 to 15 percent slopes—25 percent

Smelter loam, 4 to 30 percent slopes—20 percent

Contrasting inclusions—20 percent

### **Characteristics of the Starhope Soil**

*Position on landscape:* Depressions and swales on south- and west-facing slopes of foothills

*Parent material:* Residuum derived from andesite, latite, and welded tuff

*Elevation:* 5,000 to 6,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 40 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 4 inches—grayish brown loam

4 to 10 inches—brown and yellowish brown loam

10 to 30 inches—yellowish brown and light yellowish brown clay loam

30 inches—welded tuff

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate to very severe

*Shrink-swell potential:* High

### **Characteristics of the Peevywell Soil**

*Position on landscape:* Eroded and convex areas on foothills

*Parent material:* Alluvium derived from mixed igneous and metamorphic rock

*Elevation:* 5,000 to 6,500 feet

*Average annual precipitation:* About 13 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 12 inches—brown loam

12 to 22 inches—yellowish brown and brown clay loam

22 to 30 inches—brown clay

30 to 44 inches—indurated duripan



44 to 61 inches—yellowish brown very gravelly sandy loam

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* Low

*Potential rooting depth:* 24 to 35 inches

*Restriction affecting rooting depth:* Duripan at a depth of 30 inches

*Runoff:* Medium or rapid

*Hazard of water erosion:* Moderate or severe

*Shrink-swell potential:* High

### **Characteristics of the Smelter Soil**

*Position on landscape:* North- and east-facing slopes of foothills

*Parent material:* Residuum and alluvium derived from andesite, latite, and welded tuff

*Elevation:* 5,000 to 6,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 40 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 18 inches—dark grayish brown loam

18 to 35 inches—brown and yellowish brown clay loam

35 to 61 inches—light yellowish brown sandy clay loam

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Slow

*Available water capacity:* High

*Potential rooting depth:* 60 inches or more

*Runoff:* Medium to very rapid

*Hazard of water erosion:* Moderate to very severe

*Shrink-swell potential:* Moderate

### **Contrasting Inclusions**

Elksel very cobbly loam on south- and west-facing slopes (10 percent); Friedman cobbly loam on steep north- and east-facing slopes (5 percent); Marshdale loam in drainageways (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Starhope soil—mountain big sagebrush, bluebunch wheatgrass; Peevywell soil—alkali sagebrush, Idaho fescue; Smelter soil—mountain big sagebrush, Idaho fescue

*Main limitation:* Hazard of erosion

*General management considerations:*

- Brush management, proper distribution of livestock, and range seeding are needed.
- Suitable methods of brush management are prescribed burning, chemical spraying, and mechanical treatment.
- Range seeding is suitable on this unit. Drilling is the best suited method.

### **Capability Classification**

Ive, nonirrigated

## **107—Vitale-Blackspar complex, 30 to 60 percent slopes**

### **Composition**

Vitale very gravelly loam, 30 to 60 percent slopes—45 percent

Blackspar very cobbly loam, 30 to 60 percent slopes—35 percent

Contrasting inclusions—20 percent

### **Characteristics of the Vitale Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Residuum and colluvium derived dominantly from quartzitic sandstone and conglomerate

*Elevation:* 5,000 to 8,000 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 6 inches—dark grayish brown very gravelly loam

6 to 15 inches—brown very gravelly clay loam

15 to 23 inches—light brownish gray very gravelly loam

23 inches—quartzitic sandstone

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Restriction affecting rooting depth:* Bedrock at a depth of 23 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Blackspar Soil**

*Position on landscape:* South- and west-facing slopes of ridges

*Parent material:* Colluvium and slope alluvium derived dominantly from quartzitic sandstone and conglomerate  
*Elevation:* 5,200 to 8,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
0 to 3 inches—brown very cobbly loam  
3 to 7 inches—yellowish brown very cobbly loam  
7 to 17 inches—light yellowish brown extremely cobbly loam  
17 inches—quartzitic sandstone  
*Depth class:* Shallow  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Very low  
*Potential rooting depth:* 10 to 20 inches  
*Restriction affecting rooting depth:* Bedrock at a depth of 17 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

**Contrasting Inclusions**

Rock outcrop on ridges (10 percent); Povey gravelly loam on north- and east-facing slopes at elevations below 7,500 feet and on all aspects at elevations above 7,500 feet (5 percent); Drage gravelly loam on toe slopes and in drainageways (5 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Vitale soil—mountain big sagebrush, bluebunch wheatgrass; Blackspar soil—low sagebrush, bluebunch wheatgrass  
*General management considerations:*  
• Brush management and proper distribution of livestock are needed.  
• Chemical spraying is a suitable method of brush management. Mechanical treatment is limited by the slope. Prescribed burning is limited by the slope and by the difficulty of maintaining a fire on the Blackspar soil.  
• Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

**Capability Classification**

Vlle, nonirrigated

**108—Vitale-Milligan complex, 30 to 60 percent slopes**

**Composition**

Vitale very gravelly loam, 30 to 60 percent slopes—50 percent  
Milligan very cobbly loam, 30 to 60 percent slopes—30 percent  
Contrasting inclusions—20 percent

**Characteristics of the Vitale Soil**

*Position on landscape:* South- and west-facing mountainsides  
*Parent material:* Residuum and colluvium derived dominantly from quartzitic sandstone and related rock  
*Elevation:* 5,200 to 8,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
0 to 6 inches—brown very gravelly loam  
6 to 15 inches—brown very gravelly clay loam  
15 to 23 inches—light brownish gray very gravelly loam  
23 inches—quartzitic sandstone  
*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Available water capacity:* Low  
*Potential rooting depth:* 20 to 40 inches  
*Restriction affecting rooting depth:* Bedrock at a depth of 23 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

**Characteristics of the Milligan Soil**

*Position on landscape:* South- and west-facing mountainsides  
*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock  
*Elevation:* 5,200 to 8,000 feet  
*Average annual precipitation:* About 14 inches  
*Average annual air temperature:* About 41 degrees F  
*Frost-free period:* About 75 days  
*Typical profile:*  
0 to 8 inches—brown very cobbly loam



8 to 18 inches—yellowish brown extremely cobbly loam

18 to 24 inches—gray, fractured, quartzitic sandstone that has brown loam in the fractures

24 inches—quartzitic sandstone

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid in the upper 18 inches; very rapid below this depth

*Available water capacity:* Very low

*Potential rooting depth:* 20 to 40 inches

*Restriction affecting rooting depth:* Bedrock at a depth of 24 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Contrasting Inclusions**

Rock outcrop on ridges (10 percent); Povey gravelly loam on north- and east-facing slopes at elevations above 7,500 feet (5 percent); Rubbleland (5 percent)

### **Major Use**

#### **Rangeland**

*Dominant vegetation in potential natural plant community:*

Mountain big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.
- Fences and stock water pipelines are limited by the slope and the depth to bedrock.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

### **Capability Classification**

VIIe, nonirrigated

## **109—Vitale-Povey association, 30 to 60 percent slopes**

### **Composition**

Vitale very gravelly loam, 30 to 60 percent slopes—50 percent

Povey gravelly loam, 30 to 60 percent slopes—30 percent

Contrasting inclusions—20 percent

### **Characteristics of the Vitale Soil**

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Residuum and colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 5,200 to 8,600 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 6 inches—dark grayish brown very gravelly loam

6 to 15 inches—brown very gravelly clay loam

15 to 23 inches—light brownish gray very gravelly loam

23 inches—quartzitic sandstone

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Restriction affecting rooting depth:* Bedrock at a depth of 23 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### **Characteristics of the Povey Soil**

*Position on landscape:* North- and east-facing mountainsides at elevations below 7,500 feet; all aspects of mountainsides at elevations above 7,500 feet

*Parent material:* Colluvium derived dominantly from quartzitic sandstone and related rock

*Elevation:* 5,200 to 8,600 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 14 inches—dark grayish brown and grayish brown gravelly loam

14 to 35 inches—brown very gravelly loam

35 to 60 inches—brown extremely cobbly loam

60 inches—quartzitic sandstone

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Available water capacity:* Low

*Potential rooting depth:* 40 to 60 inches

*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

**Contrasting Inclusions**

Rock outcrop on ridges (10 percent); Dollarhide very gravelly fine sandy loam on ridges and north- and east-facing slopes (5 percent); Rubbleland (5 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Vitale soil—mountain big sagebrush, bluebunch wheatgrass; Povey soil—mountain big sagebrush, Idaho fescue

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Mechanical treatment and prescribed burning are limited by the slope.
- Fences and stock water pipelines are limited by the slope and by the depth to bedrock in the Vitale soil.
- Range seeding is not suitable on this unit because of the slope and the hazard of erosion.

**Capability Classification**

VIIe, nonirrigated

**110—Winu-Rock outcrop complex, 30 to 60 percent slopes**

**Composition**

Winu stony loam, 30 to 60 percent slopes—70 percent  
Rock outcrop—20 percent  
Contrasting inclusions—10 percent

**Characteristics of the Winu Soil**

*Position on landscape:* North- and east-facing mountainsides  
*Parent material:* Colluvium derived dominantly from latite, andesite, and basalt  
*Elevation:* 5,500 to 7,500 feet  
*Average annual precipitation:* About 18 inches  
*Average annual air temperature:* About 39 degrees F  
*Frost-free period:* Less than 60 days  
*Typical profile:*

- 0 to 13 inches—dark grayish brown and brown stony loam
- 13 to 21 inches—brown gravelly loam
- 21 to 35 inches—yellowish brown gravelly clay loam
- 35 inches—basalt

*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Available water capacity:* Low  
*Potential rooting depth:* 24 to 40 inches  
*Runoff:* Very rapid  
*Hazard of water erosion:* Very severe

**Characteristics of the Rock Outcrop**

*Position on landscape:* Convex areas, ridgetops  
*Kind of material:* Exposed basalt

**Contrasting Inclusions**

Elkcreek loam on south- and west-facing slopes (5 percent); Gaib stony loam on south- and west-facing slopes (5 percent)

**Major Use**

**Rangeland**

*Dominant vegetation in potential natural plant community:*  
Mountain big sagebrush, Idaho fescue  
*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope, the hazard of erosion, and the areas of Rock outcrop.
- Range seeding is not suitable on this unit because of the slope, the hazard of erosion, and the stony upper layer in the Winu soil.
- Fences and stock water pipelines are limited by the slope, the hazard of erosion, and the areas of Rock outcrop.

**Capability Classification**

VIIe, nonirrigated

**111—Winu-Gaib association, 30 to 60 percent slopes**

**Composition**

Winu stony loam, 30 to 60 percent slopes—50 percent  
Gaib very gravelly loam, 30 to 60 percent slopes—30 percent  
Contrasting inclusions—20 percent

**Characteristics of the Winu Soil**

*Position on landscape:* North- and east-facing mountainsides  
*Parent material:* Colluvium derived dominantly from latite, andesite, and basalt



*Elevation:* 5,500 to 7,500 feet

*Average annual precipitation:* About 18 inches

*Average annual air temperature:* About 39 degrees F

*Frost-free period:* Less than 60 days

*Typical profile:*

0 to 13 inches—dark grayish brown and brown stony loam

13 to 21 inches—brown gravelly loam

21 to 35 inches—yellowish brown gravelly clay loam

35 inches—basalt

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Low

*Potential rooting depth:* 20 to 40 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### ***Characteristics of the Gaib Soil***

*Position on landscape:* South- and west-facing mountainsides

*Parent material:* Residuum derived from andesite, latite, and basalt

*Elevation:* 5,500 to 7,500 feet

*Average annual precipitation:* About 14 inches

*Average annual air temperature:* About 41 degrees F

*Frost-free period:* About 75 days

*Typical profile:*

0 to 5 inches—brown very gravelly loam

5 to 13 inches—dark yellowish brown very cobbly clay loam

13 inches—basalt

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Available water capacity:* Very low

*Potential rooting depth:* 10 to 20 inches

*Runoff:* Very rapid

*Hazard of water erosion:* Very severe

### ***Contrasting Inclusions***

Elkcreek loam on concave south- and west-facing slopes (10 percent); Rock outcrop in convex areas (10 percent)

### ***Major Use***

#### ***Rangeland***

*Dominant vegetation in potential natural plant community:*

Winu soil—mountain big sagebrush, Idaho fescue;

Gaib soil—mountain big sagebrush, bluebunch wheatgrass

*General management considerations:*

- Brush management and proper distribution of livestock are needed.
- Chemical spraying is a suitable method of brush management. Prescribed burning and mechanical treatment are limited by the slope and the hazard of erosion.
- Range seeding is not suitable on this unit because of the slope, the hazard of erosion, and the stony upper layer in the Winu soil.
- Fences and stock water pipelines are limited by the slope, the hazard of erosion, and the depth to bedrock.

### ***Capability Classification***

VIIe, nonirrigated

# Prime Farmland

---

Prime farmland is one of several kinds of important farmland defined by the U.S. Department of Agriculture. It is of major importance in meeting the Nation's short- and long-range needs for food and fiber. Because the supply of high-quality farmland is limited, the U.S. Department of Agriculture recognizes that responsible levels of government, as well as individuals, should encourage and facilitate the wise use of our Nation's prime farmland.

Prime farmland, as defined by the U.S. Department of Agriculture, is the land that is best suited to food, feed, forage, fiber, and oilseed crops. It may be cultivated land, pasture, woodland, or other land, but it is not urban and built-up land or water areas. It either is used for food or fiber crops or is available for those crops. The soil qualities, growing season, and moisture supply are those needed for a well managed soil to produce a sustained high yield of crops in an economic manner. Prime farmland produces the highest yields with minimal expenditure of energy and economic resources, and farming it results in the least damage to the environment.

Prime farmland has an adequate and dependable supply of moisture from precipitation or irrigation. The temperature and growing season are favorable. The level of acidity or alkalinity is acceptable. Prime farmland has few or no rocks and is permeable to water and air. It is not excessively erodible or saturated with water for long periods and is not frequently flooded during the growing season. The slope ranges mainly from 0 to 6 percent. More detailed information about the criteria for prime farmland is available at the local office of the Soil Conservation Service.

A recent trend in land use in some parts of the survey area has been the loss of some prime farmland to industrial and urban uses. The loss of prime farmland to other uses puts pressure on marginal lands, which generally are more erodible, droughty, and less productive and cannot be easily cultivated.

Soils that have limitations, such as a seasonal high water table, frequent flooding during the growing season, or inadequate rainfall, qualify for prime

farmland only in areas where these limitations have been overcome by such measures as drainage, flood control, or irrigation. The need for these measures is indicated after the map unit name on the following list. Onsite evaluation is necessary to determine whether or not these limitations have been overcome by corrective measures.

The following map units meet the soil requirements for prime farmland. Some of the units meet the requirements only if an adequate and dependable supply of irrigation water is available. The location of each map unit is shown on the detailed soil maps at the back of this publication. Soil qualities that affect use and management are described in the section "Detailed Soil Map Units." This list does not constitute a recommendation for a particular land use.

- |    |   |
|----|---|
| 1  | Adamson loam, 0 to 2 percent slopes (where irrigated)                   |
| 9  | Bancroft silt loam, 1 to 4 percent slopes                               |
| 10 | Bancroft silt loam, 4 to 8 percent slopes                               |
| 15 | Bringmee loam, 0 to 2 percent slopes                                    |
| 16 | Bringmee loam, 2 to 4 percent slopes                                    |
| 17 | Bringmee loam, 4 to 8 percent slopes                                    |
| 19 | Bringmee-Little Wood complex, 1 to 4 percent slopes (where irrigated)   |
| 21 | Carey Lake loam, 0 to 2 percent slopes                                  |
| 22 | Carey Lake loam, 2 to 4 percent slopes                                  |
| 28 | Drage gravelly loam, 4 to 8 percent slopes (where irrigated)            |
| 31 | Drage very gravelly loam, cool, 0 to 3 percent slopes (where irrigated) |
| 51 | Isknot gravelly clay loam, 0 to 2 percent slopes (where irrigated)      |
| 52 | Justesen loam, 2 to 4 percent slopes                                    |
| 53 | Justesen loam, 4 to 8 percent slopes                                    |
| 64 | Little Wood gravelly loam, 0 to 2 percent slopes (where irrigated)      |
| 65 | Little Wood gravelly loam, 2 to 4 percent slopes (where irrigated)      |
| 66 | Little Wood very gravelly loam, 0 to 2 percent slopes (where irrigated) |



|    |   |     |   |
|----|---|-----|---|
| 67 | Little Wood very gravelly loam, 2 to 4 percent slopes (where irrigated)       | 76  | McCarey-Molyneux loams, 2 to 8 percent slopes |
| 68 | Little Wood very gravelly loam, cool, 1 to 4 percent slopes (where irrigated) | 78  | Molyneux loam, 2 to 4 percent slopes          |
| 74 | McCarey-Justesen loams, 2 to 8 percent slopes                                 | 79  | Molyneux loam, 4 to 8 percent slopes          |
|    |   | 102 | Simonton loam, 2 to 4 percent slopes          |
|    |   | 103 | Simonton loam, 4 to 8 percent slopes          |

# Use and Management of the Soils

---

This soil survey is an inventory and evaluation of the soils in the survey area. It can be used to adjust land uses to the limitations and potentials of natural resources and the environment. Also, it can help avoid soil-related failures in land uses.

In preparing a soil survey, soil scientists, conservationists, engineers, and others collect extensive field data about the nature and behavioral characteristics of the soils. They collect data on erosion, droughtiness, flooding, and other factors that affect various soil uses and management. Field experience and collected data on soil properties and performance are used as a basis in predicting soil behavior.

Information in this section can be used to plan the use and management of soils for crops and pasture; as rangeland; as sites for buildings, sanitary facilities, highways and other transportation systems, and parks and other recreation facilities; and for wildlife habitat. It can be used to identify the limitations of each soil for specific land uses and to help prevent construction failures caused by unfavorable soil properties.

Planners and others using soil survey information can evaluate the effect of specific land uses on productivity and on the environment in the survey area. The survey can help planners to maintain or create a land use pattern in harmony with the natural soil.

Contractors can use this survey to locate sources of sand and gravel, roadfill, and topsoil. They can use it to identify areas where bedrock, wetness, or very firm soil layers can cause difficulty in excavation.

Health officials, highway officials, engineers, and others may also find this survey useful. The survey can help them plan the safe disposal of wastes and locate sites for pavements, sidewalks, campgrounds, playgrounds, lawns, and trees and shrubs.

## Crops and Pasture

Prepared by Gale Roberts, district conservationist, Soil Conservation Service.

General management needed for crops and pasture is suggested in this section. The system of land

capability classification used by the Soil Conservation Service is explained, and the estimated yields of the main crops and hay and pasture plants are listed for each soil.

Planners of management systems for individual fields or farms should consider the detailed information given in the description of each soil under "Detailed Soil Map Units." Specific information can be obtained from the local office of the Soil Conservation Service or the Cooperative Extension Service.

About 79,000 acres of the survey area is used as cropland, hayland, and pasture. Of this, about 29,000 acres is used primarily for cultivated crops and 50,000 acres is used for hay and pasture. About 72,680 acres, or 92 percent, of the cropland, hayland, and pasture is irrigated.

Spring wheat and barley are the main crops grown in the area. Because temperatures are cool, high-quality malting barley can be grown. The short growing season limits the production of most row crops. Less than 500 acres is used for potatoes and silage corn. Spring grain commonly is grown as a cash crop before hay or other grain is established. Growing hay, grain, and pasture in combination with a livestock operation is the most common farming enterprise in the survey area.

If grain is grown, crop residue should be left on the surface to maintain the organic matter content and tilth of the soil and to control erosion. Including grasses and legumes in the cropping system also helps to control erosion and maintain fertility and tilth. Grain generally responds to nitrogen, and legumes respond to phosphorus. A good fertilization program is essential for maximum production.

Steeply sloping soils should be farmed across the slope. Tillage should be designed to keep the soil surface rough and cloddy. A minimum of 1,500 pounds of crop residue should be kept on the soil surface in winter and early in spring to protect the soil from erosion. Minimum tillage and no-till are suitable practices.

Irrigation water is supplied by streams and rivers, reservoirs, and wells. Sprinkler irrigation is the most



widely used method of applying water. Applications of irrigation water should be adjusted to the available water capacity of the soil, the water intake rate, and the needs of the crops.

Drainage from local seeps and from wet soils on bottom land is a concern in some areas. Open drains and tile lines can be used effectively. Some of the soils have a seasonal high water table and are subject to flooding, which limits the kinds of crops that can be grown and their yields.

Much of the pasture in the area is in poor condition because of continuous overgrazing, a lack of sufficient fertilizer, and the encroachment of less productive plants. As a result, the production of forage has been greatly reduced. Because of the limited plant cover, soil erosion and gullying occur in the drainageways in some areas.

Among the suitable management practices are rotation grazing, crossfencing, constructing water developments, and allowing adequate periods for regrowth. Use of high-producing, suitable plants and applications of fertilizer, including nitrogen, phosphorus, and sulfur, are needed to improve the condition of the pasture. Grasses generally respond to nitrogen and sulfur, and legumes respond to phosphorus. Livestock should not be allowed to graze too early in spring, before the plants have reached adequate growth and the soils are firm enough to withstand trampling.

Hayland can be improved by applying fertilizer, cutting hay only when it is at the proper protein content, and leaving an adequate amount of fall stubble.

### **Yields Per Acre**

The average yields per acre that can be expected of the principal crops under a high level of management are shown in table 5. In any given year, yields may be higher or lower than those indicated in the table because of variations in rainfall and other climatic factors.

The yields are based mainly on the experience and records of farmers, conservationists, and extension agents. Available yield data from nearby counties and results of field trials and demonstrations are also considered.

The management needed to obtain the indicated yields of the various crops depends on the kind of soil and the crop. Management can include drainage, erosion control, and protection from flooding; the proper planting and seeding rates; suitable high-yielding crop varieties; appropriate and timely tillage; control of weeds, plant diseases, and harmful insects; favorable

soil reaction and optimum levels of nitrogen, phosphorus, potassium, and trace elements for each crop; effective use of crop residue, barnyard manure, and green-manure crops; and harvesting that ensures the smallest possible loss.

For yields of irrigated crops, it is assumed that the irrigation system is adapted to the soils and to the crops grown, that good-quality irrigation water is uniformly applied as needed, and that tillage is kept to a minimum.

The estimated yields reflect the productive capacity of each soil for each of the principal crops. Yields are likely to increase as new production technology is developed. The productivity of a given soil compared with that of other soils, however, is not likely to change.

Crops other than those shown in table 5 are grown in the survey area, but estimated yields are not listed because the acreage of such crops is small. The local office of the Soil Conservation Service or of the Cooperative Extension Service can provide information about the management and productivity of the soils for those crops.

### **Land Capability Classification**

Land capability classification shows, in a general way, the suitability of soils for most kinds of field crops. Crops that require special management are excluded. The soils are grouped according to their limitations for field crops, the risk of damage if they are used for crops, and the way they respond to management. The criteria used in grouping the soils do not include major and generally expensive landforming that would change slope, depth, or other characteristics of the soils, nor do they include possible but unlikely major reclamation projects. Capability classification is not a substitute for interpretations designed to show suitability and limitations of groups of soils for rangeland and for engineering purposes.

In the capability system (15), soils generally are grouped at three levels: capability class, subclass, and unit. Only class and subclass are used in this survey.

*Capability classes*, the broadest groups, are designated by Roman numerals I through VIII. The numerals indicate progressively greater limitations and narrower choices for practical use. The classes are defined as follows:

Class I soils have few limitations that restrict their use.

Class II soils have moderate limitations that reduce the choice of plants or that require moderate conservation practices.



Class III soils have severe limitations that reduce the choice of plants or that require special conservation practices, or both.

Class IV soils have very severe limitations that reduce the choice of plants or that require very careful management, or both.

Class V soils are not likely to erode but have other limitations, impractical to remove, that limit their use.

Class VI soils have severe limitations that make them generally unsuitable for cultivation.

Class VII soils have very severe limitations that make them unsuitable for cultivation.

Class VIII soils and miscellaneous areas have limitations that nearly preclude their use for commercial crop production.

*Capability subclasses* are soil groups within one class. They are designated by adding a small letter, *e*, *w*, *s*, or *c*, to the class numeral, for example, IIIe. The letter *e* shows that the main hazard is the risk of erosion unless close-growing plant cover is maintained; *w* shows that water in or on the soil interferes with plant growth or cultivation (in some soils the wetness can be partly corrected by artificial drainage); *s* shows that the soil is limited mainly because it is shallow, droughty, or stony; and *c*, used in only some parts of the United States, shows that the chief limitation is climate that is very cold or very dry.

In class I there are no subclasses because the soils of this class have few limitations. Class V contains only the subclasses indicated by *w*, *s*, or *c* because the soils in class V are subject to little or no erosion. They have other limitations that restrict their use to pasture, rangeland, wildlife habitat, or recreation.

The capability classification of each map unit is given in the section "Detailed Soil Map Units."

## Rangeland

Prepared by Dennis K. Froeming, area range conservationist, Soil Conservation Service.

About 662,174 acres, or 82 percent, of the survey area is used as rangeland. Of this, about 597,094 acres is administered by the Bureau of Land Management and 65,080 acres is administered by the state or is privately owned. The rangeland is used for livestock and wildlife grazing, as recreation sites, and as valuable watershed for the Big Wood and Little Wood Rivers. Sheep and cattle operations contribute significantly to the economy of the survey area. The rangeland is best suited to grazing in spring and summer.

In areas that have similar climate and topography, differences in the kind and amount of vegetation

produced on rangeland are closely related to the kind of soil. Effective management is based on the relationship between the soils and vegetation and water.

Table 6 shows, for each soil, the range site; the total annual production of vegetation in favorable, normal, and unfavorable years; the characteristic vegetation; and the average percentage of each species. Only those soils that are used as rangeland or are suited to use as rangeland are listed. An explanation of the column headings in table 6 follows.

A *range site* is a distinctive kind of rangeland that produces a characteristic natural plant community that differs from natural plant communities on other range sites in kind, amount, and proportion of range plants (17). The relationship between soils and vegetation was established during this survey; thus, range sites generally can be determined directly from the soil map. Soil properties that affect moisture supply and plant nutrients have the greatest influence on the productivity of range plants. Soil reaction, salt content, and a seasonal high water table are also important.

Each range site is identified by a range site number, a name that includes soil or topographic characteristics and the mean annual precipitation, and the main species in the plant community. The range site numbers are used mainly to coordinate range sites within and between states. *011by003i* is an example of such a number. The first three digits identify the major land resource area. The next 2 letters are subdivisions of the land resource area. If there are no subdivisions, an *x* and *y* appear in these positions. The next three digits make up the coordinated range site number, which is followed by a letter that identifies the state in which the range site occurs. Land resource area subdivision maps are available at the local offices of the Soil Conservation Service. The key indicator species in the plant community are given in abbreviated form following the range site name and number. The abbreviations are defined in the "National List of Scientific Plant Names" (18).

*Total production* is the amount of vegetation that can be expected to grow annually on well managed rangeland that is supporting the potential natural plant community. It includes all vegetation, whether or not it is palatable to grazing animals. It includes the current year's growth of leaves, twigs, and fruit of woody plants. It does not include the increase in stem diameter of trees and shrubs. It is expressed in pounds per acre of air-dry vegetation for favorable, normal, and unfavorable years. In a favorable year, the amount and distribution of precipitation and the temperatures make growing conditions substantially better than average. In a normal



year, growing conditions are about average. In an unfavorable year, growing conditions are well below average because of low available soil moisture, cool temperatures, and other factors.

*Dry weight* is the total annual yield per acre of air-dry vegetation. Yields are adjusted to a common percent of air-dry moisture content. The relationship of green weight to air-dry weight varies according to such factors as exposure, amount of shade, recent rains, and unseasonable dry periods.

*Characteristic vegetation*—the grasses, forbs, and shrubs that make up most of the potential natural plant community on each soil—is listed by common name. Under *composition*, the expected percentage of the total annual production is given for each species making up the characteristic vegetation. The amount that can be used as forage depends on the kinds of grazing animals and on the grazing season.

Range management requires a knowledge of the kinds of soil and of the potential natural plant community. It also requires an evaluation of the present range condition. Range condition is determined by comparing the present plant community with the potential natural plant community on a particular range site. The more closely the existing community resembles the potential community, the better the range condition. Range condition is an ecological rating only. It does not have a specific meaning that pertains to the present plant community in a given use.

The objective in range management is to control grazing so that the plants growing on a site are about the same in kind and amount as the potential natural plant community for that site. Such management generally results in the optimum production of vegetation, control of undesirable brush species, conservation of water, and control of erosion. Sometimes, however, a range condition somewhat below the potential meets grazing needs, provides wildlife habitat, and protects soil and water resources.

The primary management practice needed on rangeland in this survey area is a planned grazing system that allows plants to achieve sufficient growth in spring to withstand grazing pressure, allows the soils to dry out in spring to avoid damage from trampling, allows for periodic rest or deferment of grazing, and allows for removal of livestock when an optimum amount of forage has been grazed. Practices such as constructing water developments and fences, managing brush, range seeding, and properly distributing livestock facilitate the grazing system and help to bring about needed changes in the plant community. The suitability of specific practices is determined by the various

characteristics of individual soils.

## Windbreaks and Environmental Plantings

Windbreaks protect livestock, buildings, and yards from wind and snow. They also protect fruit trees and gardens, and they furnish habitat for wildlife. Several rows of low- and high-growing broadleaf and coniferous trees and shrubs provide the most protection.

Field windbreaks are narrow plantings made at right angles to the prevailing wind and at specific intervals across the field. The interval depends on the erodibility of the soil. Field windbreaks protect cropland and crops from wind, hold snow on the fields, and provide food and cover for wildlife.

Environmental plantings help to beautify and screen houses and other buildings and to abate noise. The plants, mostly evergreen shrubs and trees, are closely spaced. To ensure plant survival, a healthy planting stock of suitable species should be planted properly on a well prepared site and maintained in good condition.

Table 7 shows the height that locally grown trees and shrubs are predicted to reach in 20 years on various soils. The estimates in table 7 are based on measurements and observation of established plantings that have been given adequate care. They can be used as a guide in planning windbreaks and screens. Additional information on planning windbreaks and screens and planting and caring for trees and shrubs can be obtained from local offices of the Soil Conservation Service or the Cooperative Extension Service or from a nursery.

## Recreation

The survey area includes many scenic areas and recreational opportunities. The Sun Valley ski resort is at the northern end of the area. Trout fishing is excellent in the rivers, creeks, and manmade reservoirs. Silver Creek, a fly fishing stream, is in the middle of the survey area.

Big game animals, including deer, elk, antelope, bear, and mountain goat, and waterfowl inhabit the area and provide good hunting opportunities. Many of these species can be found in the lower lying foothills and valleys much of the year.

Many public and private recreational facilities are available in the area. Most of these facilities provide services year round. The demand for recreational facilities is expected to increase during the next several years.

The soils of the survey area are rated in table 8



according to limitations that affect their suitability for recreation. The ratings are based on restrictive soil features, such as wetness, slope, and texture of the surface layer. Susceptibility to flooding is considered. Not considered in the ratings, but important in evaluating a site, are the location and accessibility of the area, the size and shape of the area and its scenic quality, vegetation, access to water, potential water impoundment sites, and access to public sewer lines. The capacity of the soil to absorb septic tank effluent and the ability of the soil to support vegetation are also important. Soils subject to flooding are limited for recreation use by the duration and intensity of flooding and the season when flooding occurs. In planning recreation facilities, onsite assessment of the height, duration, intensity, and frequency of flooding is essential.

In table 8, the degree of soil limitation is expressed as slight, moderate, or severe. *Slight* means that soil properties generally are favorable and that limitations are minor and easily overcome. *Moderate* means that limitations can be overcome or alleviated by planning, design, or special maintenance. *Severe* means that soil properties are unfavorable and that limitations can be offset only by costly soil reclamation, special design, intensive maintenance, limited use, or by a combination of these measures.

The information in table 8 can be supplemented by other information in this survey, for example, interpretations for dwellings without basements and for local roads and streets in table 9 and interpretations for septic tank absorption fields in table 10.

*Camp areas* require site preparation, such as shaping and leveling the tent and parking areas, stabilizing roads and intensively used areas, and installing sanitary facilities and utility lines. Camp areas are subject to heavy foot traffic and some vehicular traffic. The best soils are gently sloping and are not wet or subject to flooding during the period of use. The surface has few or no stones or boulders, absorbs rainfall readily but remains firm, and is not dusty when dry. Strong slopes and stones or boulders can greatly increase the cost of constructing campsites.

*Picnic areas* are subject to heavy foot traffic. Most vehicular traffic is confined to access roads and parking areas. The best soils for picnic areas are firm when wet, are not dusty when dry, are not subject to flooding during the period of use, and do not have slopes or stones or boulders that increase the cost of shaping sites or of building access roads and parking areas.

*Playgrounds* require soils that can withstand intensive foot traffic. The best soils are almost level and are not

wet or subject to flooding during the season of use. The surface is free of stones and boulders, is firm after rains, and is not dusty when dry. If grading is needed, the depth of the soil over bedrock or a hardpan should be considered.

*Paths and trails* for hiking and horseback riding should require little or no cutting and filling. The best soils are not wet, are firm after rains, are not dusty when dry, and are not subject to flooding more than once a year during the period of use. They have moderate slopes and few or no stones or boulders on the surface.

*Golf fairways* are subject to heavy foot traffic and some light vehicular traffic. Cutting or filling may be required. The best soils for use as golf fairways are firm when wet, are not dusty when dry, and are not subject to prolonged flooding during the period of use. They have moderate slopes and no stones or boulders on the surface. The suitability of the soil for tees or greens is not considered in rating the soils.

## Wildlife Habitat

Prepared by Mike Anderson, biologist, Soil Conservation Service.

The survey area provides favorable habitat for many kinds of wildlife. The diverse areas of rangeland, woodland, cropland, hayland, and water provide food and cover for many mammals, birds, and fish.

The largest and most abundant game fish in the survey area is rainbow trout. Brook trout inhabit the headwaters of many of the streams. Other important species include brown trout, cutthroat trout, and smallmouth bass. Important fishing waters include Magic Reservoir, the Big Wood River, the Little Wood River, and Silver Creek. Silver Creek has received national and international acclaim for its superb rainbow trout fly fishing opportunities.

Wildlife populations are determined largely by the supply of food, cover, and water. Habitats differ in their capacity to provide these essential needs. Some of these differences result from the various characteristics of the soils, and others result from the various kinds of management used. Good management is needed to improve and maintain habitat for wildlife.

Wildlife in the survey area use the riparian areas more than any other type of habitat. Big game and upland game animals use riparian areas for water, food, and cover. Many species of nongame birds and mammals use this habitat during part or all of their life cycle. Many other species, including beaver, muskrat, waterfowl, and several amphibians, live in riparian areas almost exclusively. Plant production and diversity are



highest in riparian areas, thus increasing the value of these areas to wildlife. Riparian areas are also attractive to livestock, especially cattle, because they provide shade, water, and food. The soils in general soil map units 11 and 14 are best suited to the development of riparian habitat.

Mule deer are the most abundant of the big game animals, but elk and pronghorn antelope are also in the area. The major winter range for deer is in the southern half of the survey area (21). The survey area provides crucial winter range for elk and summer range for antelope. Coyote, fox, badger, skunk, and numerous rodents, including ground and tree squirrels, are found throughout the area.

Waterfowl use habitat throughout the area, but the largest populations are along Silver Creek, in the Gannett and Picabo areas, and around Carey Lake. Principal waterfowl species include Canada geese, mallards, teal, sandhill cranes, and great blue heron.

Sage grouse is the dominant upland game bird in the area. It is found mainly in areas that support sagebrush and bunchgrass, but it also feeds in wetland and wet meadow areas late in spring and in summer. Chukars are scattered throughout the southern half of the area on rocky soils that are in canyons, have talus slopes, and are near a dependable water supply. Blue grouse are scattered throughout the northern half of the survey area in riparian areas that are close to stands of timber. These birds raise their broods in the riparian areas and feed on the insects and forbs. In winter, they commonly roost in fir trees at the slightly higher elevations.

Limited numbers of pheasants, Hungarian partridge, and quail are found in the southern half of the area. The pheasants are in the Carey area; quail are east of Magic Reservoir, along the Big Wood and Little Wood Rivers; and Hungarian partridge are throughout the southern half of the survey area. Mourning doves are found throughout the area in summer. They migrate out of the area in fall and then return in spring.

## Engineering

This section provides information for planning land uses related to urban development and to water management. Soils are rated for various uses, and the most limiting features are identified. The ratings are given in the following tables: Building Site Development, Sanitary Facilities, Construction Materials, and Water Management. The ratings are based on observed performance of the soils and on the estimated data and test data in the "Soil Properties" section.

*Information in this section is intended for land use*

*planning, for evaluating land use alternatives, and for planning site investigations prior to design and construction. The information, however, has limitations. For example, estimates and other data generally apply only to that part of the soil within a depth of 5 or 6 feet. Because of the map scale, small areas of different soils may be included within the mapped areas of a specific soil.*

*The information is not site specific and does not eliminate the need for onsite investigation of the soils or for testing and analysis by personnel experienced in the design and construction of engineering works.*

Government ordinances and regulations that restrict certain land uses or impose specific design criteria were not considered in preparing the information in this section. Local ordinances and regulations need to be considered in planning, in site selection, and in design.

Soil properties, site features, and observed performance were considered in determining the ratings in this section. During the fieldwork for this soil survey, determinations were made about grain-size distribution, liquid limit, plasticity index, soil reaction, depth to bedrock, hardness of bedrock within 5 or 6 feet of the surface, soil wetness, depth to a seasonal high water table, slope, likelihood of flooding, natural soil structure aggregation, and soil density. Data were collected about kinds of clay minerals, mineralogy of the sand and silt fractions, and the kind of adsorbed cations. Estimates were made for erodibility, permeability, corrosivity, shrink-swell potential, available water capacity, and other behavioral characteristics affecting engineering uses.

This information can be used to (1) evaluate the potential of areas for residential, commercial, industrial, and recreation uses; (2) make preliminary estimates of construction conditions; (3) evaluate alternative routes for roads, streets, highways, pipelines, and underground cables; (4) evaluate alternative sites for sanitary landfills, septic tank absorption fields, and sewage lagoons; (5) plan detailed onsite investigations of soils and geology; (6) locate potential sources of gravel, sand, earthfill, and topsoil; (7) plan drainage systems, irrigation systems, ponds, terraces, and other structures for soil and water conservation; and (8) predict performance of proposed small structures and pavements by comparing the performance of existing similar structures on the same or similar soils.

The information in the tables, along with the soil maps, the soil descriptions, and other data provided in this survey, can be used to make additional interpretations.

Some of the terms used in this soil survey have a



special meaning in soil science and are defined in the Glossary.

### Building Site Development

Table 9 shows the degree and kind of soil limitations that affect shallow excavations, dwellings with and without basements, small commercial buildings, local roads and streets, and lawns and landscaping. The limitations are considered *slight* if soil properties and site features generally are favorable for the indicated use and limitations are minor and easily overcome; *moderate* if soil properties or site features are not favorable for the indicated use and special planning, design, or maintenance is needed to overcome or minimize the limitations; and *severe* if soil properties or site features are so unfavorable or so difficult to overcome that special design, significant increases in construction costs, and possibly increased maintenance are required. Special feasibility studies may be required where the soil limitations are severe.

*Shallow excavations* are trenches or holes dug to a maximum depth of 5 or 6 feet for basements, graves, utility lines, open ditches, and other purposes. The ratings are based on soil properties, site features, and observed performance of the soils. The ease of digging, filling, and compacting is affected by the depth to bedrock, a cemented pan, or a very firm dense layer; stone content; soil texture; and slope. The time of the year that excavations can be made is affected by the depth to a seasonal high water table and the susceptibility of the soil to flooding. The resistance of the excavation walls or banks to sloughing or caving is affected by soil texture and the depth to the water table.

*Dwellings and small commercial buildings* are structures built on shallow foundations on undisturbed soil. The load limit is the same as that for single-family dwellings no higher than three stories. Ratings are made for small commercial buildings without basements, for dwellings with basements, and for dwellings without basements. The ratings are based on soil properties, site features, and observed performance of the soils. A high water table, flooding, shrink-swell potential, and organic layers can cause the movement of footings. A high water table, depth to bedrock or to a cemented pan, large stones, and flooding affect the ease of excavation and construction. Landscaping and grading that require cuts and fills of more than 5 or 6 feet are not considered.

*Local roads and streets* have an all-weather surface and carry automobile and light truck traffic all year. They have a subgrade of cut or fill soil material, a base

of gravel, crushed rock, or stabilized soil material, and a flexible or rigid surface. Cuts and fills generally are limited to less than 6 feet. The ratings are based on soil properties, site features, and observed performance of the soils. Depth to bedrock or to a cemented pan, a high water table, flooding, large stones, and slope affect the ease of excavating and grading. Soil strength (as inferred from the engineering classification of the soil), shrink-swell potential, frost action potential, and depth to a high water table affect the traffic-supporting capacity.

*Lawns and landscaping* require soils on which turf and ornamental trees and shrubs can be established and maintained. The ratings are based on soil properties, site features, and observed performance of the soils. Soil reaction, a high water table, depth to bedrock or to a cemented pan, the available water capacity in the upper 40 inches, and the content of salts, sodium, and sulfidic materials affect plant growth. Flooding, wetness, slope, stoniness, and the amount of sand, clay, or organic matter in the surface layer affect trafficability after vegetation is established.

### Sanitary Facilities

Table 10 shows the degree and the kind of soil limitations that affect septic tank absorption fields, sewage lagoons, and sanitary landfills. The limitations are considered *slight* if soil properties and site features generally are favorable for the indicated use and limitations are minor and easily overcome; *moderate* if soil properties or site features are not favorable for the indicated use and special planning, design, or maintenance is needed to overcome or minimize the limitations; and *severe* if soil properties or site features are so unfavorable or so difficult to overcome that special design, significant increases in construction costs, and possibly increased maintenance are required.

Table 10 also shows the suitability of the soils for use as daily cover for landfills. A rating of *good* indicates that soil properties and site features are favorable for the use and good performance and low maintenance can be expected; *fair* indicates that soil properties and site features are moderately favorable for the use and one or more soil properties or site features make the soil less desirable than the soils rated good; and *poor* indicates that one or more soil properties or site features are unfavorable for the use and overcoming the unfavorable properties requires special design, extra maintenance, or costly alteration.

*Septic tank absorption fields* are areas in which



effluent from a septic tank is distributed into the soil through subsurface tiles or perforated pipe. Only that part of the soil between depths of 24 and 72 inches is evaluated. The ratings are based on soil properties, site features, and observed performance of the soils. Permeability, a high water table, depth to bedrock or to a cemented pan, and flooding affect absorption of the effluent. Large stones and bedrock or a cemented pan interfere with installation.

Unsatisfactory performance of septic tank absorption fields, including excessively slow absorption of effluent, surfacing of effluent, and hillside seepage, can affect public health. Ground water can be polluted if highly permeable sand and gravel or fractured bedrock is less than 4 feet below the base of the absorption field, if slope is excessive, or if the water table is near the surface. There must be unsaturated soil material beneath the absorption field to filter the effluent effectively. Many local ordinances require that this material be of a certain thickness.

*Sewage lagoons* are shallow ponds constructed to hold sewage while aerobic bacteria decompose the solid and liquid wastes. Lagoons should have a nearly level floor surrounded by cut slopes or embankments of compacted soil. Lagoons generally are designed to hold the sewage within a depth of 2 to 5 feet. Nearly impervious soil material for the lagoon floor and sides is required to minimize seepage and contamination of ground water.

Table 10 gives ratings for the natural soil that makes up the lagoon floor. The surface layer and, generally, 1 or 2 feet of soil material below the surface layer are excavated to provide material for the embankments. The ratings are based on soil properties, site features, and observed performance of the soils. Considered in the ratings are slope, permeability, a high water table, depth to bedrock or to a cemented pan, flooding, large stones, and content of organic matter.

Excessive seepage because of rapid permeability of the soil or a water table that is high enough to raise the level of sewage in the lagoon causes a lagoon to function unsatisfactorily. Pollution results if seepage is excessive or if floodwater overtops the lagoon. A high content of organic matter is detrimental to proper functioning of the lagoon because it inhibits aerobic activity. Slope, bedrock, and cemented pans can cause construction problems, and large stones can hinder compaction of the lagoon floor.

*Sanitary landfills* are areas where solid waste is disposed of by burying it in soil. There are two types of landfill—trench and area. In a trench landfill, the waste is placed in a trench. It is spread, compacted, and

covered daily with a thin layer of soil excavated at the site. In an area landfill, the waste is placed in successive layers on the surface of the soil. The waste is spread, compacted, and covered daily with a thin layer of soil from a source away from the site.

Both types of landfill must be able to bear heavy vehicular traffic. Both types involve a risk of ground-water pollution. Ease of excavation and revegetation needs to be considered.

The ratings in table 10 are based on soil properties, site features, and observed performance of the soils. Permeability, depth to bedrock or to a cemented pan, a high water table, slope, and flooding affect both types of landfill. Texture, stones and boulders, highly organic layers, soil reaction, and content of salts and sodium affect trench type landfills. Unless otherwise stated, the ratings apply only to that part of the soil within a depth of about 6 feet. For deeper trenches, a limitation rated slight or moderate may not be valid. Onsite investigation is needed.

*Daily cover for landfill* is the soil material that is used to cover compacted solid waste in an area type sanitary landfill. The soil material is obtained offsite, transported to the landfill, and spread over the waste.

Soil texture, wetness, coarse fragments, and slope affect the ease of removing and spreading the material during wet and dry periods. Loamy or silty soils that are free of large stones or excess gravel are the best cover for a landfill. Clayey soils are sticky or cloddy and are difficult to spread; sandy soils are subject to wind erosion.

After soil material has been removed, the soil material remaining in the borrow area must be thick enough over bedrock, a cemented pan, or the water table to permit revegetation. The soil material used as final cover for a landfill should be suitable for plants. The surface layer generally has the best workability, more organic matter, and the best potential for plants. Material from the surface layer should be stockpiled for use as the final cover.

### Construction Materials

Table 11 gives information about the soils as a source of roadfill, sand, gravel, and topsoil. The soils are rated *good*, *fair*, or *poor* as a source of roadfill and topsoil. They are rated as a *probable* or *improbable* source of sand and gravel. The ratings are based on soil properties and site features that affect the removal of the soil and its use as construction material. Normal compaction, minor processing, and other standard construction practices are assumed. Each soil is evaluated to a depth of 5 or 6 feet.



*Roadfill* is soil material that is excavated in one place and used in road embankments in another place. In this table, the soils are rated as a source of roadfill for low embankments, generally less than 6 feet high and less exacting in design than higher embankments.

The ratings are for the soil material below the surface layer to a depth of 5 or 6 feet. It is assumed that soil layers will be mixed during excavating and spreading. Many soils have layers of contrasting suitability within their profile. The table showing engineering index properties provides detailed information about each soil layer. This information can help determine the suitability of each layer for use as roadfill. The performance of soil after it is stabilized with lime or cement is not considered in the ratings.

The ratings are based on soil properties, site features, and observed performance of the soils. The thickness of suitable material is a major consideration. The ease of excavation is affected by large stones, a high water table, and slope. How well the soil performs in place after it has been compacted and drained is determined by its strength (as inferred from the engineering classification of the soil) and shrink-swell potential.

Soils rated *good* contain significant amounts of sand or gravel, or both. They have at least 5 feet of suitable material, a low shrink-swell potential, few cobbles and stones, and slopes of 15 percent or less. Depth to the water table is more than 3 feet. Soils rated *fair* are more than 35 percent silt- and clay-sized particles and have a plasticity index of less than 10. They have a moderate shrink-swell potential, slopes of 15 to 25 percent, or many stones. Depth to the water table is 1 to 3 feet. Soils rated *poor* have a plasticity index of more than 10, a high shrink-swell potential, many stones, or slopes of more than 25 percent. They are wet, and the depth to the water table is less than 1 foot. These soils may have layers of suitable material, but the material is less than 3 feet thick.

*Sand and gravel* are natural aggregates suitable for commercial use with a minimum of processing. Sand and gravel are used in many kinds of construction. Specifications for each use vary widely. In table 11, only the probability of finding material in suitable quantity is evaluated. The suitability of the material for specific purposes is not evaluated, nor are factors that affect excavation of the material.

The properties used to evaluate the soil as a source of sand or gravel are gradation of grain sizes (as indicated by the engineering classification of the soil), the thickness of suitable material, and the content of rock fragments. Kinds of rock, acidity, and stratification

are given in the soil series descriptions. Gradation of grain sizes is given in the table on engineering index properties.

A soil rated as a probable source has a layer of clean sand or gravel or a layer of sand or gravel that is as much as 12 percent silty fines. This material must be at least 3 feet thick and less than 50 percent, by weight, large stones. All other soils are rated as an improbable source. Coarse fragments of soft bedrock, such as shale and siltstone, are not considered to be sand and gravel.

*Topsoil* is used to cover an area so that vegetation can be established and maintained. The upper 40 inches of a soil is evaluated for use as topsoil. Also evaluated is the reclamation potential of the borrow area.

Plant growth is affected by toxic material and by such properties as soil reaction, available water capacity, and fertility. The ease of excavating, loading, and spreading is affected by rock fragments, slope, a water table, soil texture, and thickness of suitable material. Reclamation of the borrow area is affected by slope, a water table, rock fragments, bedrock, and toxic material.

Soils rated *good* have friable loamy material to a depth of at least 40 inches. They are free of stones and cobbles, have little or no gravel, and have slopes of less than 8 percent. They are low in content of soluble salts, are naturally fertile or respond well to fertilizer, and are not so wet that excavation is difficult.

Soils rated *fair* are sandy soils, loamy soils that have a relatively high content of clay, soils that have only 20 to 40 inches of suitable material, soils that have an appreciable amount of gravel, stones, or soluble salts, or soils that have slopes of 8 to 15 percent. The soils are not so wet that excavation is difficult.

Soils rated *poor* are very sandy or clayey, have less than 20 inches of suitable material, have a large amount of gravel, stones, or soluble salts, have slopes of more than 15 percent, or have a seasonal water table at or near the surface.

The surface layer of most soils generally is preferred for topsoil because of its organic matter content. Organic matter greatly increases the absorption and retention of moisture and nutrients for plant growth.

### Water Management

Table 12 gives information on the soil properties and site features that affect water management. The degree and kind of soil limitations are given for pond reservoir areas; embankments, dikes, and levees; and aquifer-fed ponds. The limitations are considered *slight* if soil properties and site features generally are favorable for



the indicated use and limitations are minor and are easily overcome; *moderate* if soil properties or site features are not favorable for the indicated use and special planning, design, or maintenance is needed to overcome or minimize the limitations; and *severe* if soil properties or site features are so unfavorable or so difficult to overcome that special design, significant increase in construction costs, and possibly increased maintenance are required.

This table also gives for each soil the restrictive features that affect drainage, irrigation, and terraces and diversions.

*Pond reservoir areas* hold water behind a dam or embankment. Soils best suited to this use have low seepage potential in the upper 60 inches. The seepage potential is determined by the permeability of the soil and the depth to fractured bedrock or other permeable material. Excessive slope can affect the storage capacity of the reservoir area.

*Embankments, dikes, and levees* are raised structures of soil material, generally less than 20 feet high, constructed to impound water or to protect land against overflow. In this table, the soils are rated as a source of material for embankment fill. The ratings apply to the soil material below the surface layer to a depth of about 5 feet. It is assumed that soil layers will be uniformly mixed and compacted during construction.

The ratings do not indicate the ability of the natural soil to support an embankment. Soil properties to a depth even greater than the height of the embankment can affect performance and safety of the embankment. Generally, deeper onsite investigation is needed to determine these properties.

Soil material in embankments must be resistant to seepage, piping, and erosion and have favorable compaction characteristics. Unfavorable features include less than 5 feet of suitable material and a high content of stones or boulders, organic matter, or salts or sodium. A high water table affects the amount of usable material. It also affects trafficability.

*Aquifer-fed excavated ponds* are pits or dugouts that extend to a ground-water aquifer or to a depth below a permanent water table. Excluded are ponds that are fed

only by surface runoff and embankment ponds that impound water 3 feet or more above the original surface. Excavated ponds are affected by depth to a permanent water table, permeability of the aquifer, and quality of the water as inferred from the salinity of the soil. Depth to bedrock and the content of large stones affect the ease of excavation.

*Drainage* is the removal of excess surface and subsurface water from the soil. How easily and effectively the soil is drained depends on the depth to bedrock, to a cemented pan, or to other layers that affect the rate of water movement; permeability; depth to a high water table or depth of standing water if the soil is subject to ponding; slope; susceptibility to flooding; subsidence of organic layers; and potential frost action. Excavating and grading and the stability of ditchbanks are affected by depth to bedrock or to a cemented pan, large stones, slope, and the hazard of cutbanks caving. The productivity of the soil after drainage is adversely affected by extreme acidity or by toxic substances in the root zone, such as salts, sodium, or sulfur. Availability of drainage outlets is not considered in the ratings.

*Irrigation* is the controlled application of water to supplement rainfall and support plant growth. The design and management of an irrigation system are affected by depth to the water table, the need for drainage, flooding, available water capacity, intake rate, permeability, erosion hazard, and slope. The construction of a system is affected by large stones and depth to bedrock or to a cemented pan. The performance of a system is affected by the depth of the root zone, the amount of salts or sodium, and soil reaction.

*Terraces and diversions* are embankments or a combination of channels and ridges constructed across a slope to control erosion and conserve moisture by intercepting runoff. Slope, wetness, large stones, and depth to bedrock or to a cemented pan affect the construction of terraces and diversions. A restricted rooting depth, a severe hazard of wind or water erosion, an excessively coarse texture, and restricted permeability adversely affect maintenance.

# Soil Properties

---

Data relating to soil properties are collected during the course of the soil survey. The data and the estimates of soil and water features, listed in tables, are explained on the following pages.

Soil properties are determined by field examination of the soils and by laboratory index testing of some benchmark soils. Established standard procedures are followed. During the survey, many shallow borings are made and examined to identify and classify the soils and to delineate them on the soil maps. Samples are taken from some typical profiles and tested in the laboratory to determine grain-size distribution, plasticity, and compaction characteristics.

Estimates of soil properties are based on field examinations, on laboratory tests of samples from the survey area, and on laboratory tests of samples of similar soils in nearby areas. Tests verify field observations, verify properties that cannot be estimated accurately by field observation, and help to characterize key soils.

The estimates of soil properties shown in the tables include the range of grain-size distribution and Atterberg limits, the engineering classification, and the physical and chemical properties of the major layers of each soil. Pertinent soil and water features also are given.

## Engineering Index Properties

Table 13 gives estimates of the engineering classification and of the range of index properties for the major layers of each soil in the survey area. Most soils have layers of contrasting properties within the upper 5 or 6 feet.

*Depth* to the upper and lower boundaries of each layer is indicated. The range in depth and information on other properties of each layer are given for each soil series under "Soil Series and Their Morphology."

*Texture* is given in the standard terms used by the U.S. Department of Agriculture. These terms are defined according to percentages of sand, silt, and clay in the fraction of the soil that is less than 2 millimeters

in diameter. "Loam," for example, is soil that is 7 to 27 percent clay, 28 to 50 percent silt, and less than 52 percent sand. If the content of particles coarser than sand is as much as 15 percent, an appropriate modifier is added, for example, "gravelly." Textural terms are defined in the Glossary.

*Classification* of the soils is determined according to the Unified soil classification system (2) and the system adopted by the American Association of State Highway and Transportation Officials (1).

The Unified system classifies soils according to properties that affect their use as construction material. Soils are classified according to grain-size distribution of the fraction less than 3 inches in diameter and according to plasticity index, liquid limit, and organic matter content. Sandy and gravelly soils are identified as GW, GP, GM, GC, SW, SP, SM, and SC; silty and clayey soils as ML, CL, OL, MH, CH, and OH; and highly organic soils as PT. Soils exhibiting engineering properties of two groups can have a dual classification; for example, SM-SC.

The AASHTO system classifies soils according to those properties that affect roadway construction and maintenance. In this system, the fraction of a mineral soil that is less than 3 inches in diameter is classified in one of seven groups from A-1 through A-7 on the basis of grain-size distribution, liquid limit, and plasticity index. Soils in group A-1 are coarse grained and low in content of fines (silt and clay). At the other extreme, soils in group A-7 are fine grained. Highly organic soils are classified in group A-8 on the basis of visual inspection.

If laboratory data are available, the A-1, A-2, and A-7 groups are further classified as A-1-a, A-1-b, A-2-4, A-2-5, A-2-6, A-2-7, A-7-5, or A-7-6. As an additional refinement, the suitability of a soil as subgrade material can be indicated by a group index number. Group index numbers range from 0 for the best subgrade material to 20 or higher for the poorest.

*Rock fragments* larger than 3 inches in diameter are indicated as a percentage of the total soil on a dry-



weight basis. The percentages are estimates determined mainly by converting volume percentage in the field to weight percentage.

*Percentage (of soil particles) passing designated sieves* is the percentage of the soil fraction less than 3 inches in diameter based on an oven-dry weight. The sieves, numbers 4, 10, 40, and 200 (USA Standard Series), have openings of 4.76, 2.00, 0.420, and 0.074 millimeters, respectively. Estimates are based on laboratory tests of soils sampled in the survey area and in nearby areas and on estimates made in the field.

*Liquid limit and plasticity index* (Atterberg limits) indicate the plasticity characteristics of a soil. The estimates are based on test data from the survey area or from nearby areas and on field examination.

The estimates of grain-size distribution, liquid limit, and plasticity index are rounded to the nearest 5 percent. Thus, if the ranges of gradation and Atterberg limits extend a marginal amount (1 or 2 percentage points) across classification boundaries, the classification in the marginal zone is omitted in the table.

## Physical and Chemical Properties

Table 14 shows estimates of some characteristics and features that affect soil behavior. These estimates are given for the major layers of each soil in the survey area. The estimates are based on field observations and on test data for these and similar soils.

*Clay* as a soil separate consists of mineral soil particles that are less than 0.002 millimeter in diameter. In this table, the estimated clay content of each major soil layer is given as a percentage, by weight, of the soil material that is less than 2 millimeters in diameter.

The amount and kind of clay greatly affect the fertility and physical condition of the soil. They determine the ability of the soil to adsorb cations and to retain moisture. They influence shrink-swell potential, permeability, plasticity, the ease of soil dispersion, and other soil properties. The amount and kind of clay in a soil also affect tillage and earthmoving operations.

*Permeability* refers to the ability of a soil to transmit water or air. The estimates indicate the rate of downward movement of water when the soil is saturated. They are based on soil characteristics observed in the field, particularly structure, porosity, and texture. Permeability is considered in the design of soil drainage systems, septic tank absorption fields, and construction where the rate of water movement under saturated conditions affects behavior.

*Available water capacity* refers to the quantity of

water that the soil is capable of storing for use by plants. The capacity for water storage is given in inches of water per inch of soil for each major soil layer. The capacity varies, depending on soil properties that affect the retention of water and the depth of the root zone. The most important properties are the content of organic matter, soil texture, bulk density, and soil structure. Available water capacity is an important factor in the choice of plants or crops to be grown and in the design and management of irrigation systems. Available water capacity is not an estimate of the quantity of water actually available to plants at any given time.

*Soil reaction* is a measure of acidity or alkalinity and is expressed as a range in pH values. The range in pH of each major horizon is based on many field tests. For many soils, values have been verified by laboratory analyses. Soil reaction is important in selecting crops and other plants, in evaluating soil amendments for fertility and stabilization, and in determining the risk of corrosion.

*Salinity* is a measure of soluble salts in the soil at saturation. It is expressed as the electrical conductivity of the saturation extract, in millimhos per centimeter at 25 degrees C. Estimates are based on field and laboratory measurements at representative sites of nonirrigated soils. The salinity of irrigated soils is affected by the quality of the irrigation water and by the frequency of water application. Hence, the salinity of soils in individual fields can differ greatly from the value given in the table. Salinity affects the suitability of a soil for crop production, the stability of soil if used as construction material, and the potential of the soil to corrode metal and concrete.

*Shrink-swell potential* is the potential for volume change in a soil with a loss or gain in moisture. Volume change occurs mainly because of the interaction of clay minerals with water and varies with the amount and type of clay minerals in the soil. The size of the load on the soil and the magnitude of the change in soil moisture content influence the amount of swelling of soils in place. Laboratory measurements of swelling of undisturbed clods were made for many soils. For others, swelling was estimated on the basis of the kind and amount of clay minerals in the soil and on measurements of similar soils.

If the shrink-swell potential is rated moderate to very high, shrinking and swelling can cause damage to buildings, roads, and other structures. Special design is often needed.

Shrink-swell potential classes are based on the change in length of an unconfined clod as moisture content is increased from air-dry to field capacity. The



change is based on the soil fraction less than 2 millimeters in diameter. The classes are *low*, a change of less than 3 percent; *moderate*, 3 to 6 percent; and *high*, more than 6 percent. *Very high*, more than 9 percent, is sometimes used.

*Erosion factor K* indicates the susceptibility of a soil to sheet and rill erosion by water. Factor K is one of six factors used in the Universal Soil Loss Equation (USLE) to predict the average annual rate of soil loss by sheet and rill erosion in tons per acre per year. The estimates are based primarily on percentage of silt, sand, and organic matter (up to 4 percent) and on soil structure and permeability. The estimates are modified by the presence of rock fragments. Values of K range from 0.05 to 0.69. The higher the value the more susceptible the soil is to sheet and rill erosion by water.

*Erosion factor T* is an estimate of the maximum average annual rate of soil erosion by wind or water that can occur without affecting crop productivity over a sustained period. The rate is in tons per acre per year.

*Wind erodibility groups* are made up of soils that have similar properties affecting their resistance to wind erosion in cultivated areas. The groups indicate the susceptibility of soil to wind erosion. Soils are grouped according to the following distinctions:

1. Coarse sands, sands, fine sands, and very fine sands. These soils are generally not suitable for crops. They are extremely erodible, and vegetation is difficult to establish.
2. Loamy coarse sands, loamy sands, loamy fine sands, loamy very fine sands, and sapric soil material. These soils are very highly erodible. Crops can be grown if intensive measures to control wind erosion are used.
3. Coarse sandy loams, sandy loams, fine sandy loams, and very fine sandy loams. These soils are highly erodible. Crops can be grown if intensive measures to control wind erosion are used.
- 4L. Calcareous loams, silt loams, clay loams, and silty clay loams. These soils are erodible. Crops can be grown if intensive measures to control wind erosion are used.
4. Clays, silty clays, noncalcareous clay loams, and silty clay loams that are more than 35 percent clay. These soils are moderately erodible. Crops can be grown if measures to control wind erosion are used.
5. Noncalcareous loams and silt loams that are less than 20 percent clay and sandy clay loams, sandy clays, and hemic soil material. These soils are slightly erodible. Crops can be grown if measures to control wind erosion are used.
6. Noncalcareous loams and silt loams that are

more than 20 percent clay and noncalcareous clay loams that are less than 35 percent clay. These soils are very slightly erodible. Crops can be grown if ordinary measures to control wind erosion are used.

7. Silts, noncalcareous silty clay loams that are less than 35 percent clay, and fibric soil material. These soils are very slightly erodible. Crops can be grown if ordinary measures to control wind erosion are used.

8. Soils that are not subject to wind erosion because of coarse fragments on the surface or because of surface wetness.

*Organic matter* is the plant and animal residue in the soil at various stages of decomposition. In table 14, the estimated content of organic matter is expressed as a percentage, by weight, of the soil material that is less than 2 millimeters in diameter.

The content of organic matter in a soil can be maintained or increased by returning crop residue to the soil. Organic matter affects the available water capacity, infiltration rate, and tilth. It is a source of nitrogen and other nutrients for crops.

Soil and Water Features

Table 15 gives estimates of various water features. The estimates are used in land use planning that involves engineering considerations.

*Hydrologic soil groups* are used to estimate runoff from precipitation. Soils not protected by vegetation are assigned to one of four groups. They are grouped according to the infiltration of water when the soils are thoroughly wet and receive precipitation from long-duration storms.

The four hydrologic soil groups are:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These



consist chiefly of clays that have a high shrink-swell potential, soils that have a permanent high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

*Flooding*, the temporary inundation of an area, is caused by overflowing streams, by runoff from adjacent slopes, or by tides. Shallow water standing or flowing for short periods after rainfall or snowmelt is not considered flooding, nor is standing water in swamps and marshes or in closed depressional areas.

Table 15 gives the frequency and duration of flooding and the time of year when flooding is most likely. Frequency, duration, and probable dates of occurrence are estimated. Frequency is expressed as none, rare, occasional, and frequent. *None* means that flooding is not probable; *rare* that it is unlikely but possible under unusual weather conditions; *occasional* that it occurs, on the average, once or less in 2 years; and *frequent* that it occurs, on the average, more than once in 2 years. Duration is expressed as *very brief* if less than 2 days, *brief* if 2 to 7 days, *long* if 7 days to 1 month, and *very long* if more than 1 month. Probable dates are expressed in months.

The information is based on evidence in the soil profile, namely thin strata of gravel, sand, silt, or clay deposited by floodwater; irregular decrease in organic matter content with increasing depth; and absence of distinctive horizons that form in soils that are not subject to flooding.

Also considered are local information about the extent and levels of flooding and the relation of each soil on the landscape to historic floods. Information on the extent of flooding based on soil data is less specific than that provided by detailed engineering surveys that delineate flood-prone areas at specific flood frequency levels.

*High water table* (seasonal) is the highest level of a saturated zone in the soil in most years. The depth to a seasonal high water table applies to undrained soils. The estimates are based mainly on the evidence of a saturated zone, namely grayish colors or mottles in the soil. Indicated in table 15 are the depth to the seasonal high water table; the kind of water table—that is, perched or apparent; and the months of the year that the water table commonly is high. A water table that is seasonally high for less than 1 month is not indicated in table 15.

An *apparent* water table is a thick zone of free water in the soil. It is indicated by the level at which water stands in an uncased borehole after adequate time is

allowed for adjustment in the surrounding soil. A *perched* water table is water standing above an unsaturated zone. In places an upper, or perched, water table is separated from a lower one by a dry zone.

The two numbers in the column "High water table" indicate the normal range in depth to a saturated zone. Depth is given to the nearest half foot. The first numeral in the range indicates the highest water level. A plus sign preceding the range in depth indicates that the water table is above the surface of the soil. "More than 6.0" indicates that the water table is below a depth of 6 feet or that the water table is above a depth of 6 feet for less than a month.

Table 16 gives estimates of various soil features. The estimates are used in land use planning that involves engineering considerations.

*Depth to bedrock* is given if bedrock is within a depth of 5 feet. The depth is based on many soil borings and on observations during soil mapping. The rock is either soft or hard. If the rock is soft or fractured, excavations can be made with trenching machines, backhoes, or small rippers. If the rock is hard or massive, blasting or special equipment generally is needed for excavation.

*Cemented pans* are cemented or indurated subsurface layers within a depth of 5 feet. Such pans cause difficulty in excavation. Pans are classified as thin or thick. A thin pan is less than 3 inches thick if continuously indurated or less than 18 inches thick if discontinuous or fractured. Excavations can be made by trenching machines, backhoes, or small rippers. A thick pan is more than 3 inches thick if continuously indurated or more than 18 inches thick if discontinuous or fractured. Such a pan is so thick or massive that blasting or special equipment is needed in excavation.

*Subsidence* is the settlement of organic soils or of saturated mineral soils of very low density. Subsidence results from either desiccation and shrinkage or oxidation of organic material, or both, following drainage. Subsidence takes place gradually, usually over a period of several years. Table 16 shows the expected initial subsidence, which usually is a result of drainage, and total subsidence, which usually is a result of oxidation.

Not shown in the table is subsidence caused by an imposed surface load or by the withdrawal of ground water throughout an extensive area as a result of lowering the water table.

*Potential frost action* is the likelihood of upward or lateral expansion of the soil caused by the formation of segregated ice lenses (frost heave) and the subsequent collapse of the soil and loss of strength on thawing. Frost action occurs when moisture moves into the

freezing zone of the soil. Temperature, texture, density, permeability, content of organic matter, and depth to the water table are the most important factors considered in evaluating the potential for frost action. It is assumed that the soil is not insulated by vegetation or snow and is not artificially drained. Silty and highly structured clayey soils that have a high water table in winter are the most susceptible to frost action. Well drained, very gravelly, or very sandy soils are the least susceptible. Frost heave and low soil strength during thawing cause damage mainly to pavements and other rigid structures.

*Risk of corrosion* pertains to potential soil-induced electrochemical or chemical action that dissolves or weakens uncoated steel or concrete. The rate of corrosion of uncoated steel is related to such factors as soil moisture, particle-size distribution, acidity, and electrical conductivity of the soil. The rate of corrosion

of concrete is based mainly on the sulfate and sodium content, texture, moisture content, and acidity of the soil. Special site examination and design may be needed if the combination of factors creates a severe corrosion environment. The steel in installations that intersect soil boundaries or soil layers is more susceptible to corrosion than steel in installations that are entirely within one kind of soil or within one soil layer.

For uncoated steel, the risk of corrosion, expressed as *low*, *moderate*, or *high*, is based on soil drainage class, total acidity, electrical resistivity near field capacity, and electrical conductivity of the saturation extract.

For concrete, the risk of corrosion is also expressed as *low*, *moderate*, or *high*. It is based on soil texture, acidity, and amount of sulfates in the saturation extract.





# Classification of the Soils

---

The system of soil classification used by the National Cooperative Soil Survey has six categories (16). Beginning with the broadest, these categories are the order, suborder, great group, subgroup, family, and series. Classification is based on soil properties observed in the field or inferred from those observations or from laboratory measurements. Table 17 shows the classification of the soils in the survey area. The categories are defined in the following paragraphs.

**ORDER.** Eleven soil orders are recognized. The differences among orders reflect the dominant soil-forming processes and the degree of soil formation. Each order is identified by a word ending in *sol*. An example is Inceptisol.

**SUBORDER.** Each order is divided into suborders primarily on the basis of properties that influence soil genesis and are important to plant growth or properties that reflect the most important variables within the orders. The last syllable in the name of a suborder indicates the order. An example is Ochrept (*Ochr*, meaning pale, plus *ept*, from Inceptisol).

**GREAT GROUP.** Each suborder is divided into great groups on the basis of close similarities in kind, arrangement, and degree of development of pedogenic horizons; soil moisture and temperature regimes; and base status. Each great group is identified by the name of a suborder and by a prefix that indicates a property of the soil. An example is Cryochrepts (*Cry*, meaning cold, plus *ochrept*, the suborder of the Inceptisols that has a pale epipedon).

**SUBGROUP.** Each great group has a typic subgroup. Other subgroups are intergrades or extragrades. The typic is the central concept of the great group; it is not necessarily the most extensive. Intergrades are transitions to other orders, suborders, or great groups. Extragrades have some properties that are not representative of the great group but do not indicate transitions to any other known kind of soil. Each subgroup is identified by one or more adjectives preceding the name of the great group. The adjective *Typic* identifies the subgroup that typifies the great

group. An example is Typic Cryochrepts.

**FAMILY.** Families are established within a subgroup on the basis of physical and chemical properties and other characteristics that affect management. Generally, the properties are those of horizons below plow depth where there is much biological activity. Among the properties and characteristics considered are particle-size class, mineral content, temperature regime, depth of the root zone, consistence, moisture equivalent, slope, and permanent cracks. A family name consists of the name of a subgroup preceded by terms that indicate soil properties. An example is loamy-skeletal, mixed Typic Cryochrepts.

**SERIES.** The series consists of soils that have similar horizons in their profile. The horizons are similar in color, texture, structure, reaction, consistence, mineral and chemical composition, and arrangement in the profile. The texture of the surface layer or of the underlying material can differ within a series.

The classification of some of the soils in adjoining counties is different from that of adjacent soils in this survey area. These differences are the result of a gradual change in many soil characteristics over a distance of many miles. The exact point that the characteristics change enough to warrant a change in classification is difficult to define or locate. In some cases, therefore, manmade lines, such as county lines, were used.

The soils in Camas County that border the survey area on the west differ in one or more characteristics as a result of differences in names and classification. The Roanhide soils established in the western part of Camas County have slightly lower annual precipitation than the similar Moonstone soils in this survey area. This slightly higher annual precipitation has resulted in an abundance of grasses in the plant community on the Moonstone soils. These grasses annually add more organic matter to the soil surface. As a result the Moonstone soils have a slightly thicker dark surface horizon than the Roanhide soils.

Another example of soils that do not match along the



Blaine-Camas county line is that of the Peevywell soils in the survey area and the Rands soils in Camas County. The Peevywell soils have a duripan 20 to 40 inches thick, and the Rands soils do not have a duripan. Because Camas County was mapped first, the extent of the Peevywell soils that were observed and documented was too small for the soils to be mapped separately and established as a soil series. The Peevywell soils, therefore, were combined with the Rands soils because use and management needs are similar for both soils. In this survey area, however, the acreage of Peevywell soils is sufficient to establish a separate series.

The Bringmee soils in this survey area are well drained, and the Brinegar soils in Camas County are moderately well drained. There are no Brinegar soils in Blaine County, so the two different but similar soils join at the county line.

The soils that join Blaine County on the south, east, and north either match or have not yet been mapped and classified.

## Soil Series and Their Morphology

In this section, each soil series recognized in the survey area is described. The descriptions are arranged in alphabetic order.

Characteristics of the soil and the material in which it formed are identified for each series. A pedon, a small three-dimensional area of soil, that is typical of the series in the survey area is described. The detailed description of each soil horizon follows standards in the *Soil Survey Manual* (14). Many of the technical terms used in the descriptions are defined in *Soil Taxonomy* (16). Unless otherwise stated, matrix colors in the descriptions are for dry soil. Following the pedon description is the range of important characteristics of the soils in the series.

The map units of each series are described in the section "Detailed Soil Map Units."

### Adamson Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate to a depth of 28 inches; very rapid below this depth

*Position on landscape:* Stream terraces, flood plains

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 0 to 2 percent

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Coarse-loamy over sandy or sandy-skeletal, mixed, frigid Calcic Pachic Haploxerolls

#### Typical Pedon

A—0 to 5 inches; grayish brown (10YR 5/2) loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium granular structure; slightly hard, friable, slightly sticky and slightly plastic; many fine roots; many very fine interstitial pores; neutral (pH 6.6); clear smooth boundary.

BA—5 to 19 inches; grayish brown (2.5Y 5/2) loam, very dark grayish brown (2.5Y 3/2) moist; weak medium subangular blocky structure; slightly hard, friable; many fine roots; common very fine interstitial pores; neutral (pH 6.6); clear smooth boundary.

Bw—19 to 28 inches; grayish brown (10YR 5/2) fine sandy loam, very dark grayish brown (10YR 3/2) moist; massive; soft, very friable; many fine and medium roots; about 5 percent pebbles; mildly alkaline (pH 7.6); clear wavy boundary.

2Bk—28 to 61 inches; light brownish gray (10YR 6/2) very gravelly coarse sand, dark grayish brown (10YR 4/2) moist; single grain; loose; few fine roots; about 40 percent pebbles and 20 percent cobbles; slightly effervescent (accumulations of lime on undersides of rock fragments); mildly alkaline (pH 7.8).

#### Typical Pedon Location

*Map unit in which located:* Adamson loam, 0 to 2 percent slopes

*Location in survey area:* About 3 miles south and 1 mile west of Bellevue; about 800 feet west and 125 feet south of the northeast corner of sec. 23, T. 1 N., R. 18 E.

#### Range in Characteristics

*Depth to loose sand and rock fragments:* 23 to 36 inches

*Thickness of mollic epipedon:* 20 to 36 inches

*Depth to water table (flooded areas):* 48 to 72 inches from April to June

*Average annual soil temperature:* 42 to 47 degrees F

*Other characteristics:* 2Bkq horizon in some pedons

*A horizon:*

Value—3 to 5 dry, 2 or 3 moist

Chroma—1 to 3 dry or moist

Reaction—slightly acid to mildly alkaline



**BA and Bw horizons:**

Value—4 or 5 dry, 2 or 3 moist  
 Chroma—2 or 3 dry or moist  
 Texture—loam, fine sandy loam, or very fine sandy loam  
 Content of rock fragments—0 to 15 percent  
 Content of clay—8 to 18 percent  
 Reaction—slightly acid to mildly alkaline

**2Bk horizon:**

Texture—very gravelly coarse sand, very gravelly sand, extremely gravelly coarse sand, extremely cobbly loamy coarse sand, extremely cobbly coarse sand, or extremely stony coarse sand  
 Content of rock fragments—35 to 85 percent  
 Content of clay—0 to 5 percent  
 Reaction—neutral or mildly alkaline

**Adios Series**

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Position on landscape:* Sides of buttes, basalt plains

*Parent material:* Residuum and slope alluvium derived from rhyolite and andesite

*Slope:* 8 to 60 percent

*Elevation:* 4,600 to 5,200 feet

*Average annual precipitation:* 11 to 13 inches

*Average annual air temperature:* 45 to 50 degrees F

*Frost-free period:* 100 to 120 days

**Taxonomic class:** Fine, montmorillonitic, mesic Aridic Durixerolls

**Typical Pedon**

A1—0 to 2 inches; brown (10YR 5/3) stony loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable, slightly sticky and plastic; many very fine and fine roots and few medium and coarse roots; many very fine and fine tubular pores; about 5 percent pebbles and 2 percent stones; neutral (pH 7.0); clear smooth boundary.

A2—2 to 5 inches; brown (10YR 5/3) stony loam, dark brown (10YR 3/3) moist; moderate fine subangular blocky structure; soft, friable, slightly sticky and plastic; many very fine and fine roots and few medium and coarse roots; many very fine and fine tubular pores; about 5 percent pebbles and 2 percent stones; neutral (pH 7.0); clear wavy boundary.

Bt1—5 to 8 inches; yellowish brown (10YR 5/4) clay loam, dark brown (10YR 3/3) moist; strong fine subangular blocky structure; slightly hard, firm, sticky and plastic; common fine and medium roots; common very fine and fine tubular pores; few thin clay films lining pores and on faces of peds; about 5 percent pebbles and 3 percent stones; neutral (pH 7.2); abrupt wavy boundary.

Bt2—8 to 16 inches; yellowish brown (10YR 5/4) clay, dark yellowish brown (10YR 4/4) moist; strong fine and medium prismatic structure; very hard, very firm, very sticky and very plastic; common fine and medium roots concentrated along vertical faces of peds; common fine tubular pores; many thick clay films lining pores and on faces of peds; about 5 percent pebbles; mildly alkaline (pH 7.4); gradual wavy boundary.

Bt3—16 to 20 inches; light yellowish brown (10YR 6/4) clay, yellowish brown (10YR 5/4) moist; moderate fine and medium prismatic structure parting to strong fine and medium angular blocky; very hard, very firm, very sticky and very plastic; common fine and medium roots concentrated along vertical faces of peds; few fine tubular pores; many moderately thick clay films lining pores and on faces of peds; about 5 percent pebbles; mildly alkaline (pH 7.6); clear wavy boundary.

Btk—20 to 23 inches; very pale brown (10YR 7/4) clay loam, light yellowish brown (10YR 6/4) moist; strong fine and medium angular blocky structure; very hard, firm, sticky and plastic; common fine roots; few fine tubular pores; few moderately thick clay films on faces of peds; about 10 percent pebbles and 3 percent stones; strongly effervescent (about 20 percent lime); mildly alkaline (pH 7.8); abrupt smooth boundary.

Bqkm—23 to 27 inches; white (10YR 8/2), indurated duripan, pale brown (10YR 6/3) moist; massive; root mats on top of silica cap; about 10 percent pebbles, 5 percent cobbles, and 3 percent stones; continuous silica cap 1 to 2 millimeters thick at a depth of 23 inches; violently effervescent (about 30 percent lime); moderately alkaline (pH 8.2); abrupt wavy boundary.

R—27 inches; fractured rhyolite; silica and lime in fractures.

**Typical Pedon Location**

*Map unit in which located:* Adios association, 8 to 25 percent slopes

*Location in survey area:* About 3 miles southeast of dam on Magic Reservoir; about 1,800 feet north and



2,600 feet west of the southeast corner of sec. 22,  
T. 2 S., R. 18 E.

### Range in Characteristics

*Depth to bedrock:* 26 to 36 inches

*Depth to duripan:* 22 to 31 inches

*Thickness of mollic epipedon:* 7 to 11 inches

*Average annual soil temperature:* 47 to 52 degrees F

#### *A horizon:*

Chroma—2 to 4 dry or moist

Content of pebbles—0 to 5 percent

Content of stones—0 to 2 percent

#### *Bt1 horizon:*

Value—4 or 5 dry, 3 or 4 moist

Chroma—3 or 4 dry or moist

Content of pebbles—5 to 10 percent

Content of stones—0 to 3 percent

#### *Bt2 and Bt3 horizons:*

Hue—10YR or 7.5YR

Value—4 to 6 dry, 3 to 5 moist

Chroma—3 or 4 moist

Texture—clay, clay loam, or gravelly clay

Content of pebbles—0 to 15 percent

Content of stones and cobbles—0 to 10 percent

Content of clay—35 to 60 percent

Reaction—neutral or mildly alkaline

#### *Btk horizon:*

Value—5 or 6 moist

Texture—clay loam or gravelly clay loam

#### *Bqkm horizon:*

Hue—7.5YR or 10YR

Value—6 or 7 moist

Chroma—1 or 2 dry, 2 or 3 moist

Content of lime—15 to 40 percent

Reaction—mildly alkaline or moderately alkaline

Other characteristics—indurated plates 1 to 3  
inches apart

### **Balaam Series**

*Depth class:* Very deep

*Drainage class:* Somewhat excessively drained

*Permeability:* Moderately rapid in the upper 21 inches;  
very rapid below this depth

*Position on landscape:* Stream terraces, flood plains

*Parent material:* Alluvium derived from various kinds of  
rock

*Slope:* 0 to 4 percent

*Elevation:* 4,700 to 6,100 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Sandy-skeletal, mixed, frigid Entic  
Ultic Haploxerolls

### Typical Pedon

A1—0 to 3 inches; grayish brown (10YR 5/2) gravelly  
sandy loam, very dark grayish brown (10YR 3/2)  
moist; moderate fine granular structure; slightly  
hard, firm; many very fine and fine roots; many fine  
interstitial pores; about 20 percent pebbles; slightly  
acid (pH 6.2); clear smooth boundary.

A2—3 to 14 inches; grayish brown (10YR 5/2) gravelly  
sandy loam, very dark grayish brown (10YR 3/2)  
moist; weak medium subangular blocky structure;  
slightly hard, friable; many fine roots; many fine  
interstitial pores; about 30 percent pebbles; slightly  
acid (pH 6.4); gradual smooth boundary.

2Bw—14 to 21 inches; light brownish gray (10YR 6/2)  
very gravelly coarse sandy loam, dark grayish  
brown (10YR 4/2) moist; massive; slightly hard,  
friable; common fine roots; about 50 percent  
pebbles; neutral (pH 6.8); clear wavy boundary.

3Bk—21 to 61 inches; grayish brown (10YR 5/2)  
extremely gravelly coarse sand, very dark grayish  
brown (10YR 3/2) moist; single grain; loose; few  
fine roots; 50 percent pebbles and 10 percent  
cobbles; mildly alkaline (pH 7.8); slightly  
effervescent (about 5 percent lime, coatings of lime  
and silica less than 1 millimeter thick on undersides  
of coarse fragments).

### Typical Pedon Location

*Map unit in which located:* Balaam gravelly sandy loam,  
0 to 2 percent slopes

*Location in survey area:* About 3 miles south of  
Bellevue; about 1,120 feet south and 2,450 feet  
west of the northeast corner of sec. 13, T. 1 N., R.  
18 E.

### Range in Characteristics

*Depth to loose sand and rock fragments:* 14 to 35 inches

*Thickness of mollic epipedon:* 10 to 18 inches

*Average annual soil temperature:* 42 to 47 degrees F

*Base saturation:* 50 to 75 percent

*Depth to water table (flooded areas):* More than 60  
inches from April to June

#### *A horizon:*

Value—3 to 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Texture—gravelly sandy loam or very gravelly sandy loam  
Content of rock fragments—15 to 50 percent  
Reaction—strongly acid to neutral

*2Bw horizon:*

Value—4 to 6 dry, 3 or 4 moist  
Chroma—2 to 4 moist or dry  
Texture—very gravelly coarse sandy loam, very gravelly sandy loam, very gravelly fine sandy loam, or very cobbly sandy loam  
Content of clay—5 to 12 percent  
Content of rock fragments—35 to 55 percent  
Reaction—strongly acid to mildly alkaline

*3Bk horizon:*

Texture—extremely gravelly coarse sand, extremely gravelly loamy coarse sand, extremely cobbly loamy coarse sand, or extremely cobbly coarse sand  
Content of clay—0 to 10 percent  
Content of rock fragments—60 to 85 percent  
Reaction—strongly acid to mildly alkaline

**Bancroft Series**

*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderate  
*Position on landscape:* Basalt plains  
*Parent material:* Silty alluvium  
*Slope:* 1 to 8 percent  
*Elevation:* 4,800 to 5,200 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 40 to 45 degrees F  
*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-silty, mixed, frigid Calcic Argixerolls

**Typical Pedon**

A1—0 to 6 inches; brown (10YR 5/3) silt loam, dark brown (10YR 3/3) moist; weak thin platy structure; slightly hard, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many very fine and fine interstitial pores; neutral (pH 7.0); clear smooth boundary.  
A2—6 to 11 inches; brown (10YR 5/3) silt loam, dark brown (10YR 3/3) moist; moderate medium and coarse subangular blocky structure; hard, friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; common very fine

and fine interstitial and tubular pores; neutral (pH 7.2); gradual wavy boundary.

Bt1—11 to 21 inches; yellowish brown (10YR 5/4) silty clay loam, brown (10YR 4/3) moist; strong medium and coarse angular blocky structure; very hard, firm, sticky and plastic; common fine and medium roots; common very fine and fine tubular pores; few thin clay films on faces of peds and lining pores; mildly alkaline (pH 7.4); gradual wavy boundary.  
Bt2—21 to 28 inches; dark yellowish brown (10YR 4/4) silty clay loam, brown (10YR 4/3) moist; strong medium and coarse angular blocky structure; very hard, very firm, sticky and plastic; common fine and medium roots; common very fine and fine tubular pores; few thin clay films on faces of peds and lining pores; mildly alkaline (pH 7.4); gradual wavy boundary.  
Btk—28 to 33 inches; dark yellowish brown (10YR 4/4) silty clay loam, yellowish brown (10YR 5/4) moist; moderate fine and medium angular blocky structure; hard, firm, sticky and plastic; few very fine and fine roots; few very fine and fine tubular pores; common thin clay films on faces of peds and lining pores; slightly effervescent (about 5 percent lime); mildly alkaline (pH 7.8); clear wavy boundary.  
Bk1—33 to 42 inches; very pale brown (10YR 8/3) silt loam, pale brown (10YR 6/3) moist; massive; slightly hard, firm, slightly sticky and slightly plastic; few very fine and fine roots; few very fine and fine tubular pores; moderately alkaline (pH 8.0); violently effervescent (about 25 percent lime); abrupt wavy boundary.  
2Bk2—42 to 58 inches; very pale brown (10YR 7/4) gravelly loamy sand, light yellowish brown (10YR 6/4) moist; massive; hard, firm; few very fine and fine roots; about 20 percent pebbles; moderately alkaline (pH 8.0); violently effervescent (about 25 percent lime); gradual wavy boundary.  
2Bk3—58 to 80 inches; very pale brown (10YR 7/3) gravelly loam, yellowish brown (10YR 5/4) moist; massive; very hard, friable; 15 to 25 percent pebbles and cobbles; moderately alkaline (pH 8.0); violently effervescent (about 20 percent lime).

**Typical Pedon Location**

*Map unit in which located:* Bancroft silt loam, 4 to 8 percent slopes  
*Location in survey area:* About 10 miles east and 1 mile north of Carey; about 2,300 feet east and 2,400 feet north of the southwest corner of sec. 19, T. 15 N., R. 23 E.



**Range in Characteristics***Depth to bedrock:* More than 60 inches*Depth to calcic horizon:* 19 to 40 inches*Thickness of mollic epipedon:* 10 to 16 inches*Average annual soil temperature:* 42 to 47 degrees F*Content of clay in particle-size control section:* 18 to 32 percent*Other characteristics:* Btk horizon absent in some pedons*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Reaction—slightly acid or neutral

*Bt horizon:*

Value—4 to 6 dry, 3 or 4 moist

Chroma—2 to 4 dry or moist

Texture—silt loam or silty clay loam

Content of clay—18 to 32 percent

Reaction—slightly acid to mildly alkaline

*Bk horizon:*

Value—6 to 8 dry, 4 to 6 moist

Chroma—2 to 4 dry or moist

Texture—silt loam or silty clay loam

Reaction—mildly alkaline or moderately alkaline

*2Bk horizon:*

Value—7 or 8 dry

Content of rock fragments—15 to 25 percent

Reaction—mildly alkaline or moderately alkaline

**Bauscher Series***Depth class:* Deep*Drainage class:* Well drained*Permeability:* Moderately slow*Position on landscape:* Fan terraces, foothills*Parent material:* Alluvium and colluvium derived from granite*Slope:* 4 to 30 percent*Elevation:* 4,800 to 6,000 feet*Average annual precipitation:* 12 to 16 inches*Average annual air temperature:* 40 to 43 degrees F*Frost-free period:* 60 to 90 days**Taxonomic class:** Fine-loamy, mixed, frigid Pachic Ultic Argixerolls**Typical Pedon**

A1—0 to 7 inches; dark grayish brown (10YR 4/2) loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, friable, slightly sticky

and slightly plastic; many fine, medium, and coarse roots; many very fine interstitial pores; slightly acid (pH 6.2); gradual wavy boundary.

A2—7 to 14 inches; dark brown (10YR 4/3) loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium granular structure; soft, friable, slightly sticky and slightly plastic; common fine, medium, and coarse roots; many fine interstitial pores; slightly acid (pH 6.2); clear wavy boundary.

Bt1—14 to 26 inches; brown (10YR 5/3) sandy clay loam, dark brown (10YR 3/3) moist; moderate fine and medium subangular blocky structure; hard, friable, slightly sticky and slightly plastic; few fine and medium roots; few fine tubular pores; few thin clay films on faces of peds and bridging sand grains; slightly acid (pH 6.4); clear wavy boundary.

Bt2—26 to 37 inches; yellowish brown (10YR 5/4) sandy clay loam, dark yellowish brown (10YR 4/4) moist; weak medium and coarse subangular blocky structure; hard, friable, slightly sticky and slightly plastic; few fine and medium roots; few fine tubular pores; few thin clay films on faces of peds and bridging sand grains; about 5 percent pebbles; slightly acid (pH 6.4); clear wavy boundary.

BC—37 to 42 inches; light yellowish brown (10YR 6/4) coarse sandy loam, dark yellowish brown (10YR 4/4) moist; weak medium and coarse subangular blocky structure; hard, friable; few fine and medium roots; few fine and very fine tubular pores; about 5 percent pebbles; slightly acid (pH 6.4); clear wavy boundary.

Cr—42 to 60 inches; weathered granite.

**Typical Pedon Location***Map unit in which located:* Moonstone-Bauscher complex, 8 to 30 percent slopes*Location in survey area:* About 7 miles south and 4 miles west of Bellevue; about 2,000 feet east and 200 feet south of the northwest corner of sec. 32, T. 1 N., R. 18 E.**Range in Characteristics***Depth to bedrock:* 40 to 60 inches*Thickness of mollic epipedon:* 20 to 30 inches*Base saturation (in some part above a depth of 30 inches):* 50 to 75 percent*Average annual soil temperature:* 42 to 46 degrees F*Average summer soil temperature:* 60 to 65 degrees F*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

*Bt horizon:*

Hue—10YR or 7.5YR

Value—4 to 6 dry  
 Texture—sandy clay loam or loam  
 Content of rock fragments—0 to 10 percent  
 Content of clay—18 to 30 percent

*BC horizon:*

Value—5 or 6 dry  
 Chroma—3 or 4 dry  
 Content of rock fragments—5 to 20 percent

## **Bickett Series**

*Depth class:* Very deep  
*Drainage class:* Very poorly drained  
*Permeability:* Moderately slow  
*Position on landscape:* Flood plains  
*Parent material:* Material derived from herbaceous plants over silty alluvium  
*Slope:* 0 to 2 percent  
*Elevation:* 4,700 to 5,000 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 40 to 44 degrees F  
*Frost-free period:* 60 to 90 days  
**Taxonomic class:** Fine-silty, mixed (calcareous), frigid Histic Humaquepts

### **Typical Pedon**

Oek1—0 to 3 inches; dark yellowish brown (10YR 4/4) mucky peat, black (10YR 2/1) moist; about 50 percent fibers, 25 percent rubbed; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many very fine and fine interstitial pores; slightly effervescent (about 5 percent lime); neutral (pH 7.2); clear smooth boundary.

Oek2—3 to 6 inches; black (N 2/0) mucky peat, black (N 2/0) moist; about 50 percent fibers, 20 percent rubbed; moderate fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many very fine and fine interstitial pores; slightly effervescent (about 5 percent lime); neutral (pH 7.3); clear wavy boundary.

Oak—6 to 11 inches; gray (10YR 5/1) muck, black (10YR 2/1) moist; about 40 percent fibers, 10 percent rubbed; moderate fine granular structure; soft, friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many very fine and fine interstitial pores; slightly effervescent (about 5 percent lime); mildly alkaline (pH 7.6); clear smooth boundary.

2Bkg1—11 to 24 inches; light gray (2.5Y 7/1) silty clay loam, light brownish gray (2.5Y 6/1) moist; massive; very hard, very firm, very sticky and very plastic; common very fine, fine, and medium roots; few very fine and fine tubular pores; strongly effervescent (about 15 percent lime); mildly alkaline (pH 7.8); gradual wavy boundary.

2Bkg2—24 to 40 inches; light gray (2.5Y 7/1) silty clay loam, light brownish gray (2.5Y 6/1) moist; massive; very hard, firm, very sticky and very plastic; common very fine and fine roots; few very fine and fine tubular pores; 5 percent pebbles; strongly effervescent (about 15 percent lime); mildly alkaline (pH 7.4); clear wavy boundary.

3Cg—40 to 61 inches; gray (5Y 6/1) loam, dark gray (5Y 4/1) moist; massive; hard, firm, sticky and plastic; few very fine and fine roots; few very fine and fine tubular pores; 10 percent pebbles; neutral (pH 7.0).

### **Typical Pedon Location**

*Map unit in which located:* Hapur-Bickett complex, 0 to 2 percent slopes

*Location in survey area:* About 3 miles south of Gannett; about 500 feet east and 200 feet north of the southwest corner of sec. 23, T. 1 S., R. 19 E.

### **Range in Characteristics**

*Depth to water table:* 6 inches above the surface to 6 inches below

*Thickness of the organic layer:* 8 to 16 inches

*Content of organic carbon:* 12 to 18 percent

*Average annual soil temperature:* 42 to 47 degrees F

#### *O horizon:*

Hue—10YR or neutral

Value—2 to 5 dry

Content of lime—5 to 25 percent

Reaction—neutral or mildly alkaline

#### *2Bkg horizon:*

Hue—2.5Y or 5Y

Value—6 or 7 dry, 4 to 6 moist

Texture—silt loam or silty clay loam

Content of lime—10 to 30 percent

Reaction—mildly alkaline or moderately alkaline

#### *3Cg horizon:*

Hue—2.5Y or 5Y

Value—5 to 7 dry, 2 to 6 moist

Texture—clay loam, loam, or gravelly fine sandy loam

Content of rock fragments—5 to 30 percent

Content of lime—0 to 5 percent



## **Blackspar Series**

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Mountainsides

*Parent material:* Colluvium and alluvium derived from quartzitic sandstone and conglomerate

*Slope:* 30 to 75 percent

*Elevation:* 5,200 to 8,500 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 44 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Lithic Mollic Haploxeralfs

### **Typical Pedon**

A—0 to 3 inches; brown (10YR 5/3) very cobbly loam, dark brown (10YR 3/3) moist; moderate fine granular structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine interstitial pores; about 20 percent pebbles and 20 percent cobbles; neutral (pH 6.8); clear wavy boundary.

Bt1—3 to 7 inches; yellowish brown (10YR 5/4) very cobbly loam, dark yellowish brown (10YR 4/4) moist; moderate very fine and fine subangular blocky structure; hard, firm, slightly sticky and slightly plastic; common very fine and fine roots; common very fine and fine tubular pores; about 35 percent cobbles and 20 percent pebbles; few thin clay films on faces of peds and in pores; neutral (pH 6.8); clear wavy boundary.

Bt2—7 to 17 inches; light yellowish brown (10YR 6/4) extremely cobbly loam, dark yellowish brown (10YR 4/4) moist; moderate very fine and fine angular blocky structure; hard, firm, slightly sticky and slightly plastic; few very fine and fine roots; common very fine and fine tubular pores; about 30 percent cobbles and 35 percent pebbles; common thin clay films on faces of peds and in pores; neutral (pH 7.2); abrupt wavy boundary.

2R—17 inches; quartzitic sandstone.

### **Typical Pedon Location**

*Map unit in which located:* Vitale-Blackspar complex, 30 to 60 percent slopes

*Location in survey area:* About 2 miles east and 6 miles north of Fish Creek Reservoir; about 900 feet north and 400 feet east of the southwest corner of sec. 6, T. 2 N., R. 23 E.

## **Range in Characteristics**

*Depth to bedrock:* 10 to 20 inches

*Average annual soil temperature:* 42 to 45 degrees F

*A horizon:*

Value—5 or 6 dry, 2 or 3 moist

Content of rock fragments—35 to 60 percent

Content of organic matter—1 to 2 percent

*Bt horizon:*

Hue—10YR or 7.5YR

Value—4 to 6 dry

Texture—very cobbly loam, very cobbly clay loam, or extremely cobbly loam

Content of clay—20 to 30 percent

Content of rock fragments—35 to 75 percent

### **Taxadjunct Feature**

The Blackspar soils in this survey area at elevations above about 7,500 feet have cryic temperatures, which are outside the range for the series. This difference, however, does not significantly affect use and management.

## **Blackspot Series**

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Position on landscape:* Mountainsides

*Parent material:* Mixed colluvium over calcareous quartzitic residuum

*Slope:* 30 to 60 percent

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 44 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid (shallow) Haplic Durixerolls

### **Typical Pedon**

A1—0 to 1 inch; grayish brown (10YR 5/2) very gravelly loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine and fine tubular pores; about 35 percent pebbles and 5 percent cobbles; slightly effervescent (about 10 percent lime); mildly alkaline (pH 7.8); clear wavy boundary.

A2—1 to 7 inches; brown (10YR 5/3) very gravelly loam, dark brown (10YR 3/3) moist; moderate fine granular structure; soft, friable, slightly sticky and slightly plastic; common very fine and fine roots; common very fine and fine tubular pores; about 5 percent cobbles and 40 percent pebbles; strongly effervescent (about 15 percent lime); moderately alkaline (pH 8.0); gradual wavy boundary.

Bk—7 to 11 inches; pale brown (10YR 6/3) very gravelly loam, brown (10YR 4/3) moist; weak fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine and fine roots; common very fine and fine tubular pores; about 5 percent cobbles and 45 percent pebbles; violently effervescent (about 30 percent lime); moderately alkaline (pH 8.2); clear wavy boundary.

Bqk—11 to 14 inches; pale brown (10YR 6/3) very gravelly loam, brown (10YR 4/3) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; few fine tubular pores; about 5 percent cobbles and 50 percent pebbles, including 10 percent duripan fragments; violently effervescent (about 35 percent lime); strongly alkaline (pH 8.6); abrupt wavy boundary.

2Bqkm—14 to 19 inches; white, indurated duripan, very pale brown (10YR 7/3) moist; massive; few fine roots on top of duripan; about 10 percent cobbles and 60 percent pebbles cemented in place; violently effervescent (about 35 percent lime); strongly alkaline (pH 8.8); abrupt broken boundary.

2R—19 inches; fractured, calcareous quartzite with 2Bqkm horizon material in fractures.

### Typical Pedon Location

*Map unit in which located:* Blackspot-Prudy association, 30 to 60 percent slopes

*Location in survey area:* About 8 miles south and 3 miles east of Gannett; about 400 feet west and 1,200 feet south of the northeast corner of sec. 18, T. 2 S., R. 18 E.

### Range in Characteristics

*Average annual soil temperature:* 42 to 45 degrees F

*Thickness of mollic epipedon:* 7 to 10 inches

*Depth to duripan:* 13 to 17 inches

*Depth to bedrock:* 19 to 22 inches

*Other characteristics:* Bqk horizon absent in some pedons

*A horizon:*

Hue—10YR or 2.5Y

Value—4 or 5 dry, 2 or 3 moist

Content of pebbles—35 to 45 percent

Content of cobbles—5 to 10 percent

Content of clay—10 to 18 percent

*Bk horizon:*

Hue—10YR or 2.5Y

Value—6 or 7 dry, 4 or 5 moist

Chroma—2 or 3 dry or moist

Texture—very gravelly loam, extremely gravelly loam, or extremely gravelly sandy loam

Content of pebbles—40 to 50 percent

Content of cobbles—5 to 15 percent

Content of clay—10 to 18 percent

Reaction—moderately alkaline or strongly alkaline

Effervescence—strongly effervescent or violently effervescent

*Bqk horizon:*

Hue—10YR or 2.5Y

Value—6 or 7 dry, 4 or 5 moist

Chroma—2 or 3 dry or moist

Texture—very gravelly loam, extremely gravelly loam, or extremely gravelly sandy loam

Content of pebbles—40 to 55 percent

Content of cobbles—5 to 15 percent

Content of clay—10 to 18 percent

Effervescence—strongly effervescent or violently effervescent

Reaction—moderately alkaline or strongly alkaline

*2Bqkm horizon:*

Value—7 or 8 dry, 6 or 7 moist

Chroma—2 or 3 dry or moist

Content of pebbles—50 to 60 percent

Content of cobbles—5 to 10 percent

Other characteristics—continuous laminar cap 1 to 3 millimeters thick

### Bostrum Series

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Position on landscape:* Basalt plains

*Parent material:* Residuum derived from basalt

*Slope:* 2 to 12 percent

*Elevation:* 4,600 to 4,900 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 45 to 50 degrees F

*Frost-free period:* 100 to 120 days

**Taxonomic class:** Fine, montmorillonitic, mesic Typic Palexeralfs



### Typical Pedon

A—0 to 2 inches; grayish brown (10YR 5/2) cobbly silt loam, dark grayish brown (10YR 4/2) moist; moderate thin and medium platy structure parting to strong fine and medium granular; slightly hard, friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; common fine vesicular pores; about 20 percent cobbles, 5 percent stones, and 5 percent pebbles; neutral (7.0); clear smooth boundary.

E—2 to 4 inches; pale brown (10YR 6/3) cobbly silt loam, brown (10YR 4/3) moist; moderate fine subangular blocky structure; slightly hard, friable, sticky and plastic; many very fine, fine, and medium roots; many very fine and fine tubular pores; about 15 percent cobbles and 5 percent pebbles; neutral (pH 7.0); clear wavy boundary.

Bt1—4 to 6 inches; yellowish brown (10YR 5/4) silty clay, dark yellowish brown (10YR 4/4) moist; moderate fine angular blocky structure; hard, friable, very sticky and very plastic; common very fine and fine roots; many very fine and fine tubular pores; about 10 percent pebbles; common moderately thick clay films on faces of peds and lining pores; neutral (pH 7.2); abrupt wavy boundary.

Bt2—6 to 20 inches; yellowish brown (10YR 5/4) silty clay, dark yellowish brown (10YR 4/4) moist; strong medium and coarse prismatic structure parting to strong fine and medium angular blocky; very hard, firm, very sticky and very plastic; common very fine and fine roots; few very fine and fine tubular pores; about 5 percent pebbles; common moderately thick clay films on faces of peds and lining pores; mildly alkaline (pH 7.4); gradual wavy boundary.

Bt3—20 to 28 inches; brown (10YR 5/3) silty clay, brown (10YR 4/3) moist; moderate medium and coarse prismatic structure parting to weak fine and medium angular blocky; very hard, firm, very sticky and very plastic; few fine roots; few very fine and fine tubular pores; about 5 percent pebbles; common moderately thick clay films on faces of peds and lining pores; mildly alkaline (pH 7.4); clear wavy boundary.

Btk—28 to 32 inches; light yellowish brown (10YR 6/4) silty clay loam, yellowish brown (10YR 5/4) moist; weak fine and medium angular blocky structure; hard, friable, sticky and plastic; few fine roots; few very fine and fine tubular pores; few moderately thick clay films on faces of peds and lining pores; about 5 percent pebbles; slightly effervescent

(about 10 percent lime); mildly alkaline (pH 7.6); abrupt wavy boundary.

R—32 inches; lime-coated basalt.

### Typical Pedon Location

*Map unit in which located:* Bostrum-Yuttrue-Hamrub complex, 2 to 12 percent slopes

*Location in survey area:* About 3 miles south of Magic Reservoir; about 2,600 feet west and 350 feet south of the northeast corner of sec. 31, T. 2 S., R. 18 E.

### Range in Characteristics

*Average annual soil temperature:* 47 to 52 degrees F

*Depth to bedrock:* 20 to 40 inches

#### A horizon:

Value—5 or 6 dry, 3 or 4 moist

Chroma—1 to 3 dry or moist

Content of pebbles—5 to 10 percent

Content of cobbles—15 to 20 percent

Content of stones—0 to 5 percent

#### E horizon:

Value—6 or 7 dry, 3 or 4 moist

Chroma—1 to 3 dry or moist

Content of pebbles—5 to 10 percent

Content of stones—0 to 5 percent

Content of cobbles—15 to 20 percent

Content of clay—15 to 25 percent

#### Bt horizon:

Value—4 to 6 dry, 3 or 4 moist

Texture—silty clay, clay, or silty clay loam

Content of pebbles—0 to 5 percent

Content of clay—35 to 50 percent

Reaction—neutral or mildly alkaline

#### Btk horizon:

Value—4 to 6 dry, 3 to 5 moist

Chroma—3 or 4 dry or moist

Content of pebbles—0 to 5 percent

Content of clay—30 to 40 percent

Reaction—neutral to moderately alkaline

### Bringmee Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow in the upper 47 inches; moderately rapid or rapid below this depth

*Position on landscape:* Fan terraces, stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 0 to 8 percent  
*Elevation:* 4,800 to 6,000 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 40 to 45 degrees F  
*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-loamy, mixed, frigid Pachic Ultic Argixerolls

**Typical Pedon**

- Ap—0 to 7 inches; dark grayish brown (10YR 4/2) loam, very dark brown (10YR 2/2) moist; weak fine granular structure; soft, very friable; many very fine roots; many very fine and fine tubular pores; slightly acid (pH 6.2); clear smooth boundary.
- BA—7 to 15 inches; dark grayish brown (10YR 4/2) loam, very dark brown (10YR 2/2) moist; weak fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine tubular pores; slightly acid (pH 6.4); clear smooth boundary.
- Bt1—15 to 26 inches; dark grayish brown (10YR 4/2) clay loam, very dark brown (10YR 2/2) moist; moderate medium subangular blocky structure; hard, friable, sticky and plastic; common very fine and fine roots; common very fine and fine tubular pores; few thin clay films on faces of peds; about 10 percent pebbles; slightly acid (pH 6.2); clear smooth boundary.
- Bt2—26 to 34 inches; grayish brown (10YR 5/2) clay loam, very dark grayish brown (10YR 3/2) moist; moderate medium subangular blocky structure; hard, friable, sticky and plastic; common very fine and fine roots; common very fine and fine tubular pores; common thin clay films on faces of peds; about 14 percent pebbles; slightly acid (pH 6.4); clear wavy boundary.
- Bt3—34 to 47 inches; brown (10YR 5/3) sandy clay loam, dark brown (10YR 4/3) moist; moderate medium subangular blocky structure; hard, firm, sticky and plastic; few very fine and fine roots; few fine tubular pores; about 14 percent pebbles; few fine distinct relict mottles; neutral (pH 6.6); clear wavy boundary.
- 2C—47 to 61 inches; light yellowish brown (10YR 6/4) gravelly sandy loam, yellowish brown (10YR 5/4) moist; few fine faint relict mottles; massive; slightly hard, friable, slightly sticky and slightly plastic; about 30 percent pebbles; neutral (pH 6.8).

**Typical Pedon Location**

*Map unit in which located:* Bringmee loam, 4 to 8 percent slopes

*Location in survey area:* About 3.5 miles north and 4 miles east of Carey; about 2,500 feet west and 600 feet south of the northeast corner of sec. 5, T. 1 S., R. 22 E.

**Range in Characteristics**

- Depth to bedrock:* More than 60 inches  
*Depth to sand and gravel:* 40 to 60 inches  
*Average annual soil temperature:* 42 to 47 degrees F  
*Thickness of mollic epipedon:* 20 to 36 inches  
*Reaction:* Moderately acid to neutral  
*Base saturation in upper 75 centimeters:* 50 to 75 percent
- A horizon:*  
Value—3 or 4 dry, 2 or 3 moist  
Chroma—1 or 2 dry or moist  
Content of rock fragments—0 to 20 percent
- Bt horizon:*  
Value—4 to 6 dry  
Chroma—2 to 4 dry or moist  
Texture—clay loam, sandy clay loam, loam  
Content of rock fragments—5 to 15 percent  
Content of clay—20 to 35 percent
- 2C horizon:*  
Value—5 to 7 dry, 4 or 5 moist  
Chroma—3 or 4 dry or moist  
Texture—gravelly sandy loam, very gravelly loamy coarse sand, or very gravelly loamy sand  
Content of rock fragments—25 to 60 percent  
Content of clay—0 to 15 percent

**Bruneel Series**

- Depth class:* Very deep  
*Drainage class:* Poorly drained  
*Permeability:* Moderate in the upper 23 inches; very rapid below this depth  
*Position on landscape:* Flood plains  
*Parent material:* Recent alluvium derived from various kinds of rock  
*Slope:* 0 to 2 percent  
*Elevation:* 4,700 to 6,000 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 40 to 44 degrees F  
*Frost-free period:* 60 to 90 days
- Taxonomic class:** Coarse-loamy over sandy or sandy-skeletal, mixed, frigid Typic Haplaquolls

**Typical Pedon**

A1—0 to 7 inches; grayish brown (10YR 5/2) loam, very



dark grayish brown (10YR 3/2) moist; weak medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many fine roots; common fine tubular pores; slightly effervescent (10 percent lime); moderately alkaline (pH 7.9); clear wavy boundary.

A2—7 to 14 inches; grayish brown (10YR 5/2) loam, very dark grayish brown (10YR 3/2) moist; many fine faint yellowish brown (10YR 5/4) mottles, dark yellowish brown (10YR 3/4) moist; weak medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common fine roots; many fine tubular pores; mildly alkaline (pH 7.4); clear wavy boundary.

Bg—14 to 23 inches; light gray (2.5Y 6/0) loam, gray (2.5Y 5/0) moist; common fine faint yellowish brown (10YR 5/4) mottles, dark yellowish brown (10YR 3/4) moist; massive; slightly hard, friable, slightly sticky and slightly plastic; common fine roots; mildly alkaline (pH 7.4); clear wavy boundary.

2Cg1—23 to 27 inches; grayish brown (10YR 5/2) very gravelly loamy sand, dark brown (10YR 3/3) moist; few faint yellowish brown (10YR 5/4) mottles; massive; soft, very friable; few fine roots; few very fine tubular pores; about 50 percent pebbles; mildly alkaline (pH 7.4); clear wavy boundary.

2Cg2—27 to 61 inches; multicolored extremely gravelly coarse sand; single grain; loose; few fine roots; about 65 percent pebbles; mildly alkaline (pH 7.4).

#### Typical Pedon Location

*Map unit in which located:* Bruneel loam, 0 to 2 percent slopes

*Location in survey area:* About 6 miles south and 1 mile west of Bellevue; about 100 feet west and 1,100 feet south of the northeast corner of sec. 2, T. 1 S., R. 18 E.

#### Range in Characteristics

*Depth to loose sand and gravel:* 20 to 30 inches

*Depth to seasonal high water table:* 12 to 18 inches for more than 90 days consecutively

*Thickness of mollic epipedon:* 10 to 20 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Effervescence:* Noneffervescent or slightly effervescent

*Reaction:* Neutral to moderately alkaline

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—1 or 2 dry or moist

*Bg horizon:*

Hue—10YR, 2.5Y, or neutral

Value—4 to 6 dry, 3 to 5 moist

Chroma—0 to 2 dry or moist

Mottles—distinct or prominent

Texture—loam or fine sandy loam

Content of clay—10 to 18 percent

Content of rock fragments—0 to 15 percent

*2Cg horizon:*

Hue—10YR or 2.5Y

Value—3 to 6 moist

Chroma—0 to 2 dry or moist

Texture—very gravelly loamy sand, extremely gravelly loamy sand, or extremely gravelly coarse sand

Content of clay—0 to 5 percent

Content of rock fragments—40 to 70 percent

Content of cobbles—5 to 20 percent

### Carey Lake Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Position on landscape:* Fan terraces

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 0 to 4 percent

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 44 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-loamy, mixed, frigid Pachic Argixerolls

#### Typical Pedon

Ap—0 to 8 inches; grayish brown (10YR 5/2) loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; common very fine and fine roots; many very fine interstitial pores; neutral (pH 7.2); clear wavy boundary.

A—8 to 12 inches; grayish brown (10YR 5/2) loam, very dark grayish brown (10YR 3/2) moist; weak fine subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; common very fine and fine roots; many very fine tubular pores; neutral (pH 7.0); abrupt wavy boundary.

Bt—12 to 20 inches; grayish brown (10YR 5/2) clay loam, dark brown (10YR 3/3) moist; strong fine and medium subangular blocky structure; slightly hard, friable, sticky and plastic; common very fine and fine roots; common very fine and fine tubular pores;



- few thin clay films on faces of peds and lining pores; neutral (pH 6.8); abrupt wavy boundary.
- BC1—20 to 31 inches; brown (10YR 5/3) fine sandy loam, dark brown (10YR 3/3) moist; weak medium subangular blocky structure; soft, very friable, slightly plastic; few very fine and fine roots; common fine tubular pores; neutral (pH 7.0); clear smooth boundary.
- BC2—31 to 42 inches; grayish brown (10YR 5/2) fine sandy loam, very dark grayish brown (10YR 3/2) moist; few fine and medium faint yellowish brown (10YR 5/6) relict mottles; weak medium subangular blocky structure; slightly hard, friable; few very fine and fine roots; common fine tubular pores; neutral (pH 7.2); clear smooth boundary.
- 2C1—42 to 47 inches; brown (10YR 5/3) fine sandy loam, dark brown (10YR 3/3) moist; many fine and medium prominent yellowish brown (10YR 5/6) relict mottles; massive; slightly hard, friable; few very fine and fine roots; few fine tubular pores; neutral (pH 7.2); gradual wavy boundary.
- 2C2—47 to 72 inches; grayish brown (10YR 5/2) loam, very dark grayish brown (10YR 3/2) moist; many fine and medium prominent yellowish brown (10YR 5/6) relict mottles; massive; slightly hard, friable; few very fine and fine roots; few fine tubular pores; neutral (pH 7.2).

**Typical Pedon Location**

*Map unit in which located:* Carey Lake loam, 0 to 2 percent slopes

*Location in survey area:* About 1.5 miles south and 0.5 mile east of Carey; about 50 feet west and 100 feet south of the northeast corner of sec. 3, T. 2 S., R. 21 E.

**Range in Characteristics**

*Depth to bedrock:* More than 60 inches

*Average annual soil temperature:* 42 to 47 degrees F

*Thickness of mollic epipedon:* 20 to 60 inches or more

*Depth to base of argillic horizon:* 20 to 28 inches

*A horizon:*

Value—2 or 3 dry or moist

*Bt horizon:*

Texture—loam, clay loam, or silt loam

Content of rock fragments—0 to 10 percent

Content of clay—22 to 33 percent

*BC horizon:*

Texture—fine sandy loam, loam, or clay loam

Content of rock fragments—0 to 10 percent

Content of clay—15 to 28 percent

Reaction—neutral or mildly alkaline

- 2C horizon:*
- Texture—very fine sandy loam, fine sandy loam, or loam
- Content of rock fragments—0 to 14 percent
- Reaction—neutral to moderately alkaline

**Cinderhurst Series**

*Depth class:* Very shallow

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Basalt plains

*Parent material:* Volcanic tephra

*Slope:* 2 to 15 percent

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 44 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Lithic Mollic Haploxeralfs

**Typical Pedon**

- A—0 to 3 inches; brown (10YR 4/3) extremely cobbly silt loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly plastic; common very fine and fine roots; many very fine interstitial pores; about 50 percent cobbles and 15 percent pebbles; slightly acid (pH 6.2); clear smooth boundary.
- Bt—3 to 8 inches; yellowish brown (10YR 5/4) very cobbly silt loam, dark yellowish brown (10YR 4/4) moist; weak fine subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; common very fine, fine, medium, and coarse roots; common very fine tubular pores; about 35 percent cobbles and 5 percent pebbles; thin clay films on sand grains; slightly acid (pH 6.4); abrupt smooth boundary.
- 2R—8 inches; basalt with vertical fractures 2 to 5 centimeters wide and 1 to 3 meters apart; Bt horizon material in fractures; few very fine, fine, and medium roots in fractures.

**Typical Pedon Location**

*Map unit in which located:* Lava flows-Cinderhurst complex, 2 to 15 percent slopes

*Location in survey area:* About 15 miles east and 6 miles north of Carey; about 1,800 feet north and 50



feet west of the southeast corner of sec. 19, T. 1 N., R. 24 E.

#### Range in Characteristics

*Depth to bedrock:* 4 to 10 inches

*Average annual soil temperature:* 42 to 47 degrees F

*Reaction:* Slightly acid or neutral

*A horizon:*

Value—4 or 5 dry

Chroma—3 or 4 dry, 2 to 4 moist

Content of rock fragments—60 to 75 percent

Content of clay—15 to 20 percent

*Bt horizon:*

Hue—10YR or 7.5YR

Value—4 or 5 dry, 3 or 4 moist

Chroma—3 or 4 moist

Texture—very cobbly silt loam, very gravelly silt loam, or extremely cobbly loam

Content of rock fragments—40 to 70 percent

Content of clay—18 to 25 percent

### Cox Series

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Position on landscape:* Basalt plains

*Parent material:* Eolian material derived from various kinds of rock

*Slope:* 2 to 15 percent

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* 10 to 12 inches

*Average annual air temperature:* 45 to 50 degrees F

*Frost-free period:* 100 to 120 days

**Taxonomic class:** Loamy-skeletal, mixed, mesic Lithic Ultic Haploxerolls

#### Typical Pedon

A—0 to 3 inches; dark brown (10YR 4/3) very stony sandy loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable; many very fine, fine, and medium roots; many very fine interstitial pores; about 40 percent stones and 10 percent cobbles; slightly acid (pH 6.4); clear wavy boundary.

AB—3 to 7 inches; dark yellowish brown (10YR 4/4) very cobbly fine sandy loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable; common very fine, fine, and medium roots; many very fine interstitial pores; about 40 percent

cobbles and 10 percent stones; neutral (pH 6.6); clear wavy boundary.

Bw—7 to 12 inches; dark yellowish brown (10YR 4/4) very cobbly fine sandy loam, dark brown (10YR 3/3) moist; weak fine and medium subangular blocky structure; soft, very friable; common very fine, fine, and medium roots; many very fine tubular pores; about 50 percent cobbles; neutral (pH 7.0); abrupt wavy boundary.

2R—12 inches; basalt.

#### Typical Pedon Location

*Map unit in which located:* Cox-Rehfield-Rock outcrop complex, 2 to 15 percent slopes

*Location in survey area:* About 22 miles east and 8 miles south of Carey; about 500 feet east and 400 feet north of the southwest corner of sec. 9, T. 2 S., R. 25 E.

#### Range in Characteristics

*Depth to bedrock:* 10 to 20 inches

*Thickness of mollic epipedon:* 8 to 12 inches

*Average annual soil temperature:* 47 to 52 degrees F

*Base saturation above the lithic contact:* Less than 75 percent

*Other characteristics:* AB horizon absent in some pedons

*A horizon:*

Value—4 or 5 dry

Chroma—2 or 3 dry or moist

*Bw horizon:*

Value—4 or 5 dry, 3 or 4 moist

Texture—very cobbly fine sandy loam, very stony sandy loam, or extremely stony sandy loam

Content of rock fragments—35 to 60 percent

Content of clay—10 to 18 percent

Reaction—slightly acid to mildly alkaline

### Deerhorn Series

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Position on landscape:* Basalt plains, sides of buttes

*Parent material:* Eolian material over basalt

*Slope:* 2 to 15 percent

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* 8 to 12 inches

*Average annual air temperature:* 45 to 50 degrees F

*Frost-free period:* 100 to 120 days

**Taxonomic class:** Fine-loamy, mixed, mesic Argic  
Durixerolls

**Typical Pedon**

- A—0 to 9 inches; dark grayish brown (10YR 4/2) fine sandy loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable; many very fine and fine roots; common very fine interstitial pores; neutral (pH 7.0); clear wavy boundary.
- Bt—9 to 17 inches; brown (10YR 5/3) sandy clay loam, dark brown (10YR 4/3) moist; moderate fine and medium subangular blocky structure; hard, firm, slightly sticky and slightly plastic; common very fine and fine roots; common very fine and fine tubular pores; few thin clay films on faces of peds and lining pores; mildly alkaline (pH 7.6); abrupt wavy boundary.
- Bk—17 to 21 inches; very pale brown (10YR 7/3) loam, pale brown (10YR 6/3) moist; weak fine and medium subangular blocky structure; hard, firm, slightly sticky and slightly plastic; common very fine and fine roots; few very fine and fine tubular pores; mildly alkaline (pH 7.8); slightly effervescent (about 10 percent lime); abrupt wavy boundary.
- 2Bqkm—21 to 24 inches; very pale brown (10YR 7/3), indurated duripan; mildly alkaline (pH 7.8); violently effervescent (about 20 percent lime); abrupt wavy boundary.
- 2R—24 inches; fractured basalt.

**Typical Pedon Location**

*Map unit in which located:* Deerhorn-Wildors complex, 2 to 8 percent slopes

*Location in survey area:* About 19 miles east and 6 miles south of Carey; about 2,600 feet east and 800 feet south of the northwest corner of sec. 33, T. 2 S., R. 24 E.

**Range in Characteristics**

- Depth to bedrock:* 22 to 35 inches
- Depth to duripan:* 20 to 30 inches
- Average annual soil temperature:* 47 to 52 degrees F
- A horizon:*  
Value—4 or 5 dry, 2 or 3 moist
- Bt horizon:*  
Hue—10YR or 7.5YR  
Chroma—2 or 3 dry or moist  
Texture—sandy clay loam, sandy loam, or loam  
Content of clay—18 to 30 percent
- 2Bqkm horizon:*  
Hue—10YR or 7.5YR

Value—7 or 8 dry, 6 or 7 moist  
Chroma—3 or 4 moist

**Dollarhide Series**

- Depth class:* Shallow
- Drainage class:* Well drained
- Permeability:* Moderately rapid
- Position on landscape:* Mountainsides, ridges
- Parent material:* Colluvium and volcanic tephra-influenced colluvium derived from quartzitic sandstone and related rock
- Slope:* 30 to 75 percent
- Elevation:* 5,200 to 9,250 feet
- Average annual precipitation:* 16 to 24 inches
- Average annual air temperature:* 36 to 41 degrees F
- Frost-free period:* Less than 60 days

**Taxonomic class:** Loamy-skeletal, mixed Lithic  
Cryoborolls

**Typical Pedon**

- A—0 to 7 inches; brown (10YR 5/3) very gravelly fine sandy loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable; many very fine, fine, and medium roots; many very fine and fine interstitial pores; about 40 percent pebbles and 10 percent cobbles; neutral (pH 6.8); clear wavy boundary.
- Bw—7 to 13 inches; yellowish brown (10YR 5/4) extremely cobbly fine sandy loam, dark yellowish brown (10YR 4/4) moist; weak fine granular structure; soft, very friable; common very fine roots; many very fine and fine interstitial pores; about 50 percent cobbles and 15 percent pebbles; neutral (pH 7.0); abrupt wavy boundary.
- 2R1—13 to 23 inches; fractured quartzite; vertical and horizontal fractures 1 to 2 millimeters wide; soil material in less than 5 percent of fractures; common very fine and fine roots along fracture planes.
- 2R2—23 inches; quartzite that is not fractured.

**Typical Pedon Location**

*Map unit in which located:* Ketchum-Dollarhide complex, 30 to 60 percent slopes

*Location in survey area:* About 1 mile northeast of Bell Mountain Lookout; about 2,500 feet north and 2,500 feet east of the southwest corner of sec. 7, T. 1 N., R. 20 E.

**Range in Characteristics**

*Depth to bedrock:* 10 to 20 inches



*Thickness of mollic epipedon:* 7 to 10 inches

*Content of clay in textural control section:* 8 to 18 percent

*Average annual soil temperature:* 39 to 43 degrees F

*Average summer soil temperature:* 54 to 59 degrees F

*A horizon:*

Value—3 or 4 moist

Content of rock fragments—35 to 60 percent

Reaction—neutral or mildly alkaline

*Bw horizon:*

Value—3 or 4 moist

Texture—extremely cobbly fine sandy loam or extremely cobbly loam

Content of rock fragments—60 to 75 percent

Reaction—neutral or mildly alkaline

## **Drage Series**

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Position on landscape:* Fan terraces, stream terraces

*Parent material:* Alluvium derived from various kinds of igneous and metamorphic rock

*Slope:* 1 to 15 percent

*Elevation:* 4,800 to 6,100 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 45 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Calcic Argixerolls

### **Typical Pedon**

A—0 to 8 inches; dark grayish brown (10YR 4/2) gravelly loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; common very fine, fine, and medium roots; many very fine and fine interstitial pores; about 16 percent pebbles; neutral (pH 6.8); abrupt smooth boundary.

BA—8 to 14 inches; brown (10YR 5/3) gravelly loam, dark brown (10YR 3/3) moist; weak medium subangular blocky structure; soft, friable, sticky and plastic; common very fine, fine, and medium roots; many very fine and fine interstitial pores; about 16 percent pebbles; few thin clay films on faces of peds and lining pores; neutral (pH 6.8); clear smooth boundary.

Bt1—14 to 25 inches; yellowish brown (10YR 5/4) very gravelly clay loam, dark yellowish brown (10YR 4/4)

moist; moderate medium angular blocky structure; slightly hard, friable, sticky and plastic; few very fine and fine roots; many very fine and fine interstitial pores; about 35 percent pebbles; many thin clay films on faces of peds and lining pores; neutral (pH 7.0); gradual wavy boundary.

Bt2—25 to 30 inches; yellowish brown (10YR 5/4) very gravelly clay loam, dark yellowish brown (10YR 4/4) moist; moderate medium angular blocky structure; hard, firm, sticky and plastic; few very fine and fine roots; many very fine and fine interstitial pores; about 40 percent pebbles and 10 percent cobbles; many thin clay films on faces of peds and lining pores; neutral (pH 7.2); gradual wavy boundary.

Bk—30 to 61 inches; very pale brown (10YR 7/4) extremely gravelly sandy loam, yellowish brown (10YR 5/4) moist; weak fine subangular blocky structure; slightly hard, friable; few very fine and fine roots; about 50 percent pebbles and 15 percent cobbles; violently effervescent (about 10 percent lime); mildly alkaline (pH 7.6).

### **Typical Pedon Location**

*Map unit in which located:* Drage gravelly loam, cool, 2 to 15 percent slopes

*Location in survey area:* About 4 miles north and 2 miles east of Hailey; about 1,200 feet north and 3,400 feet east of the southwest corner of sec. 16, T. 3 N., R. 18 E.

### **Range in Characteristics**

*Depth to bedrock:* More than 60 inches

*Thickness of mollic epipedon:* 10 to 17 inches

*Depth to lime accumulation:* 25 to 45 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Other characteristics:* BA horizon absent in some pedons

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Content of rock fragments—15 to 55 percent

Reaction—neutral or mildly alkaline

*Bt horizon:*

Value—4 or 5 dry, 3 or 4 moist

Chroma—3 or 4 dry or moist

Texture—very gravelly clay loam or very gravelly sandy clay loam

Content of rock fragments—35 to 60 percent

Content of clay—28 to 35 percent

Reaction—neutral or mildly alkaline

*Bk horizon:*

Value—6 or 7 dry, 5 or 6 moist

Chroma—3 or 4 dry or moist

Texture—extremely gravelly loam, extremely gravelly sandy loam, or extremely cobbly sandy loam

Content of rock fragments—60 to 75 percent

Reaction—mildly alkaline or moderately alkaline

**Taxadjunct Feature**

The Drage soils in this survey area at elevations above about 6,000 feet have cryic temperatures, which are outside the range for the series. This difference, however, does not significantly affect use and management.

**Earcree Series***Depth class:* Very deep*Drainage class:* Well drained*Permeability:* Moderately rapid*Positions on landscape:* Mountainsides, foothills*Parent material:* Colluvium and alluvium over residuum derived from granite*Slope:* 8 to 60 percent*Elevation:* 5,000 to 8,200 feet*Average annual precipitation:* 16 to 20 inches*Average annual air temperature:* 36 to 41 degrees F*Frost-free period:* Less than 60 days

**Taxonomic class:** Coarse-loamy, mixed Pachic  
Cryoborolls

**Typical Pedon**

A1—0 to 12 inches; dark grayish brown (10YR 4/2) gravelly coarse sandy loam, black (10YR 2/1) moist; weak fine and medium granular structure; soft, very friable; many very fine, fine, and medium roots; many very fine interstitial pores; about 30 percent pebbles; neutral (pH 6.6); clear wavy boundary.

A2—12 to 24 inches; brown (10YR 4/3) gravelly coarse sandy loam, very dark grayish brown (10YR 3/2) moist; weak fine subangular blocky structure; soft, very friable; many very fine, fine, and medium roots; common very fine and fine interstitial pores; about 30 percent pebbles; neutral (pH 6.6); abrupt wavy boundary.

A3—24 to 37 inches; brown (10YR 5/3) gravelly coarse sandy loam, dark brown (10YR 3/3) moist; massive; loose, friable; common very fine, fine, and medium roots; many very fine interstitial pores; about 30 percent pebbles; neutral (pH 6.8); clear wavy boundary.

C1—37 to 52 inches; pale brown (10YR 6/3) gravelly coarse sandy loam, brown (10YR 4/3) moist; massive; loose; few very fine, fine, and medium roots; many very fine interstitial pores; about 34 percent pebbles; neutral (pH 6.8); diffuse irregular boundary.

C2—52 to 70 inches; pale brown (10YR 6/3) very gravelly loamy coarse sand, brown (10YR 5/3) moist; massive; loose; few very fine, fine, and medium roots; many very fine pores; about 55 percent pebbles; neutral (pH 6.6).

**Typical Pedon Location**

*Map unit in which located:* Earcree-Moonstone association, 30 to 60 percent slopes

*Location in survey area:* About 1 mile south and 12 miles west of Bellevue; about 2,560 feet east and 2,200 feet south of the northwest corner of sec. 2, T. 1 N., R. 16 E.

**Range in Characteristics***Thickness of mollic epipedon:* 30 to 50 inches*Depth to bedrock:* More than 60 inches*Content of clay in control section:* 10 to 18 percent*Content of rock fragments:* 5 to 35 percent*Reaction:* Moderately acid to neutral*Average annual soil temperature:* 39 to 43 degrees F*A horizon:*

Value—3 to 5 dry

*C horizon:*

Hue—10YR to 5Y

Value—5 to 7 dry, 4 to 6 moist

Chroma—2 to 4 dry or moist

Texture—gravelly coarse sandy loam, gravelly sandy loam, or very gravelly loamy coarse sand

Content of rock fragments—30 to 45 percent

**Elkcreek Series***Depth class:* Moderately deep*Drainage class:* Well drained*Permeability:* Moderately slow*Position on landscape:* Foothills, mountainsides*Parent material:* Residuum derived from andesite and basalt*Slope:* 4 to 60 percent*Elevation:* 4,800 to 6,500 feet*Average annual precipitation:* 12 to 16 inches*Average annual air temperature:* 40 to 45 degrees F*Frost-free period:* 60 to 90 days



**Taxonomic class:** Fine-loamy, mixed, frigid Ultic Argixerolls

#### Typical Pedon

A1—0 to 6 inches; grayish brown (10YR 5/2) loam, very dark brown (10YR 2/2) moist; weak fine granular structure; soft, very friable, slightly plastic; many fine, medium, and coarse roots; many very fine and fine interstitial pores; neutral (pH 6.8); gradual wavy boundary.

A2—6 to 11 inches; brown (10YR 5/3) loam, very dark grayish brown (10YR 3/2) moist; moderate fine subangular blocky structure; hard, firm, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many very fine and fine interstitial pores; neutral (pH 7.0); clear wavy boundary.

Bt1—11 to 18 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 4/4) moist; strong fine and medium angular blocky structure; very firm, sticky and plastic; common very fine, fine, medium, and coarse roots; many fine and very fine interstitial pores; neutral (pH 7.2); gradual wavy boundary.

Bt2—18 to 28 inches; light yellowish brown (10YR 6/4) clay loam, dark yellowish brown (10YR 4/4) moist; strong medium and coarse angular blocky structure; very hard, very firm, sticky and plastic; common very fine, fine, medium, and coarse roots; many fine and very fine interstitial pores; neutral (pH 7.2); gradual wavy boundary.

BC—28 to 34 inches; yellowish brown (10YR 5/4) loam, dark yellowish brown (10YR 4/4) moist; massive parting to weak fine and medium subangular blocky structure; hard, firm, sticky and plastic; common very fine, fine, medium, and coarse roots; neutral (pH 7.2); abrupt wavy boundary.

R—34 inches; fractured basalt.

#### Typical Pedon Location

*Map unit in which located:* Elkcreek-Polecreek complex, 4 to 30 percent slopes

*Location in survey area:* About 8 miles south and 8 miles west of Bellevue; about 2,400 feet east and 300 feet south of the northwest corner of sec. 11, T. 1 S., R. 17 E.

#### Range in Characteristics

*Thickness of mollic epipedon:* 10 to 16 inches

*Depth to bedrock:* 26 to 40 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Reaction:* Slightly acid, neutral

*Base saturation:* 50 to 75 percent

*Other characteristics:* AB horizon present in some pedons

#### A horizon:

Value—4 or 5 dry

Chroma—1 to 3 dry or moist

Content of rock fragments—0 to 15 percent

#### Bt horizon:

Hue—10YR or 7.5YR

Value—3 to 5 moist

Chroma—2 to 4 dry or moist

Texture—clay loam or sandy clay loam

Content of clay—20 to 35 percent

Content of rock fragments—5 to 15 percent

#### BC horizon:

Value—5 or 6 dry

Texture—loam or clay loam

Content of rock fragments—5 to 20 percent

### Elksel Series

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Slow

*Position on landscape:* Mountainsides

*Parent material:* Colluvium and residuum derived from andesite, latite, basalt, and rhyolite

*Slope:* 30 to 60 percent

*Elevation:* 4,700 to 7,500 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 44 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Clayey-skeletal, montmorillonitic, frigid Ultic Argixerolls

#### Typical Pedon

A1—0 to 3 inches; grayish brown (10YR 5/2) very cobbly loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable; common very fine, fine, and medium roots; many very fine interstitial pores; about 25 percent cobbles and 10 percent pebbles; neutral (pH 6.6); clear wavy boundary.

A2—3 to 10 inches; dark grayish brown (10YR 4/2) very cobbly loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, friable, slightly sticky and slightly plastic; common very fine, fine, and medium roots; many very fine interstitial pores; about 35 percent cobbles and 5 percent pebbles; neutral (pH 6.8); abrupt wavy boundary.



AB—10 to 13 inches; dark grayish brown (10YR 4/2) very cobbly clay loam, dark brown (10YR 3/3) moist; moderate fine subangular blocky structure; slightly hard, firm, sticky and plastic; few very fine roots; many very fine interstitial pores; about 40 percent cobbles and 10 percent pebbles; few thin clay films in pores; neutral (pH 6.8); abrupt wavy boundary.

Bt1—13 to 17 inches; brown (10YR 5/3) very cobbly clay, dark yellowish brown (10YR 4/4) moist; strong fine subangular blocky structure; very hard, very firm, very sticky and very plastic; few very fine roots; few very fine tubular pores; about 45 percent cobbles and 10 percent pebbles; common moderately thick clay films in pores; neutral (pH 7.0); clear wavy boundary.

Bt2—17 to 33 inches; yellowish brown (10YR 5/4) extremely cobbly clay, dark yellowish brown (10YR 4/4) moist; strong fine angular blocky structure; very hard, very firm, very sticky and very plastic; few very fine tubular pores; about 60 percent cobbles and 10 percent pebbles; many thick clay films in pores; neutral (pH 7.2); gradual irregular boundary.

Bt3—33 to 45 inches; yellowish brown (10YR 5/4) extremely cobbly sandy clay, dark yellowish brown (10YR 4/4) moist; strong fine angular blocky structure; very hard, very firm, very sticky and very plastic; few very fine tubular pores; about 60 percent cobbles and 15 percent pebbles; many thick clay films in pores; neutral (pH 7.2); gradual irregular boundary.

R—45 inches; fractured andesite; fractures 1 to 4 millimeters wide; Bt3 horizon material in fractures; few very fine roots in fractures.

#### Typical Pedon Location

*Map unit in which located:* Elksel-Friedman-Starhope complex, 30 to 60 percent slopes

*Location in survey area:* About 2 miles east and 4 miles north of Carey; about 800 feet west and 100 feet south of the northeast corner of sec. 35, T. 1 N., R. 21 E.

#### Range in Characteristics

*Depth to bedrock:* 40 to 60 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Base saturation in upper 75 centimeters:* 50 to 75 percent

*Other characteristics:* AB horizon absent in some pedons, Bqm horizon present below a depth of 40 inches in some pedons

#### Bt horizon:

Hue—10YR or 7.5YR

Value—3 to 5 dry, 3 or 4 moist

Texture—very cobbly clay loam, very cobbly clay, extremely cobbly clay, extremely cobbly sandy clay, very gravelly clay, or extremely gravelly clay

Content of rock fragments—35 to 80 percent

Content of clay—35 to 55 percent

### Friedman Series

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Slow

*Position on landscape:* Mountainsides

*Parent material:* Colluvium derived from latite, andesite, and welded tuff

*Slope:* 30 to 60 percent

*Elevation:* 5,000 to 8,000 feet

*Average annual precipitation:* 16 to 22 inches

*Average annual air temperature:* 36 to 41 degrees F

*Frost-free period:* Less than 60 days

**Taxonomic class:** Clayey-skeletal, montmorillonitic Argic Pachic Cryoborolls

#### Typical Pedon

A1—0 to 5 inches; dark brown (10YR 3/3) cobbly loam, very dark brown (10YR 2/2) moist; moderate fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many fine and very fine interstitial pores; about 10 percent cobbles and 5 percent pebbles; neutral (pH 6.6); gradual wavy boundary.

A2—5 to 17 inches; dark brown (10YR 3/3) gravelly loam, very dark brown (10YR 2/2) moist; moderate fine granular structure; slightly hard, firm, sticky and plastic; many very fine, fine, medium, and coarse roots; many fine and very fine interstitial pores; about 15 percent pebbles and 5 percent cobbles; neutral (pH 6.8); gradual wavy boundary.

BA—17 to 24 inches; brown (10YR 4/3) gravelly clay loam, very dark grayish brown (10YR 3/2) moist; moderate fine subangular blocky structure; hard, firm, sticky and plastic; common very fine, fine, medium, and coarse roots; many fine and very fine interstitial and tubular pores; about 20 percent pebbles and 10 percent cobbles; slightly acid (pH 6.4); clear wavy boundary.



Bt1—24 to 36 inches; dark yellowish brown (10YR 4/4) very gravelly clay, dark brown (10YR 3/3) moist; strong fine and medium subangular blocky structure; very hard, very firm, very sticky and very plastic; common very fine, fine, medium, and coarse roots; common fine and very fine tubular pores; common moderately thick clay films on faces of peds; about 35 percent pebbles and 10 percent cobbles; neutral (pH 6.8); clear wavy boundary.

Bt2—36 to 47 inches; yellowish brown (10YR 5/4) very gravelly clay loam, dark yellowish brown (10YR 3/4) moist; strong fine and medium subangular blocky structure; very hard, very firm, very sticky and very plastic; few very fine, fine, medium, and coarse roots; common fine and very fine tubular pores; common moderately thick clay films on faces of peds; about 30 percent pebbles and 5 percent cobbles; slightly acid (pH 6.8); abrupt wavy boundary.

Bt3—47 to 54 inches; brown (10YR 5/3) very gravelly sandy clay loam, dark yellowish brown (10YR 3/6) moist; moderate fine and medium subangular blocky structure; hard, firm, sticky and plastic; few very fine, fine, medium, and coarse roots; few fine and very fine tubular pores; few thin clay films on faces of peds; about 25 percent pebbles and 15 percent cobbles; neutral (pH 7.0); diffuse irregular boundary.

2R—54 inches; partially weathered latite.

#### Typical Pedon Location

*Map unit in which located:* Friedman-Elksel-Winridge complex, 30 to 60 percent slopes

*Location in survey area:* About 5.5 miles north and 2.5 miles west of Carey; about 1,000 feet east and 800 feet south of the northwest corner of sec. 14, T. 1 N., R. 21 E.

#### Range in Characteristics

*Depth to bedrock:* 40 to 60 inches

*Thickness of mollic epipedon:* 16 to 40 inches

*Average annual soil temperature:* 39 to 43 degrees F

*Average summer soil temperature:* 54 to 59 degrees F

*Content of rock fragments in control section:* 35 to 60 percent

*A horizon:*

Value—3 to 5 dry, 2 or 3 moist

Chroma—1 to 3 dry or moist

Organic matter content—3 to 5 percent

Content of rock fragments—15 to 30 percent

*BA horizon:*

Value—3 to 5 dry, 2 or 3 moist

Chroma—1 to 3 dry or moist

Content of rock fragments—15 to 30 percent

Texture—gravelly clay loam or gravelly loam

*Bt1 and Bt2 horizon:*

Hue—10YR or 7.5YR

Value—4 to 6 dry, 3 or 4 moist

Chroma—2 to 4 dry or moist

Content of rock fragments—35 to 60 percent

Content of clay—35 to 45 percent

Texture—very gravelly clay or very gravelly clay loam

*Bt3 horizon:*

Hue—10YR or 7.5YR

Value—4 to 6 dry, 3 or 4 moist

Chroma—2 to 6 dry or moist

Content of rock fragments—35 to 60 percent

Content of clay—20 to 25 percent

#### Furshur Series

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Very slow

*Position on landscape:* Mountainsides, undulating ridges

*Parent material:* Residuum and slope alluvium derived from rhyolite

*Slope:* 2 to 60 percent

*Elevation:* 4,700 to 5,600 feet

*Average annual precipitation:* 12 to 14 inches

*Average annual air temperature:* 40 to 45 degrees F

*Frost-free period:* 70 to 100 days

**Taxonomic class:** Clayey, montmorillonitic, frigid, shallow Abruptic Durixeralfs

#### Typical Pedon

A—0 to 2 inches; dark grayish brown (10YR 4/2) very channery loam, very dark grayish brown (10YR 3/2) moist; moderate medium, thick, and very thick platy structure; hard, friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine, fine, and medium tubular pores; about 40 percent channers; neutral (pH 6.8); clear smooth boundary.

BA—2 to 5 inches; brown (10YR 5/3) clay loam, dark brown (10YR 3/3) moist; moderate medium subangular blocky structure; hard, friable, sticky and plastic; many very fine, fine, and medium roots; common fine tubular pores; few thin clay films lining pores and on faces of peds; 15 percent pebble-

sized pan fragments; about 5 percent pebbles and 5 percent cobbles; neutral (pH 7.0); abrupt wavy boundary.

Bt1—5 to 13 inches; yellowish brown (10YR 5/4) clay, dark yellowish brown (10YR 4/4) moist; strong medium prismatic structure; very hard, firm, very sticky and very plastic; common very fine and fine roots and few medium and coarse roots; few fine tubular pores; continuous thick clay films lining pores and on faces of peds; 5 percent pebbles and 5 percent cobbles; neutral (pH 7.0); clear wavy boundary.

Bt2—13 to 15 inches; brownish yellow (10YR 6/6) gravelly clay, yellowish brown (10YR 5/6) moist; moderate medium angular blocky structure; very hard, very firm, very sticky and very plastic; common very fine and few medium roots; few fine tubular pores; many moderately thick clay films lining pores and on faces of peds; 20 percent pebbles and 10 percent cobbles; neutral (pH 7.2); abrupt smooth boundary.

Bqkm—15 to 20 inches; very pale brown (10YR 8/3), indurated duripan; few very fine and fine roots matted on top of horizon; continuous laminar cap 1 to 3 millimeters thick at a depth of 15 inches; slightly effervescent (about 10 percent lime); mildly alkaline (pH 7.8); abrupt smooth boundary.

R—20 inches; fractured, layered rhyolitic bedrock; lime and silica in fractures.

#### Typical Pedon Location

*Map unit in which located:* Elksel-Peevywell-Furshur complex, 30 to 60 percent slopes

*Location in survey area:* About 2 miles southeast of the junction of U.S. Highways 93 and 20; about 1,700 feet west and 1,500 feet north of the southeast corner of sec. 25, T. 1 S., R. 18 E.

#### Range in Characteristics

*Depth to bedrock:* 18 to 24 inches

*Depth to duripan:* 14 to 20 inches

*Average annual soil temperature:* 42 to 47 degrees F

*A horizon:*

Value—4 or 5 dry

Chroma—2 or 3 dry or moist

*BA horizon:*

Chroma—3 or 4 dry

*Bt horizon:*

Hue—7.5YR or 10YR

Value—5 or 6 dry

Chroma—4 to 6 moist

Content of rock fragments—5 to 30 percent

Content of clay—50 to 60 percent

Texture—clay or gravelly clay

*Bqkm horizon:*

Hue—7.5YR or 10YR

Value—7 or 8 dry, 5 to 8 moist

Chroma—1 to 4 dry, 2 to 4 moist

Reaction—mildly alkaline or moderately alkaline

### Gaib Series

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Position on landscape:* Foothills, mountainsides

*Parent material:* Residuum derived from andesite, latite, and basalt

*Slope:* 4 to 60 percent

*Elevation:* 4,800 to 7,500 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 44 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Lithic Ultic Argixerolls

#### Typical Pedon

A—0 to 5 inches; brown (10YR 4/3) very gravelly loam, dark brown (10YR 3/3) moist; weak medium subangular blocky structure; soft, very friable, slightly sticky; common very fine and fine roots; many fine and medium tubular pores; about 25 percent pebbles and 10 percent cobbles; moderately acid (pH 6.0); clear smooth boundary.

Bt—5 to 13 inches; dark yellowish brown (10YR 4/4) very cobbly clay loam, dark yellowish brown (10YR 3/4) moist; moderate medium angular blocky structure; hard, friable, sticky and plastic; common very fine and fine roots; many fine and medium tubular pores; few thin clay films on faces of peds; about 10 percent pebbles and 30 percent cobbles; neutral (pH 6.8); abrupt smooth boundary.

R—13 inches; fractured basalt.

#### Typical Pedon Location

*Map unit in which located:* Gaib-Rock outcrop complex, 30 to 60 percent slopes

*Location in survey area:* About 3 miles southwest of Hailey; about 800 feet west and 300 feet south of the northeast corner of sec. 24, T. 2 N., R. 17 E.



### Range in Characteristics

*Depth to bedrock:* 10 to 20 inches

*Thickness of mollic epipedon:* 7 to 12 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Reaction:* Moderately acid to neutral

*Base saturation:* 50 to 75 percent

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

*Bt horizon:*

Hue—7.5YR or 10YR

Value—4 or 5 dry, 3 or 4 moist

Chroma—2 to 4 dry or moist

Texture—very cobbly clay loam or very stony sandy clay loam

Content of rock fragments—35 to 60 percent

Content of clay—24 to 35 percent

### Gimlett Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate in the upper 27 inches; very rapid below this depth

*Position on landscape:* Stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 0 to 2 percent

*Elevation:* 5,300 to 6,000 feet

*Average annual precipitation:* 16 to 18 inches

*Average annual air temperature:* 39 to 42 degrees F

*Frost-free period:* 60 to 75 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Pachic Ultic Haploxerolls

### Typical Pedon

A1—0 to 3 inches; very dark grayish brown (10YR 3/2) very gravelly sandy loam, very dark brown (10YR 2/2) moist; weak very fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine roots and few medium and coarse roots; many very fine and fine interstitial pores; about 45 percent pebbles; slightly acid (pH 6.1); clear smooth boundary.

A2—3 to 9 inches; very dark grayish brown (10YR 3/2) very gravelly loam, very dark brown (10YR 2/2) moist; weak very fine and fine subangular blocky structure parting to moderate very fine and fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine roots

and few medium and coarse roots; many very fine and fine interstitial pores; about 50 percent pebbles; moderately acid (pH 6.0); clear wavy boundary.

AB—9 to 18 inches; dark grayish brown (10YR 4/2) very gravelly loam, very dark grayish brown (10YR 3/2) moist; weak very fine and fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine and fine roots and few medium and coarse roots; common very fine and fine interstitial pores and few very fine and fine tubular pores; about 45 percent pebbles; moderately acid (pH 6.0); clear wavy boundary.

Bw1—18 to 27 inches; dark brown (10YR 4/3) very gravelly sandy loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine, fine, medium, and coarse roots; common very fine and fine interstitial pores and few very fine and fine tubular pores; about 45 percent pebbles and 5 percent cobbles; moderately acid (pH 5.8); gradual wavy boundary.

2Bw2—27 to 33 inches; yellowish brown (10YR 5/4) extremely cobbly sandy loam, dark yellowish brown (10YR 3/6) moist; weak fine subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; common very fine and fine roots and few medium and coarse roots; common very fine and fine interstitial pores; about 25 percent pebbles, 40 percent cobbles, and 5 percent stones; moderately acid (pH 5.8); clear wavy boundary.

2Bw3—33 to 38 inches; yellowish brown (10YR 5/4) extremely cobbly loamy coarse sand, dark yellowish brown (10YR 3/6) moist; weak fine subangular blocky structure; loose; common very fine, fine, and medium roots; common very fine and fine interstitial pores; about 25 percent pebbles, 40 percent cobbles, and 5 percent stones; moderately acid (pH 5.8); clear wavy boundary.

2Bw4—38 to 49 inches; brown (10YR 5/3) extremely cobbly coarse sand, dark yellowish brown (10YR 3/6) moist; single grain; loose; common very fine, fine, and medium roots; many very fine and fine interstitial pores; about 25 percent pebbles, 40 percent cobbles, and 10 percent stones; moderately acid (pH 5.7); gradual wavy boundary.

2Bq—49 to 63 inches; brown (10YR 5/3) extremely cobbly coarse sand, dark yellowish brown (10YR 3/4) moist; single grain; loose; few very fine, fine, and medium roots; many very fine, fine, and medium interstitial pores; white (10YR 8/2) silica coatings on undersides of coarse fragments; about



25 percent pebbles, 40 percent cobbles, and 10 percent stones; moderately acid (pH 6.0).

### Typical Pedon Location

*Map unit in which located:* Gimlett very gravelly sandy loam, 0 to 2 percent slopes

*Location in survey area:* About  $\frac{3}{4}$  mile north and  $\frac{3}{4}$  mile west of Ketchum; about 2,150 feet east and 950 feet north of the southwest corner of sec. 12, T. 4 N., R. 17 E.

### Range in Characteristics

*Depth to cobbles and stones:* 22 to 40 inches

*Thickness of mollic epipedon:* 20 to 27 inches

*Reaction:* Moderately acid to neutral

*Average annual soil temperature:* 41 to 44 degrees F

#### A1 horizon:

Value—3 to 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Content of rock fragments—35 to 60 percent

#### A2 and AB horizons:

Value—3 to 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Texture—very gravelly sandy loam, very gravelly loam, or very gravelly sandy clay loam

Content of rock fragments—35 to 60 percent

Content of clay—14 to 19 percent

#### Bw and 2Bw horizons:

Value—5 or 6 dry, 3 or 4 moist

Chroma—4 to 6 dry or moist

Texture—extremely cobbly sandy loam, extremely cobbly loamy sand, extremely cobbly loamy coarse sand, or extremely cobbly coarse sand

Content of rock fragments—60 to 85 percent

Content of clay—8 to 15 percent

#### 2Bq horizon:

Value—5 or 6 dry, 2 or 3 moist

Chroma—3 to 6 dry or moist

Texture—extremely cobbly loamy coarse sand or extremely cobbly coarse sand

Content of rock fragments—60 to 85 percent

Content of clay—0 to 8 percent

Other characteristics—weak accumulations of lime on undersides of coarse fragments in some pedons

## Gooding Series

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Position on landscape:* Basalt plains

*Parent material:* Alluvium over basalt or rhyolite

*Slope:* 2 to 20 percent

*Elevation:* 4,600 to 5,300 feet

*Average annual precipitation:* 10 to 13 inches

*Average annual air temperature:* 45 to 50 degrees F

*Frost-free period:* 90 to 110 days

**Taxonomic class:** Fine, montmorillonitic, mesic Xerollic Paleargids

### Typical Pedon

A1—0 to 2 inches; brown (10YR 5/3) silt loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine interstitial pores; about 5 percent pebbles; neutral (pH 7.2); clear broken boundary.

A2—2 to 7 inches; brown (10YR 5/3) silt loam, dark brown (10YR 3/3) moist; moderate medium and thick platy structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine tubular pores; about 5 percent pebbles; neutral (pH 7.2); gradual wavy boundary.

E—7 to 9 inches; pale brown (10YR 6/3) silt loam, brown (10YR 5/3) moist; moderate fine and medium angular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine roots, most of which are concentrated at lower boundary; many very fine and fine tubular pores; common bleached silt and sand particles on faces of peds; about 5 percent pebbles; neutral (pH 7.0); abrupt smooth boundary.

Bt1—9 to 15 inches; yellowish brown (10YR 5/4) silty clay, brown (10YR 4/3) moist; strong medium prismatic structure; very hard, very firm, very sticky and very plastic; common very fine and fine roots; common very fine and fine tubular pores; continuous thick clay films lining pores and on faces of peds; about 5 percent pebbles; neutral (pH 7.2); gradual smooth boundary.

Bt2—15 to 23 inches; yellowish brown (10YR 5/4) silty clay, brown (10YR 4/3) moist; strong medium and coarse angular blocky structure; extremely hard, very firm, very sticky and very plastic; few fine and medium roots; common very fine and fine tubular pores; continuous thick clay films lining pores and on faces of peds; about 5 percent pebbles; mildly alkaline (pH 7.4); gradual wavy boundary.

Bt3—23 to 34 inches; pale brown (10YR 6/3) silty clay, brown (10YR 4/3) moist; strong medium and coarse



angular blocky structure; very hard, firm, very sticky and very plastic; few fine roots; common very fine and fine tubular pores; many moderately thick clay films lining pores and on faces of peds; about 5 percent pebbles; mildly alkaline (pH 7.4); gradual wavy boundary.

Btk—34 to 44 inches; very pale brown (10YR 8/4) silty clay loam, light yellowish brown (10YR 6/4) moist; moderate medium and coarse angular blocky structure; hard, firm, very sticky and very plastic; few fine roots; many very fine and fine tubular pores; common moderately thick clay films lining pores and on faces of peds; strongly effervescent (about 10 percent lime); mildly alkaline (pH 7.6); clear wavy boundary.

Bk—44 to 49 inches; very pale brown (10YR 7/4) silty clay loam, strong brown (7.5YR 5/6) moist; moderate thin and medium platy structure; hard, firm, sticky and plastic; few fine and medium roots matted on top of duripan; few very fine and fine tubular pores; violently effervescent (about 30 percent lime); moderately alkaline (pH 8.0); abrupt smooth boundary.

Bqkm—49 to 62 inches; very pale brown (10YR 7/4) weakly cemented duripan; massive; extremely hard, extremely firm; many very fine and fine discontinuous tubular pores filled with lime and silica; plates cemented with lime and silica; violently effervescent (about 30 percent lime); moderately alkaline (pH 8.2); abrupt smooth boundary.

2R—62 inches; basalt that has a silica cap.

#### Typical Pedon Location

*Map unit in which located:* Gooding-Gooding, eroded-Hamrub complex, 2 to 12 percent slopes

*Location in survey area:* About 3 miles east of Magic Reservoir Dam; about 1,200 feet west and 1,200 feet north of the southeast corner of sec. 14, T. 2 S., R. 18 E.

#### Range in Characteristics

*Depth to bedrock:* 48 to 72 inches

*Depth to duripan:* 40 to 60 inches

*Average annual soil temperature:* 47 to 52 degrees F

*Other characteristics:* A/E horizon in some pedons

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

*E horizon:*

Value—5 to 7 dry, 3 to 5 moist

*Bt and Btk horizons:*

Hue—10YR or 7.5YR

Value—4 to 8 dry, 3 to 5 moist

Chroma—2 to 4 dry or moist

Texture—silty clay, clay, or silty clay loam

Content of clay—35 to 59 percent

Other characteristics—15 to 25 percent more clay in the upper 2.5 centimeters of the Bt horizon than in the E horizon

*Bk horizon:*

Texture—silty clay loam or clay loam

*Bqkm horizon:*

Hue—10YR or 7.5YR

Value—4 to 7 dry

Chroma—3 or 4 dry

Content of lime—15 to 40 percent

Thickness of plates—2 to 10 millimeters

Vertical distance between plates—3 to 12 centimeters

### Goodington Series

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Position on landscape:* Basalt plains

*Parent material:* Loess over residuum derived from basalt

*Slope:* 2 to 20 percent

*Elevation:* 4,800 to 6,200 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 45 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine, montmorillonitic, frigid Typic Palexerolls

#### Typical Pedon

A1—0 to 6 inches; grayish brown (10YR 5/2) silt loam, very dark grayish brown (10YR 3/2) moist; moderate thin platy structure; slightly hard, friable, slightly sticky and slightly plastic; many fine roots; many fine tubular pores; neutral (pH 6.8); clear smooth boundary.

A2—6 to 10 inches; grayish brown (10YR 5/2) silt loam, very dark grayish brown (10YR 3/2) moist; weak medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many fine roots; many fine tubular pores; neutral (pH 6.6); clear smooth boundary.

BA—10 to 12 inches; brown (7.5YR 4/2) silty clay loam, dark brown (7.5YR 3/2) moist; moderate fine subangular blocky structure; hard, firm, sticky and

plastic; common fine roots; many fine tubular pores; pale brown (10YR 6/3) silt coatings on faces of peds; slightly acid (pH 6.4); abrupt smooth boundary.

Bt1—12 to 18 inches; brown (7.5YR 5/4) silty clay, dark brown (7.5YR 4/4) moist; strong medium prismatic structure; very hard, very firm, very sticky and very plastic; few fine roots; many fine tubular pores; many slickensides on faces of peds; slightly acid (pH 6.2); clear smooth boundary.

Bt2—18 to 26 inches; brown (7.5YR 5/4) silty clay, dark brown (7.5YR 4/4) moist; strong medium angular blocky structure; very hard, very firm, very sticky and very plastic; few fine roots; common fine tubular pores; continuous thick clay films on faces of peds; neutral (pH 6.8); clear smooth boundary.

Bt3—26 to 34 inches; brown (7.5YR 5/4) silty clay loam, dark brown (7.5YR 4/4) moist; moderate medium angular blocky structure; very hard, very firm, very sticky and very plastic; few fine roots; common fine tubular pores; continuous moderately thick clay films on faces of peds; moderately alkaline (pH 8.2); clear smooth boundary.

Bk—34 to 56 inches; pinkish gray (7.5YR 6/2) silty clay loam, dark brown (7.5YR 4/2) moist; moderate medium angular blocky structure; very hard, very firm, very sticky and very plastic; few fine tubular pores; nearly continuous pinkish white (7.5YR 8/2) lime coatings on faces of peds and in pores; strongly effervescent (about 20 percent lime); moderately alkaline (pH 8.4); clear smooth boundary.

R—56 inches; hard, lime-coated basalt.

#### Typical Pedon Location

*Map unit in which located:* Goodington silt loam, 2 to 4 percent slopes

*Location in survey area:* About 6 miles east and 6 miles north of Carey; about 2,200 feet west and 2,000 feet north of the southeast corner of sec. 15, T. 1 N., R. 22 E.

#### Range in Characteristics

*Depth to bedrock:* 40 to 60 inches

*Thickness of mollic epipedon:* 10 to 15 inches

*Average annual soil temperature:* 42 to 47 degrees F

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Content of clay—15 to 25 percent

Reaction—slightly acid or neutral

*Bt1 and Bt2 horizons:*

Hue—7.5YR or 10YR

Value—4 or 5 dry, 3 or 4 moist

Chroma—2 to 4 dry or moist

Texture—silty clay or clay

Content of clay—40 to 55 percent

Absolute clay increase—20 percent in upper 7.5 centimeters

Reaction—neutral to moderately alkaline

*Bt3 and Bk horizons:*

Hue—7.5YR or 10YR

Value—5 or 6 dry, 3 or 4 moist

Chroma—2 to 4 dry or moist

Texture—silt loam or silty clay loam

Content of clay—25 to 40 percent

Content of rock fragments—0 to 10 percent

Reaction—mildly alkaline or moderately alkaline

#### Hamrub Series

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Position on landscape:* Basalt plains

*Parent material:* Loess over alluvium

*Slope:* 2 to 12 percent

*Elevation:* 4,600 to 4,800 feet

*Average annual precipitation:* 11 to 13 inches

*Average annual air temperature:* 45 to 50 degrees F

*Frost-free period:* 90 to 110 days

**Taxonomic class:** Fine-silty, mixed, mesic Aridic Calcic Argixerolls

#### Typical Pedon

A1—0 to 2 inches; brown (10YR 5/3) silt loam, dark brown (10YR 3/3) moist; weak thin platy structure parting to moderate fine granular structure; soft, very friable, slightly sticky and slightly plastic; many fine and medium roots and few coarse roots; many very fine and fine tubular pores; neutral (pH 7.0); clear smooth boundary.

A2—2 to 5 inches; brown (10YR 5/3) silt loam, dark brown (10YR 3/3) moist; moderate fine granular structure; soft, very friable, slightly sticky and slightly plastic; many fine and medium roots and few coarse roots; many very fine and fine tubular pores; neutral (pH 7.2); clear wavy boundary.

BA—5 to 10 inches; yellowish brown (10YR 5/4) silt loam, dark brown (10YR 3/3) moist; weak fine and medium subangular blocky structure; slightly hard,



friable, sticky and plastic; common fine and medium roots and few coarse roots; many very fine and fine tubular pores; neutral (pH 7.2); clear wavy boundary.

Bt—10 to 26 inches; yellowish brown (10YR 5/4) silty clay loam, brown (10YR 4/3) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, sticky and plastic; common fine and medium roots and few coarse roots; common very fine and fine tubular pores; common thin clay films on faces of peds and lining pores; neutral (pH 7.2); gradual wavy boundary.

Btk—26 to 41 inches; yellowish brown (10YR 5/4) silty clay loam, dark yellowish brown (10YR 4/4) moist; weak fine subangular blocky structure; slightly hard, friable, sticky and plastic; common fine and medium roots; common very fine and fine tubular pores; few thin clay films on faces of peds and lining pores; about 5 percent pebbles; strongly effervescent (about 20 percent lime); mildly alkaline (pH 7.6); abrupt broken boundary.

Bqk—41 to 43 inches; very pale brown (10YR 7/4) silt loam, light yellowish brown (10YR 6/4) moist; weak fine subangular blocky structure; hard, firm, slightly sticky and slightly plastic; few fine roots matted on duripan fragments; few fine tubular pores; about 10 percent gravel-sized duripan fragments; strongly effervescent (about 20 percent lime); mildly alkaline (pH 7.8); abrupt smooth boundary.

Bqkm—43 to 48 inches; white (10YR 8/2), indurated duripan; massive; common fine roots matted on top of laminar cap; violently effervescent (about 35 percent lime); strongly alkaline (pH 8.5); abrupt wavy boundary.

2R—48 inches; fractured rhyolite; Bqkm horizon material in fractures.

#### Typical Pedon Location

*Map unit in which located:* Gooding-Gooding, eroded-Hamrub complex, 2 to 12 percent slopes

*Location in survey area:* About 8 miles south and 5 miles west of Gannett; about 2,000 feet east and 850 feet south of the northwest corner of sec. 13, T. 2 S., R. 18 E.

#### Range in Characteristics

*Average annual soil temperature:* 47 to 52 degrees F

*Depth to bedrock:* 45 to 60 inches

*Depth to duripan:* 40 to 50 inches

*Thickness of mollic epipedon:* 10 to 13 inches

*Depth to secondary lime:* 24 to 31 inches

#### A horizon:

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Content of clay—16 to 20 percent

#### BA horizon:

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 to 4 dry or moist

Content of clay—16 to 20 percent

#### Bt horizon:

Hue—10YR or 7.5YR

Value—5 or 6 dry, 3 or 4 moist

Texture—silt loam or silty clay loam

Content of clay—20 to 32 percent

Reaction—neutral or mildly alkaline

#### Btk horizon:

Value—5 or 6 dry, 3 or 4 moist

Chroma—3 or 4 dry or moist

Texture—silt loam or silty clay loam

Content of rock fragments—0 to 5 percent

Content of clay—20 to 32 percent

Content of lime—15 to 25 percent

Reaction—mildly alkaline or moderately alkaline

#### Bqk horizon:

Value—6 or 7 dry, 5 or 6 moist

Chroma—3 or 4 dry or moist

Texture—silt loam or loam

Content of gravel-sized duripan fragments—0 to 10 percent

Content of clay—16 to 20 percent

Content of lime—15 to 25 percent

Reaction—mildly alkaline or moderately alkaline

#### Bqkm horizon:

Value—7 or 8 dry, 5 to 7 moist

Chroma—2 or 3 dry or moist

Content of pebbles—0 to 5 percent

Content of cobbles—0 to 5 percent

Content of lime—25 to 40 percent

Reaction—moderately alkaline or strongly alkaline

### Hapur Series

*Depth class:* Very deep

*Drainage class:* Poorly drained

*Permeability:* Moderately slow

*Position on landscape:* Flood plains

*Parent material:* Silty alluvium derived from various kinds of rock

*Slope:* 0 to 2 percent



*Elevation:* 4,700 to 5,500 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 40 to 44 degrees F  
*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-loamy, frigid Typic Calciaquolls

**Typical Pedon**

- Ak1—0 to 3 inches; gray (10YR 5/1) silt loam, very dark gray (10YR 3/1) moist; strong medium subangular structure; soft, very friable, slightly sticky and plastic; many very fine, fine, and medium roots; many very fine and fine tubular pores; strongly effervescent (about 20 percent lime); moderately alkaline (pH 8.4); clear wavy boundary.
- Ak2—3 to 10 inches; gray (10YR 5/1) silty clay loam, very dark gray (10YR 3/1) moist; weak fine and medium subangular blocky structure; slightly hard, friable, sticky and plastic; many very fine, fine, and medium roots; many very fine and fine tubular pores; strongly effervescent (about 20 percent lime); moderately alkaline (pH 8.2); clear wavy boundary.
- Bkg—10 to 15 inches; gray (5Y 6/1) silty clay loam, dark gray (5Y 4/1) moist; moderate fine and medium subangular blocky structure; hard, firm, sticky and plastic; common very fine, fine, and medium roots; common very fine and fine tubular pores; slightly effervescent (about 10 percent lime); mildly alkaline (pH 7.8); abrupt wavy boundary.
- Cg—15 to 30 inches; light gray (2.5Y 7/1) clay loam, gray (2.5Y 6/1) moist; massive; hard, firm, sticky and plastic; common very fine and fine roots; common very fine and fine tubular pores; mildly alkaline (pH 7.4); clear wavy boundary.
- 2Cg1—30 to 44 inches; light gray (2.5Y 7/1) fine sandy loam, gray (2.5Y 6/1) moist; massive; slightly hard, friable, sticky and slightly plastic; common very fine and fine roots; few very fine and fine tubular pores; mildly alkaline (pH 7.4); clear wavy boundary.
- 2Cg2—44 to 51 inches; light gray (2.5Y 7/1) loamy fine sand, gray (2.5Y 6/1) moist; massive; slightly hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; many very fine and fine interstitial pores; mildly alkaline (pH 7.4); gradual wavy boundary.
- 3Cg—51 to 63 inches; light gray (2.5Y 7/1) very gravelly loamy sand, gray (2.5Y 6/1) moist; single grain; loose; many very fine and fine interstitial pores; about 40 percent pebbles; mildly alkaline (pH 7.4).

**Typical Pedon Location**

*Map unit in which located:* Hapur-Picabo silt loams, 0 to 2 percent slopes

*Location in survey area:* About 2.5 miles south of Gannett; about 2,600 feet south and 50 feet east of the northwest corner of sec. 23, T. 1 S., R. 19 E.

**Range in Characteristics**

- Depth to water table:* 6 to 12 inches  
*Depth to sand and gravel:* 40 inches or more  
*Average annual soil temperature:* 42 to 47 degrees F  
*Effervescence:* Slightly effervescent or strongly effervescent in the upper part; slightly effervescent or noneffervescent below a depth of 20 inches  
*Other characteristics:* AB horizon present in some pedons
- Ak horizon:*  
Value—4 or 5 dry, 2 or 3 moist  
Chroma—1 or 2 dry or moist  
Reaction—mildly alkaline to strongly alkaline
- Bkg and Cg horizons:*  
Hue—5Y, 2.5Y, or 10YR  
Value—6 or 7 dry, 4 or 5 moist  
Chroma—0 to 2 dry or moist  
Texture—silty clay loam, clay loam, or loam  
Average content of clay—20 to 35 percent  
Content of rock fragments—0 to 15 percent  
Reaction—neutral to strongly alkaline
- 3Cg horizon:*  
Content of clay—0 to 8 percent  
Content of rock fragments—25 to 70 percent

**Hutton Series**

- Depth class:* Very deep  
*Drainage class:* Poorly drained  
*Permeability:* Very slow  
*Position on landscape:* Flood plains  
*Parent material:* Alluvium derived from various kinds of rock  
*Slope:* 0 to 2 percent  
*Elevation:* 4,700 to 6,000 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 41 to 45 degrees F  
*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine, montmorillonitic, frigid Cumulic Haplaquolls

**Typical Pedon**

- A1—0 to 2 inches; dark gray (10YR 4/1) clay loam, black (10YR 2/1) moist; weak thin platy structure; soft, friable, slightly sticky and slightly plastic; common very fine and fine roots; many very fine



and fine tubular pores; neutral (pH 6.6); clear smooth boundary.

A2—2 to 4 inches; dark gray (10YR 4/1) clay loam, black (10YR 2/1) moist; strong fine granular structure; slightly hard, friable, slightly sticky and slightly plastic; common fine roots; many fine tubular pores; neutral (pH 6.8); clear smooth boundary.

BA—4 to 13 inches; dark gray (10YR 4/1) clay loam, very dark brown (10YR 2/2) moist; weak fine angular blocky structure; hard, firm, sticky and plastic; common fine roots; many fine tubular pores; neutral (pH 6.8); gradual smooth boundary.

Bg1—13 to 19 inches; dark gray (10YR 4/1) clay loam, very dark gray (10YR 3/1) moist; few fine prominent brown (7.5YR 5/4, moist) mottles; strong medium angular blocky structure; hard, firm, sticky and plastic; common fine roots; common fine tubular pores; neutral (pH 6.9); gradual smooth boundary.

Bg2—19 to 24 inches; gray (10YR 5/1) clay, very dark grayish brown (10YR 3/2) moist; common fine prominent dark brown (7.5YR 4/4, moist) mottles; strong medium angular blocky structure; very hard, very firm, very sticky and very plastic; few fine roots; few fine tubular pores; neutral (pH 6.6); clear smooth boundary.

Cg—24 to 62 inches; gray (2.5Y 5/1) clay, dark gray (2.5Y 4/1) moist; massive; very hard, very firm, very sticky and very plastic; neutral (pH 6.6).

#### Typical Pedon Location

*Map unit in which located:* Hutton clay loam, 0 to 2 percent slopes

*Location in survey area:* About 6 miles northwest of Carey; about 1,060 feet north and 80 feet west of the southeast corner of sec. 7, T. 1 S., R. 21 E.

#### Range in Characteristics

*Thickness of mollic epipedon:* 24 to 30 inches

*Depth to water table:* 12 to 30 inches

*Content of clay in control section:* 35 to 55 percent

*Content of rock fragments in control section:* 0 to 15 percent

*Average annual soil temperature:* 42 to 47 degrees F

*Average summer soil temperature:* 60 to 65 degrees F

*Other characteristics:* BA horizon absent in some pedons

*A horizon:*

Value—4 or 5 dry, 1 to 3 moist

Chroma—1 or 2 dry or moist

*Bg horizon:*

Hue—10YR or 2.5Y

Value—4 or 5 dry, 2 or 3 moist

Texture in lower part—silty clay, clay, or gravelly clay

Content of clay—28 to 40 percent in the upper part, 40 to 60 percent in the lower part

*Cg horizon:*

Value—4 to 7 dry

Content of clay—40 to 60 percent

#### Hutton Variant

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Very slow in the upper 39 inches; very rapid below this depth

*Position on landscape:* Stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 0 to 2 percent

*Elevation:* 4,950 to 6,000 feet

*Average annual precipitation:* 14 to 18 inches

*Average annual air temperature:* 39 to 42 degrees F

*Frost-free period:* Less than 60 days

**Taxonomic class:** Fine, montmorillonitic, frigid Pachic Ultic Argixerolls

#### Typical Pedon

A—0 to 3 inches; very dark gray (10YR 3/1) clay loam, black (10YR 2/1) moist; weak medium and thick platy structure parting to moderate fine and medium subangular blocky; hard, very friable, sticky and plastic; many very fine and fine roots and common medium roots; many very fine and fine interstitial pores; about 5 percent pebbles; strongly acid (pH 5.4); abrupt smooth boundary.

ABt—3 to 8 inches; very dark gray (10YR 3/1) clay loam, black (10YR 2/1) moist; weak medium and coarse prismatic structure parting to strong fine and medium subangular blocky; common medium roots; few very fine and fine tubular pores; few thin clay films lining pores and on faces of peds; about 10 percent pebbles; moderately acid (pH 5.8); clear smooth boundary.

Bt1—8 to 13 inches; dark gray (10YR 4/1) clay, black (10YR 2/1) moist; strong medium and coarse subangular blocky structure; very hard, firm, very sticky and very plastic; common very fine and fine roots; few very fine and fine tubular pores; few thin clay films lining pores and on faces of peds; about 10 percent pebbles; moderately acid (pH 5.9); clear wavy boundary.

- Bt2**—13 to 17 inches; dark grayish brown (10YR 4/2) clay, very dark grayish brown (10YR 3/2) moist; strong medium, coarse, and very coarse prismatic structure; very hard, firm, very sticky and very plastic; few very fine and fine roots concentrated along faces of peds; few very fine tubular pores; common thin clay films lining pores and on faces of peds; about 10 percent pebbles; moderately acid (pH 6.0); gradual wavy boundary.
- Bt3**—17 to 24 inches; grayish brown (10YR 5/2) gravelly clay, very dark grayish brown (10YR 3/2) moist; strong coarse and very coarse prismatic structure; extremely hard, very firm, very sticky and very plastic; few very fine and fine roots concentrated along faces of peds; few very fine tubular pores; common thin clay films lining pores and on faces of peds; about 15 percent pebbles; slightly acid (pH 6.3); gradual wavy boundary.
- 2Bt4**—24 to 31 inches; grayish brown (10YR 5/2) very gravelly sandy clay loam, very dark grayish brown (10YR 3/2) moist; moderate medium and coarse subangular blocky structure; hard, friable, sticky and plastic; common very fine and fine roots; many very fine and fine interstitial pores and few very fine and fine tubular pores; few thin clay films lining pores and on faces of peds; about 5 percent cobbles and 35 percent pebbles; slightly acid (pH 6.3); clear wavy boundary.
- 2Bt5**—31 to 39 inches; grayish brown (10YR 5/2) very gravelly sandy clay loam, dark brown (10YR 4/3) moist; weak fine and medium subangular blocky structure; slightly hard, very friable, slightly sticky and slightly plastic; common very fine and fine roots; many very fine and fine interstitial pores; few clay bridges between sand grains; about 10 percent cobbles and 40 percent pebbles; slightly acid (pH 6.2); gradual wavy boundary.
- 2B**—39 to 52 inches; brown (10YR 5/3) extremely gravelly sandy loam, dark brown (10YR 4/3) moist; massive; soft, very friable, slightly sticky and slightly plastic; few very fine and fine roots; many very fine and fine interstitial pores; about 10 percent cobbles and 60 percent pebbles; slightly acid (pH 6.3); gradual wavy boundary.
- 2Bq**—52 to 66 inches; multicolored extremely gravelly coarse sand; single grain; loose; few very fine and fine roots; many very fine and fine interstitial pores; about 20 percent cobbles and 60 percent pebbles; silica coatings less than 1 millimeter thick on undersides of some cobbles; slightly acid (pH 6.2).

### Typical Pedon Location

*Map unit in which located:* Hutton Variant clay loam, 0 to 2 percent slopes

*Location in survey area:* About ½ mile southeast of Hailey; about 3,400 feet east and 1,900 feet south of the northwest corner of sec. 15, T. 2 N., R. 18 E.

### Range in Characteristics

*Average annual soil temperature:* 41 to 44 degrees F

*Depth to loose sand and gravel:* 31 to 40 inches

*Thickness of mollic epipedon:* 20 to 31 inches

*Other characteristics:* Bkq horizon present in some pedons

*A horizon:*

Value—3 to 5 dry, 2 or 3 moist

Chroma—1 to 3 dry or moist

*Bt horizon:*

Value—4 or 5 dry

Chroma—1 to 4 dry or moist

Texture—clay or gravelly clay

Content of pebbles—5 to 15 percent

Content of clay—40 to 55 percent

*2Bt horizon:*

Hue—2.5Y or 10YR

Value—3 or 4 moist

Chroma—2 to 4 dry or moist

Texture—very gravelly sandy clay loam or very gravelly sandy clay

*2B and 2Bq horizons:*

Texture—extremely gravelly sandy loam, extremely gravelly loamy coarse sand, or extremely gravelly coarse sand

Content of pebbles—55 to 65 percent

Content of cobbles—5 to 20 percent

### Isknot Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Slow in the upper 35 inches; rapid or very rapid below this depth

*Position on landscape:* Stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 0 to 2 percent

*Elevation:* 4,950 to 6,100 feet

*Average annual precipitation:* 14 to 18 inches

*Average annual air temperature:* 39 to 42 degrees F

*Frost-free period:* Less than 60 days



**Taxonomic class:** Clayey-skeletal, montmorillonitic, frigid Pachic Ultic Argixerolls

### Typical Pedon

- A—0 to 2 inches; very dark gray (10YR 3/1) gravelly clay loam, black (10YR 2/1) moist; weak thin platy structure parting to moderate very fine and fine granular; slightly hard, very friable, slightly sticky and slightly plastic; many very fine roots and common fine, medium, and coarse roots; many very fine and fine interstitial pores and few very fine tubular pores; about 20 percent pebbles; moderately acid (pH 5.8); abrupt wavy boundary.
- Bt1—2 to 7 inches; very dark gray (10YR 3/1) gravelly clay loam, black (10YR 2/1) moist; moderate very fine and fine subangular blocky structure; hard, friable, sticky and plastic; many very fine roots and few fine, medium, and coarse roots; common very fine and fine interstitial pores and few very fine tubular pores; few thin clay films lining pores and on faces of peds; about 15 percent pebbles; moderately acid (pH 5.6); clear wavy boundary.
- Bt2—7 to 11 inches; very dark grayish brown (10YR 3/2) gravelly clay loam, black (10YR 2/1) moist; moderate very fine and fine subangular blocky structure; hard, friable, sticky and plastic; common very fine roots and few fine and medium roots; common very fine and fine tubular and interstitial pores; few thin clay films lining pores and on faces of peds; about 25 percent pebbles; moderately acid (pH 5.6); clear wavy boundary.
- Bt3—11 to 17 inches; dark grayish brown (10YR 4/2) very gravelly clay loam, very dark grayish brown (10YR 3/2) moist; moderate very fine and fine subangular blocky structure; hard, friable, sticky and plastic; common very fine roots and few fine and medium roots; common very fine and fine tubular and interstitial pores; common thin clay films lining pores and on faces of peds; about 5 percent cobbles and 40 percent pebbles; moderately acid (pH 5.7); gradual wavy boundary.
- Bt4—17 to 26 inches; dark grayish brown (10YR 4/2) very gravelly sandy clay loam, very dark grayish brown (10YR 3/2) moist; weak very fine and fine subangular blocky structure; hard, friable, slightly sticky and slightly plastic; common very fine and few fine roots; few very fine and fine interstitial pores; common thin clay films lining pores and on faces of peds; about 10 percent cobbles and 45 percent pebbles; moderately acid (pH 5.8); gradual wavy boundary.

Bt5—26 to 35 inches; brown (10YR 5/3) very gravelly sandy clay loam, dark brown (10YR 4/3) moist; massive; slightly hard, very friable, slightly sticky and slightly plastic; common very fine roots; many very fine and common fine interstitial pores; few clay bridges between sand grains; moderately acid (pH 5.8); clear wavy boundary.

2Bq—35 to 42 inches; brown (10YR 5/3) extremely gravelly sandy loam, dark brown (10YR 4/3) moist; massive; soft, very friable, slightly sticky and slightly plastic; common very fine roots; common very fine and fine interstitial pores; about 20 percent cobbles and 50 percent pebbles; silica coatings less than 1 millimeter thick on underside of coarse fragments; moderately acid (pH 6.0); gradual wavy boundary.

2Bkq—42 to 61 inches; pale brown (10YR 6/3) extremely gravelly loamy sand, brown (10YR 4/3) moist; single grain; loose; few very fine roots; common very fine and fine and few medium interstitial pores; about 1 percent stones, 25 percent cobbles, and 50 percent pebbles; lime and silica coatings less than 1 millimeter thick on underside of coarse fragments; moderately acid (pH 6.0).

### Typical Pedon Location

*Map unit in which located:* Isknot gravelly clay loam, 0 to 2 percent slopes

*Location in survey area:* About ½ mile southeast of Hailey; about 2,700 feet east and 1,700 feet south of the northwest corner of sec. 15, T. 2 N., R. 18 E.

### Range in Characteristics

*Average annual soil temperature:* 41 to 46 degrees F

*Depth to loose sand and gravel:* 26 to 35 inches

*Thickness of mollic epipedon:* 20 to 28 inches

*A horizon:*

Value—3 or 4 dry

Chroma—1 or 2 dry or moist

*Bt horizon:*

Value—3 to 5 dry, 2 to 4 moist

Chroma—1 to 4 dry, 1 to 3 moist

Texture—gravelly clay loam, very gravelly clay loam, very gravelly sandy clay loam, very gravelly sandy clay, or very gravelly clay

Content of pebbles—10 to 50 percent

Content of cobbles—0 to 20 percent

Content of clay—35 to 45 percent

*2Bq and 2Bkq horizons:*

Hue and chroma—widely varied because of stratification

Texture—extremely gravelly sandy loam, extremely

gravelly loamy sand, or extremely cobbly coarse sand  
Content of pebbles—40 to 65 percent  
Content of stones—0 to 5 percent  
Content of cobbles—15 to 30 percent

**Justesen Series**

*Depth class:* Very deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Position on landscape:* Fan terraces, basalt plains  
*Parent material:* Alluvium derived from various kinds of rock  
*Slope:* 2 to 30 percent  
*Elevation:* 4,700 to 6,000 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 40 to 45 degrees F  
*Frost-free period:* 60 to 90 days  
**Taxonomic class:** Fine-loamy, mixed, frigid Calcic Argixerolls

**Typical Pedon**

A1—0 to 2 inches; brown (10YR 5/3) loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots and few coarse roots; many very fine and fine tubular pores; neutral (pH 7.0); clear smooth boundary.

A2—2 to 5 inches; yellowish brown (10YR 5/4) loam, dark brown (10YR 3/3) moist; moderate medium and thick platy structure; slightly hard, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots and few coarse roots; many very fine and fine tubular pores; neutral (pH 7.0); clear wavy boundary.

BA—5 to 7 inches; yellowish brown (10YR 5/4) loam, dark brown (10YR 3/3) moist; moderate coarse subangular blocky structure; slightly hard, friable, slightly sticky and plastic; common very fine, fine, and medium roots; many very fine and fine tubular pores; neutral (pH 7.2); clear wavy boundary.

Bt1—7 to 15 inches; brown (10YR 5/3) clay loam, dark brown (10YR 3/3) moist; moderate fine and medium prismatic structure; hard, firm, sticky and plastic; common very fine, fine, and medium roots; common very fine and fine tubular pores; few thin clay films on faces of peds and lining pores; about 5 percent pebbles; neutral (pH 7.2); gradual wavy boundary.

Bt2—15 to 20 inches; pale brown (10YR 6/3) loam,

brown (10YR 4/3) moist; moderate medium and coarse subangular blocky structure; hard, friable, sticky and plastic; common very fine and fine roots; common very fine and fine tubular pores; few thin clay films on faces of peds and lining pores; about 5 percent pebbles; neutral (pH 7.2); gradual wavy boundary.

BC—20 to 24 inches; pale brown (10YR 6/3) loam, brown (10YR 5/3) moist; moderate medium and coarse subangular blocky structure; hard, friable, slightly sticky and slightly plastic; common very fine and fine roots; few fine tubular pores; about 5 percent pebbles; mildly alkaline (pH 7.4); clear smooth boundary.

Bk1—24 to 30 inches; light brownish gray (10YR 6/2) loam, grayish brown (10YR 5/2) moist; weak medium and coarse subangular blocky structure; hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; few fine tubular pores; about 5 percent pebbles; violently effervescent; moderately alkaline (pH 8.0); gradual wavy boundary.

Bk2—30 to 42 inches; light gray (10YR 7/2) loam, light brownish gray (10YR 6/2) moist; massive; hard, firm, slightly sticky and slightly plastic; few very fine and fine roots; few fine tubular pores; about 10 percent pebbles; violently effervescent; moderately alkaline (pH 8.2); clear wavy boundary.

Bk3—42 to 62 inches; white (10YR 8/2) fine sandy loam, light brownish gray (10YR 6/2) moist; massive; slightly hard, very friable, slightly sticky; few fine tubular pores; about 10 percent pebbles; violently effervescent; moderately alkaline (pH 8.2).

**Typical Pedon Location**

*Map unit in which located:* Justesen loam, 4 to 8 percent slopes (fig. 11)  
*Location in survey area:* About 3 miles south and ½ mile west of Carey; about 700 feet north and 50 feet west of the southeast corner of sec. 4, T. 2 S., R. 21 E.

**Range in Characteristics**

*Average annual soil temperature:* 42 to 47 degrees F  
*Thickness of mollic epipedon:* 11 to 15 inches  
*Depth to secondary lime:* 24 to 44 inches  
*A horizon:*  
Value—4 or 5 dry, 2 or 3 moist  
Chroma—2 to 4 dry, 2 or 3 moist  
*Bt horizon:*  
Value—5 or 6 dry  
Chroma—2 or 3 dry or moist





Figure 11.—Profile of Justesen loam, 4 to 8 percent slopes.

Texture—loam, clay loam, or silty clay loam  
Content of pebbles—0 to 5 percent

Content of clay—23 to 34 percent  
Reaction—neutral or mildly alkaline

*Bk and BC horizons:*

Texture—fine sandy loam or loam  
Content of pebbles—0 to 15 percent

### **Ketchum Series**

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Position on landscape:* Mountainsides

*Parent material:* Colluvium derived from quartzitic sandstone and related rock

*Slope:* 30 to 60 percent

*Elevation:* 6,000 to 8,500 feet

*Average annual precipitation:* 18 to 24 inches

*Average annual air temperature:* 36 to 39 degrees F

*Frost-free period:* Less than 60 days

**Taxonomic class:** Loamy-skeletal, mixed Typic Cryochrepts

### **Typical Pedon**

Oi1—2 inches to 1 inch; undecomposed forest litter.

Oi2—1 inch to 0; decomposed forest litter.

A1—0 to 3 inches; brown (10YR 5/3) very gravelly loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 40 percent pebbles and 5 percent cobbles; neutral (pH 6.8); abrupt wavy boundary.

A2—3 to 11 inches; pale brown (10YR 6/3) very gravelly fine sandy loam, dark brown (10YR 4/3) moist; weak fine and medium granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 35 percent pebbles and 10 percent cobbles; neutral (pH 6.8); abrupt wavy boundary.

Bw1—11 to 32 inches; light gray (10YR 7/2) very gravelly fine sandy loam, yellowish brown (10YR 5/4) moist; weak fine subangular blocky structure; soft, very friable; common very fine, fine, medium, and coarse roots; common very fine tubular pores; about 45 percent pebbles and 10 percent cobbles; neutral (pH 7.0); gradual wavy boundary.

Bw2—32 to 42 inches; very pale brown (10YR 7/3) very gravelly sandy loam, brown (10YR 5/3) moist; weak



fine subangular blocky structure; soft, very friable; common very fine, fine, medium, and coarse roots; many very fine and fine tubular pores; about 40 percent pebbles and 10 percent cobbles; neutral (pH 7.0); clear wavy boundary.

BC—42 to 48 inches; light yellowish brown (10YR 6/4) very gravelly sandy loam, dark yellowish brown (10YR 4/4) moist; weak medium subangular blocky structure; soft, very friable; common very fine, fine, medium, and coarse roots; many very fine and fine tubular pores; about 50 percent pebbles and 5 percent cobbles; neutral (pH 7.0); clear smooth boundary.

C—48 to 61 inches; light gray (10YR 7/2) extremely gravelly coarse sandy loam, brown (10YR 5/3) moist; single grain; friable; many very fine, fine, medium, and coarse roots; about 75 percent pebbles and 10 percent cobbles; neutral (pH 7.0).

#### Typical Pedon Location

*Map unit in which located:* Ketchum-Povey complex, 30 to 60 percent slopes

*Location in survey area:* About 4 miles east and 3 miles north of Hailey; about 1,400 feet south and 100 feet west of the northeast corner of sec. 19, T. 3 N., R. 19 E.

#### Range in Characteristics

*Depth to bedrock:* More than 60 inches

*Average annual soil temperature:* 38 to 42 degrees F

*Average summer soil temperature:* 54 to 59 degrees F

*Content of clay in textural control section:* 10 to 20 percent

*Base saturation to a depth of 75 centimeters:* 60 to 75 percent

*Other characteristics:* Bw2 and O horizons absent in some pedons

#### A1 horizon:

Value—4 or 5 dry, 2 or 3 moist

Content of rock fragments—35 to 60 percent

#### A2 and Bw1 horizons:

Value—6 or 7 dry, 4 or 5 moist

Texture—very gravelly loam, very gravelly sandy loam, or very gravelly fine sandy loam

Content of rock fragments—35 to 60 percent

#### Bw2 horizon:

Hue—2.5Y or 10YR

Texture—very gravelly loam or very gravelly sandy loam

Content of rock fragments—35 to 60 percent

#### BC horizon:

Hue—2.5Y or 10YR

Texture—very gravelly sandy loam, very gravelly fine sandy loam, or very gravelly loam

Content of rock fragments—35 to 60 percent

#### C horizon:

Value—6 or 7 dry, 4 or 5 moist

Texture—extremely gravelly fine sandy loam, or extremely gravelly coarse sandy loam

Content of rock fragments—60 to 80 percent

Reaction—neutral or mildly alkaline

### Laurentzen Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Position on landscape:* Foothills

*Parent material:* Alluvium derived from basalt

*Slope:* 4 to 30 percent

*Elevation:* 5,000 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-silty, mixed, frigid Pachic Ultic Argixerolls

#### Typical Pedon

A1—0 to 6 inches; dark brown (10YR 4/3) silt loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many fine and very fine interstitial pores; neutral (pH 6.6); clear wavy boundary.

A2—6 to 13 inches; dark brown (10YR 4/3) silt loam, dark brown (10YR 3/3) moist; weak fine subangular blocky structure; soft, very friable, slightly sticky and slightly plastic; common very fine, fine, and medium roots; few very fine tubular pores; neutral (pH 6.8); clear smooth boundary.

Bt1—13 to 26 inches; brown (10YR 4/3) clay loam, dark brown (10YR 3/3) moist; moderate fine and medium subangular blocky structure; hard, firm, sticky and plastic; common fine and very fine roots; common very fine and fine tubular pores; neutral (pH 7.0); gradual wavy boundary.

Bt2—26 to 40 inches; yellowish brown (10YR 5/4) clay loam, dark brown (7.5YR 4/4) moist; strong fine and medium subangular blocky structure; very hard,



very firm, sticky and plastic; few very fine and fine roots; common very fine, fine, and medium tubular pores; common moderately thick clay films on faces of peds; about 5 to 10 percent pebbles; neutral (pH 7.0); gradual wavy boundary.

Bt3—40 to 63 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 3/4) moist; strong medium and coarse subangular blocky structure; hard, firm, sticky and plastic; few very fine and fine roots; few fine and medium tubular pores; common moderately thick clay films on faces of peds; about 5 to 10 percent pebbles; neutral (pH 7.0); abrupt wavy boundary.

2R—63 inches; basalt.

#### Typical Pedon Location

*Map unit in which located:* Laurentzen-Mulshoe complex, 4 to 30 percent slopes

*Location in survey area:* About 6 miles south and 9 miles west of Bellevue; about 2,300 feet west and 1,500 feet south of the northeast corner of sec. 32, T. 1 N., R. 17 E.

#### Range in Characteristics

*Depth to bedrock:* 60 to 72 inches

*Thickness of mollic epipedon:* 20 to 35 inches

*Base saturation:* 50 to 75 percent

*Average annual soil temperature:* 42 to 46 degrees F

*Average summer soil temperature:* 61 to 65 degrees F

*Reaction:* Slightly acid or neutral

*A horizon:*

Hue—10YR or 7.5YR

Value—4 or 5 dry, 2 or 3 moist

Texture—loam or silt loam

*Bt horizon:*

Hue—10YR to 5YR

Chroma—2 to 4 dry or moist

Texture—clay loam, loam, or silty clay loam

Content of clay—22 to 35 percent

Content of sand coarser than very fine sand—less than 15 percent

### Lavacreek Series

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Mountainsides

*Parent material:* Mantle of volcanic tephra over colluvium derived from quartzitic sandstone and related rock

*Slope:* 15 to 60 percent

*Elevation:* 5,300 to 9,250 feet

*Average annual precipitation:* 18 to 22 inches

*Average annual air temperature:* 37 to 41 degrees F

*Frost-free period:* Less than 60 days

**Taxonomic class:** Loamy-skeletal, mixed Andeptic Cryoborolls

#### Typical Pedon

A1—0 to 4 inches; dark brown (10YR 3/3) very gravelly silt loam, very dark brown (10YR 3/2) moist; weak fine granular structure; soft, very friable; many very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 35 percent pebbles; neutral (pH 6.6); clear wavy boundary.

A2—4 to 23 inches; brown (10YR 4/3) very gravelly silt loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable; many very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 40 percent pebbles; neutral (pH 6.6); gradual wavy boundary.

BA—23 to 36 inches; dark yellowish brown (10YR 4/4) very cobbly loam, dark yellowish brown (10YR 3/4) moist; weak fine subangular blocky structure; soft, very friable; many very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 30 percent cobbles and 25 percent pebbles; neutral (pH 6.8); gradual wavy boundary.

Bw—36 to 41 inches; yellowish brown (10YR 5/4) extremely cobbly loam, dark yellowish brown (10YR 4/4) moist; weak fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine, fine, and medium roots; many very fine tubular pores; about 35 percent cobbles and 30 percent pebbles; few discontinuous bleached sand and silt grains on faces of peds; neutral (pH 6.8); clear wavy boundary.

2C—41 to 49 inches; very pale brown (10YR 7/3) extremely cobbly sandy loam, yellowish brown (10YR 5/4) moist; weak fine subangular blocky structure; soft, very friable; few very fine roots; many very fine tubular pores; about 40 percent cobbles and 30 percent pebbles; neutral (pH 6.8); diffuse irregular boundary.

2R—49 inches; fractured quartzite; less than 5 percent C horizon material in fractures.

#### Typical Pedon Location

*Map unit in which located:* Lavacreek-Dollarhide very gravelly silt loams, cold, 15 to 60 percent slopes

*Location in survey area:* About 4 miles north and 1 mile



east of Lavalake Ranch; about 2,500 feet north and 800 feet east of the southwest corner of sec. 2, T. 1 N., R. 23 E.

### Range in Characteristics

*Depth to bedrock:* 40 to 60 inches

*Thickness of mollic epipedon:* 10 to 23 inches

*Bulk density ( $\frac{1}{3}$  bar water tension) in upper 75*

*centimeters:* 0.95 gram per centimeter or less

*Average annual soil temperature:* 37 to 43 degrees F

*Average summer soil temperature:* 54 to 59 degrees F

*Reaction:* Moderately acid to neutral

*Other characteristics:* C horizon absent in some pedons

#### A horizon:

Value—3 to 5 dry

Content of rock fragments—35 to 50 percent

#### Bw horizon:

Hue—10YR or 7.5YR

Value—4 to 6 dry, 3 or 4 moist

Chroma—3 or 4 dry or moist

Texture—very gravelly silt loam, very cobbly loam, or extremely cobbly loam

Content of rock fragments—35 to 65 percent

Content of clay—10 to 20 percent

#### 2C horizon:

Value—6 or 7 dry

Texture—very gravelly loam, extremely gravelly loam, or extremely cobbly sandy loam

Content of rock fragments—35 to 70 percent

Content of clay—10 to 20 percent

### Little Wood Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate in the upper 26 inches; rapid or very rapid below this depth

*Position on landscape:* Stream terraces

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 0 to 4 percent

*Elevation:* 4,700 to 6,200 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 41 to 45 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Ultic Argixerolls

#### Typical Pedon

Ap—0 to 8 inches; brown (10YR 4/3) gravelly loam,

very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly plastic; common very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 15 percent pebbles; slightly acid (pH 6.5); clear smooth boundary.

A—8 to 13 inches; brown (10YR 4/3) gravelly loam, very dark grayish brown (10YR 3/2) moist; weak fine subangular blocky structure; soft, very friable, slightly plastic; common very fine, fine, medium, and coarse roots; common very fine tubular pores; about 25 percent pebbles; slightly acid (pH 6.5); abrupt smooth boundary.

Bt1—13 to 18 inches; brown (10YR 5/3) very gravelly sandy clay loam, dark brown (10YR 3/3) moist; moderate medium subangular blocky structure; slightly hard, friable, sticky and plastic; few very fine, fine, and medium roots; many very fine tubular pores; about 35 percent pebbles and 10 percent cobbles; few thin clay films on faces of peds; neutral (pH 6.8); clear wavy boundary.

Bt2—18 to 26 inches; yellowish brown (10YR 5/4) very gravelly sandy clay loam, dark yellowish brown (10YR 4/4) moist; strong medium subangular blocky structure; slightly hard, friable, sticky and plastic; few very fine, fine, and medium roots; many very fine tubular pores; about 45 percent pebbles and 10 percent cobbles; common moderately thick clay films on faces of peds; neutral (pH 6.8); clear wavy boundary.

BC—26 to 32 inches; yellowish brown (10YR 5/4) extremely gravelly coarse sandy loam, dark yellowish brown (10YR 4/4) moist; massive; soft, very friable, slightly sticky and slightly plastic; few very fine, fine, and medium roots; many very fine interstitial pores; about 50 percent pebbles and 10 percent cobbles; few thin clay films bridging sand grains; neutral (pH 7.0); abrupt smooth boundary.

C1—32 to 42 inches; brown (10YR 5/3) extremely gravelly loamy coarse sand, dark brown (10YR 4/3) moist; single grain; loose, very friable; few very fine, fine, and medium roots; many very fine interstitial pores; about 50 percent pebbles and 15 percent cobbles; neutral (pH 7.0); gradual wavy boundary.

C2—42 to 61 inches; pale brown (10YR 6/3) extremely gravelly coarse sand, brown (10YR 5/3) moist; single grain; loose, very friable; about 60 percent pebbles and 15 percent cobbles; neutral (pH 7.2).

#### Typical Pedon Location

*Map unit in which located:* Little Wood gravelly loam, 0 to 2 percent slopes



*Location in survey area:* About 2 miles north and 2.5 miles west of Carey; about 1,800 feet east and 2,000 feet north of the southwest corner of sec. 8, T. 1 S., R. 21 E.

#### **Range in Characteristics**

*Thickness of mollic epipedon:* 11 to 19 inches  
*Average annual soil temperature:* 42 to 47 degrees F  
*Average summer soil temperature:* 60 to 65 degrees F  
*Reaction:* Slightly acid or neutral  
*Base saturation:* 50 to 75 percent

#### *A horizon:*

Value—3 to 5 dry, 2 or 3 moist  
 Chroma—1 to 3 dry or moist  
 Texture—gravelly loam or very gravelly loam  
 Content of rock fragments—15 to 60 percent

#### *Bt horizon:*

Hue—10YR or 7.5YR  
 Value—4 to 6 dry, 3 or 4 moist  
 Chroma—2 to 4 dry or moist  
 Texture—very gravelly sandy clay loam, very gravelly clay loam, or extremely cobbly sandy clay loam  
 Content of rock fragments—35 to 70 percent  
 Content of clay—20 to 35 percent

#### *BC horizon:*

Chroma—3 or 4 moist  
 Texture—extremely gravelly coarse sandy loam, extremely cobbly sandy loam, or extremely gravelly loamy coarse sand  
 Content of rock fragments—35 to 70 percent

#### *C horizon:*

Texture—extremely gravelly loamy coarse sand, extremely gravelly coarse sand, extremely cobbly loamy coarse sand, or extremely cobbly coarse sand  
 Content of rock fragments—60 to 80 percent  
 Other characteristics—weak accumulations of lime and silica on underside of coarse fragments in some pedons

### **Lockman Series**

*Depth class:* Deep  
*Drainage class:* Well drained  
*Permeability:* Moderately rapid  
*Position on landscape:* Mountainsides  
*Parent material:* Residuum and colluvium derived from granite  
*Slope:* 30 to 60 percent

*Elevation:* 6,000 to 8,200 feet

*Average annual precipitation:* 18 to 22 inches

*Average annual air temperature:* 37 to 41 degrees F

*Frost-free period:* Less than 60 days

**Taxonomic class:** Coarse-loamy, mixed Typic Cryoborolls

#### **Typical Pedon**

- A1—0 to 10 inches; brown (10YR 5/3) sandy loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable; many very fine, fine, medium, and coarse roots; many very fine and fine interstitial pores; about 10 percent pebbles; neutral (pH 7.0); gradual wavy boundary.
- A2—10 to 15 inches; brown (10YR 5/3) sandy loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; slightly hard, very friable; many very fine, fine, medium, and coarse roots; many very fine and fine interstitial pores; about 10 percent pebbles; neutral (pH 7.2); clear wavy boundary.
- Bw—15 to 23 inches; pale brown (10YR 6/3) gravelly sandy loam, dark yellowish brown (10YR 4/4) moist; moderate fine and medium granular structure; slightly hard, friable; common very fine and fine roots; many very fine and fine interstitial pores; about 20 percent pebbles and 5 percent cobbles; neutral (pH 7.2); gradual wavy boundary.
- C—23 to 44 inches; pale brown (10YR 6/3) gravelly loamy sand, dark yellowish brown (10YR 4/4) moist; moderate fine and medium granular structure; slightly hard, friable; common very fine and fine roots; many very fine and fine interstitial pores; about 25 percent pebbles and 5 percent cobbles; neutral (pH 6.6); gradual wavy boundary.
- Cr—44 to 58 inches; light yellowish brown (10YR 6/4) gruss and weathered granite.
- R—58 inches; granite.

#### **Typical Pedon Location**

*Map unit in which located:* Earcree-Lockman complex, 30 to 60 percent slopes  
*Location in survey area:* About 3 miles south and 9 miles west of Hailey; about 1,400 feet west and 1,600 feet south of the northeast corner of sec. 25, T. 2 N., R. 16 E.

#### **Range in Characteristics**

*Depth to bedrock:* 40 to 60 inches  
*Average annual soil temperature:* 38 to 43 degrees F  
*Content of clay in textural control section:* 5 to 15 percent

*Average summer soil temperature:* 44 to 47 degrees F

*Base saturation:* 50 to 75 percent

*Reaction:* Moderately acid to neutral

*A horizon:*

Value—3 to 5 dry, 2 or 3 moist

Chroma—1 to 3 dry or moist

*Bw horizon:*

Value—5 to 7 dry, 4 or 5 moist

Chroma—2 to 4 dry or moist

Texture—sandy loam or gravelly sandy loam

*C horizon:*

Hue—10YR to 5Y

Value—6 to 8 dry, 4 to 6 moist

Chroma—3 to 6 dry or moist

Texture—gravelly sandy loam or gravelly loamy sand

## **Manard Series**

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Position on landscape:* Basalt plains

*Parent material:* Residuum derived from basalt

*Slope:* 1 to 8 percent

*Elevation:* 4,700 to 6,200 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine, montmorillonitic, frigid Typic Durixerolls

### **Typical Pedon**

A—0 to 6 inches; dark grayish brown (10YR 4/2) very stony silt loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine and fine tubular pores; about 15 percent stones and 5 percent cobbles; neutral (pH 7.0); clear wavy boundary.

BA—6 to 11 inches; dark brown (10YR 4/3) very stony silt loam, dark brown (10YR 3/3) moist; weak fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; common very fine and fine tubular pores; about 15 percent stones, 10 percent cobbles, and 5 percent pebbles; neutral (pH 7.0); abrupt smooth boundary.

Bt—11 to 20 inches; brown (10YR 5/3) silty clay, dark

yellowish brown (10YR 4/4) moist; moderate fine and medium prismatic structure; hard, firm, sticky and plastic; few very fine and fine roots on horizontal and vertical faces of peds; few very fine and fine tubular pores; about 5 percent stones and 5 percent cobbles; common thick clay films on faces of peds; neutral (pH 7.2); gradual smooth boundary.

Btk—20 to 26 inches; brown (10YR 5/3) clay, dark yellowish brown (10YR 4/4) moist; weak fine and medium subangular blocky structure; hard, firm, sticky and plastic; few very fine and fine roots on horizontal and vertical faces of peds; few very fine and fine tubular pores; about 5 percent stones and 5 percent cobbles; few moderately thick clay films on faces of peds; slightly effervescent (about 10 percent lime); mildly alkaline (pH 7.4); abrupt wavy boundary.

Bqkm—26 to 28 inches; very pale brown (10YR 7/3), indurated duripan, pale brown (10YR 6/3) moist; abrupt smooth boundary.

R—28 inches; lime-coated basalt.

### **Typical Pedon Location**

*Map unit in which located:* Goodington-Manard complex, 2 to 8 percent slopes

*Location in survey area:* About 12 miles east and 5 miles north of Carey; about 2,500 feet east and 200 feet north of the southwest corner of sec. 33, T. 1 N., R. 23 E.

### **Range in Characteristics**

*Depth to bedrock:* 21 to 38 inches

*Depth to duripan:* 20 to 37 inches

*Thickness of mollic epipedon:* 7 to 11 inches

*Average annual soil temperature:* 42 to 47 degrees F

*Average summer soil temperature:* 61 to 66 degrees F

*Reaction:* Slightly acid to mildly alkaline

*A horizon:*

Hue—10YR or 7.5YR

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Texture—stony silt loam or silt loam

Content of rock fragments—0 to 25 percent

*BA horizon:*

Value—4 or 5 dry

Texture—stony silt loam or silt loam

Content of rock fragments—0 to 25 percent

*Bt horizon:*

Hue—10YR to 5YR

Value—5 or 6 dry, 3 or 4 moist

Chroma—3 or 4 dry or moist



Texture—silty clay or clay  
 Content of rock fragments—0 to 10 percent  
 Content of clay—40 to 50 percent

*Btk horizon:*

Value—5 or 6 dry  
 Chroma—3 or 4 dry  
 Texture—silty clay or clay  
 Content of rock fragments—0 to 10 percent  
 Content of clay—35 to 50 percent

*Bqkm horizon:*

Value—6 to 8 dry  
 Chroma—2 or 3 dry

## **Marshdale Series**

*Depth class:* Very deep

*Drainage class:* Poorly drained

*Permeability:* Moderate

*Position on landscape:* Drainageways, flood plains

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 0 to 2 percent

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-loamy, mixed, frigid Cumulic Haplaquolls

### **Typical Pedon**

A1—0 to 4 inches; dark grayish brown (10YR 4/2) loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine and fine interstitial pores; mildly alkaline (pH 7.6); clear smooth boundary.

A2—4 to 14 inches; dark grayish brown (10YR 4/2) loam, very dark gray (10YR 3/1) moist; few fine distinct dark yellowish brown (10YR 4/4, dry) mottles; weak fine and medium subangular blocky structure; soft, friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine and fine interstitial pores; about 5 percent pebbles; mildly alkaline (pH 7.6) clear wavy boundary.

A3—14 to 27 inches; dark grayish brown (2.5Y 4/2) loam, very dark grayish brown (2.5Y 3/2) moist; few fine distinct dark yellowish brown (10YR 4/4, dry) mottles; massive; slightly hard, friable, slightly sticky

and slightly plastic; common very fine and fine roots; about 5 percent pebbles; mildly alkaline (pH 7.8); clear wavy boundary.

Cg1—27 to 50 inches; light brownish gray (2.5Y 6/2) loam, dark grayish brown (2.5Y 4/2) moist; massive; slightly hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; about 10 percent pebbles; moderately alkaline (pH 8.0); abrupt wavy boundary.

2Cg2—50 to 65 inches; light gray (2.5Y 6/1) gravelly coarse sand, gray (2.5Y 5/1) moist; single grain; loose; about 25 percent pebbles; mildly alkaline (pH 7.6).

### **Typical Pedon Location**

*Map unit in which located:* Marshdale-Bruneel loams, 0 to 2 percent slopes

*Location in survey area:* About 6 miles west and 14 miles north of Carey; about 1,000 feet north and 2,700 feet west of the southeast corner of sec. 15, T. 2 N., R. 20 E.

### **Range in Characteristics**

*Thickness of mollic epipedon:* 24 to 50 inches

*Depth to secondary lime:* 40 to more than 60 inches

*Depth to water table:* 6 to 18 inches

*Average annual soil temperature:* 42 to 47 degrees F

*A1 horizon:*

Hue—5Y to 7.5YR

Value—3 to 5 dry, 2 or 3 moist

Chroma—1 to 3 dry or moist

Reaction—neutral or mildly alkaline

*A2 and A3 horizons:*

Value—4 or 5 dry

Chroma—1 or 2 dry

Texture—loam, sandy clay loam, or clay loam

Content of clay—18 to 30 percent

Content of rock fragments—0 to 10 percent

*2Cg horizon:*

Value—6 or 7 dry

Chroma—1 to 4 dry

Texture—gravelly coarse sand or very gravelly coarse sand

Content of rock fragments—20 to 45 percent

## **McBiggam Series**

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Slow

*Position on landscape:* Basalt plains

*Parent material:* Loess over residuum derived from basalt

*Slope:* 2 to 8 percent

*Elevation:* 5,300 to 5,600 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-silty, mixed, frigid Typic Palexerolls

### Typical Pedon

A1—0 to 3 inches; very dark grayish brown (10YR 3/2) silt loam, very dark brown (10YR 2/2) moist; moderate very fine granular structure; soft, friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine interstitial pores; about 10 percent gravel-sized cinders; slightly acid (pH 6.4); clear smooth boundary.

A2—3 to 10 inches; dark brown (10YR 3/3) silt loam, very dark brown (10YR 2/2) moist; moderate fine and medium granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine interstitial pores; about 10 percent gravel-sized cinders; neutral (pH 6.6); clear smooth boundary.

BA—10 to 15 inches; dark brown (10YR 4/3) silt loam, very dark grayish brown (10YR 3/2) moist; strong fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine, fine, and medium tubular pores; neutral (pH 7.0); clear smooth boundary.

Bt—15 to 26 inches; light yellowish brown (10YR 6/4) silty clay loam, dark brown (10YR 4/3) moist; strong fine and medium angular blocky structure; hard, firm, sticky and plastic; common very fine, fine, and medium roots; common very fine and fine tubular pores; few thin clay films on faces of peds and lining pores; few thin bleached sand and silt grains on faces of peds; about 5 percent cobbles and 5 percent pebbles; neutral (pH 7.0); abrupt smooth boundary.

2Btb—26 to 36 inches; brown (7.5YR 4/2) silty clay, dark brown (7.5YR 3/4) moist; strong medium and coarse prismatic structure; very hard, very firm, very sticky and plastic; common very fine and fine roots; few very fine tubular pores; many continuous slickensides on faces of peds; many moderately thick clay films lining pores; mildly alkaline (pH 7.4); abrupt wavy boundary.

2Btkb1—36 to 46 inches; brown (7.5YR 4/4) silty clay,

dark brown (7.5YR 3/4) moist; strong medium angular blocky structure; very hard, very firm, very sticky and plastic; few very fine and fine roots; common very fine tubular pores; many continuous slickensides on faces of peds; common moderately thick clay films lining pores; strongly effervescent; mildly alkaline (pH 7.8); clear wavy boundary.

2Btkb2—46 to 80 inches; brown (7.5YR 5/4) silty clay loam, brown (7.5YR 4/4) moist; massive; hard, firm, sticky and plastic; few fine roots; few fine tubular pores; nearly continuous pinkish white (7.5YR 8/2) lime coatings on faces of peds and in pores; strongly effervescent; mildly alkaline (pH 8.2).

### Typical Pedon Location

*Map unit in which located:* McBiggam silt loam, 2 to 8 percent slopes

*Location in survey area:* About 2 miles north and 18 miles east of Carey; about 2,500 feet east and 400 feet north of the southwest corner of sec. 15, T. 1 S., R. 24 E.

### Range in Characteristics

*Thickness of mollic epipedon:* 11 to 15 inches

*Depth to buried B horizon:* 22 to 36 inches

*Average annual soil temperature:* 42 to 45 degrees F

*Reaction:* Slightly acid to moderately alkaline

*Average content of clay in upper 20 inches of argillic horizon:* 26 to 35 percent

*A horizon:*

Value—3 to 5 dry, 2 or 3 moist

*Bt horizon:*

Value—4 to 6 dry

Texture—silt loam or silty clay loam

Content of rock fragments—5 to 10 percent

Content of clay—22 to 32 percent

*2Btb and 2Btkb1 horizons:*

Value—3 to 5 dry, 3 or 4 moist

Content of clay—40 to 50 percent

Reaction—neutral or mildly alkaline

*2Btkb2 horizon:*

Value—5 to 8 dry, 4 or 5 moist

Chroma—2 to 4 dry or moist

Texture—silty clay loam or clay loam

Content of rock fragments—0 to 5 percent

Content of clay—30 to 40 percent

Reaction—mildly alkaline or moderately alkaline

### McCarey Series

*Depth class:* Moderately deep



*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Position on landscape:* Buttes, basalt plains  
*Parent material:* Loess over residuum derived from basalt  
*Slope:* 2 to 30 percent  
*Elevation:* 4,700 to 5,500 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 41 to 45 degrees F  
*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-loamy, mixed, frigid Calcic Argixerolls

### Typical Pedon

- A1—0 to 4 inches; dark grayish brown (10YR 4/2) loam, very dark brown (10YR 2/2) moist; weak very fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine and fine interstitial pores; neutral (pH 6.8); clear wavy boundary.
- A2—4 to 10 inches; dark brown (10YR 4/3) loam, very dark grayish brown (10YR 3/2) moist; moderate medium granular structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine, fine, and medium roots; many very fine and fine interstitial pores; neutral (pH 7.0); clear wavy boundary.
- Bt—10 to 22 inches; yellowish brown (10YR 5/4) clay loam, brown (10YR 4/3) moist; strong medium subangular blocky structure; hard, firm, slightly sticky and slightly plastic; common very fine and fine roots; common very fine and fine tubular pores; few thin clay films on faces of peds and lining pores; neutral (pH 7.2); clear smooth boundary.
- Bk1—22 to 25 inches; very pale brown (10YR 7/3) loam, pale brown (10YR 6/3) moist; moderate fine subangular blocky structure; hard, firm, slightly sticky and slightly plastic; few very fine and fine roots; few very fine and fine tubular pores; about 5 percent pebbles; violently effervescent (about 20 percent lime); moderately alkaline (pH 8.2); clear smooth boundary.
- Bk2—25 to 37 inches; white (10YR 8/2) silt loam, very pale brown (10YR 7/3) moist; massive; few very fine and fine roots; few fine and very fine tubular pores; about 10 percent pebbles; violently effervescent (about 20 percent lime); abrupt smooth boundary.
- R—37 inches; basalt.

### Typical Pedon Location

*Map unit in which located:* McCarey-Molyneux loams, 2 to 8 percent slopes

*Location in survey area:* About 12 miles east of Carey; about 500 feet east and 50 feet north of the southwest corner of sec. 34, T. 1 S., R. 24 E.

### Range in Characteristics

*Depth to bedrock:* 20 to 40 inches  
*Depth to secondary lime:* 15 to 25 inches  
*Average annual soil temperature:* 42 to 47 degrees F  
*Content of clay in control section:* 20 to 34 percent

#### A horizon:

Value—4 or 5 dry  
 Reaction—slightly acid to mildly alkaline

#### Bt horizon:

Hue—5YR to 10YR  
 Value—5 or 6 dry, 3 to 5 moist  
 Chroma—2 to 4 dry or moist  
 Texture—silt loam, clay loam, or silty clay loam  
 Content of rock fragments—0 to 10 percent  
 Reaction—neutral to moderately alkaline

#### Bk horizon:

Value—5 to 7 moist  
 Texture—silt loam or loam  
 Effervescence—strongly effervescent or violently effervescent  
 Reaction—neutral to moderately alkaline

### Milligan Series

*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderately rapid to a depth of 18 inches; very rapid below this depth  
*Position on landscape:* Mountainsides  
*Parent material:* Colluvium derived from quartzitic sandstone and related rock  
*Slope:* 30 to 75 percent  
*Elevation:* 5,200 to 8,500 feet  
*Average annual precipitation:* 12 to 18 inches  
*Average annual air temperature:* 40 to 43 degrees F  
*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal over fragmental, mixed, frigid Typic Haploxerolls

### Typical Pedon

- A—0 to 8 inches; brown (10YR 5/3) very cobbly loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable; many very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 20 percent pebbles and 40 percent cobbles; slightly acid (pH 6.4); gradual wavy boundary.

Bw—8 to 18 inches; yellowish brown (10YR 5/4) extremely cobbly loam, dark yellowish brown (10YR 3/4) moist; weak fine granular structure; soft, very friable; common very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 45 percent cobbles and 20 percent pebbles; neutral (pH 6.8); abrupt wavy boundary.

C—18 to 24 inches; gray (N 5/0), displaced, fractured quartzite; some voids and some brown (10YR 5/3) loam between rock fragments; few fine and medium roots; 85 percent rock fragments; abrupt wavy boundary.

2R—24 inches; hard quartzite.

### Typical Pedon Location

*Map unit in which located:* Rubbleland-Milligan complex, 60 to 75 percent slopes

*Location in survey area:* About 5 miles east and 2 miles south of Bellevue; about 2,000 feet south and 200 feet west of the northeast corner of sec. 1, T. 1 N., R. 19 E.

### Range in Characteristics

*Depth to bedrock:* 20 to 40 inches

*Thickness of mollic epipedon:* 7 to 15 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Content of clay in textural control section:* 8 to 15 percent

#### A horizon:

Value—4 or 5 dry

Chroma—2 or 3 dry or moist

Content of rock fragments—35 to 60 percent

Reaction—slightly acid or neutral

#### Bw horizon:

Value—4 to 6 dry, 3 or 4 moist

Chroma—3 or 4 dry or moist

Texture—very gravelly loam, extremely gravelly loam, or extremely cobbly loam

Content of rock fragments—55 to 75 percent

Reaction—neutral or mildly alkaline

### Taxadjunct Feature

The Milligan soils in this survey area at elevations above about 7,500 feet have cryic temperatures, which are outside the range for the series. This difference, however, does not significantly affect use and management.

## Molyneux Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderately slow

*Position on landscape:* Fan terraces, basalt plains

*Parent material:* Alluvium derived from various kinds of rock

*Slope:* 2 to 15 percent

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-loamy, mixed, frigid Ultic Argixerolls

### Typical Pedon

A1—0 to 8 inches; dark grayish brown (10YR 4/2) loam, very dark brown (10YR 2/2) moist; moderate thin and medium platy structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; common very fine interstitial pores; about 10 percent pebbles; slightly acid (pH 6.2); clear wavy boundary.

A2—8 to 13 inches; brown (10YR 5/3) loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; few very fine, fine, medium, and coarse roots; many very fine, fine, and medium interstitial pores; about 5 percent pebbles; slightly acid (pH 6.2); abrupt wavy boundary.

Bt1—13 to 24 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 3/4) moist; moderate medium prismatic structure; hard, friable, sticky and plastic; few very fine, fine, medium, and coarse roots; many fine and medium tubular pores; about 10 percent pebbles; slightly acid (pH 6.4); clear wavy boundary.

Bt2—24 to 50 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 4/4) moist; strong fine and medium angular blocky structure; very hard, firm, sticky and plastic; few very fine and medium roots; many fine and medium interstitial pores; many thin clay films on faces of peds; about 10 percent pebbles; neutral (pH 6.6); clear wavy boundary.

Bt3—50 to 75 inches; yellowish brown (10YR 5/4) gravelly sandy clay loam, dark yellowish brown (10YR 3/4) moist; moderate medium subangular blocky structure; very hard, firm, sticky and plastic; few very fine, fine, and medium roots; many fine and medium interstitial pores; many thin clay films on faces of peds; about 15 percent gravel; neutral (pH 6.8).



### Typical Pedon Location

*Map unit in which located:* Molyneux loam, cool, 2 to 15 percent slopes

*Location in survey area:* About 3 miles west and 1 mile north of Hailey; about 1,000 feet south and 1,000 feet west of the northeast corner of sec. 24, T. 2 N., R. 17 E.

### Range in Characteristics

*Depth to bedrock:* 60 inches or more

*Thickness of mollic epipedon:* 10 to 20 inches

*Average annual soil temperature:* 42 to 47 degrees F

*Base saturation in upper 75 centimeters:* 50 to 75 percent

*Reaction:* Slightly acid to mildly alkaline

*A horizon:*

Content of clay—10 to 15 percent

Content of rock fragments—0 to 10 percent

*Bt1 and Bt2 horizons:*

Value—3 to 5 dry, 2 to 4 moist

Chroma—2 to 4 dry or moist

Content of clay—27 to 35 percent

Content of rock fragments—0 to 15 percent

Texture—clay loam, silt loam, or loam

*Bt3 horizon:*

Value—3 to 5 moist

Chroma—3 or 4 dry or moist

Texture—gravelly sandy clay loam or gravelly clay loam

Content of rock fragments—15 to 25 percent

## Moonstone Series

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderately rapid

*Position on landscape:* Foothills, mountainsides

*Parent material:* Colluvium and residuum derived from granite

*Slope:* 8 to 60 percent

*Elevation:* 4,800 to 7,800 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Coarse-loamy, mixed, frigid Pachic Ultic Haploxerolls

### Typical Pedon

A—0 to 17 inches; dark grayish brown (10YR 4/2) gravelly coarse sandy loam, very dark grayish

brown (10YR 3/2) moist; moderate medium granular structure; soft, very friable; many very fine and fine roots; many fine and medium interstitial pores; 20 percent pebbles; neutral (pH 6.8); clear wavy boundary.

AB—17 to 26 inches; brown (10YR 4/3) gravelly coarse sandy loam, dark brown (10YR 3/3) moist; weak medium granular structure; slightly hard, friable; common very fine and fine roots; common very fine and fine tubular pores; 25 percent fine pebbles; neutral (pH 6.8); diffuse irregular boundary.

Bw—26 to 34 inches; pale brown (10YR 6/3) gravelly coarse sandy loam, brown (10YR 4/3) moist; weak medium subangular blocky structure; slightly hard, friable; common very fine and fine roots; common fine and medium tubular pores; 15 percent fine pebbles; neutral (pH 6.6); abrupt wavy boundary.

Cr—34 inches; very pale brown (10YR 7/3), weathered granite.

### Typical Pedon Location

*Map unit in which located:* Earcree-Moonstone association, 8 to 30 percent slopes

*Location in survey area:* About 11 miles west and 2 miles south of Bellevue; about 1,250 feet west and 800 feet south of the northeast corner of sec. 13, T. 1 N., R. 16 E.

### Range in Characteristics

*Depth to bedrock:* 20 to 40 inches

*Thickness of mollic epipedon:* 22 to 32 inches

*Average annual soil temperature:* 42 to 47 degrees F

*Base saturation in upper 75 centimeters:* 50 to 75 percent

*Content of clay in textural control section:* 10 to 15 percent

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry, 1 to 3 moist

Content of rock fragments—15 to 35 percent

Reaction—slightly acid or neutral

*Bw horizon:*

Value—4 to 6 dry, 3 or 4 moist

Texture—gravelly coarse sandy loam or coarse sandy loam

Content of rock fragments—5 to 35 percent

## Muldoon Series

*Depth class:* Deep

*Drainage class:* Well drained



*Permeability:* Moderately slow  
*Position on landscape:* Fan terraces  
*Parent material:* Alluvium derived from various kinds of igneous and metamorphic rock  
*Slope:* 2 to 15 percent  
*Elevation:* 4,800 to 6,500 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 40 to 43 degrees F  
*Frost-free period:* 60 to 90 days  
**Taxonomic class:** Fine-loamy, mixed, frigid Ultic Argixerolls

**Typical Pedon**

- A1—0 to 3 inches; brown (10YR 5/3) loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine interstitial pores; slightly acid (pH 6.2); clear smooth boundary.
- A2—3 to 7 inches; brown (10YR 5/3) loam, dark brown (10YR 3/3) moist; weak fine subangular blocky structure; soft, very friable; many very fine and fine roots; many fine tubular pores; few thin clay films on faces of peds; slightly acid (pH 6.4); abrupt smooth boundary.
- Bt1—7 to 11 inches; yellowish brown (10YR 5/4) clay loam, dark brown (10YR 3/3) moist; weak fine and medium subangular blocky structure; soft, very friable, sticky and plastic; many very fine, fine, and medium roots; many fine tubular pores; common thin clay films on faces of peds; slightly acid (pH 6.4); clear wavy boundary.
- Bt2—11 to 22 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 3/4) moist; moderate medium subangular blocky structure; hard, friable, very sticky and plastic; common fine and medium roots; many fine tubular pores; many moderately thick clay films on faces of peds and lining pores; neutral (pH 6.8); gradual smooth boundary.
- Bt3—22 to 32 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 3/4) moist; strong fine angular blocky structure; very hard, firm, very sticky and very plastic; few fine and medium roots; common very fine tubular pores; many thick clay films on faces of peds and lining pores; neutral (pH 6.8); gradual smooth boundary.
- Bt4—32 to 45 inches; light yellowish brown (10YR 6/4) clay loam, dark yellowish brown (10YR 4/4) moist; moderate fine subangular blocky structure; hard, firm, very sticky and very plastic; few fine roots; few very fine tubular pores; about 5 percent pebbles;

common moderately thick clay films on faces of peds and lining pores; neutral (pH 7.2); clear smooth boundary.

2Bqm—45 to 56 inches; light yellowish brown (10YR 6/4), indurated duripan, dark yellowish brown (10YR 4/4) moist; massive; few very fine tubular pores; plates cemented with silica (veins of silica about 1 to 4 millimeters thick in plates); neutral (pH 7.2).

**Typical Pedon Location**

*Map unit in which located:* Muldoon-Peevywell loams, 2 to 15 percent slopes  
*Location in survey area:* About 11 miles north and 5 miles west of Carey; about 300 feet west and 450 feet south of the northeast corner of sec. 35, T. 2 N., R. 20 E.

**Range in Characteristics**

*Depth to bedrock:* More than 60 inches  
*Depth to duripan:* 40 to 60 inches  
*Thickness of mollic epipedon:* 10 to 16 inches  
*Base saturation in upper 30 inches:* 50 to 75 percent  
*Average annual soil temperature:* 42 to 46 degrees F  
*Other characteristics:* A2, Bt1, or Bt4 horizons absent in some pedons

*A horizon:*  
Value—4 or 5 dry, 2 or 3 moist

*Bt horizon:*  
Hue—10YR or 7.5YR  
Value—2 to 5 moist  
Chroma—2 to 4 dry or moist  
Texture—clay loam, silty clay loam, or cobbly clay loam  
Content of rock fragments—0 to 30 percent  
Content of clay—27 to 35 percent

*2Bqm horizon:*  
Distance between plates—2 to 10 centimeters

**Mulshoe Series**

*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Position on landscape:* Mountainsides, basalt plains, foothills  
*Parent material:* Residuum and colluvium derived from basalt  
*Slope:* 4 to 60 percent  
*Elevation:* 4,800 to 7,500 feet  
*Average annual precipitation:* 12 to 16 inches



*Average annual air temperature:* 40 to 43 degrees F  
*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Ultic  
 Argixerolls

#### Typical Pedon

A1—0 to 6 inches; brown (10YR 4/3) very stony loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, friable, slightly sticky and slightly plastic; many very fine, fine, and coarse roots; common very fine and fine interstitial pores; about 15 percent stones and 5 percent cobbles; neutral (pH 6.8); clear wavy boundary.

A2—6 to 10 inches; brown (10YR 4/3) very stony loam, dark brown (10YR 3/3) moist; weak fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine, fine, and coarse roots; few very fine and fine tubular pores; about 50 percent stones and 5 percent pebbles; neutral (pH 6.8); clear smooth boundary.

Bt—10 to 23 inches; yellowish brown (10YR 5/4) very stony clay loam, dark yellowish brown (10YR 4/4) moist; strong fine and medium angular blocky structure; very hard, firm, sticky and plastic; few fine and medium roots; few very fine and fine tubular pores; common moderately thick clay films on faces of peds; about 25 percent stones, 5 percent cobbles, and 5 percent pebbles; neutral (pH 7.0); clear smooth boundary.

Cr—23 to 28 inches; 90 percent very pale brown (10YR 8/3) weathered bedrock and 10 percent yellowish brown (10YR 5/4) clay loam in cracks and root channels; few thin clay films on rock fragments; few fine and medium roots in cracks and along fracture planes.

R—28 inches; hard basalt.

#### Typical Pedon Location

*Map unit in which located:* Mulshoe-Gaib-Rock outcrop complex, 4 to 30 percent slopes

*Location in survey area:* About 3 miles south and 7 miles west of Bellevue; about 500 feet west and 500 feet south of the northeast corner of sec. 33, T. 1 N., R. 17 E.

#### Range in Characteristics

*Depth to bedrock:* 20 to 40 inches

*Thickness of mollic epipedon:* 7 to 14 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Base saturation:* 50 to 75 percent

*Other characteristics:* Cr horizon absent in some pedons

#### A horizon:

Value—3 to 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Content of rock fragments—35 to 60 percent

Reaction—slightly acid or neutral

#### Bt horizon:

Hue—7.5YR or 10YR

Value—3 to 5 dry, 3 or 4 moist

Chroma—3 or 4 dry, 2 to 4 moist

Texture—very stony clay loam, very cobbly clay loam, or very gravelly clay loam

Content of rock fragments—35 to 60 percent

Content of clay—28 to 35 percent

### Pagari Series

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Basalt plains

*Parent material:* Eolian-influenced alluvium over basalt

*Slope:* 2 to 15 percent

*Elevation:* 4,600 to 4,800 feet

*Average annual precipitation:* 10 to 12 inches

*Average annual air temperature:* 46 to 50 degrees F

*Frost-free period:* 100 to 120 days

**Taxonomic class:** Loamy-skeletal, mixed, mesic Aridic  
 Calcic Argixerolls

#### Typical Pedon

A1—0 to 3 inches; grayish brown (10YR 5/2) very cobbly sandy loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine roots and common medium and coarse roots; many very fine and fine interstitial pores; about 10 percent stones, 40 percent cobbles, and 5 percent pebbles; neutral (pH 7.0); clear wavy boundary.

A2—3 to 11 inches; brown (10YR 5/3) very cobbly sandy loam, dark brown (10YR 3/3) moist; weak fine subangular blocky structure; soft, friable, slightly sticky and slightly plastic; many very fine and fine roots and common medium and coarse roots; common very fine and fine tubular pores; about 10 percent stones, 40 percent cobbles, and 5 percent pebbles; neutral (pH 7.0); gradual wavy boundary.

AB—11 to 17 inches; brown (10YR 5/3) very cobbly sandy loam, dark brown (10YR 3/3) moist; weak



- fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common fine, medium, and coarse roots; common very fine and fine tubular pores; about 10 percent stones, 40 percent cobbles, and 5 percent pebbles; neutral (pH 7.2); clear wavy boundary.
- Bt—17 to 31 inches; yellowish brown (10YR 5/4) extremely cobbly loam, dark yellowish brown (10YR 4/4) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, sticky and plastic; common very fine, fine, and medium roots; common very fine and fine tubular pores; few thin clay films on faces of peds, lining pores, and bridging sand grains; about 10 percent stones, 40 percent cobbles, and 10 percent pebbles; neutral (pH 7.2); clear wavy boundary.
- Bk1—31 to 36 inches; pale brown (10YR 6/3) extremely cobbly loam, brown (10YR 5/3) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; common very fine and fine tubular pores; about 10 percent stones, 40 percent cobbles, and 15 percent pebbles; slightly effervescent (about 10 percent lime); mildly alkaline (pH 7.4); clear wavy boundary.
- Bk2—36 to 46 inches; very pale brown (10YR 7/3) extremely cobbly loam, pale brown (10YR 6/3) moist; massive; slightly hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; many very fine and fine interstitial pores; about 10 percent stones, 40 percent cobbles, and 15 percent pebbles; violently effervescent (about 20 percent lime); mildly alkaline (pH 7.6); abrupt irregular boundary.
- 2R—46 inches; fractured basalt.

**Typical Pedon Location**

*Map unit in which located:* Pagari-Rehfield complex, 2 to 15 percent slopes

*Location in survey area:* About 9 miles east and 2 miles south of Carey; about 1,250 feet east and 100 feet north of the southwest corner of sec. 12, T. 2 S., R. 22 E.

**Range in Characteristics**

*Depth to bedrock:* 40 to 60 inches

*Thickness of mollic epipedon:* 10 to 17 inches

*Average annual soil temperature:* 47 to 52 degrees F

*Reaction:* Neutral or mildly alkaline

*Depth to secondary carbonates:* 24 to 36 inches

*Other characteristics:* AB horizon absent in some pedons

- A horizon:*
- Value—4 or 5 dry, 3 or 4 moist
  - Chroma—2 to 4 dry or moist
  - Content of clay—10 to 15 percent
  - Content of rock fragments—35 to 60 percent
- AB horizon:*
- Value—4 or 5 dry, 3 or 4 moist
  - Chroma—2 to 4 dry or moist
  - Texture—very cobbly sandy loam or very cobbly loam
  - Content of rock fragments—35 to 60 percent
  - Content of rock fragments larger than 3 inches—25 to 50 percent
  - Content of clay—10 to 17 percent
- Bt horizon:*
- Value—5 or 6 dry, 3 or 4 moist
  - Chroma—3 or 4 dry or moist
  - Texture—extremely cobbly loam, extremely cobbly sandy clay loam, or extremely cobbly clay loam
  - Content of rock fragments—60 to 75 percent
  - Content of rock fragments larger than 3 inches—35 to 60 percent
  - Content of clay—18 to 30 percent
- Bk horizon:*
- Value—5 to 7 dry, 4 to 6 moist
  - Chroma—3 or 4 dry or moist
  - Texture—extremely cobbly sandy loam, extremely cobbly sandy clay loam, or extremely cobbly loam
  - Content of rock fragments—60 to 75 percent
  - Content of rock fragments larger than 3 inches—35 to 60 percent
  - Content of clay—14 to 25 percent
  - Content of lime—5 to 30 percent

**Pedleford Series**

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Basalt plains, sides of buttes

*Parent material:* Alluvium derived from loess and eolian material over basalt

*Slope:* 2 to 30 percent

*Elevation:* 4,700 to 5,400 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 41 to 45 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Calcic Haploxerolls



**Typical Pedon**

A—0 to 5 inches; dark brown (10YR 4/3) very stony loam, dark brown (10YR 3/3) moist; weak fine granular structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine and fine roots and few medium and coarse roots; many very fine and fine interstitial pores; about 30 percent stones, 10 percent cobbles, and 5 percent pebbles; neutral (pH 7.0); clear wavy boundary.

Bw—5 to 13 inches; brown (10YR 5/3) very stony loam, dark brown (10YR 3/3) moist; moderate fine and medium subangular blocky structure; hard, firm, slightly sticky and slightly plastic; many very fine and fine roots and few medium and coarse roots; common very fine and fine tubular pores; about 30 percent stones, 10 percent cobbles, and 5 percent pebbles; mildly alkaline (pH 7.4); abrupt wavy boundary.

Bk1—13 to 29 inches; very pale brown (10YR 7/3) very stony silt loam, yellowish brown (10YR 5/4) moist; massive; very hard, firm, slightly sticky and slightly plastic; few very fine and fine roots; few very fine and fine tubular pores; about 30 percent stones, 20 percent cobbles, and 5 percent pebbles; moderately alkaline (pH 8.2); violently effervescent (about 20 percent lime); gradual wavy boundary.

Bk2—29 to 33 inches; very pale brown (10YR 7/3) very cobbly loam, yellowish brown (10YR 5/4) moist; massive; hard, firm, slightly sticky and slightly plastic; few very fine and fine tubular pores; about 35 percent cobbles, 15 percent stones, and 5 percent pebbles; mildly alkaline (pH 7.8); violently effervescent (about 20 percent lime); abrupt wavy boundary.

2R—33 inches; hard, lime-coated basalt.

**Typical Pedon Location**

*Map unit in which located:* McCarey-Pedleford complex, 2 to 30 percent slopes

*Location in survey area:* About 13 miles east of Carey; about 300 feet east and 50 feet north of the southwest corner of sec. 26, T. 1 S., R. 23 E.

**Range in Characteristics**

*Depth to bedrock:* 20 to 40 inches

*Depth to calcic horizon:* 13 to 20 inches

*Thickness of mollic epipedon:* 10 to 14 inches

*Average annual soil temperature:* 42 to 47 degrees F

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

*Bw horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Texture—very stony sandy loam, very stony loam, or very cobbly loam

Content of rock fragments—35 to 60 percent

Content of clay—13 to 19 percent

Reaction—neutral to moderately alkaline

*Bk horizon:*

Value—6 to 8 dry, 5 to 8 moist

Chroma—2 to 4 dry or moist

Texture—very stony silt loam, very stony loam, or very cobbly loam

Content of rock fragments—35 to 60 percent

Content of clay—10 to 16 percent

Reaction—moderately alkaline or strongly alkaline

**Peevywell Series**

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Position on landscape:* Fan terraces, foot slopes, mountainsides

*Parent material:* Alluvium and colluvium derived from various kinds of igneous and metamorphic rock

*Slope:* 2 to 60 percent

*Elevation:* 4,700 to 6,500 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 44 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine, montmorillonitic, frigid Typic Durixerolls

**Typical Pedon**

A1—0 to 3 inches; brown (10YR 5/3) loam, dark brown (10YR 3/3) moist; weak thin platy structure; soft, very friable; many very fine, fine, and medium roots; many very fine interstitial pores; slightly acid (pH 6.2); clear wavy boundary.

A2—3 to 12 inches; brown (10YR 5/3) loam, dark brown (10YR 3/3) moist; weak fine angular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine, fine, and medium roots; many very fine tubular pores; slightly acid (pH 6.4); abrupt wavy boundary.

Bt1—12 to 18 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 4/4) moist; strong fine angular blocky structure; hard, firm, sticky and plastic; common very fine, fine, and medium roots;

- common very fine and fine tubular pores; common moderately thick clay films on faces of peds and lining pores; neutral (pH 6.6); clear wavy boundary.
- Bt2—18 to 22 inches; brown (7.5YR 5/4) clay loam, dark brown (7.5YR 4/4) moist; strong fine angular blocky structure; hard, firm, sticky and plastic; few very fine and fine roots; common very fine and fine tubular pores; many moderately thick clay films on faces of peds and lining pores; neutral (pH 6.6); abrupt smooth boundary.
- Bt3—22 to 30 inches; brown (7.5YR 5/4) clay, dark brown (7.5YR 4/4) moist; strong medium and coarse prismatic structure; very hard, very firm, very sticky and very plastic; few very fine and fine roots; few very fine tubular pores; about 10 percent pebbles; many prominent slickensides on faces of peds; neutral (pH 7.0); abrupt smooth boundary.
- 2Bq—30 to 34 inches; light brown (7.5YR 6/4) very gravelly sandy loam, strong brown (7.5YR 4/6) moist; massive; very hard, very firm; many silica laminae between rock fragments; few fine roots matted along fractures; few fine tubular pores; about 40 percent pebbles and 10 percent cobbles; weakly cemented with silica; mildly alkaline (pH 7.4); clear smooth boundary.
- 2Bqm—34 to 44 inches; light brown (7.5YR 6/4), indurated duripan, strong brown (7.5YR 4/6) moist; massive; few very fine tubular pores; about 40 percent pebbles and 15 percent cobbles; strongly cemented plates that have a laminar cap 1 to 4 millimeters thick; continuous silica cementation between rock fragments; mildly alkaline (pH 7.4); clear wavy boundary.
- 2B—44 to 61 inches; light yellowish brown (10YR 6/4) very gravelly sandy loam, dark yellowish brown (10YR 4/4) moist; massive; hard, firm, slightly sticky and slightly plastic; few fine interstitial pores; about 45 percent pebbles; slightly effervescent; mildly alkaline (pH 7.6).

**Typical Pedon Location**

*Map unit in which located:* Muldoon-Peevywell loams, 2 to 15 percent slopes

*Location in survey area:* About 3 miles west and 7 miles north of Carey; about 450 feet north and 50 feet east of the southwest corner of sec. 18, T. 1 N., R. 20 E.

**Range in Characteristics**

*Depth to duripan:* 24 to 35 inches

*Depth to bedrock:* 40 to more than 60 inches

*Average annual soil temperature:* 42 to 46 degrees F

- Thickness of mollic epipedon:* 10 to 16 inches
- Reaction:* Slightly acid to mildly alkaline
- Base saturation in upper 75 centimeters:* Less than 75 percent
- Other characteristics of some pedons:* 2Bq horizon absent, 3B horizon present, or bedrock below a depth of 40 inches
- A horizon:*
- Value—4 or 5 dry, 3 or 4 moist
  - Chroma—2 or 3 dry or moist
  - Content of rock fragments—0 to 25 percent
- Bt horizon:*
- Hue—10YR, 7.5YR, or 5YR
  - Value—5 or 6 dry, 4 or 5 moist
  - Chroma—3 or 4 dry or moist
  - Texture—clay loam, silty clay, clay, gravelly clay loam, or gravelly clay
  - Content of rock fragments—5 to 25 percent
  - Average content of clay—35 to 55 percent
- 2Bq horizon:*
- Content of rock fragments—35 to 70 percent
- 2Bqm horizon:*
- Thickness—10 to 19 inches
  - Content of rock fragments—35 to 70 percent
  - Cementation below laminar cap—weak to strong
- 2B horizon:*
- Hue—10YR or 7.5YR
  - Value—6 or 7 dry, 4 or 5 moist
  - Chroma—3 or 4 dry or moist
  - Texture—very gravelly sandy loam or gravelly loamy sand

**Picabo Series**

- Depth class:* Very deep
- Drainage class:* Somewhat poorly drained
- Permeability:* Moderate
- Position on landscape:* Stream terraces
- Parent material:* Alluvium derived from various kinds of rock
- Slope:* 0 to 2 percent
- Elevation:* 4,700 to 5,000 feet
- Average annual precipitation:* 12 to 16 inches
- Average annual air temperature:* 40 to 45 degrees F
- Frost-free period:* 70 to 90 days
- Taxonomic class:** Coarse-silty, carbonatic, frigid Aquic Calcixerolls

**Typical Pedon**

Ak—0 to 4 inches; grayish brown (10YR 5/2) silt loam,



dark brown (10YR 3/3) moist; weak very fine and fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and common fine roots; many very fine and fine interstitial pores and few very fine tubular pores; strongly effervescent (about 44 percent lime); strongly alkaline (pH 8.8); gradual wavy boundary.

ABk—4 to 9 inches; light brownish gray (10YR 6/2) silt loam, very dark grayish brown (10YR 3/2) moist; weak very thin and thin platy structure parting to weak very fine granular; soft, very friable, slightly sticky and slightly plastic; common very fine and few fine and medium roots; many very fine and few fine interstitial pores; strongly effervescent (about 49 percent lime); strongly alkaline (pH 8.5); clear smooth boundary.

Bk1—9 to 16 inches; light brownish gray (10YR 6/2) silt loam, very dark grayish brown (10YR 3/2) moist; weak thin and medium platy structure parting to weak very fine and fine granular; slightly hard, very friable, slightly sticky and slightly plastic; common very fine roots and few fine and medium roots; few very fine tubular pores and common very fine and fine interstitial pores; strongly effervescent (about 60 percent lime); moderately alkaline (pH 8.3); clear wavy boundary.

Bk2—16 to 23 inches; light gray (10YR 7/1) loam, gray (10YR 5/1) moist; weak very fine and fine subangular blocky structure; slightly hard, very friable, sticky and plastic; common very fine roots and few fine and medium roots; few very fine interstitial pores and common very fine and few fine tubular pores; violently effervescent (about 66 percent lime); moderately alkaline (pH 8.0); gradual wavy boundary.

Bkg1—23 to 32 inches; light gray (10YR 7/1) silt loam (laboratory texture) and silty clay loam (field texture because of the content of lime), gray (10YR 6/1) moist; weak very fine, fine, and medium subangular blocky structure; hard, friable, sticky and plastic; few very fine, fine, and medium roots; common very fine and fine tubular pores; violently effervescent (about 66 percent lime); moderately alkaline (pH 8.0); gradual wavy boundary.

Bkg2—32 to 39 inches; light gray (10YR 7/1) silt loam (laboratory texture) and silty clay loam (field texture because of the content of lime), gray (10YR 5/1) moist; weak very fine, fine, and medium subangular blocky structure; hard, friable, sticky and plastic; about 5 percent gravel-sized, irregularly shaped,

lime-cemented concretions; violently effervescent (about 69 percent lime); moderately alkaline (pH 7.9); abrupt smooth boundary.

2Bkg3—39 to 51 inches; white (5Y 8/1) gravelly silt loam, light gray (5Y 7/2) moist; massive; very hard, firm, sticky and plastic; few very fine roots; common fine tubular pores; 30 percent gravel-sized, irregularly shaped, lime-cemented concretions; violently effervescent (about 77 percent lime); moderately alkaline (pH 7.9); gradual wavy boundary.

3Bkg4—51 to 53 inches; white (5Y 8/2) silt loam, light olive gray (5Y 6/2) moist; few fine faint light olive yellow (2.5Y 6/8, dry) mottles; massive; very hard, firm, sticky and plastic; few very fine roots; few fine and medium tubular pores; strongly effervescent (about 25 percent lime); moderately alkaline (pH 7.9); abrupt smooth boundary.

4BCkg—53 to 55 inches; gray (N 6/0) silt loam (laboratory texture) and silty clay loam (field texture because of the content of lime), bluish gray (5B 5/1) moist; many medium and large distinct olive yellow (2.5Y 6/6, dry) mottles; massive; hard, firm, slightly sticky and plastic; common very fine and fine tubular pores; slightly effervescent (about 10 percent lime); moderately alkaline (pH 7.9); abrupt wavy boundary.

5Cg1—55 to 61 inches; gray (2.5Y 5/0) very fine sandy loam, dark bluish gray (5B 4/1) moist; few fine and medium faint olive yellow (2.5Y 6/6, dry) mottles; massive; hard, firm, slightly sticky and slightly plastic; common very fine and fine tubular pores; moderately alkaline (pH 8.0); abrupt wavy boundary.

6Cg2—61 to 72 inches; dark gray (2.5Y 4/0) extremely gravelly loamy sand, dark bluish gray (5B 4/1) moist; single grain; loose, very friable; 55 percent pebbles and 10 percent cobbles; moderately alkaline (pH 7.9).

#### Typical Pedon Location

*Map unit in which located:* Picabo silt loam, 0 to 2 percent slopes

*Location in survey area:* About 2 miles south and  $\frac{3}{4}$  mile east of Gannett; about 1,100 feet west and 40 feet north of the southeast corner of sec. 14, T. 1 S., R. 19 E.

#### Range in Characteristics

*Average annual soil temperature:* 42 to 47 degrees F

*Depth to lime concretions:* 36 to 50 inches

*Depth to water table:* 24 to 48 inches



*Other characteristics:* Mollic epipedon with value of more than 5.5 dry and 3.5 moist in some pedons because of a high content of lime (more than 40 percent)

*Ak horizon:*

Hue—10YR or 2.5Y  
Value—5 or 6 dry, 3 to 5 moist  
Chroma—1 to 3 dry or moist  
Texture—silt loam or gravelly loam  
Total content of clay—10 to 18 percent  
Content of carbonate clay—5 to 8 percent  
Sodium adsorption ratio—25 to 40  
Reaction—moderately alkaline or strongly alkaline

*Bk horizon:*

Hue—10YR, 2.5Y, or 5Y  
Value—3 to 6 moist  
Chroma—1 to 3 moist  
Texture—loam or silt loam  
Content of lime concretions—0 to 5 percent  
Total content of clay—10 to 18 percent  
Content of carbonate clay—5 to 6 percent  
Sodium adsorption ratio—1 to 10  
Reaction—moderately alkaline or strongly alkaline

*2Bkg horizon:*

Value—7 or 8 dry, 6 or 7 moist  
Chroma—1 or 2 dry, 2 or 3 moist  
Texture—gravelly silt loam or silt loam  
Content of lime concretions—10 to 35 percent  
Total content of clay—30 to 38 percent  
Content of carbonate clay—24 to 26 percent

*3Bkg, 4BCkg, and 5Cg horizons:*

Chroma—0 to 4 dry, 1 to 4 moist  
Texture—very fine sandy loam, loam, or silt loam

*6Cg horizon:*

Hue—5Y, 2.5Y, or 5B  
Value—4 or 5 dry or moist  
Chroma—0 or 2 dry, 1 to 3 moist  
Texture—very gravelly loamy sand, very gravelly sand, or extremely gravelly loamy sand  
Content of pebbles—35 to 70 percent

**Polecreek Series**

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Very slow

*Position on landscape:* Foothills

*Parent material:* Residuum derived from basalt and andesite

*Slope:* 4 to 30 percent

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 44 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Clayey-skeletal, montmorillonitic, frigid Lithic Ultic Argixerolls

**Typical Pedon**

- A—0 to 4 inches; dark brown (10YR 4/3) very stony loam, very dark grayish brown (10YR 3/2) moist; weak thin platy structure; soft, very friable, slightly sticky and plastic; many very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 25 percent stones; slightly acid (pH 6.4); clear smooth boundary.
- Bt1—4 to 6 inches; brown (10YR 5/3) very cobbly clay, dark brown (10YR 3/3) moist; strong fine and medium subangular blocky structure; very hard, friable, very sticky and very plastic; many very fine, fine, medium, and coarse roots; common very fine tubular pores; many thin clay films on faces of peds; about 40 percent cobbles and 10 percent pebbles; slightly acid (pH 6.4); abrupt smooth boundary.
- Bt2—6 to 13 inches; brown (7.5YR 4/4) very gravelly clay, dark brown (7.5YR 4/4) moist; strong medium and coarse prismatic structure; extremely hard, very firm, very sticky and very plastic; common very fine, fine, medium, and coarse roots; few fine and very fine tubular pores; about 40 percent pebbles and 15 percent cobbles; many slickensides on faces of peds; slightly acid (pH 6.4); abrupt smooth boundary.
- R—13 inches; fractured basalt.

**Typical Pedon Location**

*Map unit in which located:* Elkcreek-Polecreek complex, 4 to 30 percent slopes

*Location in survey area:* About 1 mile south and 3 miles east of Moonstone Mountain; about 50 feet south and 2,500 feet east of the northwest corner of sec. 11, T. 1 S., R. 17 E.

**Range in Characteristics**

*Depth to bedrock:* 10 to 20 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Reaction:* Slightly acid or neutral

*Base saturation:* 50 to 75 percent

*A horizon:*

Hue—7.5YR or 10YR

Value—4 or 5 dry, 2 or 3 moist

*Bt horizon:*

Hue—5YR or 7.5YR

Value—5 or 6 dry



Texture—very cobbly clay, very cobbly clay loam,  
very cobbly silty clay loam, or very gravelly clay  
Content of clay—35 to 60 percent

### **Povey Series**

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Mountains

*Parent material:* Colluvium derived from quartzitic  
sandstone and related rock

*Slope:* 15 to 60 percent

*Elevation:* 5,000 to 9,250 feet

*Average annual precipitation:* 18 to 20 inches

*Average annual air temperature:* 37 to 41 degrees F

*Frost-free period:* Less than 60 days

**Taxonomic class:** Loamy-skeletal, mixed Pachic  
Cryoborolls

#### **Typical Pedon**

A1—0 to 8 inches; dark grayish brown (10YR 4/2)  
gravelly loam, very dark grayish brown (10YR 3/2)  
moist; weak fine granular structure; soft, very  
friable, slightly sticky and slightly plastic; many very  
fine and fine roots; many very fine and fine  
interstitial pores; about 20 percent pebbles; neutral  
(pH 6.6); clear wavy boundary.

A2—8 to 14 inches; grayish brown (10YR 5/2) gravelly  
loam, very dark grayish brown (10YR 3/2) moist;  
weak fine granular structure; soft, very friable,  
slightly sticky and slightly plastic; many very fine  
and fine roots; many very fine and fine interstitial  
pores; about 20 percent pebbles; neutral (pH 6.8);  
clear smooth boundary.

Bw1—14 to 21 inches; brown (10YR 5/3) very gravelly  
loam, dark brown (10YR 3/3) moist; weak fine and  
medium subangular blocky structure; slightly hard,  
friable, slightly sticky and slightly plastic; common  
very fine and fine roots; common very fine and fine  
tubular pores; about 25 percent pebbles and 10  
percent cobbles; neutral (pH 6.8); gradual wavy  
boundary.

Bw2—21 to 35 inches; brown (10YR 5/3) very gravelly  
loam, dark brown (10YR 4/3) moist; moderate fine  
and medium subangular blocky structure; slightly  
hard, firm, slightly sticky and slightly plastic; few  
very fine and fine roots; common very fine and fine  
tubular pores; about 40 percent pebbles and 15  
percent cobbles; neutral (pH 6.8); gradual wavy  
boundary.

C—35 to 60 inches; brown (10YR 5/3) extremely cobbly  
loam, brown (10YR 4/3) moist; massive; slightly  
hard, friable, slightly sticky and slightly plastic; few  
fine and very fine roots; few fine and very fine  
tubular pores; about 50 percent cobbles and 20  
percent pebbles; neutral (pH 7.0); gradual wavy  
boundary.

2R—60 inches; hard, quartzitic sandstone.

#### **Typical Pedon Location**

*Map unit in which located:* Povey-Vitale association, 30  
to 60 percent slopes

*Location in survey area:* About 3 miles west and 1 mile  
south of Hailey; about 2,760 feet south and 900 feet  
west of the northeast corner of sec. 20, T. 2 N., R.  
18 E.

#### **Range in Characteristics**

*Depth to bedrock:* More than 40 inches

*Thickness of mollic epipedon:* 16 to 44 inches

*Average annual soil temperature:* 37 to 43 degrees F

*Content of clay in control section:* 10 to 20 percent

*Average summer soil temperature:* 54 to 59 degrees F

*A horizon:*

Value—2 or 3 moist

Chroma—2 or 3 dry or moist

Texture—gravelly loam or very gravelly silt loam

Content of rock fragments—15 to 40 percent

*Bw horizon:*

Value—3 to 5 dry

Chroma—3 or 4 dry, 1 to 4 moist

Texture—very gravelly loam, very cobbly loam, or  
extremely gravelly fine sandy loam

Content of rock fragments—35 to 70 percent

*C horizon:*

Value—3 or 4 moist

Chroma—2 to 4 dry or moist

Texture—very cobbly loam, extremely cobbly loam,  
or extremely cobbly sandy loam

Content of rock fragments—50 to 70 percent

Reaction—neutral or mildly alkaline

### **Prudy Series**

*Depth class:* Deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Mountainsides

*Parent material:* Mixed colluvium over calcareous  
quartzitic residuum



*Slope:* 30 to 60 percent

*Elevation:* 4,700 to 6,000 feet

*Average annual precipitation:* 16 to 20 inches

*Average annual air temperature:* 37 to 41 degrees F

*Frost-free period:* Less than 60 days

**Taxonomic class:** Fine-loamy, mixed Calcic  
Cryoborolls

### Typical Pedon

A1—0 to 3 inches; dark grayish brown (10YR 4/2) loam, very dark grayish brown (10YR 3/2) moist; moderate fine granular structure; soft, friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine interstitial pores and common very fine and fine tubular pores; about 5 percent pebbles; mildly alkaline (pH 7.6); clear smooth boundary.

A2—3 to 10 inches; dark brown (10YR 4/3) loam, very dark grayish brown (10YR 3/2) moist; weak fine and medium subangular blocky structure; soft, friable, slightly sticky and slightly plastic; many very fine and fine roots and few medium and coarse roots; many very fine and fine tubular pores; about 5 percent gravel; mildly alkaline (pH 7.6); gradual smooth boundary.

BAk—10 to 14 inches; brown (10YR 4/3) loam, dark brown (10YR 3/3) moist; weak medium and coarse subangular blocky structure; slightly hard, friable, slightly sticky and plastic; many very fine and fine roots; common very fine and fine tubular pores; about 10 percent pebbles; strongly effervescent (about 20 percent lime); mildly alkaline (pH 7.8); clear smooth boundary.

Bk1—14 to 21 inches; pale brown (10YR 6/3) loam, brown (10YR 5/3) moist; moderate medium subangular blocky structure; hard, firm, sticky and plastic; many very fine and fine roots and few medium roots; common very fine and fine tubular pores; about 10 percent pebbles; violently effervescent (about 35 percent lime); moderately alkaline (pH 8.2); gradual smooth boundary.

Bk2—21 to 25 inches; pale brown (10YR 6/3) gravelly loam, brown (10YR 5/3) moist; moderate medium subangular blocky structure; hard, firm, slightly sticky and plastic; common very fine, fine, and medium roots; common very fine and fine tubular pores; about 30 percent pebbles; violently effervescent (about 35 percent lime); moderately alkaline (pH 8.4); gradual wavy boundary.

Bk3—25 to 42 inches; very pale brown (10YR 7/3) gravelly loam, pale brown (10YR 6/3) moist; weak

medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; few fine and medium roots; few very fine and fine tubular pores; about 10 percent cobbles and 20 percent pebbles; violently effervescent (about 35 percent lime); strongly alkaline (pH 8.6); abrupt smooth boundary.

2Bqkm—42 to 50 inches; white (10YR 8/2), indurated duripan, very pale brown (10YR 7/4) moist; massive; few fine and medium roots matted on top of duripan; about 10 percent cobbles and 25 percent pebbles cemented in place; violently effervescent (about 35 percent lime); strongly alkaline (pH 8.6); abrupt smooth boundary.

2R—50 inches; fractured, calcareous quartzite; Bqkm horizon material in fractures.

### Typical Pedon Location

*Map unit in which located:* Blackspot-Prudy association, 30 to 60 percent slopes

*Location in survey area:* About 3.5 miles south and 0.5 mile east of Gannett; about 1,400 feet south and 400 feet west of the northeast corner of sec. 26, T. 1 S., R. 19 E.

### Range in Characteristics

*Average annual soil temperature:* 39 to 43 degrees F

*Thickness of mollic epipedon:* 10 to 15 inches

*Depth to duripan:* 40 to 48 inches

*Depth to bedrock:* 50 to 60 inches

*Depth to secondary lime:* 12 to 21 inches

*Other characteristics of some pedons:* 2Bqk horizon present or BAk horizon absent

#### A horizon:

Value—4 or 5 dry, 2 or 3 moist

Content of pebbles—0 to 10 percent

Content of clay—18 to 24 percent

Effervescence—noneffervescent or slightly effervescent

Reaction—neutral or mildly alkaline

#### BAk horizon:

Value—4 to 6 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

Content of pebbles—5 to 20 percent

Content of clay—18 to 24 percent

Effervescence—slightly effervescent to strongly effervescent

Reaction—mildly alkaline or moderately alkaline

#### Bk horizon:

Value—5 to 7 dry, 5 or 6 moist

Chroma—3 or 4 dry or moist



Texture—loam, gravelly loam, or gravelly fine sandy loam

Content of pebbles—10 to 20 percent

Content of cobbles—0 to 10 percent

Content of clay—18 to 27 percent

Effervescence—strongly effervescent or violently effervescent

Reaction—moderately alkaline or strongly alkaline

*2Bqkm horizon:*

Value—7 or 8 dry, 6 or 7 moist

Chroma—2 to 4 dry or moist

Content of pebbles—20 to 30 percent

Content of cobbles—5 to 10 percent

Thickness of continuous laminar cap—1 to 3 millimeters

## **Rehfield Series**

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Basalt plains

*Parent material:* Eolian-influenced alluvium derived from various kinds of rock

*Slope:* 2 to 8 percent

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* 11 to 13 inches

*Average annual air temperature:* 46 to 50 degrees F

*Frost-free period:* 90 to 120 days

**Taxonomic class:** Fine-loamy, mixed, mesic Ultic Argixerolls

### **Typical Pedon**

A—0 to 3 inches; brown (10YR 5/3) sandy loam, dark brown (10YR 3/3) moist; weak medium and thick platy structure; soft, friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine interstitial pores; about 5 percent pebbles; neutral (pH 6.6); clear wavy boundary.

Bw—3 to 11 inches; brown (10YR 5/3) sandy loam, dark brown (10YR 3/3) moist; weak fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; common very fine tubular pores; about 10 percent pebbles; neutral (pH 6.8); clear wavy boundary.

Bt1—11 to 23 inches; yellowish brown (10YR 5/4) sandy loam, dark yellowish brown (10YR 4/4) moist; moderate medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine, fine, medium, and coarse

roots; common fine tubular pores; about 5 percent cobbles and 5 percent pebbles; neutral (pH 7.0); clear wavy boundary.

Bt2—23 to 42 inches; yellowish brown (10YR 5/4) sandy clay loam, dark yellowish brown (10YR 4/4) moist; moderate medium subangular blocky structure; slightly hard, firm, sticky and plastic; common very fine, fine, medium, and coarse roots; common very fine tubular pores; about 5 percent cobbles and 5 percent pebbles; neutral (pH 7.2); abrupt irregular boundary.

2C—42 to 67 inches; light yellowish brown (10YR 6/4) loamy sand, dark yellowish brown (10YR 4/4) moist; single grain; soft, very friable, nonsticky and nonplastic; common very fine, fine, medium, and coarse roots; few fine tubular pores; about 5 percent pebbles; neutral (pH 7.2).

### **Typical Pedon Location**

*Map unit in which located:* Deerhorn-Rehfield-Rock outcrop complex, 2 to 15 percent slopes

*Location in survey area:* About 16 miles east and 5 miles south of Carey; about 3,000 feet north and 1,100 feet east of the southwest corner of sec. 17, T. 2 S., R. 24 E.

### **Range in Characteristics**

*Depth to bedrock:* More than 60 inches

*Thickness of mollic epipedon:* 10 to 14 inches

*Reaction:* Slightly acid to mildly alkaline

*Base saturation in upper 30 inches:* 50 to 75 percent

*Average annual soil temperature:* 47 to 52 degrees F

#### *A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

#### *Bt horizon:*

Hue—10YR or 7.5YR

Value—5 or 6 dry, 4 or 5 moist

Chroma—3 or 4 moist or dry

Texture—loam, sandy loam, or sandy clay loam

Content of rock fragments—0 to 10 percent

Content of clay—18 to 31 percent

#### *2C horizon:*

Chroma—3 or 4 dry or moist

Texture—gravelly loamy sand, loamy sand, or very fine sandy loam

Content of rock fragments—0 to 35 percent

## **Rockybar Series**

*Depth class:* Very deep



*Drainage class:* Well drained  
*Permeability:* Moderate  
*Position on landscape:* Outwash terraces  
*Parent material:* Glacial outwash derived from igneous and metamorphic rock  
*Slope:* 2 to 30 percent  
*Elevation:* 5,500 to 6,500 feet  
*Average annual precipitation:* 12 to 16 inches  
*Average annual air temperature:* 40 to 43 degrees F  
*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Mollic Haploxeralfs

**Typical Pedon**

- A—0 to 5 inches; yellowish brown (10YR 5/4) extremely cobbly loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable, slightly sticky; many very fine, fine, and medium roots; many very fine and fine interstitial pores; about 20 percent stones, 30 percent cobbles, and 15 percent pebbles; neutral (pH 6.8); clear smooth boundary.
- BA—5 to 9 inches; yellowish brown (10YR 5/4) extremely cobbly loam, dark yellowish brown (10YR 4/4) moist; weak fine and medium granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, and medium roots; many very fine and fine interstitial pores; about 15 percent stones, 30 percent cobbles, and 15 percent pebbles; neutral (pH 7.0); clear smooth boundary.
- Bt1—9 to 20 inches; light yellowish brown (10YR 6/4) extremely cobbly loam, dark yellowish brown (10YR 4/4) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine and fine roots; common very fine and fine tubular pores; about 10 percent stones, 40 percent cobbles, and 15 percent pebbles; few thin clay films on faces of peds and lining pores; neutral (pH 7.0); gradual wavy boundary.
- Bt2—20 to 31 inches; light yellowish brown (10YR 6/4) extremely cobbly clay loam, dark yellowish brown (10YR 4/4) moist; strong fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine and fine roots; common very fine and fine tubular pores; about 10 percent stones, 40 percent cobbles, and 15 percent pebbles; few thin clay films on faces of peds, lining pores, and on rock fragments; neutral (pH 7.2); gradual wavy boundary.
- BC—31 to 47 inches; light yellowish brown (10YR 6/4) extremely cobbly loam, yellowish brown (10YR 5/4)

moist; weak fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; common very fine and fine interstitial pores; about 10 percent stones, 40 percent cobbles, and 15 percent pebbles; neutral (pH 7.2); clear wavy boundary.

C—47 to 62 inches; yellowish brown (10YR 5/4) extremely cobbly loam, dark yellowish brown (10YR 4/4) moist; massive; slightly hard, friable, slightly sticky and slightly plastic; common very fine and fine interstitial pores; about 10 percent stones, 35 percent cobbles, and 25 percent pebbles; slightly acid (pH 6.6).

**Typical Pedon Location**

*Map unit in which located:* Rockybar extremely cobbly loam, 2 to 30 percent slopes  
*Location in survey area:* About 13 miles north of Carey; about 900 feet south and 2,000 feet west of the northeast corner of sec. 15, T. 2 N., R. 21 E.

**Range in Characteristics**

*Depth to bedrock:* More than 60 inches  
*Average annual soil temperature:* 42 to 47 degrees F  
*Thickness of solum:* 30 to 48 inches  
*Reaction:* Slightly acid or neutral

*A horizon:*  
Value—4 or 5 dry

*BA horizon:*  
Value—4 or 5 dry, 3 or 4 moist  
Content of rock fragments—60 to 80 percent  
Content of clay—15 to 25 percent

*Bt horizon:*  
Hue—7.5YR or 10YR  
Value—5 or 6 dry, 4 or 5 moist  
Texture—extremely cobbly loam or extremely cobbly clay loam  
Content of rock fragments—60 to 80 percent  
Content of clay—25 to 33 percent

*BC and C horizons:*  
Hue—7.5YR or 10YR  
Chroma—4 to 6 dry or moist  
Texture—extremely cobbly sandy loam or extremely cobbly loam  
Content of rock fragments—60 to 80 percent  
Content of clay—15 to 27 percent

**Simonton Series**

*Depth class:* Very deep  
*Drainage class:* Well drained



*Permeability:* Moderately slow

*Position on landscape:* Fan terraces

*Parent material:* Alluvium derived from granite

*Slope:* 2 to 30 percent

*Elevation:* 4,800 to 6,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-loamy, mixed, frigid Ultic  
Argixerolls

#### Typical Pedon

A1—0 to 7 inches; brown (10YR 4/3) silt loam, very dark grayish brown (10YR 3/2) moist; weak fine and medium granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine, fine, medium, and coarse roots; common very fine and fine tubular pores; neutral (pH 6.8); clear wavy boundary.

A2—7 to 11 inches; brown (10YR 5/3) silt loam, dark brown (10YR 3/3) moist; weak medium subangular structure; soft, very friable, slightly sticky and slightly plastic; common very fine, fine, medium, and coarse roots; common very fine tubular pores; neutral (pH 6.8); abrupt wavy boundary.

Bt1—11 to 25 inches; light yellowish brown (10YR 6/4) clay loam, dark yellowish brown (10YR 4/4) moist; strong medium angular blocky structure; extremely hard, firm, sticky and plastic; few very fine, fine, and medium roots; many very fine, fine, and medium tubular pores; common thin clay films bridging mineral grains; slightly acid (pH 6.4); gradual wavy boundary.

Bt2—25 to 43 inches; light yellowish brown (10YR 6/4) clay loam, brown (10YR 4/3) moist; weak medium and coarse prismatic structure parting to moderate medium subangular blocky; very hard, very firm, sticky and plastic; few very fine, fine, and medium roots; many very fine and fine tubular pores; many thin clay films bridging mineral grains; neutral (pH 6.6); gradual wavy boundary.

Bt3—43 to 61 inches; light brown (7.5YR 6/4) sandy clay loam, brown (7.5YR 5/4) moist; massive; extremely hard, friable, slightly sticky and slightly plastic; few very fine, fine, and medium roots; many very fine, fine, and medium interstitial pores; many moderately thick clay films bridging mineral grains; slightly acid (pH 6.4).

#### Typical Pedon Location

*Map unit in which located:* Simonton-Bauscher complex, 4 to 15 percent slopes

*Location in survey area:* About 5 miles south and 2 miles west of Hailey; about 20 feet south and 1,500 feet west of the northeast corner of sec. 6, T. 1 S., R. 18 E.

#### Range in Characteristics

*Depth to bedrock:* More than 60 inches

*Average annual soil temperature:* 42 to 47 degrees F

*Thickness of mollic epipedon:* 10 to 16 inches

*Base saturation in upper 30 inches:* 50 to 75 percent

*Reaction:* Slightly acid or neutral

*Other characteristics:* BC horizon present in some pedons

*A horizon:*

Value—2 or 3 moist

Texture—loam or silt loam

*Bt horizon:*

Value—4 to 6 dry, 3 to 5 moist

Texture—clay loam, sandy clay loam, or loam

Content of pebbles—0 to 10 percent

Content of clay—18 to 32 percent

#### Smelter Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Slow

*Position on landscape:* Fan terraces, foothills

*Parent material:* Residuum and alluvium derived from andesite, latite, and welded tuff

*Slope:* 4 to 30 percent

*Elevation:* 5,200 to 6,500 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 39 to 42 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine-silty, mixed, frigid Pachic  
Argixerolls

#### Typical Pedon

A1—0 to 9 inches; dark grayish brown (10YR 4/2) loam, very dark grayish brown (10YR 3/2) moist; weak fine and medium granular structure; soft, very friable, slightly sticky and slightly plastic, many very fine and fine roots; many very fine and fine interstitial pores; about 5 percent pebbles; neutral (pH 6.6); gradual wavy boundary.

A2—9 to 18 inches; dark grayish brown (10YR 4/2) loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, sticky and plastic;

many very fine and fine roots; few fine tubular pores; about 5 percent pebbles; neutral (pH 6.6); abrupt smooth boundary.

Bt1—18 to 26 inches; brown (10YR 5/3) clay loam, dark brown (10YR 3/3) moist; strong medium and coarse prismatic structure; very hard, firm, sticky and plastic; few very fine and fine roots; few fine tubular pores; about 10 percent pebbles; continuous clay films on faces of peds and lining pores; neutral (pH 7.0); clear wavy boundary.

Bt2—26 to 35 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 4/4) moist; strong medium and coarse prismatic structure; very hard, firm, sticky and plastic; few fine roots; common very fine and fine tubular pores; about 10 percent pebbles; continuous moderately thick clay films on faces of peds and lining pores; neutral (pH 7.0); clear wavy boundary.

BC—35 to 61 inches; light yellowish brown (10YR 6/4) sandy clay loam, dark yellowish brown (10YR 4/4) moist; massive; hard, friable, sticky and plastic; few very fine roots; common very fine and fine tubular pores; about 10 percent pebbles; neutral (pH 7.2).

#### Typical Pedon Location

*Map unit in which located:* Starhope-Peevywell-Smelter loams, 4 to 30 percent slopes

*Location in survey area:* About 2 miles north and 7 miles east of Bellevue; about 2,500 feet south and 100 feet east of the northwest corner of sec. 17, T. 2 N., R. 20 E.

#### Range in Characteristics

*Depth to bedrock:* More than 60 inches

*Thickness of mollic epipedon:* 20 to 30 inches

*Average annual soil temperature:* 41 to 44 degrees F

*Reaction:* Slightly acid or neutral

*Depth to argillic horizon:* 14 to 22 inches

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—2 or 3 dry or moist

*Bt horizon:*

Hue—10YR or 7.5YR

Value—3 to 5 dry, 2 to 4 moist

Chroma—2 to 4 dry or moist

Texture—clay loam or silty clay loam

Content of rock fragments—0 to 10 percent

Content of clay—27 to 35 percent

*BC horizon:*

Hue—10YR or 7.5YR

Value—6 or 7 dry, 4 to 6 moist

Chroma—2 to 4 dry or moist

Texture—clay loam, sandy clay loam, or loam

Content of rock fragments—5 to 15 percent

Content of clay—20 to 30 percent

#### Taxadjunct Feature

The Smelter soils in this survey area on north-facing slopes at elevations above about 6,000 feet have cryic temperatures, which are outside the range for the series. This difference, however, does not significantly affect use and management.

#### Starhope Series

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Slow

*Position on landscape:* Foothills, mountainsides, undulating ridgetops

*Parent material:* Residuum derived from andesite, latite, welded tuff, and rhyolite

*Slope:* 4 to 60 percent

*Elevation:* 5,000 to 7,500 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 39 to 42 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Fine, montmorillonitic, frigid Ultic Argixerolls

#### Typical Pedon

A1—0 to 4 inches; grayish brown (10YR 5/2) loam, very dark grayish brown (10YR 3/2) moist; weak fine granular structure; soft, very friable, slightly plastic; many very fine and fine roots; many very fine interstitial pores; neutral (pH 6.6); abrupt wavy boundary.

A2—4 to 7 inches; brown (10YR 5/3) loam, dark brown (10YR 3/3) moist; weak fine subangular blocky structure; soft, very friable, slightly sticky and plastic; many very fine and fine roots; many very fine interstitial and tubular pores; slightly acid (pH 6.4); abrupt smooth boundary.

BA—7 to 10 inches; yellowish brown (10YR 5/4) loam, dark brown (10YR 3/3) moist; moderate fine subangular blocky structure; slightly hard, friable, sticky and plastic; common very fine and fine roots; common very fine tubular pores; few thin clay films on faces of peds; slightly acid (pH 6.4); abrupt smooth boundary.

Bt1—10 to 17 inches; light yellowish brown (10YR 6/4)



clay loam, dark yellowish brown (10YR 4/4) moist; weak fine angular blocky structure; very hard, very firm, sticky and plastic; few very fine roots; common very fine tubular pores; many moderately thick clay films on faces of peds and lining pores; few thin bleached sand and silt grains on faces of peds; about 5 percent fine gravel; neutral (pH 6.6); clear smooth boundary.

Bt2—17 to 26 inches; yellowish brown (10YR 5/4) clay loam, dark yellowish brown (10YR 4/4) moist; weak fine prismatic structure; very hard, very firm, sticky and plastic; few very fine roots; many slickensides on faces of peds; neutral (pH 6.8); clear wavy boundary.

Bt3—26 to 30 inches; light yellowish brown (10YR 6/4) clay loam, yellowish brown (10YR 5/4) moist; moderate fine subangular blocky structure; hard, firm, sticky and plastic; few very fine roots; common moderately thick clay films on faces of peds and lining pores; about 10 percent cobbles; neutral (pH 6.8); abrupt wavy boundary.

R—30 inches; welded tuff.

#### Typical Pedon Location

*Map unit in which located:* Starhope-Peevywell-Smelter loams, 4 to 30 percent slopes

*Location in survey area:* About ½ mile north of Little Fishcreek Reservoir; about 900 feet south and 1,800 feet east of the northwest corner of sec. 2, T. 1 N., R. 21 E.

#### Range in Characteristics

*Depth to bedrock:* 20 to 40 inches

*Thickness of mollic epipedon:* 7 to 18 inches

*Base saturation in upper 75 centimeters:* 50 to 75 percent

*Average annual soil temperature:* 41 to 44 degrees F

*Reaction:* Slightly acid or neutral

*Other characteristics:* BA and Bt3 horizons absent in some pedons

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Texture—loam or very cobbly clay loam

*Bt horizon:*

Hue—5Y, 5YR, 7.5YR, or 10YR

Value—4 to 6 dry, 3 to 5 moist

Chroma—3 or 4 dry or moist

Texture—clay loam, gravelly clay loam, or cobbly clay

Content of rock fragments—0 to 30 percent

Content of clay—35 to 50 percent

### Trevino Series

*Depth class:* Shallow

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Basalt plains, buttes

*Parent material:* Eolian-influenced slope alluvium derived from various kinds of rock

*Slope:* 2 to 15 percent

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* 10 to 13 inches

*Average annual air temperature:* 46 to 50 degrees F

*Frost-free period:* 100 to 120 days

**Taxonomic class:** Loamy, mixed, mesic Lithic Xerollic Camborthids

#### Typical Pedon

A—0 to 5 inches; brown (10YR 5/3) extremely stony silt loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable, slightly plastic; common very fine, fine, medium, and coarse roots; many very fine interstitial pores; about 50 percent stones and 15 percent cobbles; slightly effervescent (about 10 percent lime); mildly alkaline (pH 7.8); clear wavy boundary.

Bw—5 to 9 inches; pale brown (10YR 6/3) extremely stony silt loam, brown (10YR 4/3) moist; weak fine subangular blocky structure; slightly hard, friable, slightly plastic; common very fine, fine, medium, and coarse roots; common very fine and fine tubular pores; about 40 percent cobbles, 15 percent stones, and 10 percent pebbles; violently effervescent (about 25 percent lime); moderately alkaline (pH 8.4); clear wavy boundary.

Bk—9 to 12 inches; pale brown (10YR 6/3) extremely stony silt loam, brown (10YR 4/3) moist; massive; loose, very friable; few very fine, fine, and medium roots; about 30 percent cobbles, 10 percent pebbles, and 25 percent stones; violently effervescent (about 30 percent lime); moderately alkaline (pH 8.4); abrupt wavy boundary.

2R—12 inches; fractured basalt.

#### Typical Pedon Location

*Map unit in which located:* Deerhorn-Wildors-Trevino complex, 2 to 15 percent slopes

*Location in survey area:* About 14 miles east and 7 miles south of Carey; about 1,400 feet west and 50 feet north of the southeast corner of sec. 27, T. 2 S., R. 23 E.

#### Range in Characteristics

*Depth to bedrock:* 10 to 20 inches

*Average annual soil temperature:* 47 to 52 degrees F

*Reaction:* Neutral to moderately alkaline

*A horizon:*

Value—4 or 5 dry, 3 or 4 moist

Chroma—2 or 3 dry or moist

Content of rock fragments—60 to 65 percent

Content of clay—12 to 18 percent

*Bw horizon:*

Value—6 or 7 dry, 4 or 5 moist

Chroma—3 or 4 dry or moist

Content of rock fragments—60 to 65 percent

Content of clay—12 to 18 percent

*Bk horizon:*

Value—6 to 8 dry, 4 or 5 moist

Chroma—2 to 4 dry or moist

Content of rock fragments—60 to 65 percent

Content of clay—12 to 18 percent

Effervescence—strongly effervescent or violently effervescent

Content of lime—15 to 30 percent

**Taxadjunct Feature**

The Trevino soils in this survey area have a loamy-skeletal control section, which is outside the range for the series. This difference, however, does not significantly affect use and management.

**Vitale Series**

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Mountainsides

*Parent material:* Colluvium and residuum derived from quartzitic sandstone and related metasedimentary rock

*Slope:* 30 to 60 percent

*Elevation:* 5,000 to 9,000 feet

*Average annual precipitation:* 12 to 16 inches

*Average annual air temperature:* 40 to 43 degrees F

*Frost-free period:* 60 to 90 days

**Taxonomic class:** Loamy-skeletal, mixed, frigid Typic Argixerolls

**Typical Pedon**

A—0 to 6 inches; dark grayish brown (10YR 4/2) very gravelly loam, very dark grayish brown (10YR 3/2) moist; weak thin platy structure parting to moderate medium granular structure; slightly hard, friable, slightly sticky and slightly plastic; common fine

roots; many fine interstitial pores; slightly acid (pH 6.5); clear wavy boundary.

Bt1—6 to 10 inches; brown (10YR 5/3) very gravelly clay loam, dark brown (10YR 3/3) moist; weak and moderate very fine subangular blocky structure; hard, friable, slightly sticky and slightly plastic; common fine roots; many fine interstitial pores; common thin clay films on faces of peds and in some pores; mildly alkaline (pH 7.6); clear wavy boundary.

Bt2—10 to 15 inches; brown (7.5YR 5/3) very gravelly clay loam, dark brown (7.5YR 3/3) moist; weak very fine subangular blocky structure; hard, friable, slightly sticky and slightly plastic; common fine roots; many fine interstitial pores; common thin clay films on faces of peds and in some pores; mildly alkaline (pH 7.6); clear wavy boundary.

Bt3—15 to 23 inches; light brownish gray (10YR 6/2) very gravelly loam, dark yellowish brown (10YR 4/4) moist; weak very fine subangular blocky structure; hard, friable, slightly sticky and slightly plastic; common fine roots between rock fragments; many fine interstitial pores; clay films on rock fragments; abrupt wavy boundary.

R—23 inches; quartzitic sandstone.

**Typical Pedon Location**

*Map unit in which located:* Vitale-Povey association, 30 to 60 percent slopes

*Location in survey area:* About 3 miles east of Bellevue; about 50 feet north and 50 feet east of the southwest corner of sec. 28, T. 2 N., R. 19 E.

**Range in Characteristics**

*Depth to bedrock:* 20 to 40 inches

*Thickness of mollic epipedon:* 10 to 15 inches

*Average annual soil temperature:* 42 to 46 degrees F

*Content of rock fragments:* 35 to 60 percent

*Other characteristics:* Bt3 horizon absent in some pedons

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—1 to 3 dry or moist

Reaction—slightly acid or neutral

*Bt horizon:*

Value—3 or 4 moist

Chroma—2 to 4 dry or moist

Texture—very gravelly clay loam, very gravelly loam, or very cobbly loam

Average content of rock fragments—35 to 60 percent

Reaction—neutral or mildly alkaline



### Taxadjunct Feature

The Vitale soils in this survey area at elevations above about 7,500 feet have cryic temperatures, which are outside the range for the series. This difference, however, does not significantly affect use and management.

### Wildors Series

*Depth class:* Moderately deep

*Drainage class:* Well drained

*Permeability:* Moderate

*Position on landscape:* Sides of buttes, basalt plains

*Parent material:* Eolian material over basalt

*Slope:* 2 to 15 percent

*Elevation:* 4,600 to 5,000 feet

*Average annual precipitation:* 10 to 13 inches

*Average annual air temperature:* 45 to 50 degrees F

*Frost-free period:* 100 to 120 days

**Taxonomic class:** Loamy-skeletal, mixed, mesic  
Orthodic Durixerolls

### Typical Pedon

A—0 to 2 inches; brown (10YR 5/3) very stony sandy loam, dark brown (10YR 3/3) moist; weak fine granular structure; soft, very friable, slightly sticky and slightly plastic; many very fine and fine roots; many very fine and fine interstitial pores; about 30 percent stones, 10 percent cobbles, and 10 percent pebbles; neutral (pH 7.0); clear wavy boundary.

Bw1—2 to 9 inches; yellowish brown (10YR 5/4) very stony sandy loam, dark brown (10YR 3/3) moist; weak fine subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine and fine roots; common very fine and fine interstitial pores; about 30 percent stones, 10 percent cobbles, and 10 percent pebbles; neutral (pH 7.2); gradual wavy boundary.

Bw2—9 to 15 inches; yellowish brown (10YR 5/4) extremely stony loam, dark yellowish brown (10YR 4/4) moist; moderate fine and medium subangular blocky structure; slightly hard, friable, slightly sticky and slightly plastic; common very fine and fine roots; few very fine and fine tubular pores; about 40 percent stones, 15 percent cobbles, and 10 percent pebbles; mildly alkaline (pH 7.4); abrupt wavy boundary.

Bqk—15 to 21 inches; light yellowish brown (10YR 6/4) extremely stony loam, brown (10YR 5/3) moist; moderate medium subangular blocky structure;

slightly hard, friable, slightly sticky and slightly plastic; few very fine and fine roots; few very fine and fine tubular pores; about 10 percent weakly cemented duripan fragments; about 40 percent stones, 15 percent cobbles, and 10 percent pebbles; mildly alkaline (pH 7.8); abrupt wavy boundary.

Bqkm—21 to 24 inches; very pale brown (10YR 7/3), indurated duripan, pale brown (10YR 6/3) moist; massive; few very fine and fine roots matted on top of duripan; about 15 percent stones, 10 percent cobbles, and 10 percent pebbles; cemented plates that have a laminar cap 2 to 8 millimeters thick; continuous silica and lime cementation between rock fragments; violently effervescent (about 30 percent lime); moderately alkaline (pH 8.2); abrupt wavy boundary.

2R—24 inches; lime-coated basalt.

### Typical Pedon Location

*Map unit in which located:* Deerhorn-Wildors complex, 2 to 8 percent slopes

*Location in survey area:* About 7 miles south and 15 miles east of Carey; about 300 feet east and 1,200 feet south of the northwest corner of sec. 30, T. 2 S., R. 24 E.

### Range in Characteristics

*Depth to bedrock:* 23 to 30 inches

*Depth to duripan:* 21 to 28 inches

*Average annual soil temperature:* 47 to 52 degrees F

*Thickness of mollic epipedon:* 7 to 16 inches

*Content of rock fragments:* 35 to 65 percent

*Other characteristics:* Bk horizon present in some pedons

#### A horizon:

Value—3 to 5 dry, 2 to 3 moist

Chroma—2 or 3 dry or moist

Content of rock fragments—35 to 60 percent

Reaction—neutral or mildly alkaline

#### Bw horizon:

Value—3 or 5 dry

Texture—very stony sandy loam, very stony loam, or extremely stony loam

Content of rock fragments—40 to 65 percent

Content of clay—11 to 19 percent

Reaction—neutral or mildly alkaline

#### Bqk horizon:

Value—5 or 6 dry, 4 or 5 moist

Content of fractured pan fragments—30 to 40 percent



Distance between fractures—2 to 7 centimeters  
*Bqkm horizon:*  
Content of rock fragments—50 to 70 percent

**Winridge Series**

*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Very slow  
*Position on landscape:* Mountainsides  
*Parent material:* Colluvium and residuum derived from andesite, latite, or welded tuff  
*Slope:* 30 to 60 percent  
*Elevation:* 5,000 to 7,500 feet  
*Average annual precipitation:* 16 to 20 inches  
*Average annual air temperature:* 37 to 41 degrees F  
*Frost-free period:* Less than 60 days  
**Taxonomic class:** Fine, montmorillonitic Argic Vertic Cryoborolls

**Typical Pedon**

A—0 to 4 inches; dark grayish brown (10YR 4/2) clay loam, very dark grayish brown (10YR 3/2) moist; strong fine subangular blocky structure; soft, very friable, sticky and plastic; many very fine roots; common very fine tubular pores; about 10 percent pebbles; vertical cracks 1 to 3 centimeters wide and 10 to 20 centimeters apart; slightly acid (pH 6.2); abrupt smooth boundary.

Bt1—4 to 10 inches; dark grayish brown (10YR 4/2) gravelly clay, very dark grayish brown (10YR 3/2) moist; strong fine subangular blocky structure; very hard, firm, very sticky and plastic; common very fine, fine, and medium roots; many very fine and fine tubular pores; about 15 percent pebbles and 5 percent cobbles; vertical cracks 1 to 3 centimeters wide and 10 to 20 centimeters apart; many moderately thick clay films on faces of peds; slightly acid (pH 6.4); abrupt smooth boundary.

3t2—10 to 16 inches; brown (10YR 4/3) clay, dark brown (10YR 3/3) moist; strong medium and coarse prismatic structure; extremely hard, very firm, very sticky and very plastic; common very fine, fine, and medium roots; few very fine tubular pores; about 10 percent pebbles; vertical cracks 1 to 2 centimeters wide and 10 to 20 centimeters apart; continuous moderately thick clay films on faces of peds; slightly acid (pH 6.4); clear wavy boundary.

3t3—16 to 23 inches; olive brown (2.5Y 4/4) sandy clay loam, dark grayish brown (2.5Y 4/2) moist; moderate medium subangular blocky structure;

hard, firm, sticky and plastic; few very fine and fine roots; many very fine tubular pores; about 5 percent fine pebbles; common thin clay films on faces of peds; slightly acid (pH 6.4); clear smooth boundary.  
R—23 inches; partially weathered andesite.

**Typical Pedon Location**

*Map unit in which located:* Friedman-Elksel-Winridge complex, 30 to 60 percent slopes  
*Location in survey area:* About 8 miles north and 1 mile west of Carey; about 1,500 feet south and 50 feet west of the northeast corner of sec. 16, T. 1 N., R. 21 E.

**Range in Characteristics**

*Depth to bedrock:* 20 to 40 inches  
*Thickness of mollic epipedon:* 16 to 30 inches  
*Average annual soil temperature:* 39 to 43 degrees F  
*Average summer soil temperature:* 54 to 59 degrees F  
*Reaction:* Slightly acid or neutral  
*Other characteristics:* Bt3 horizon absent in some pedons

*A horizon:*  
Value—4 or 5 dry, 3 or 4 moist  
Chroma—2 or 3 dry or moist  
Content of clay—27 to 35 percent

*Bt1 and Bt2 horizons:*  
Hue—10YR or 7.5YR  
Value—4 or 5 dry, 3 or 4 moist  
Chroma—2 to 4 dry or moist  
Texture—clay, gravelly clay, or cobbly clay  
Content of rock fragments—5 to 35 percent  
Content of clay—40 to 60 percent

*Bt3 horizon:*  
Hue—10YR, 7.5YR, or 2.5Y  
Value—4 to 6 dry, 4 or 5 moist  
Texture—sandy clay loam, gravelly clay loam, or cobbly clay loam  
Content of rock fragments—5 to 25 percent  
Content of clay—27 to 40 percent

**Winu Series**

*Depth class:* Moderately deep  
*Drainage class:* Well drained  
*Permeability:* Moderately slow  
*Position on landscape:* Mountainsides  
*Parent material:* Colluvium derived from latite, andesite, and basalt  
*Slope:* 30 to 60 percent  
*Elevation:* 5,500 to 7,500 feet



*Average annual precipitation:* 16 to 20 inches

*Average annual air temperature:* 37 to 41 degrees F

*Frost-free period:* Less than 60 days

**Taxonomic class:** Fine-loamy, mixed Argic Pachic Cryoborolls

### Typical Pedon

A1—0 to 6 inches; dark grayish brown (10YR 4/2) stony loam, very dark gray (10YR 3/1) moist; weak fine granular structure; soft, very friable, slightly plastic; many very fine and fine roots; many very fine interstitial pores; about 2 percent stones and 10 percent pebbles; neutral (pH 7.0); clear wavy boundary.

A2—6 to 13 inches; dark brown (10YR 4/3) stony loam, very dark grayish brown (10YR 3/2) moist; moderate fine and medium subangular blocky structure; soft, very friable, slightly plastic; many very fine and fine roots; common very fine and fine pores; about 10 percent stones and 10 percent pebbles; neutral (pH 7.0); abrupt wavy boundary.

Bt1—13 to 21 inches; brown (10YR 4/3) gravelly loam, dark brown (10YR 3/3) moist; moderate fine and medium subangular blocky structure; soft, friable, slightly sticky and plastic; few very fine and fine roots; common fine and very fine tubular pores; about 15 percent pebbles and 5 percent cobbles; neutral (pH 7.3); clear wavy boundary.

Bt2—21 to 29 inches; yellowish brown (10YR 5/4) gravelly clay loam, dark brown (10YR 3/3) moist; strong fine and medium subangular blocky structure; hard, firm, sticky and plastic; few very fine and fine roots; common fine and very fine tubular pores; about 10 percent gravel and 10 percent cobbles; neutral (pH 7.3); clear wavy boundary.

Bt3—29 to 35 inches; yellowish brown (10YR 5/4) gravelly loam, dark yellowish brown (10YR 4/4) moist; strong fine subangular blocky structure; very hard, firm, sticky and plastic; common very fine and fine tubular pores; about 20 percent gravel and 10 percent cobbles; neutral (pH 7.3); abrupt smooth boundary.

R—35 inches; basalt.

### Typical Pedon Location

*Map unit in which located:* Winu-Gaib association, 30 to 60 percent slopes

*Location in survey area:* About 1 mile north of Moonstone Mountain; about 2,000 feet east and 1,500 feet south of the northwest corner of sec. 32, T. 1 N., R. 17 E.

### Range in Characteristics

*Depth to bedrock:* 24 to 40 inches

*Thickness of mollic epipedon:* 16 to 30 inches

*Average annual soil temperature:* 39 to 43 degrees F

*Average summer soil temperature:* 54 to 59 degrees F

*A horizon:*

Value—4 or 5 dry, 2 or 3 moist

Chroma—1 to 3 dry or moist

Content of rock fragments—5 to 30 percent

*Bt horizon:*

Texture—gravelly loam or gravelly clay loam

Content of rock fragments—15 to 30 percent

Content of clay—20 to 30 percent

Reaction—slightly acid or neutral

### Yutru Series

*Depth class:* Very deep

*Drainage class:* Well drained

*Permeability:* Very slow

*Position on landscape:* Basalt plains

*Parent material:* Fine-textured alluvium derived from various kinds of rock

*Slope:* 0 to 12 percent

*Elevation:* 4,600 to 4,800 feet

*Average annual precipitation:* 11 to 16 inches

*Average annual air temperature:* 45 to 50 degrees F

*Frost-free period:* 100 to 120 days

**Taxonomic class:** Fine, montmorillonitic, mesic Vertic Xerochrepts

### Typical Pedon

A—0 to 2 inches; pale brown (10YR 6/3) silty clay, brown (10YR 4/3) moist; strong very fine granular structure; soft, very friable, sticky and plastic; many very fine and fine roots; many very fine interstitial pores and few fine tubular pores; neutral (pH 7.0); gradual wavy boundary.

BA—2 to 7 inches; pale brown (10YR 6/3) silty clay, brown (10YR 5/3) moist; moderate medium subangular blocky structure parting to moderate fine granular structure; slightly hard, friable, very sticky and very plastic; many very fine and fine roots; common very fine and fine tubular pores; neutral (pH 7.2); abrupt wavy boundary.

Bw1—7 to 17 inches; pale brown (10YR 6/3) silty clay brown (10YR 5/3) moist; strong medium and coarse angular blocky structure; extremely hard, extremely firm, very sticky and very plastic; common fine, medium, and coarse roots; few fine tubular pores;

common slickensides present; 0 to 5 percent pebbles; neutral (pH 7.3); gradual wavy boundary.

Bw2—17 to 26 inches; yellowish brown (10YR 5/4) silty clay, dark yellowish brown (10YR 4/4) moist; strong medium and coarse angular blocky structure; extremely hard, extremely firm, very sticky and very plastic; common fine, medium, and coarse roots; few fine tubular pores; many slickensides present; mildly alkaline (pH 7.5); clear smooth boundary.

Bw3—26 to 35 inches; pale brown (10YR 6/3) silty clay, brown (10YR 5/3) moist; strong medium and coarse angular blocky structure; very hard, very firm, very sticky and very plastic; few fine, medium, and coarse roots; few fine tubular pores; common slickensides; mildly alkaline (pH 7.8); slightly effervescent (about 5 to 15 percent lime); clear wavy boundary.

Bk1—35 to 42 inches; light yellowish brown (10YR 6/4) silty clay loam, yellowish brown (10YR 5/4) moist; moderate medium angular blocky structure; hard, friable, sticky and very plastic; few very fine and fine roots; few fine tubular pores; moderately alkaline (pH 8.0); strongly effervescent (about 20 percent lime); clear wavy boundary.

Bk2—42 to 63 inches; white (10YR 8/1) clay loam, light gray (10YR 7/2) moist; moderate fine prismatic structure parting to strong fine and medium angular blocky structure; hard, friable, sticky and plastic; few very fine and fine roots; few fine tubular pores; moderately alkaline (pH 8.4); violently effervescent (about 35 percent lime).

#### Typical Pedon Location

Map unit in which located: Bostrum-Yuttrue-Hamrub complex, 2 to 12 percent slopes

*Location in survey area:* About 8.2 miles south and 3.2 miles west of Gannett; about 1,600 feet south and 1,300 feet west of the northeast corner of sec. 19, T. 2 S., R. 19 E.

#### Range in Characteristics

*Average annual soil temperature:* 47 to 52 degrees F

*Depth of vertical cracks:* 50 to 60 centimeters

*Width of vertical cracks:* 2 to 5 millimeters

#### *A and BA horizons:*

Hue—10YR or 7.5YR

Value—5 or 6 dry

Chroma—3 or 4 dry or moist

Content of pebbles—0 to 5 percent

Content of cobbles—0 to 5 percent

Content of clay—40 to 60 percent

#### *Bw horizon:*

Hue—10YR or 7.5YR

Texture—silty clay or clay

Content of pebbles—0 to 5 percent

Content of clay—40 to 60 percent

#### *Bk horizon:*

Hue—10YR or 7.5YR

Texture—silty clay loam or clay loam

Content of pebbles—0 to 5 percent

Content of clay—35 to 40 percent

#### Taxadjunct Feature

The Yuttrue soils in this survey area have vertical cracks that are 2 to 5 millimeters wide and extend to a depth of 50 to 60 centimeters. This feature is outside the range for the series. This difference, however, does not significantly affect use and management.





# Formation of the Soils

---

Soil is a natural, three-dimensional body on the surface of the earth that supports or is capable of supporting plants. It is a mixture of minerals, organic matter, water, and air, all of which occur in varying proportions. Soils differ in their appearance, productivity, and management requirements in different areas and within short distances. The characteristics of a soil are determined by the interaction of five factors: (1) the parent material; (2) the climate in which the soil material has accumulated and has existed since accumulation; (3) the relief, which influences the drainage, moisture content, and aeration of the soil, the susceptibility of the soil to erosion, and the exposure of the soil to sun and wind; (4) the biological forces, or plants and animals living on and in the soil, that act on the soil material; and (5) the length of time the climate and biological forces have acted on the soil material.

## Parent Material

The soils in the survey area formed in residual, colluvial, and alluvial material, reworked lacustrine sediment, glacial outwash, and eolian material (fig. 12). These materials are derived from material that ranges in age from Paleozoic (Little Wood and Milligan Formations) to Holocene (recent alluvium and lava flows) (13).

The soils on mountains and foothills formed in material derived from four major kinds of rock: (1) Paleozoic quartzite, conglomerate, calcareous quartzite, and related metasedimentary rock; (2) Paleozoic and Cretaceous quartz-monzonite, aplite, granodiorite, and related rock; (3) Oligocene and Miocene andesite, latite, tuff, and rhyolite; and (4) Pliocene silicic and basaltic flows.

The soils on mountains and foothills that formed in material derived dominantly from Paleozoic quartzite, conglomerate, calcareous quartzite, and related metasedimentary rock exhibit varying degrees of development. They formed mainly in colluvium, colluvium over residuum, and colluvium influenced by volcanic ash.

The soils that formed in colluvium derived from quartzite or conglomerate do not contain lime, have a weakly to moderately developed profile, and are very gravelly or cobbly or extremely gravelly or cobbly. Milligan, Vitale, Povey, and Ketchum soils are examples.

The soils that formed in colluvium and in colluvium over residuum derived dominantly from calcareous quartzite are in relatively stable positions on the landscape. They are calcareous throughout. The upper part is gravelly or very gravelly, and it exhibits only slight development because of the content of lime, which must be leached before formation and translocation of clay can take place. The lower part of these soils is a duripan. Prudy and Blackspot soils are examples.

The soils that formed in tephra-influenced colluvium derived dominantly from quartzite or conglomerate are in the mountainous area adjacent to the Craters of the Moon National Monument. Because of their proximity to recent volcanic activity (occurring 750 to 2,000 years ago), substantial amounts of volcanic tephra have been incorporated into the upper part of the profile of these soils (12). The soils are characterized by a very gravelly, weakly developed profile that does not contain accumulations of lime. Bulk density is low (0.95 gram per centimeter or less) in the upper 75 centimeters of the profile. Lavacreek soils are an example.

The soils on mountains and foothills that formed mainly in colluvium derived dominantly from Paleozoic and Cretaceous (Idaho Batholith Formation and related rock) quartz-monzonite, aplite, granodiorite, and related rock commonly are coarse textured (11). They typically have a dark gravelly coarse sandy loam A horizon and a moderately developed B horizon that commonly is gravelly sandy loam or gravelly loamy coarse sand and does not contain lime. These soils exhibit only moderate development, partly because the parent material is resistant to weathering. Earcree and Moonstone soils are examples.

The material derived dominantly from Oligocene and Miocene (Challis Volcanic Formation) andesite, latite,






Figure 12.—Cross section of the Wood River Valley showing the pattern of soils on terraces on the valley floor and on mountains and foothills.

tuff, and rhyolite is younger than that derived from the Little Wood, Milligan, and Idaho Batholith Formations; therefore, in some areas it overlies material of the older formations. The Challis Volcanic Formation ranges in elevation from about 4,800 to 8,500 feet. The soils on mountains and foothills in areas of this formation formed mainly in colluvium, alluvium, and residuum. These soils typically do not have accumulations of lime, but they have a strongly developed profile, partly because the parent material is easily weathered. Those that formed in colluvium and alluvium have a dark loam, cobbly loam, or very cobbly loam A horizon and a cobbly clay, very cobbly clay, very gravelly clay loam, or clay loam B horizon. Elksel, Friedman, and Smelter soils are examples. Those that formed in residuum typically have a dark loam or clay loam A horizon. Starhope and Winridge soils are examples.

Other parent material that is similar to that of the Challis Volcanic Formation is Tertiary (Picabo Volcanic

Formation) tuff, latite, andesite, and rhyolite. This material is in an area south of Picabo; it forms the foothills and mountains on the southern end of the Wood River Valley. The soils that formed in this material are similar to those that formed in material derived from the Challis Volcanic Formation. Friedman and Elksel soils are examples.

The rest of the soils on mountains and foothills formed in material derived dominantly from Pliocene silicic and basaltic flows (Magic Volcanic Formation). These soils are in the southwestern part of the survey area, near Moonstone Mountain. They formed in residuum, colluvium, and alluvium. Those that formed in residuum and colluvium typically do not have accumulations of lime. They have a moderately developed or strongly developed profile that includes a dark A horizon and well developed underlying horizons. Elkcreek, Winu, and Gaib soils are examples. Those that formed in alluvium typically have a dark A horizon,



have moderately developed or strongly developed underlying horizons, and commonly do not have accumulations of lime. Laurentzen soils are an example.

As a result of the volcanic activity in the survey area, many lava flows and basalt flows are spread out over much of the southern and eastern parts of the area. These flows vary in age from recent to Tertiary. The most recent lava flows are those of the Craters of the Moon Formation (12). These flows are very young and have distinct characteristics, such as the "Pahoehoe" basalt. The surface pattern resembles sequences of lava ropes oriented in the direction of the flow. This type of flow is also characterized by sinkholes, fissures, and pressure ridges. The other type of lava flow is the "Aa Aa" flow, which is characterized by a jumbled mass of broken lava, cinders, and splatter cones (10). The soils on these recent flows formed mainly in loess and volcanic tephra. They commonly are very shallow to bedrock, have a weakly developed profile, and do not have accumulations of lime. Cinderhurst soils are an example.

The Snake River Basalt Formation consists of somewhat older flows of Pleistocene age that exhibit linear etching from erosion. These flows have a thin mantle of loess and alluvium over basalt and in some areas loess over residuum derived from basalt. The soils that formed in this material have a moderately expressed profile. They are younger than the soils on foothills and mountains and have developed in a lower precipitation zone. They have a moderately expressed B horizon and commonly have accumulations of lime in the B horizon. McCarey, Pedleford, Bancroft, and McBiggam soils are examples.

A duripan has developed in some soils that are on the older flows within the Snake River Basalt Formation and are in the 11- to 13-inch precipitation zone. In this zone, leaching of soluble material, dominantly lime and silica, is limited, but the material that is leached downward forms a cemented layer, or duripan. Over time lime and silica plug the pores and voids, and this layer becomes thicker and more cemented (6). Deerhorn and Wildors are examples of soils that formed in the older flows.

In some areas distinct drainageways have developed on basalt plains, and local alluvium has accumulated. The soils in these areas receive more moisture, mainly from runoff and snowpack, than the soils on adjacent side slopes (9). This additional moisture leaches lime, bases, and silica from the soils; thus, they have a moderately expressed profile and base saturation of

less than 75 percent in the upper 30 inches. Molyneux and Rehfield soils are examples.

The older late- to mid-Pleistocene basalt generally is associated with the Bellevue, Moonstone, and Macon Flat Volcanic Formations. Most of this basalt originated around volcanic vents in the vicinity of Magic Reservoir, and the flows are tipped toward the south and southwest and bounded by the mountains to the north. These areas eventually were buried by younger Snake River basalt flows and recent basalt flows. Soils that formed in these areas have a strongly developed profile. They commonly are heavy textured and have accumulations of lime. Some of these soils also have a duripan. Bostrum, Adios, Gooding, Hamrub, and Yutrué soils are examples.

Some basalt flowed to the north into the valleys of major drainageways such as the Big Wood River, the Little Wood River, and Fish Creek. These flows commonly have been scoured and eroded or buried by alluvium and glacial outwash. Most of these areas, therefore, are considered remnant basalt plains. The soils that formed in these areas have a strongly developed profile, commonly are heavy textured, and have some lime accumulation in the underlying horizons. Some also have a duripan. These soils developed in a wetter precipitation zone than the soils on flows that tip toward the south or southwest; therefore, they have a thicker A horizon.

The soils that formed on flood plains, stream terraces, fan terraces, and outwash terraces in the survey area formed in alluvium, glacial outwash, and reworked lacustrine sediment of recent to Pleistocene age. The broad valley floors along the Big Wood River, the Little Wood River, and Fish Creek have a sequence of stream terraces and outwash terraces. The outwash terraces are oldest, and they occupy the higher positions in the alluvial valley. These terraces were deposited as proglacial outwash (11).

At the same time or shortly after the proglacial outwash was deposited, successive basalt flows spread over the valley floor at the southern end of the major drainageways. These flows essentially acted as basalt dams on the drainageways, causing a buildup of lacustrine sediment in the upper part of the valley and shifting the flow of the rivers and streams across the valley in an east-west direction. This damming occurred several times, resulting in a series of stream terraces in the valleys. Most of the original glacial outwash in these areas has been reworked by water and is now considered to be alluvium. Only a few remnant outwash terraces remain. An example is the area at the



confluence of Friedman and Muldoon Creeks. The soils that formed in this glacial outwash have a moderately developed profile, are very cobbly or gravelly or extremely cobbly or gravelly throughout, and have base saturation of less than 75 percent in the upper 30 inches. They do not have accumulations of lime. Rockybar soils are an example.

The soils on flood plains formed in recent alluvium, have a high water table, and are somewhat poorly drained to very poorly drained. They exhibit weakly expressed profile development. These soils commonly have a dark A horizon and are underlain by stratified gravel, cobbles, and sand. Bruneel and Marshdale soils are examples.

The soils on the first stream terraces above the flood plains also formed in recent alluvium and are well drained to somewhat excessively drained. They also have a weakly expressed profile and are underlain by gravel, cobbles, and sand. Balaam and Adamson soils are examples.

The soils that formed on the next stream terraces have moderate profile development. These terraces have been in place long enough for the parent rock to weather and for clay to be translocated into the B horizon. The soils on these terraces formed in gravelly and very gravelly alluvium. They are well drained and are underlain by loose sand, gravel, and cobbles. Little Wood soils are an example. Bringmee and Carey Lake soils also formed on these terraces but in less gravelly material. These soils have well expressed accumulations of clay in the profile, but they do not have accumulations of lime.

The soils on the older fan terraces typically are well developed and well drained. These soils formed in alluvium derived from material of the Challis Volcanic Formation. They have a medium to heavy textured argillic horizon and a duripan in the B horizon. The duripan in these soils typically is older than that of other soils in the survey area. It formed when the climate of the area was considerably more moist, immediately following glaciation. During this period silica in solution moved downward in the soil and over time plugged the pores and voids in the underlying layer, making it thicker and more cemented. The duripan that formed is noncalcareous because the moisture allowed the low amount of lime present to be leached deeper into the profile and because the parent material is inherently low in lime (5). Because the downward movement of the clay was restricted by the duripan, clay accumulated above the pan and an argillic horizon formed. Peevywell and Muldoon soils are examples.

Soils on the younger fan terraces formed in alluvium

derived from various kinds of rock. These soils have a moderately expressed profile. They commonly have accumulations of clay in the B horizon. Molyneux, Drage, and Justesen soils are examples.

Most of the lacustrine material that accumulated upstream as a result of basalt damming the streams has been reworked by more recent alluvial activity; therefore, these areas resemble flood plains and stream terraces. A small area of this reworked lacustrine sediment is near Picabo. Soils that formed in alluvium in these areas typically are somewhat poorly drained to very poorly drained and commonly are high in content of lime and organic matter, especially in the A horizon. Picabo, Bickett, and Hapur soils are examples.

## Climate

Climate has a strong influence on soil formation. Temperature and precipitation affect the weathering of rock and its constituent minerals; the illuviation and eluviation of material; the kinds and amount of vegetation; and the accumulation and decomposition of organic matter.

The climate in the survey area is characterized by warm, dry summers and cold, moist winters. Generally, as elevation increases, average annual precipitation increases and average annual temperature decreases. The warmest and driest area is in the southern part of the survey area, where elevation is lowest. This area receives about 11 to 13 inches of precipitation annually and has an average annual temperature of about 47 to 49 degrees F. The highest amount of precipitation and the coldest temperatures occur in the mountains in the northern part of the survey area. This area annually receives 12 to more than 20 inches of precipitation and has an average annual temperature of about 34 to 44 degrees.

The soils in the warmest and driest areas typically have a thin dark A horizon and have accumulations of lime in the B horizon. Because of the low precipitation, movement of water through the soil is not sufficient to leach the lime from the profile. Some of these soils have an accumulation of silica, which forms a duripan in the B horizon. Adios, Gooding, Hamrub, Deerhorn, and Wildors are examples of soils that have a duripan. Bostrum and Yutruue are examples of soils that do not have a duripan but have accumulations of clay in the B horizon. The vegetation on these soils is mainly alkali sagebrush, Wyoming big sagebrush, and bluebunch wheatgrass.

Lime in the soils in the 12- to 16-inch precipitation zone has been leached to a greater depth in the profile,



and in some areas it has been leached out completely. These soils are cooler mainly because they are at higher elevations. The additional moisture contributes to the weathering of minerals to form clay and then to translocate it. The vegetation on these soils also reflects the additional moisture and cooler temperatures. These soils support mountain big sagebrush, threetip sagebrush, basin big sagebrush, bluebunch wheatgrass, and Idaho fescue. Because of the abundance of grasses in the plant community, considerably more organic matter is produced and incorporated into the A horizon annually. The microbial activity is slowed because of the cooler temperatures, and thus the breakdown of organic matter is slowed. The combination of more organic matter being produced and less being broken down has resulted in a thicker dark A horizon in these soils than in the soils that receive less precipitation. Molyneux, Carey Lake, Smelter, Laurentzen, and Simonton soils are examples. The leaching of clay, silica, and bases has resulted in some of the soils in this higher precipitation zone having a base saturation of less than 75 percent in the upper 30 inches.

Soils in the coldest and wettest (16 to more than 20 inches of precipitation) parts of the survey area support mainly mountain big sagebrush, mountain snowberry, and Idaho fescue plant communities. These soils are similar to those in the 12- to 16-inch precipitation zone. They do not have accumulations of lime, but they commonly have an even thicker dark A horizon. Povey, Lavacreek, Earcree, Winu, and Friedman soils are examples. Some of the soils in the higher precipitation zone support an overstory of Douglas fir. Snowberry is the dominant understory plant in these areas. Because these areas support little, if any, grass, less organic matter is incorporated into the soil annually. In addition, the cold temperatures slow the microbial activity. These soils, therefore, have a thin, light-colored A horizon. Ketchum soils are an example.

## Relief

The survey area is characterized by steep mountains, gently rolling to steep foothills, undulating lava flows, fan terraces, flood plains, and stream terraces. These surfaces influence soils by affecting erosion, effective precipitation, soil drainage, air drainage, and exposure to sun and wind.

Soils on steep mountains and foothills commonly vary in depth of the profile and thickness of the A horizon. Soils on north and east aspects receive less sunlight than those on south and west aspects. On

north and east aspects, the soil temperatures generally are lower and the snowpack is greater. Because the soils receive moisture from the snowpack later in the growing season, they support a thick plant cover that helps to control erosion. Consequently, the soils are deeper. The lower soil temperatures inhibit the breakdown of the organic matter produced by the abundant vegetation, and thus a thick, dark A horizon forms. Povey, Earcree, Friedman, and Lavacreek are examples of soils that exhibit these characteristics. Areas of these soils are also on south and west aspects at elevations above 7,500 feet.

Soils on south and west aspects generally are shallower and have a thinner A horizon than those on north and east aspects. Direct sunlight heats and dries the soil quickly during the growing season. This speeds up the breakdown of organic matter and limits plant growth, resulting in a thin, dark A horizon. The rate of erosion is higher because of the limited ground cover; thus, these soils are shallower. Examples are Elksel, Starhope, Vitale, and Milligan soils.

Soils on flood plains and stream terraces are very deep and nearly level. Their proximity to watercourses and springs makes them subject to flooding or to a fluctuating water table. Bickett soils, for example, have a thick layer of organic material on the surface and are gleyed in the B horizon. Hapur, Picabo, Bruneel, and Hutton soils have organic matter in the A horizon and are mottled or gleyed in the B horizon.

Soils on fan terraces are very deep and well drained. Most of these soils are on east and west aspects, but some are on south aspects. Winds often blow the snow from smooth and convex positions into drainageways and other concave positions, thus increasing the effective moisture in these areas. The soils in these areas, such as those of the Muldoon and Molyneux series, have a thick, dark A horizon because of the increased vegetation. Soils in convex positions, such as those of the Peevywell, Justesen, and Drage series, support less vegetation and have a much thinner A horizon.

Precipitation increases at higher elevations in some areas on fan terraces; thus, the soils in these areas produce more vegetation and have a darker A horizon. In addition, gently sloping soils on fan terraces receive more effective moisture than those on adjacent steep, south aspects.

Because of the way the eolian material was deposited and reworked by water, the soils on lava flows range from deep or very deep in concave positions to moderately deep, shallow, or very shallow in convex positions. Bedrock is exposed in some areas.



Cinderhurst soils are an example of very shallow soils on the most recent flows. Examples of moderately deep soils are McCarey, Pedleford, and Deerhorn soils. Rehfield soils are an example of very deep soils in concave positions.

## Living Organisms

Living organisms, including plants and animals, have a significant function in soil formation. The kinds and amount of vegetation that grow on soils have a strong influence on the development of the soils.

Soils that developed at the lowest elevations in the southern part of the survey area, where average annual precipitation is about 11 to 13 inches, support limited vegetation. Alkali sagebrush, Wyoming big sagebrush, and bluebunch wheatgrass are the main plants. Because the production of vegetation is limited, the annual addition of organic matter is also limited. Consequently, these soils have a thin, dark A horizon. Deerhorn, Hamrub, Gooding, and Bostrum soils are examples.

The soils at mid elevations in the survey area formed under 12 to 16 inches of precipitation and cooler temperatures. These soils support mainly mountain big sagebrush, threetip sagebrush, bluebunch wheatgrass, and Idaho fescue. This abundance of grasses adds appreciable amounts of organic matter to the soil surface, resulting in soils that have a thicker dark A horizon. Micro-organisms are also very active in this environment, and they influence the color of the soil, its structure, and its physical appearance. Molyneux, Justesen, Smelter, Vitale, Starhope, and Bancroft soils are examples.

At the highest elevations and generally on north- and east-facing slopes, where the average annual precipitation is 16 to more than 20 inches, the soils support mainly mountain big sagebrush, snowberry, and Idaho fescue and some Douglas fir. The abundant shrubs and grasses produce a substantial amount of organic matter that annually is added to the soil and results in a thick, dark A horizon. Because of the cold temperatures, micro-organisms are not as active and their influence on the breakdown of organic matter, soil structure, and the physical appearance of soils is not so great. Earcree and Povey soils are examples.

Douglas fir and snowberry produce less organic matter; thus the soils that support mainly these plants have a lighter colored A horizon. Ketchum soils are an example.

The somewhat poorly drained to very poorly drained soils on flood plains support water-tolerant grasses,

sedges, and forbs. These soils generally are very high in organic matter content because of the abundant plant growth. Hutton, Hapur, Marshdale, Picabo, and Bruneel soils are examples. This environment, in most cases, is conducive to microbial activity, which aids in the decomposition of organic matter and the incorporation of it into the upper part of the soil profile. The permanent high water table in some of the very poorly drained soils has inhibited the growth of aerobic micro-organisms and little of the organic matter has been incorporated into the soils, leaving an organic mat on the soil surface. Bickett soils are an example.

## Time

The length of time the landforms in the survey area have been exposed and the variability of parent material, relief, and vegetation all contribute to the wide variety of soils in the survey area; however, the different horizons in the soil profile and the degree of their development can be directly related to time.

Soils that formed in eolian material that has been reworked by water are on the oldest lava flows in the area. These soils exhibit a high degree of development. In some areas lime and silica have been leached from the upper part of the profile and have accumulated in the lower part, forming a duripan, commonly at the point of lithic contact (8). Clay also has moved down through the profile and has accumulated above the pan, forming an argillic horizon. Examples of soils that have both a duripan and an argillic horizon are those of the Gooding and Manard series. Soils that have only an argillic horizon are those of the Goodington and Yutree series.

Soils on the younger lava flows are characterized by a calcic horizon because of the downward movement of lime in the profile and by a moderately expressed argillic horizon because of the limited movement of clay. McCarey, Pedleford, and Bancroft soils are examples.

Cinderhurst soils are an example of the youngest and least developed soils on lava flows. Little movement of clay has taken place in these soils; thus, they have only a weakly expressed argillic horizon.

Soils on the foothills and mountains are quite variable. Ketchum, Moonstone, Earcree, Milligan, and Povey soils formed in sedimentary and intrusive igneous rock on steep slopes. Because the parent material is resistant to weathering and the soil material is constantly moving downslope, these soils exhibit little development even though they are quite old. An accumulation of organic matter and a weakly expressed B horizon are the extent of the development in these soils.

An accumulation of organic matter and a medium textured argillic horizon are present in the Elkcreek, Winu, and Gaib soils on Tertiary basalt. These soils generally are the same age as Friedman, Starhope, and Elksel soils, which formed in material from the Challis Volcanic Formation and have a fine-textured argillic horizon.

A well expressed argillic horizon and duripan are present in Muldoon and Peevywell soils, which are on the oldest fan terraces. Soils on younger fan terraces do not have a duripan, but they do exhibit a well

expressed argillic horizon. Examples are Justesen, Molyneux, and Carey Lake soils. Little Wood and Drage soils are on relatively young fan terraces and stream terraces, and they have a weakly expressed argillic horizon.

Some of the youngest soils in the area are on flood plains and stream terraces. Adamson, Bruneel, and Hapur soils, which formed in recent alluvium, have a weak B horizon and an accumulation of organic matter in the A horizon.





# References

---

- (1) American Association of State Highway and Transportation Officials. 1982. Standard specifications for highway materials and methods of sampling and testing. Ed. 13, 2 vols., illus.
- (2) American Society for Testing and Materials. 1985. Standard test method for classification of soils for engineering purposes. ASTM Stand. D 2487.
- (3) Harrison, W.D., and M.E. Johnson. [n.d.] Improved mapping delineation accuracy using landsat MSS spectral maps. Report presented at West. Reg. Work Plann. Conf. for Soil Surv., San Diego, California.
- (4) Harrison, W.D., M.E. Johnson, and P.F. Biggam. 1987. Video image analysis of large-scale vertical aerial photography to facilitate soil mapping. Soil Sci. Am. Spec. Publ. No. 20, pp. 1-8, illus.
- (5) Herriman, R.C., and R.B. Parsons. 1979. Land use and management of soils with relict duripans in southwestern Oregon, USA. *Geoderma* 22(2): 99-103.
- (6) Hipple, Karl W. 1983. Lime and silica cemented layers in soils. *In* Soil Survey Horizons, vol. 24, no. 3, pp. 5-10.
- (7) Hipple, Karl W., and W.D. Harrison. [n.d.] Improved low intensity soil survey map unit design using large scale vertical aerial photographs. Report presented at West. Reg. Work Plann. Conf. for Soil Surv., San Diego, California.
- (8) Logan, Glen H. 1983. Soil cementation in Idaho soils—how to identify, describe, classify, and interpret. *In* Soil Survey Horizons, vol. 24, no. 2, pp. 25-28.
- (9) Passey, H.S., Vern K. Hugie, E.W. Williams, and D.E. Ball. 1982. Relationship between soil, plant community, and climate on rangeland of the Intermountain West. U.S. Dep. Agric. Tech. Bull. 1669, pp. 33-34.
- (10) Ross, Clyde P. 1963. Geology along U.S. Highway 93 in Idaho. U.S. Geol. Surv. and Idaho Bur. Mines and Geol. Pam. 130, 98 pp.
- (11) Schmidt, D.L. 1962. Quaternary geology of the Bellevue area in Blaine and Camas Counties, Idaho. U.S. Geol. Surv. Open File Rep. 62-120.
- (12) Stearns, Harold. 1967. Geology of Craters of the Moon, Idaho. Nat. Park Serv., 34 pp.
- (13) Umpleby, Westgate, et al. 1930. Geology and ore deposits of the Woodriver region, Idaho, with a description of the Minnie Moore and nearby mines. U.S. Geol. Surv. Bull. 814, 8 pp.
- (14) United States Department of Agriculture. 1951. Soil survey manual. U.S. Dep. Agric. Handb. 18, 503 pp., illus.
- (15) United States Department of Agriculture. 1961. Land capability classification. U.S. Dep. Agric. Handb. 210, 21 pp.
- (16) United States Department of Agriculture. 1975. Soil taxonomy: A basic system of soil classification for making and interpreting soil surveys. Soil Conserv. Serv., U.S. Dep. Agric. Handb. 436, 754 pp., illus.
- (17) United States Department of Agriculture. 1976. National range handbook. Soil Conserv. Serv., 130 pp.



- (18) United States Department of Agriculture. 1982. National list of scientific plant names. Soil Conserv. Serv., Tech. Publ. 159, vols. 1 and 2.
- (19) United States Department of Agriculture. [n.d.] Soil survey of Blaine Soil Conservation District, Idaho.
- (20) United States Department of Agriculture. [n.d.] Wood River Soil Survey.
- (21) United States Department of the Interior. 1978. Bennett Hills environmental impact statement. Bur. Land Manage., Shoshone Dist., Idaho, pp. 8-69, maps.

# Glossary

---

**Aeration, soil.** The exchange of air in soil with air from the atmosphere. The air in a well aerated soil is similar to that in the atmosphere; the air in a poorly aerated soil is considerably higher in carbon dioxide and lower in oxygen.

**Aggregate, soil.** Many fine particles held in a single mass or cluster. Natural soil aggregates, such as granules, blocks, or prisms, are called peds. Clods are aggregates produced by tillage or logging.

**Alluvial fan.** The fanlike deposit of a stream where it issues from a gorge upon a plain or of a tributary stream near or at its junction with its main stream.

**Alluvium.** Material, such as sand, silt, or clay, deposited on land by streams.

**Animal-unit-month (AUM).** The amount of forage required by one mature cow of approximately 1,000 pounds weight, with or without a calf, for 1 month.

**Area reclaim** (in tables). An area difficult to reclaim after the removal of soil for construction and other uses. Revegetation and erosion control are extremely difficult.

**Association, soil.** A group of soils or miscellaneous areas geographically associated in a characteristic repeating pattern and defined and delineated as a single map unit.

**Available water capacity (available moisture capacity).** The capacity of soils to hold water available for use by most plants. It is commonly defined as the difference between the amount of soil water at field moisture capacity and the amount at wilting point. It is commonly expressed as inches of water per inch of soil. The capacity, in inches, in a 60-inch profile or to a limiting layer is expressed as—

|                 |              |
|-----------------|--------------|
| Very low .....  | 0 to 3       |
| Low .....       | 3 to 6       |
| Moderate .....  | 6 to 9       |
| High .....      | 9 to 12      |
| Very high ..... | more than 12 |

**Base saturation.** The degree to which material having cation-exchange properties is saturated with

exchangeable bases (sum of Ca, Mg, Na, K), expressed as a percentage of the total cation-exchange capacity.

**Bedrock.** The solid rock that underlies the soil and other unconsolidated material or that is exposed at the surface.

**Bottom land.** The normal flood plain of a stream, subject to flooding.

**Boulders.** Rock fragments larger than 2 feet (60 centimeters) in diameter.

**Brush management.** Use of mechanical, chemical, or biological methods to reduce or eliminate competition of woody vegetation to allow understory grasses and forbs to recover or to make conditions favorable for reseeding. It increases production of forage, which reduces the hazard of erosion. Brush management may improve the habitat for some species of wildlife.

**Butte.** An isolated small mountain or hill with steep or precipitous sides and a top variously flat, rounded, or pointed that may be a residual mass isolated by erosion or an exposed volcanic neck.

**Calcareous soil.** A soil containing enough calcium carbonate (commonly combined with magnesium carbonate) to effervesce visibly when treated with cold, dilute hydrochloric acid.

**Canopy.** The leafy crown of trees or shrubs. (See Crown.)

**Canyon.** A long, deep, narrow, very steep-sided valley with high, precipitous walls in an area of high local relief.

**Capillary water.** Water held as a film around soil particles and in tiny spaces between particles. Surface tension is the adhesive force that holds capillary water in the soil.

**Cation.** An ion carrying a positive charge of electricity. The common soil cations are calcium, potassium, magnesium, sodium, and hydrogen.

**Cation-exchange capacity.** The total amount of exchangeable cations that can be held by the soil, expressed in terms of milliequivalents per 100 grams of soil at neutrality (pH 7.0) or at some



other stated pH value. The term, as applied to soils, is synonymous with base-exchange capacity but is more precise in meaning.

**Cemented pan** (in tables). A cemented pan is too close to the surface for the specified use.

**Channery soil.** A soil that is, by volume, more than 15 percent thin, flat fragments of sandstone, shale, slate, limestone, or schist as much as 6 inches along the longest axis. A single piece is called a channer.

**Chemical treatment.** Control of unwanted vegetation by use of chemicals.

**Clay.** As a soil separate, the mineral soil particles less than 0.002 millimeter in diameter. As a soil textural class, soil material that is 40 percent or more clay, less than 45 percent sand, and less than 40 percent silt.

**Clay film.** A thin coating of oriented clay on the surface of a soil aggregate or lining pores or root channels. Synonyms: clay coating, clay skin.

**Claypan.** A slowly permeable soil horizon that contains much more clay than the horizons above it. A claypan is commonly hard when dry and plastic or stiff when wet.

**Climax plant community.** The plant community on a given site that will be established if present environmental conditions continue to prevail and the site is properly managed.

**Coarse fragments.** Mineral or rock particles larger than 2 millimeters in diameter.

**Coarse textured soil.** Sand or loamy sand.

**Cobble (or cobblestone).** A rounded or partly rounded fragment of rock 3 to 10 inches (7.6 to 25 centimeters) in diameter.

**Cobbly soil material.** Material that is 15 to 35 percent, by volume, rounded or partially rounded rock fragments 3 to 10 inches (7.6 to 25 centimeters) in diameter. Very cobbly soil material is 35 to 60 percent of these rock fragments, and extremely cobbly soil material is more than 60 percent.

**Colluvium.** Soil material, rock fragments, or both, moved by creep, slide, or local wash and deposited at the base of steep slopes.

**Complex slope.** Irregular or variable slope. Planning or constructing terraces, diversions, and other water-control measures on a complex slope is difficult.

**Complex, soil.** A map unit of two or more kinds of soil or miscellaneous areas in such an intricate pattern or so small in area that it is not practical to map them separately at the selected scale of mapping. The pattern and proportion of the soils or

miscellaneous areas are somewhat similar in all areas.

**Concretions.** Grains, pellets, or nodules of various sizes, shapes, and colors consisting of concentrated compounds or cemented soil grains. The composition of most concretions is unlike that of the surrounding soil. Calcium carbonate and iron oxide are common compounds in concretions.

**Conglomerate.** A coarse grained, clastic rock composed of rounded to subangular rock fragments more than 2 millimeters in diameter. It commonly has a matrix of sand and finer material. Conglomerate is the consolidated equivalent of gravel.

**Conservation cropping system.** Growing crops in combination with needed cultural and management practices. In a good conservation cropping system, the soil-improving crops and practices more than offset the soil-depleting crops and practices. Cropping systems are needed on all tilled soils. Soil-improving practices in a conservation cropping system include the use of rotations that contain grasses and legumes and the return of crop residue to the soil. Other practices include the use of green manure crops of grasses and legumes, proper tillage, adequate fertilization, and weed and pest control.

**Consistence, soil.** The feel of the soil and the ease with which a lump can be crushed by the fingers. Terms commonly used to describe consistence are—

*Loose.*—Noncoherent when dry or moist; does not hold together in a mass.

*Friable.*—When moist, crushes easily under gentle pressure between thumb and forefinger and can be pressed together into a lump.

*Firm.*—When moist, crushes under moderate pressure between thumb and forefinger, but resistance is distinctly noticeable.

*Plastic.*—Readily deformed by moderate pressure but can be pressed into a lump; will form a "wire" when rolled between thumb and forefinger.

*Sticky.*—Adheres to other material and tends to stretch somewhat and pull apart rather than to pull free from other material.

*Hard.*—When dry, moderately resistant to pressure; can be broken with difficulty between thumb and forefinger.

*Soft.*—When dry, breaks into powder or individual grains under very slight pressure.

*Cemented.*—Hard; little affected by moistening.



**Control section.** The part of the soil on which classification is based. The thickness varies among different kinds of soil, but for many it is that part of the soil profile between depths of 10 inches and 40 or 80 inches.

**Corrosive.** High risk of corrosion to uncoated steel or deterioration of concrete.

**Cropping system.** Growing crops using a planned system of rotation and management practices.

**Crop residue management.** Returning crop residue to the soil. Crop residue management helps to maintain soil structure, organic matter content, and fertility and helps to control erosion.

**Crown.** The upper part of a tree or shrub, including the living branches and their foliage.

**Cutbanks cave** (in tables). The walls of excavations tend to cave in or slough.

**Deferred grazing.** Postponing grazing or arresting grazing for a prescribed period.

**Depth to rock** (in tables). Bedrock is too near the surface for the specified use.

**Diversion (or diversion terrace).** A ridge of earth, generally a terrace, built to protect downslope areas by diverting runoff from its natural course.

**Drainage class** (natural). Refers to the frequency and duration of periods of saturation or partial saturation during soil formation, as opposed to altered drainage, which is commonly the result of artificial drainage or irrigation but may be caused by the sudden deepening of channels or the blocking of drainage outlets. Seven classes of natural soil drainage are recognized:

*Excessively drained.*—These soils have very high and high hydraulic conductivity and low water-holding capacity. They are not suited to crop production unless irrigated.

*Somewhat excessively drained.*—These soils have high hydraulic conductivity and low water-holding capacity. Without irrigation, only a narrow range of crops can be grown and yields are low.

*Well drained.*—These soils have intermediate water-holding capacity. They retain optimum amounts of moisture, but they are not wet close enough to the surface or long enough during the growing season to adversely affect yields.

*Moderately well drained.*—These soils are wet close enough to the surface or long enough that planting or harvesting operations or yields of some field crops are adversely affected unless artificial drainage is provided. Moderately well drained soils commonly have a layer with low hydraulic conductivity, a wet layer relatively high in the

profile, additions of water by seepage, or some combination of these.

*Somewhat poorly drained.*—These soils are wet close enough to the surface or long enough that planting or harvesting operations or crop growth is markedly restricted unless artificial drainage is provided. Somewhat poorly drained soils commonly have a layer with low hydraulic conductivity, a wet layer high in the profile, additions of water through seepage, or a combination of these.

*Poorly drained.*—These soils commonly are so wet at or near the surface during a considerable part of the year that field crops cannot be grown under natural conditions. Poorly drained conditions are caused by a saturated zone, a layer with low hydraulic conductivity, seepage, or a combination of these.

*Very poorly drained.*—These soils are wet to the surface most of the time. They are wet enough to prevent the growth of important crops (except rice) unless artificially drained.

**Drainage, surface.** Runoff, or surface flow of water, from an area.

**Eluviation.** The movement of material in true solution or colloidal suspension from one place to another within the soil. Soil horizons that have lost material through eluviation are eluvial; those that have received material are illuvial.

**Eolian soil material.** Earthy parent material accumulated through wind action; commonly refers to sandy material in dunes or to loess in blankets on the surface.

**Erosion.** The wearing away of the land surface by water, wind, ice, or other geologic agents and by such processes as gravitational creep.

*Erosion* (geologic). Erosion caused by geologic processes acting over long geologic periods and resulting in the wearing away of mountains and the building up of such landscape features as flood plains and coastal plains. Synonym: natural erosion.

*Erosion* (accelerated). Erosion much more rapid than geologic erosion, mainly as a result of the activities of man or other animals or of a catastrophe in nature, for example, fire, that exposes the surface.

**Escarpment.** A relatively continuous and steep slope or cliff breaking the general continuity of more gently sloping land surfaces and produced by erosion or faulting. Synonym: scarp.



**Excess fines** (in tables). Excess silt and clay in the soil. The soil does not provide a source of gravel or sand for construction purposes.

**Excess salt** (in tables). The soil has excess water-soluble salts that restrict the growth of most plants.

**Extrusive rock.** Igneous rock derived from deep-seated molten matter (magma) emplaced on the earth's surface.

**Fan terrace.** A relict alluvial fan, no longer a site of active deposition, incised by younger and lower alluvial surfaces.

**Fast intake** (in tables). The rapid movement of water into the soil.

**Fertility, soil.** The quality that enables a soil to provide plant nutrients, in adequate amounts and in proper balance, for the growth of specified plants when light, moisture, temperature, tilth, and other growth factors are favorable.

**Fibric soil material (peat).** The least decomposed of all organic soil material. Peat contains a large amount of well preserved fiber that is readily identifiable according to botanical origin. Peat has the lowest bulk density and the highest water content at saturation of all organic soil material.

**Field moisture capacity.** The moisture content of a soil, expressed as a percentage of the oven-dry weight, after the gravitational, or free, water has drained away; the field moisture content 2 or 3 days after a soaking rain; also called *normal field capacity*, *normal moisture capacity*, or *capillary capacity*.

**Fine textured soil.** Sandy clay, silty clay, and clay.

**Flood plain.** A nearly level alluvial plain that borders a stream and is subject to flooding unless protected artificially.

**Fluvial.** Of or pertaining to rivers; produced by river action, as a fluvial plain.

**Foothill.** A steeply sloping upland that has relief of as much as 1,000 feet (300 meters) and fringes a mountain range or high-plateau escarpment.

**Foot slope.** The inclined surface at the base of a hill.

**Forb.** Any herbaceous plant not a grass or a sedge.

**Frost action** (in tables). Freezing and thawing of soil moisture. Frost action can damage roads, buildings and other structures, and plant roots.

**Genesis, soil.** The mode of origin of the soil. Refers especially to the processes or soil-forming factors responsible for the formation of the solum, or true soil, from the unconsolidated parent material.

**Glacial outwash** (geology). Gravel, sand, and silt, commonly stratified, deposited by glacial meltwater.

**Gleyed soil.** Soil that formed under poor drainage, resulting in the reduction of iron and other elements in the profile and in gray colors and mottles.

**Gravel.** Rounded or angular fragments of rock up to 3 inches (2 millimeters to 7.6 centimeters) in diameter. An individual piece is a pebble.

**Gravelly soil material.** Material that is 15 to 50 percent, by volume, rounded or angular rock fragments, not prominently flattened, up to 3 inches (7.6 centimeters) in diameter.

**Ground water** (geology). Water filling all the unblocked pores of underlying material below the water table.

**Gully.** A miniature valley with steep sides cut by running water and through which water ordinarily runs only after rainfall. The distinction between a gully and a rill is one of depth. A gully generally is an obstacle to farm machinery and is too deep to be obliterated by ordinary tillage; a rill is of lesser depth and can be smoothed over by ordinary tillage.

**Hard bedrock.** Bedrock that cannot be excavated except by blasting or by the use of special equipment that is not commonly used in construction.

**Hardpan.** A hardened or cemented soil horizon, or layer. The soil material is sandy, loamy, or clayey and is cemented by iron oxide, silica, calcium carbonate, or other substance.

**Hard to pack** (in tables). The soil is difficult to compact.

**Hemic soil material (mucky peat).** Organic soil material intermediate in degree of decomposition between the less decomposed fibric material and the more decomposed sapric material.

**Horizon, soil.** A layer of soil, approximately parallel to the surface, having distinct characteristics produced by soil-forming processes. In the identification of soil horizons, an uppercase letter represents the major horizons. Numbers or lowercase letters that follow represent subdivisions of the major horizons. An explanation of the subdivisions is given in the *Soil Survey Manual*. The major horizons of mineral soil are as follows:  
*O horizon*.—An organic layer of fresh and decaying plant residue.

*A horizon*.—The mineral horizon at or near the surface in which an accumulation of humified organic matter is mixed with the mineral material. Also, a plowed surface horizon, most of which was originally part of a B horizon.



**B horizon.**—The mineral horizon below an A horizon. The B horizon is in part a layer of transition from the overlying A to the underlying C horizon. The B horizon also has distinctive characteristics such as (1) accumulation of clay, sesquioxides, humus, or a combination of these; (2) prismatic or blocky structure; (3) redder or browner colors than those in the A horizon; or (4) a combination of these.

**E horizon.**—The mineral horizon in which the main feature is loss of silicate clay, iron, aluminum, or some combination of these.

**C horizon.**—The mineral horizon or layer, excluding indurated bedrock, that is little affected by soil-forming processes and does not have the properties typical of the overlying soil material. The material of a C horizon may be either like or unlike that in which the solum formed. If the material is known to differ from that in the solum, the number 2 precedes the letter C.

**R layer.**—Hard, consolidated bedrock beneath the soil. The bedrock commonly underlies a C horizon but can be directly below an A or a B horizon.

**Humus.** The well decomposed, more or less stable part of the organic matter in mineral soils.

**Hydrologic soil groups.** Refers to soils grouped according to their runoff-producing characteristics. The chief consideration is the inherent capacity of soil bare of vegetation to permit infiltration. The slope and the kind of plant cover are not considered but are separate factors in predicting runoff. Soils are assigned to four groups. In group A are soils having a high infiltration rate when thoroughly wet and having a low runoff potential. They are mainly deep, well drained, and sandy or gravelly. In group D, at the other extreme, are soils having a very slow infiltration rate and thus a high runoff potential. They have a claypan or clay layer at or near the surface, have a permanent high water table, or are shallow over nearly impervious bedrock or other material. A soil is assigned to two hydrologic groups if part of the acreage is artificially drained and part is undrained.

**Igneous rock.** Rock formed by solidification from a molten or partially molten state. Major varieties include plutonic and volcanic rock. Examples are andesite, basalt, and granite.

**Illuviation.** The movement of soil material from one horizon to another in the soil profile. Generally, material is removed from an upper horizon and deposited in a lower horizon.

**Impervious soil.** A soil through which water, air, or roots penetrate slowly or not at all. No soil is absolutely impervious to air and water all the time.

**Infiltration rate.** The rate at which water penetrates the surface of the soil at any given instant, usually expressed in inches per hour. The rate can be limited by the infiltration capacity of the soil or the rate at which water is applied at the surface.

**Intermittent stream.** A stream or reach of a stream that flows for prolonged periods only when it receives ground-water discharge or long, continued contributions from melting snow or other surface and shallow subsurface sources.

**Irrigation.** Application of water to soils to assist in production of crops. Methods of irrigation are—  
**Border.**—Water is applied at the upper end of a strip in which the lateral flow of water is controlled by small earth ridges called border dikes, or borders.

**Controlled flooding.**—Water is released at intervals from closely spaced field ditches and distributed uniformly over the field.

**Corrugation.**—Water is applied to small, closely spaced furrows or ditches in fields of close-growing crops or in orchards so that it flows in only one direction.

**Sprinkler.**—Water is sprayed over the soil surface through pipes or nozzles from a pressure system.

**Subirrigation.**—Water is applied in open ditches or tile lines until the water table is raised enough to wet the soil.

**Lacustrine deposit** (geology). Material deposited in lake water and exposed when the water level is lowered or the elevation of the land is raised.

**Landslide.** The rapid downhill movement of a mass of soil and loose rock, generally when wet or saturated. The speed and distance of movement, as well as the amount of soil and rock material, vary greatly.

**Large stones** (in tables). Rock fragments 3 inches (7.6 centimeters) or more across. Large stones adversely affect the specified use of the soil.

**Leaching.** The removal of soluble material from soil or other material by percolating water.

**Liquid limit.** The moisture content at which the soil passes from a plastic to a liquid state.

**Loam.** Soil material that is 7 to 27 percent clay particles, 28 to 50 percent silt particles, and less than 52 percent sand particles.

**Loess.** Fine grained material, dominantly of silt-sized particles, deposited by wind.



**Low strength.** The soil is not strong enough to support loads.

**Mechanical treatment.** Use of mechanical equipment for seeding, brush management, and other management practices.

**Medium textured soil.** Very fine sandy loam, loam, silt loam, or silt.

**Metamorphic rock.** Rock of any origin altered in mineralogical composition, chemical composition, or structure by heat, pressure, and movement. Nearly all such rocks are crystalline.

**Mineral soil.** Soil that is mainly mineral material and low in organic material. Its bulk density is more than that of organic soil.

**Minimum tillage.** Only the tillage essential to crop production and prevention of soil damage.

**Miscellaneous area.** An area that has little or no natural soil and supports little or no vegetation.

**Moderately coarse textured soil.** Coarse sandy loam, sandy loam, and fine sandy loam.

**Moderately fine textured soil.** Clay loam, sandy clay loam, and silty clay loam.

**Morphology, soil.** The physical makeup of the soil, including the texture, structure, porosity, consistence, color, and other physical, mineral, and biological properties of the various horizons, and the thickness and arrangement of those horizons in the soil profile.

**Mottling, soil.** Irregular spots of different colors that vary in number and size. Mottling generally indicates poor aeration and impeded drainage. Descriptive terms are as follows: abundance—*few*, *common*, and *many*; size—*fine*, *medium*, and *coarse*; and contrast—*faint*, *distinct*, and *prominent*. The size measurements are of the diameter along the greatest dimension. *Fine* indicates less than 5 millimeters (about 0.2 inch); *medium*, from 5 to 15 millimeters (about 0.2 to 0.6 inch); and *coarse*, more than 15 millimeters (about 0.6 inch).

**Mountain.** A natural elevation of the land surface, rising more than 1,000 feet above surrounding lowlands, commonly of restricted summit area (relative to a plateau) and generally having steep sides and considerable bare-rock surface. A mountain can occur as a single, isolated mass or in a group forming a chain or range.

**Muck.** Dark, finely divided, well decomposed organic soil material. (See Sapric soil material.)

**Munsell notation.** A designation of color by degrees of three simple variables—hue, value, and chroma. For example, a notation of 10YR 6/4 is a color of 10YR hue, value of 6, and chroma of 4.

**Neutral soil.** A soil having a pH value between 6.6 and 7.3. (See Reaction, soil.)

**Nutrient, plant.** Any element taken in by a plant essential to its growth. Plant nutrients are mainly nitrogen, phosphorus, potassium, calcium, magnesium, sulfur, iron, manganese, copper, boron, and zinc obtained from the soil and carbon, hydrogen, and oxygen obtained from the air and water.

**Observed rooting depth.** Depth to which roots have been observed to penetrate.

**Organic matter.** Plant and animal residue in the soil in various stages of decomposition.

**Pan.** A compact, dense layer in a soil that impedes the movement of water and the growth of roots. For example, *hardpan*, *fragipan*, *claypan*, *plowpan*, and *traffic pan*.

**Parent material.** The unconsolidated organic and mineral material in which soil forms.

**Peat.** Unconsolidated material, largely undecomposed organic matter, that has accumulated under excess moisture. (See Fibric soil material.)

**Ped.** An individual natural soil aggregate, such as a granule, a prism, or a block.

**Pedon.** The smallest volume that can be called "a soil." A pedon is three dimensional and large enough to permit study of all horizons. Its area ranges from about 10 to 100 square feet (1 square meter to 10 square meters), depending on the variability of the soil.

**Percolation.** The downward movement of water through the soil.

**Percs slowly** (in tables). The slow movement of water through the soil, adversely affecting the specified use.

**Permeability.** The quality of the soil that enables water to move downward through the profile.

Permeability is measured as the number of inches per hour that water moves downward through the saturated soil. Terms describing permeability are:

|                        |                        |
|------------------------|------------------------|
| Very slow .....        | less than 0.06 inch    |
| Slow .....             | 0.06 to 0.2 inch       |
| Moderately slow .....  | 0.2 to 0.6 inch        |
| Moderate .....         | 0.6 inch to 2.0 inches |
| Moderately rapid ..... | 2.0 to 6.0 inches      |
| Rapid .....            | 6.0 to 20 inches       |
| Very rapid .....       | more than 20 inches    |

**Phase, soil.** A subdivision of a soil series based on features that affect its use and management. For example, slope, stoniness, and thickness.

**pH value.** A numerical designation of acidity and alkalinity in soil. (See Reaction, soil.)



**Piping** (in tables). Formation of subsurface tunnels or pipelike cavities by water moving through the soil.

**Plasticity index.** The numerical difference between the liquid limit and the plastic limit; the range of moisture content within which the soil remains plastic.

**Plastic limit.** The moisture content at which a soil changes from semisolid to plastic.

**Playa.** The generally dry and nearly level lake plain that occupies the lowest parts of closed depressional areas, such as those on intermontane basin floors. Temporary flooding occurs primarily in response to precipitation and runoff.

**Ponding.** Standing water on soils in closed depressions. The water can be removed only by percolation or evapotranspiration.

**Poor filter** (in tables). Because of rapid permeability or an impermeable layer near the surface, the soil may not adequately filter effluent from a waste disposal system.

**Poorly graded.** Refers to a coarse grained soil or soil material consisting mainly of particles of nearly the same size. Because there is little difference in size of the particles, density can be increased only slightly by compaction.

**Potential rooting depth (effective rooting depth).** Depth to which roots could penetrate if the content of moisture in the soil were adequate. The soil has no properties restricting the penetration of roots to this depth.

**Prescribed burning.** The application of fire to land under such conditions of weather, soil moisture, and time of day as presumably will result in the intensity of heat and spread required to accomplish specific forest management, wildlife, grazing, or fire hazard reduction purposes.

**Productivity, soil.** The capability of a soil for producing a specified plant or sequence of plants under specific management.

**Profile, soil.** A vertical section of the soil extending through all its horizons and into the parent material.

**Proper grazing use.** Grazing at an intensity that maintains enough cover to protect the soil and maintain or improve the quantity and quality of the desirable vegetation. This increases the vigor and reproduction of the key plants and promotes the accumulation of litter and mulch necessary to conserve soil and water.

**Range condition.** The present composition of the plant community on a range site in relation to the potential natural plant community for that site.

Range condition is expressed as excellent, good, fair, or poor, on the basis of how much the present plant community has departed from the potential.

**Rangeland.** Land on which the potential natural vegetation is predominantly grasses, grasslike plants, forbs, or shrubs suitable for grazing or browsing. It includes natural grasslands, savannas, many wetlands, some deserts, tundras, and areas that support certain forb and shrub communities.

**Range site.** An area of rangeland where climate, soil, and relief are sufficiently uniform to produce a distinct natural plant community. A range site is the product of all the environmental factors responsible for its development. It is typified by an association of species that differ from those on other range sites in kind or proportion of species or total production.

**Reaction, soil.** A measure of acidity or alkalinity of a soil, expressed in pH values. A soil that tests to pH 7.0 is described as precisely neutral in reaction because it is neither acid nor alkaline. The degrees of acidity or alkalinity, expressed as pH values, are—

|                              |                |
|------------------------------|----------------|
| Extremely acid .....         | below 4.5      |
| Very strongly acid .....     | 4.5 to 5.0     |
| Strongly acid.....           | 5.1 to 5.5     |
| Medium acid.....             | 5.6 to 6.0     |
| Slightly acid.....           | 6.1 to 6.5     |
| Neutral .....                | 6.6 to 7.3     |
| Mildly alkaline.....         | 7.4 to 7.8     |
| Moderately alkaline.....     | 7.9 to 8.4     |
| Strongly alkaline .....      | 8.5 to 9.0     |
| Very strongly alkaline ..... | 9.1 and higher |

**Relief.** The elevations or inequalities of a land surface, considered collectively.

**Residuum (residual soil material).** Unconsolidated, weathered or partly weathered mineral material that accumulated as consolidated rock disintegrated in place.

**Rill.** A steep-sided channel resulting from accelerated erosion. A rill generally is a few inches deep and not wide enough to be an obstacle to farm machinery.

**Road cut.** A sloping surface produced by mechanical means during road construction. It is commonly on the uphill side of the road.

**Rock fragments.** Rock or mineral fragments having a diameter of 2 millimeters or more; for example, pebbles, cobbles, stones, and boulders.

**Rooting depth** (in tables). Shallow root zone. The soil is shallow over a layer that greatly restricts roots.

**Root zone.** The part of the soil that can be penetrated by plant roots.



**Runoff.** The precipitation discharged into stream channels from an area. The water that flows off the surface of the land without sinking into the soil is called surface runoff. Water that enters the soil before reaching surface streams is called ground-water runoff or seepage flow from ground water.

**Saline soil.** A soil containing soluble salts in an amount that impairs growth of plants. A saline soil does not contain excess exchangeable sodium.

**Sand.** As a soil separate, individual rock or mineral fragments from 0.05 millimeter to 2.0 millimeters in diameter. Most sand grains consist of quartz. As a soil textural class, a soil that is 85 percent or more sand and not more than 10 percent clay.

**Sandstone.** Sedimentary rock containing dominantly sand-sized particles.

**Sapric soil material (muck).** The most highly decomposed of all organic soil material. Muck has the least amount of plant fiber, the highest bulk density, and the lowest water content at saturation of all organic soil material.

**Saprolite** (soil science). Unconsolidated residual material underlying the soil and grading to hard bedrock below.

**Sedimentary rock.** Rock made up of particles deposited from suspension in water. The chief kinds of sedimentary rock are conglomerate, formed from gravel; sandstone, formed from sand; shale, formed from clay; and limestone, formed from soft masses of calcium carbonate. There are many intermediate types. Some wind-deposited sand is consolidated into sandstone.

**Seepage** (in tables). The movement of water through the soil. Seepage adversely affects the specified use.

**Series, soil.** A group of soils that have profiles that are almost alike, except for differences in texture of the surface layer or of the underlying material. All the soils of a series have horizons that are similar in composition, thickness, and arrangement.

**Sheet erosion.** The removal of a fairly uniform layer of soil material from the land surface by the action of rainfall and surface runoff.

**Shrink-swell** (in tables). The shrinking of soil when dry and the swelling when wet. Shrinking and swelling can damage roads, dams, building foundations, and other structures. It can also damage plant roots.

**Silica.** A combination of silicon and oxygen. The mineral form is called quartz.

**Silt.** As a soil separate, individual mineral particles that range in diameter from the upper limit of clay

(0.002 millimeter) to the lower limit of very fine sand (0.05 millimeter). As a soil textural class, soil that is 80 percent or more silt and less than 12 percent clay.

**Similar soils.** Soils that share limits of diagnostic criteria, behave and perform in a similar manner, and have similar conservation needs or management requirements for the major land uses in the survey area.

**Site class.** A grouping of site indexes into 5 to 7 production capability levels. Each level can be represented by a site curve.

**Site index.** A designation of the quality of a forest site based on the height of the dominant stand at an arbitrarily chosen age. For example, if the average height attained by dominant and codominant trees in a fully stocked stand at the age of 50 years is 75 feet, the site index is 75.

**Slickensides.** Polished and grooved surfaces produced by one mass sliding past another. In soils, slickensides may occur at the bases of slip surfaces on the steeper slopes; on faces of blocks, prisms, and columns; and in swelling clayey soils, where there is marked change in moisture content.

**Slick spot.** A small area of soil having a puddled, crusted, or smooth surface and an excess of exchangeable sodium. The soil generally is silty or clayey, is slippery when wet, and is low in productivity.

**Slope.** The inclination of the land surface from the horizontal. Percentage of slope is the vertical distance divided by horizontal distance, then multiplied by 100. Thus, a slope of 20 percent is a drop of 20 feet in 100 feet of horizontal distance. In this survey the following slope classes are recognized:

|                        |                      |
|------------------------|----------------------|
| Nearly level.....      | 0 to 2 percent       |
| Gently sloping .....   | 2 to 8 percent       |
| Strongly sloping.....  | 8 to 15 percent      |
| Moderately steep ..... | 15 to 30 percent     |
| Steep.....             | 30 to 60 percent     |
| Very steep.....        | more than 60 percent |

**Slope** (in tables). Slope is great enough that special practices are required to ensure satisfactory performance of the soil for a specific use.

**Slow intake** (in tables). The slow movement of water into the soil.

**Slow refill** (in tables). The slow filling of ponds, resulting from restricted permeability in the soil.

**Small stones** (in tables). Rock fragments less than 3 inches (7.6 centimeters) in diameter. Small stones adversely affect the specified use of the soil.



**Sodicity.** The degree to which a soil is affected by exchangeable sodium. Sodicity is expressed as a sodium adsorption ratio (SAR) of a saturation extract, or the ratio of  $\text{Na}^+$  to  $\text{Ca}^{++} + \text{Mg}^{++}$ . The degrees of sodicity and their respective ratios are—

|               |                |
|---------------|----------------|
| Slight .....  | less than 13:1 |
| Moderate..... | 13-30:1        |
| Strong .....  | more than 30:1 |

**Sodic soil.** A soil having so high a degree of alkalinity (pH 8.5 or higher), or so high a percentage of exchangeable sodium (15 percent or more of the total exchangeable bases), or both, that plant growth is restricted.

**Soft bedrock.** Bedrock that can be excavated with trenching machines, backhoes, small rippers, and other equipment commonly used in construction.

**Soil.** A natural, three-dimensional body at the earth's surface. It is capable of supporting plants and has properties resulting from the integrated effect of climate and living matter acting on earthy parent material, as conditioned by relief over periods of time.

**Soil separates.** Mineral particles less than 2 millimeters in equivalent diameter and ranging between specified size limits. The names and sizes, in millimeters, of separates recognized in the United States are as follows:

|                        |                 |
|------------------------|-----------------|
| Very coarse sand ..... | 2.0 to 1.0      |
| Coarse sand .....      | 1.0 to 0.5      |
| Medium sand .....      | 0.5 to 0.25     |
| Fine sand .....        | 0.25 to 0.10    |
| Very fine sand .....   | 0.10 to 0.05    |
| Silt .....             | 0.05 to 0.002   |
| Clay .....             | less than 0.002 |

**Solum.** The upper part of a soil profile, above the C horizon, in which the processes of soil formation are active. The solum in soil consists of the A, E, and B horizons. Generally, the characteristics of the material in these horizons are unlike those of the underlying material. The living roots and plant and animal activities are largely confined to the solum.

**Stone line.** A concentration of coarse fragments in a soil. Generally, it is indicative of an old weathered surface. In a cross section, the line may be one fragment or more thick. It generally overlies material that weathered in place and is overlain by recent sediment of variable thickness.

**Stones.** Rock fragments 10 to 24 inches (25 to 60 centimeters) in diameter if rounded or 6 to 15 inches (15 to 38 centimeters) in length if flat.

**Stony.** Refers to a soil containing stones in numbers that interfere with or prevent tillage.

**Structure, soil.** The arrangement of primary soil particles into compound particles or aggregates. The principal forms of soil structure are—*platy* (laminated), *prismatic* (vertical axis of aggregates longer than horizontal), *columnar* (prisms with rounded tops), *blocky* (angular or subangular), and *granular*. *Structureless* soils are either *single grain* (each grain by itself, as in dune sand) or *massive* (the particles adhering without any regular cleavage, as in many hardpans).

**Stubble mulch.** Stubble or other crop residue left on the soil or partly worked into the soil. It protects the soil from wind and water erosion after harvest, during preparation of a seedbed for the next crop, and during the early growing period of the new crop.

**Subsoil.** Technically, the B horizon; roughly, the part of the solum below plow depth.

**Subsurface layer.** Technically, the E horizon. Generally refers to a leached horizon lighter in color and lower in content of organic matter than the overlying surface layer.

**Surface layer.** The soil ordinarily moved in tillage, or its equivalent in uncultivated soil, ranging in depth from 4 to 10 inches (10 to 25 centimeters). Frequently designated as the "plow layer," or the "Ap horizon."

**Talus.** Rock fragments of any size or shape, commonly coarse and angular, derived from and lying at the base of a cliff or very steep rock slope. The accumulated mass of such loose, broken rock formed chiefly by falling, rolling, or sliding.

**Taxadjuncts.** Soils that cannot be classified in a series recognized in the classification system. Such soils are named for a series they strongly resemble and are designated as taxadjuncts to that series because they differ in ways too small to be of consequence in interpreting their use and behavior.

**Tephra.** All clastic volcanic material that is ejected from a vent during an eruption and transported through the air. It includes volcanic ash, cinders, scoria, pumice, and blocks.

**Terrace.** An embankment, or ridge, constructed across sloping soils on the contour or at a slight angle to the contour. The terrace intercepts surface runoff so that water soaks into the soil or flows slowly to a prepared outlet. A terrace in a field generally is built so that the field can be farmed. A terrace intended mainly for drainage has a deep channel



that is maintained in permanent sod.

**Terrace** (geologic). An old alluvial plain, ordinarily flat or undulating, bordering a river, a lake, or the sea.

**Texture, soil.** The relative proportions of sand, silt, and clay particles in a mass of soil. The basic textural classes, in order of increasing proportion of fine particles, are *sand*, *loamy sand*, *sandy loam*, *loam*, *silt loam*, *silt*, *sandy clay loam*, *clay loam*, *silty clay loam*, *sandy clay*, *silty clay*, and *clay*. The sand, loamy sand, and sandy loam classes may be further divided by specifying "coarse," "fine," or "very fine."

**Thin layer** (in tables). Otherwise suitable soil material too thin for the specified use.

**Tilth.** The physical condition of the soil as related to tillage, seedbed preparation, seedling emergence, and root penetration.

**Toe slope.** The outermost inclined surface at the base of a hill; part of a foot slope.

**Topsoil.** The upper part of the soil, which is the most favorable material for plant growth. It is ordinarily rich in organic matter and is used to topdress roadbanks, lawns, and land affected by mining.

**Tuff.** A compacted deposit that is 50 percent or more volcanic ash and dust.

**Valley fill.** In glaciated regions, material deposited in stream valleys by glacial meltwater. In

nonglaciated regions, alluvium deposited by heavily loaded streams.

**Variant, soil.** A soil having properties sufficiently different from those of other known soils to justify a new series name, but occurring in such a limited geographic area that creation of a new series is not justified.

**Variegation.** Refers to patterns of contrasting colors assumed to be inherited from the parent material rather than to be the result of poor drainage.

**Weathering.** All physical and chemical changes produced in rocks or other deposits at or near the earth's surface by atmospheric agents. These changes result in disintegration and decomposition of the material.

**Well graded.** Refers to soil material consisting of coarse grained particles that are well distributed over a wide range in size or diameter. Such soil normally can be easily increased in density and bearing properties by compaction. Contrasts with poorly graded soil.

**Wilting point (or permanent wilting point).** The moisture content of soil, on an oven-dry basis, at which a plant (specifically a sunflower) wilts so much that it does not recover when placed in a humid, dark chamber.

# Tables

---



TABLE 1.--TEMPERATURE AND PRECIPITATION

(Recorded in the period 1951-81 at Hailey and Picabo, Idaho)

| Month        | Temperature                 |                             |           |  |   |  | Precipitation |                              |                |   |                     |
|--------------|-----------------------------|-----------------------------|-----------|--|---|--|---------------|------------------------------|----------------|---|---------------------|
|              | Average<br>daily<br>maximum | Average<br>daily<br>minimum | Average   | 2 years in<br>10 will have--               |   | Average<br>number of<br>growing<br>degree<br>days* | Average       | 2 years in 10<br>will have-- |                | Average<br>number of<br>days with<br>0.10 inch<br>or more | Average<br>snowfall |
|              |                             |                             |           | Maximum<br>temperature<br>higher<br>than-- | Minimum<br>temperature<br>lower<br>than-- |  |               | Less<br>than--               | More<br>than-- |   |                     |
|              | <u>°F</u>                   | <u>°F</u>                   | <u>°F</u> | <u>°F</u>                                  | <u>°F</u>                                 | <u>Units</u>                                       | <u>In</u>     | <u>In</u>                    | <u>In</u>      |   | <u>In</u>           |
| HAILEY:      |                             |                             |           |  |   |  |               |                              |                |   |                     |
| January----  | 30.8                        | 8.5                         | 19.7      | 48   | -20                                       | 0  | 2.63          | 0.97                         | 4.01           | 5   | 25.2                |
| February---- | 36.7                        | 13.4                        | 25.1      | 51   | -11                                       | 9  | 1.83          | .43                          | 2.93           | 4   | 14.1                |
| March-----   | 42.4                        | 19.1                        | 30.8      | 59   | -3  | 19   | 1.25          | .50                          | 1.87           | 4   | 7.9                 |
| April-----   | 53.9                        | 28.5                        | 41.2      | 74   | 12  | 124  | 1.11          | .39                          | 1.72           | 3   | 1.6                 |
| May-----     | 64.9                        | 36.6                        | 50.8      | 84   | 21  | 343  | 1.34          | .38                          | 2.10           | 4   | .6                  |
| June-----    | 74.3                        | 43.4                        | 58.9      | 92   | 27  | 567  | 1.47          | .26                          | 2.41           | 4   | .0                  |
| July-----    | 84.9                        | 49.3                        | 67.1      | 96   | 34  | 840  | .53           | .10                          | .86            | 2   | .0                  |
| August-----  | 83.5                        | 47.6                        | 65.6      | 95   | 31  | 794  | .79           | .06                          | 1.34           | 2   | .0                  |
| September--  | 73.6                        | 39.4                        | 56.5      | 90   | 22  | 495  | .87           | .15                          | 1.42           | 2   | .1                  |
| October----  | 61.4                        | 31.3                        | 46.4      | 81   | 13  | 221  | .77           | .14                          | 1.26           | 2   | 1.3                 |
| November---  | 44.6                        | 22.2                        | 33.4      | 65   | 1   | 12   | 1.62          | .40                          | 2.58           | 5   | 8.7                 |
| December---  | 33.2                        | 11.9                        | 22.6      | 52   | -16                                       | 0  | 2.37          | .65                          | 3.76           | 5   | 26.0                |
| Yearly:      |                             |                             |           |  |   |  |               |                              |                |   |                     |
| Average----  | 57.0                        | 29.3                        | 43.2      | ---  | ---                                       | ---  | ---           | ---                          | ---            | ---   | ---                 |
| Extreme----  | ---                         | ---                         | ---       | 96   | -24                                       | ---  | ---           | ---                          | ---            | ---   | ---                 |
| Total-----   | ---                         | ---                         | ---       | ---  | ---                                       | 3,424  | 16.58         | 13.09                        | 19.89          | 42  | 85.5                |
| PICABO:      |                             |                             |           |  |   |  |               |                              |                |   |                     |
| January----  | 30.2                        | 7.1                         | 18.7      | 46   | -22                                       | 0  | 2.03          | 0.91                         | 2.98           | 6   | 13.7                |
| February---- | 35.8                        | 10.8                        | 23.3      | 50   | -14                                       | 12   | 1.21          | .37                          | 1.90           | 4   | 7.2                 |
| March-----   | 43.0                        | 18.0                        | 30.5      | 64   | -3  | 44   | 1.14          | .52                          | 1.67           | 4   | 5.0                 |
| April-----   | 54.9                        | 27.1                        | 41.0      | 77   | 12  | 108  | .98           | .38                          | 1.48           | 4   | 1.9                 |
| May-----     | 65.9                        | 34.8                        | 50.4      | 85   | 19  | 322  | 1.11          | .31                          | 1.74           | 4   | .5                  |
| June-----    | 75.2                        | 42.1                        | 58.7      | 95   | 27  | 561  | 1.23          | .31                          | 1.97           | 3   | .0                  |
| July-----    | 86.5                        | 47.9                        | 67.2      | 97   | 33  | 843  | .25           | .02                          | .41            | 1   | .0                  |
| August-----  | 84.2                        | 45.9                        | 65.1      | 97   | 31  | 778  | .59           | .04                          | 1.01           | 2   | .0                  |
| September--  | 73.8                        | 37.6                        | 55.7      | 90   | 21  | 477  | .69           | .04                          | 1.17           | 2   | .0                  |
| October----  | 61.4                        | 28.2                        | 44.8      | 81   | 12  | 187  | .76           | .21                          | 1.20           | 2   | .4                  |
| November---  | 44.2                        | 20.3                        | 32.3      | 64   | 0   | 9  | 1.52          | .68                          | 2.25           | 5   | 5.6                 |
| December---  | 33.1                        | 11.0                        | 22.1      | 51   | -16                                       | 7  | 1.89          | .58                          | 2.95           | 5   | 12.8                |
| Yearly:      |                             |                             |           |  |   |  |               |                              |                |   |                     |
| Average----  | 57.4                        | 27.6                        | 42.5      | ---  | ---                                       | ---  | ---           | ---                          | ---            | ---   | ---                 |
| Extreme----  | ---                         | ---                         | ---       | 98   | -23                                       | ---  | ---           | ---                          | ---            | ---   | ---                 |
| Total-----   | ---                         | ---                         | ---       | ---  | ---                                       | 3,348  | 13.40         | 10.50                        | 16.13          | 42  | 47.1                |

\* A growing degree day is a unit of heat available for plant growth. It can be calculated by adding the maximum and minimum daily temperatures, dividing the sum by 2, and subtracting the temperature below which growth is minimal for the principal crops in the area (40 degrees F).

TABLE 2.--FREEZE DATES IN SPRING AND FALL  
(Recorded in the period 1951-81 at Hailey and Picabo, Idaho)

| Probability                          | Temperature       |                   |                   |
|--------------------------------------|-------------------|-------------------|-------------------|
|                                      | 24° F<br>or lower | 28° F<br>or lower | 32° F<br>or lower |
| HAILEY:                              |                   |                   |                   |
| Last freezing temperature in spring: |                   |                   |                   |
| 1 year in 10 later than--            | May 28            | June 6            | July 2            |
| 2 years in 10 later than--           | May 20            | May 31            | June 24           |
| 5 years in 10 later than--           | May 5             | May 18            | June 11           |
| First freezing temperature in fall:  |                   |                   |                   |
| 1 year in 10 earlier than--          | Sept. 20          | Aug. 31           | July 30           |
| 2 years in 10 earlier than--         | Sept. 26          | Sept. 8           | Aug. 11           |
| 5 years in 10 earlier than--         | Oct. 8            | Sept. 22          | Sept. 3           |
| PICABO:                              |                   |                   |                   |
| Last freezing temperature in spring: |                   |                   |                   |
| 1 year in 10 later than--            | May 21            | June 18           | July 1            |
| 2 years in 10 later than--           | May 16            | June 10           | June 25           |
| 5 years in 10 later than--           | May 7             | May 27            | June 14           |
| First freezing temperature in fall:  |                   |                   |                   |
| 1 year in 10 earlier than--          | Sept. 11          | Sept. 3           | July 28           |
| 2 years in 10 earlier than--         | Sept. 18          | Sept. 9           | Aug. 9            |
| 5 years in 10 earlier than--         | Oct. 1            | Sept. 22          | Aug. 31           |



TABLE 3.--GROWING SEASON

(Recorded in the period 1951-81 at Hailey and  
Picabo, Idaho)

| Probability   | Daily minimum temperature<br>during growing season |                         |                         |
|---------------|--|-------------------------|-------------------------|
|               | Higher<br>than<br>24° F                            | Higher<br>than<br>28° F | Higher<br>than<br>32° F |
|               | <u>Days</u>  | <u>Days</u>             | <u>Days</u>             |
| HAILEY:       |  |                         |                         |
| 9 years in 10 | 122  | 90                      | 39                      |
| 8 years in 10 | 133  | 102                     | 54                      |
| 5 years in 10 | 155  | 127                     | 83                      |
| 2 years in 10 | 176  | 151                     | 112                     |
| 1 year in 10  | 187  | 164                     | 128                     |
| PICABO:       |  |                         |                         |
| 9 years in 10 | 119  | 84                      | 36                      |
| 8 years in 10 | 128  | 95                      | 50                      |
| 5 years in 10 | 147  | 117                     | 78                      |
| 2 years in 10 | 165  | 139                     | 105                     |
| 1 year in 10  | 175  | 150                     | 120                     |

TABLE 4.--ACREAGE AND PROPORTIONATE EXTENT OF THE SOILS

| Map<br>symbol | Soil name   | Acres  | Percent |
|---------------|---|--------|---------|
| 1             | Adamson loam, 0 to 2 percent slopes-----  | 1,869  | 0.2     |
| 2             | Adios-Gooding-Bostrum complex, 4 to 20 percent slopes-----                        | 5,014  | 0.6     |
| 3             | Adios association, 8 to 25 percent slopes-----                                    | 4,009  | 0.5     |
| 4             | Balaam gravelly sandy loam, 0 to 2 percent slopes-----                            | 1,460  | 0.2     |
| 5             | Balaam very gravelly sandy loam, 2 to 4 percent slopes-----                       | 403    | *       |
| 6             | Balaam-Adamson complex, 0 to 2 percent slopes-----                                | 2,501  | 0.3     |
| 7             | Balaam-Adamson complex, cool, 0 to 2 percent slopes-----                          | 2,175  | 0.3     |
| 8             | Balaam-Adamson-Riverwash complex, 0 to 2 percent slopes-----                      | 10,707 | 1.3     |
| 9             | Bancroft silt loam, 1 to 4 percent slopes-----                                    | 1,606  | 0.2     |
| 10            | Bancroft silt loam, 4 to 8 percent slopes-----                                    | 6,562  | 0.8     |
| 11            | Bickett mucky peat, 0 to 2 percent slopes-----                                    | 1,256  | 0.2     |
| 12            | Blackspar-Rock outcrop complex, 45 to 75 percent slopes-----                      | 2,605  | 0.3     |
| 13            | Blackspot-Prudy association, 30 to 60 percent slopes-----                         | 3,903  | 0.5     |
| 14            | Bostrum-Yutrie-Hamrub complex, 2 to 12 percent slopes-----                        | 1,264  | 0.2     |
| 15            | Bringmee loam, 0 to 2 percent slopes-----   | 1,850  | 0.2     |
| 16            | Bringmee loam, 2 to 4 percent slopes-----   | 2,935  | 0.4     |
| 17            | Bringmee loam, 4 to 8 percent slopes-----   | 1,124  | 0.1     |
| 18            | Bringmee-Hutton complex, 1 to 4 percent slopes-----                               | 2,129  | 0.3     |
| 19            | Bringmee-Little Wood complex, 1 to 4 percent slopes-----                          | 1,576  | 0.2     |
| 20            | Bruneel loam, 0 to 2 percent slopes-----  | 3,393  | 0.4     |
| 21            | Carey Lake loam, 0 to 2 percent slopes-----                                       | 5,136  | 0.6     |
| 22            | Carey Lake loam, 2 to 4 percent slopes-----                                       | 1,853  | 0.2     |
| 23            | Cox-Rehfield-Rock outcrop complex, 2 to 15 percent slopes-----                    | 2,177  | 0.3     |
| 24            | Deerhorn-Rehfield-Rock outcrop complex, 2 to 15 percent slopes-----               | 15,599 | 1.9     |
| 25            | Deerhorn-Wildors complex, 2 to 8 percent slopes-----                              | 8,467  | 1.0     |
| 26            | Deerhorn-Wildors-Trevino complex, 2 to 15 percent slopes-----                     | 8,197  | 1.0     |
| 27            | Dollarhide-Rock outcrop complex, 60 to 75 percent slopes-----                     | 5,476  | 0.7     |
| 28            | Drage gravelly loam, 4 to 8 percent slopes-----                                   | 920    | 0.1     |
| 29            | Drage gravelly loam, 8 to 12 percent slopes-----                                  | 398    | *       |
| 30            | Drage gravelly loam, cool, 2 to 15 percent slopes-----                            | 9,939  | 1.2     |
| 31            | Drage very gravelly loam, cool, 0 to 3 percent slopes-----                        | 1,567  | 0.2     |
| 32            | Earcree-Lockman complex, 30 to 60 percent slopes-----                             | 1,840  | 0.2     |
| 33            | Earcree-Moonstone association, 8 to 30 percent slopes-----                        | 1,853  | 0.2     |
| 34            | Earcree-Moonstone association, 30 to 60 percent slopes-----                       | 11,706 | 1.4     |
| 35            | Elkcreek-Gaib complex, 30 to 60 percent slopes-----                               | 3,719  | 0.5     |
| 36            | Elkcreek-Polecreek complex, 4 to 30 percent slopes-----                           | 2,916  | 0.4     |
| 37            | Elksel-Friedman-Starhope complex, 30 to 60 percent slopes-----                    | 34,067 | 4.2     |
| 38            | Elksel-Peevywell-Furshur complex, 30 to 60 percent slopes-----                    | 13,496 | 1.7     |
| 39            | Elksel-Starhope-Rock outcrop complex, 30 to 60 percent slopes-----                | 24,218 | 3.0     |
| 40            | Friedman-Elksel-Winridge complex, 30 to 60 percent slopes-----                    | 55,656 | 6.9     |
| 41            | Gaib-Rock outcrop complex, 30 to 60 percent slopes-----                           | 6,055  | 0.7     |
| 42            | Gimlett very gravelly sandy loam, 0 to 2 percent slopes-----                      | 2,182  | 0.3     |
| 43            | Gooding-Gooding, eroded-Hamrub complex, 2 to 12 percent slopes-----               | 18,802 | 2.3     |
| 44            | Goodington silt loam, 2 to 4 percent slopes-----                                  | 1,392  | 0.2     |
| 45            | Goodington-Manard complex, 2 to 8 percent slopes-----                             | 3,872  | 0.5     |
| 46            | Hapur silt loam, 0 to 2 percent slopes-----                                       | 629    | 0.1     |
| 47            | Hapur-Bickett complex, 0 to 2 percent slopes-----                                 | 2,136  | 0.3     |
| 48            | Hapur-Picabo silt loams, 0 to 2 percent slopes-----                               | 2,553  | 0.3     |
| 49            | Hutton clay loam, 0 to 2 percent slopes-----                                      | 1,856  | 0.2     |
| 50            | Hutton Variant clay loam, 0 to 2 percent slopes-----                              | 798    | 0.1     |
| 51            | Isknat gravelly clay loam, 0 to 2 percent slopes-----                             | 1,395  | 0.2     |
| 52            | Justesen loam, 2 to 4 percent slopes-----   | 1,219  | 0.2     |
| 53            | Justesen loam, 4 to 8 percent slopes-----   | 970    | 0.1     |
| 54            | Justesen loam, 8 to 12 percent slopes-----  | 316    | *       |
| 55            | Justesen loam, 12 to 30 percent slopes-----                                       | 669    | 0.1     |
| 56            | Ketchum-Dollarhide complex, 30 to 60 percent slopes-----                          | 3,125  | 0.4     |
| 57            | Ketchum-Povey complex, 30 to 60 percent slopes-----                               | 21,843 | 2.7     |
| 58            | Laurentzen-Mulshoe complex, 4 to 30 percent slopes-----                           | 4,781  | 0.6     |
| 59            | Lava flows-----   | 64,790 | 8.1     |
| 60            | Lava flows-Cinderhurst complex, 2 to 15 percent slopes-----                       | 27,765 | 3.4     |
| 61            | Lavacreek-Dollarhide very gravelly silt loams, 30 to 60 percent slopes-----       | 4,342  | 0.5     |
| 62            | Lavacreek-Dollarhide very gravelly silt loams, cold, 15 to 60 percent slopes----- | 5,203  | 0.6     |

See footnote at end of table.



TABLE 4.--ACREAGE AND PROPORTIONATE EXTENT OF THE SOILS--Continued

| Map<br>symbol | Soil name  | Acres   | Percent |
|---------------|--|---------|---------|
| 63            | Lavacreek-Vitale association, 30 to 60 percent slopes-----         | 8,638   | 1.1     |
| 64            | Little Wood gravelly loam, 0 to 2 percent slopes-----              | 4,338   | 0.5     |
| 65            | Little Wood gravelly loam, 2 to 4 percent slopes-----              | 2,773   | 0.3     |
| 66            | Little Wood very gravelly loam, 0 to 2 percent slopes-----         | 6,474   | 0.8     |
| 67            | Little Wood very gravelly loam, 2 to 4 percent slopes-----         | 2,382   | 0.3     |
| 68            | Little Wood very gravelly loam, cool, 1 to 4 percent slopes-----   | 526     | 0.1     |
| 69            | Little Wood-Balaam complex, 0 to 2 percent slopes-----             | 1,210   | 0.1     |
| 70            | Manard silt loam, 1 to 4 percent slopes-----                       | 455     | 0.1     |
| 71            | Marshdale loam, 0 to 2 percent slopes-----                         | 1,282   | 0.2     |
| 72            | Marshdale-Bruneel loams, 0 to 2 percent slopes-----                | 4,798   | 0.6     |
| 73            | McBiggam silt loam, 2 to 8 percent slopes-----                     | 6,367   | 0.8     |
| 74            | McCarey-Justesen loams, 2 to 8 percent slopes-----                 | 3,063   | 0.4     |
| 75            | McCarey-Justesen-Rock outcrop complex, 2 to 15 percent slopes----- | 16,211  | 2.0     |
| 76            | McCarey-Molyneux loams, 2 to 8 percent slopes-----                 | 11,897  | 1.5     |
| 77            | McCarey-Pedleford complex, 2 to 30 percent slopes-----             | 2,309   | 0.3     |
| 78            | Molyneux loam, 2 to 4 percent slopes-----                          | 2,471   | 0.3     |
| 79            | Molyneux loam, 4 to 8 percent slopes-----                          | 825     | 0.1     |
| 80            | Molyneux loam, cool, 2 to 15 percent slopes-----                   | 3,861   | 0.5     |
| 81            | Moonstone-Bauscher complex, 8 to 30 percent slopes-----            | 5,913   | 0.7     |
| 82            | Moonstone-Earcree association, 30 to 60 percent slopes-----        | 20,850  | 2.6     |
| 83            | Muldoon-Peevywell loams, 2 to 15 percent slopes-----               | 11,003  | 1.4     |
| 84            | Mulshoe-Gaib-Rock outcrop complex, 4 to 30 percent slopes-----     | 8,499   | 1.1     |
| 85            | Mulshoe-Gaib-Winu complex, 30 to 60 percent slopes-----            | 9,643   | 1.2     |
| 86            | Pagari-Rehfield complex, 2 to 15 percent slopes-----               | 1,890   | 0.2     |
| 87            | Peevywell-Simonton loams, 2 to 8 percent slopes-----               | 1,921   | 0.2     |
| 88            | Peevywell-Simonton complex, 8 to 30 percent slopes-----            | 6,879   | 0.9     |
| 89            | Picabo silt loam, 0 to 2 percent slopes-----                       | 7,898   | 1.0     |
| 90            | Picabo gravelly loam, 0 to 2 percent slopes-----                   | 415     | 0.1     |
| 91            | Pits, gravel-----  | 214     | *       |
| 92            | Povey-Dollarhide complex, 30 to 60 percent slopes-----             | 8,585   | 1.1     |
| 93            | Povey-Rock outcrop complex, 30 to 60 percent slopes-----           | 2,595   | 0.3     |
| 94            | Povey association, cold, 15 to 60 percent slopes-----              | 6,999   | 0.9     |
| 95            | Povey-Vitale association, 30 to 60 percent slopes-----             | 43,442  | 5.4     |
| 96            | Rehfield-Gooding complex, 2 to 15 percent slopes-----              | 4,438   | 0.5     |
| 97            | Riverwash-----   | 846     | 0.1     |
| 98            | Rock outcrop-Adios complex, 25 to 60 percent slopes-----           | 936     | 0.1     |
| 99            | Rockybar extremely cobbly loam, 2 to 30 percent slopes-----        | 3,832   | 0.5     |
| 100           | Rubbleland-----  | 933     | 0.1     |
| 101           | Rubbleland-Milligan complex, 60 to 75 percent slopes-----          | 5,480   | 0.7     |
| 102           | Simonton loam, 2 to 4 percent slopes-----                          | 1,686   | 0.2     |
| 103           | Simonton loam, 4 to 8 percent slopes-----                          | 714     | 0.1     |
| 104           | Simonton-Bauscher complex, 4 to 15 percent slopes-----             | 2,712   | 0.3     |
| 105           | Starhope-Furshur complex, 4 to 15 percent slopes-----              | 1,008   | 0.1     |
| 106           | Starhope-Peevywell-Smelter loams, 4 to 30 percent slopes-----      | 17,182  | 2.1     |
| 107           | Vitale-Blackspar complex, 30 to 60 percent slopes-----             | 27,127  | 3.4     |
| 108           | Vitale-Milligan complex, 30 to 60 percent slopes-----              | 24,023  | 3.0     |
| 109           | Vitale-Povey association, 30 to 60 percent slopes-----             | 44,219  | 5.5     |
| 110           | Winu-Rock outcrop complex, 30 to 60 percent slopes-----            | 1,609   | 0.2     |
| 111           | Winu-Gaib association, 30 to 60 percent slopes-----                | 6,583   | 0.8     |
|               | Water-----   | 3,341   | 0.4     |
|               | Total-----   | 807,529 | 100.0   |

\* Less than 0.1 percent.

TABLE 5.--YIELDS PER ACRE OF CROPS AND PASTURE

(Yields in the N columns are for nonirrigated soils; those in the I columns are for irrigated soils. Yields are those that can be expected under a high level of management. Absence of a yield indicates that the soil is not suited to the crop or the crop generally is not grown on the soil. Only the soils suitable for crops and pasture are listed)

| Soil name and<br>map symbol     | Wheat |     | Barley |     | Oats |     | Alfalfa hay |      | Grass hay |      | Pasture |      |
|---------------------------------|-------|-----|--------|-----|------|-----|-------------|------|-----------|------|---------|------|
|                                 | N     | I   | N      | I   | N    | I   | N           | I    | N         | I    | N       | I    |
|                                 | Bu    | Bu  | Bu     | Bu  | Bu   | Bu  | Tons        | Tons | Tons      | Tons | AUM*    | AUM* |
| 1-----<br>Adamson               | 20    | 60  | 20     | 60  | ---  | 55  | ---         | 4.5  | ---       | ---  | ---     | 11.0 |
| 4-----<br>Balaam                | ---   | 55  | ---    | 65  | ---  | 50  | ---         | 4.0  | ---       | ---  | ---     | 8.0  |
| 5-----<br>Balaam                | ---   | 50  | ---    | 60  | ---  | 45  | ---         | 3.5  | ---       | ---  | ---     | 7.0  |
| 6-----<br>Balaam-Adamson        | ---   | 54  | ---    | 60  | ---  | 49  | ---         | 3.9  | ---       | ---  | ---     | 8.0  |
| 7-----<br>Balaam-Adamson        | ---   | --- | ---    | --- | ---  | --- | ---         | 3.7  | ---       | ---  | ---     | 9.0  |
| 9, 10-----<br>Bancroft          | 25    | 65  | 25     | 75  | ---  | 60  | ---         | 5.0  | ---       | ---  | ---     | 12.0 |
| 11-----<br>Bickett              | ---   | --- | ---    | --- | ---  | --- | ---         | ---  | ---       | ---  | 6.0     | ---  |
| 15-----<br>Bringmee             | 20    | 60  | 25     | 70  | ---  | 55  | ---         | 4.5  | ---       | ---  | ---     | 11.0 |
| 16-----<br>Bringmee             | 20    | 60  | 25     | 70  | ---  | 55  | ---         | 4.5  | ---       | ---  | ---     | 11.0 |
| 17-----<br>Bringmee             | 15    | 60  | 20     | 70  | ---  | 50  | ---         | 4.5  | ---       | ---  | ---     | 11.0 |
| 18-----<br>Bringmee-Hutton      | ---   | --- | 27     | --- | ---  | --- | 2.5         | ---  | 2.0       | ---  | 6.0     | ---  |
| 19-----<br>Bringmee-Little Wood | ---   | 56  | ---    | 63  | ---  | 66  | ---         | 4.0  | ---       | ---  | ---     | 10.0 |
| 20-----<br>Bruneel              | ---   | --- | ---    | --- | ---  | --- | ---         | ---  | 3.5       | ---  | 8.0     | ---  |
| 21-----<br>Carey Lake           | 25    | 70  | 25     | 75  | ---  | 60  | ---         | 5.0  | ---       | ---  | ---     | 12.0 |
| 22-----<br>Carey Lake           | 25    | 70  | 25     | 75  | ---  | 60  | ---         | 5.0  | ---       | ---  | ---     | 12.0 |
| 28-----<br>Drage                | ---   | 60  | ---    | 70  | ---  | 60  | ---         | 4.5  | ---       | ---  | ---     | 11.0 |
| 29-----<br>Drage                | ---   | 40  | ---    | 45  | ---  | 50  | ---         | 3.5  | ---       | ---  | ---     | 9.0  |
| 30-----<br>Drage                | ---   | --- | ---    | --- | ---  | --- | ---         | 3.0  | ---       | ---  | ---     | 7.5  |

See footnote at end of table.



TABLE 5.--YIELDS PER ACRE OF CROPS AND PASTURE--Continued

| Soil name and<br>map symbol   | Wheat   |         | Barley  |         | Oats    |         | Alfalfa hay |           | Grass hay |           | Pasture   |           |
|-------------------------------|---------|---------|---------|---------|---------|---------|-------------|-----------|-----------|-----------|-----------|-----------|
|                               | N<br>Bu | I<br>Bu | N<br>Bu | I<br>Bu | N<br>Bu | I<br>Bu | N<br>Tons   | I<br>Tons | N<br>Tons | I<br>Tons | N<br>AUM* | I<br>AUM* |
| 31-----<br>Drage              | ---     | ---     | ---     | ---     | ---     | ---     | ---         | 3.0       | ---       | ---       | ---       | 7.5       |
| 42-----<br>Gimlett            | 15      | 50      | 20      | 55      | ---     | 50      | ---         | 4.0       | ---       | ---       | ---       | 11.0      |
| 44-----<br>Goodington         | 20      | 65      | 25      | 75      | ---     | 60      | ---         | 4.5       | ---       | ---       | ---       | 11.0      |
| 45-----<br>Goodington-Manard  | ---     | ---     | ---     | ---     | ---     | ---     | ---         | 3.0       | ---       | ---       | ---       | 8.0       |
| 46-----<br>Hapur              | ---     | ---     | ---     | ---     | ---     | ---     | ---         | ---       | 3.0       | ---       | 8.0       | ---       |
| 47-----<br>Hapur-Bickett      | ---     | ---     | ---     | ---     | ---     | ---     | ---         | ---       | ---       | ---       | 8.0       | ---       |
| 48-----<br>Hapur-Picabo       | ---     | ---     | ---     | ---     | ---     | ---     | ---         | ---       | 2.8       | ---       | 9.0       | ---       |
| 49-----<br>Hutton             | 30      | ---     | 30      | ---     | 55      | ---     | ---         | ---       | 2.0       | ---       | 7.0       | ---       |
| 50-----<br>Hutton Variant     | 25      | 65      | 20      | 70      | ---     | 65      | ---         | 4.5       | ---       | ---       | ---       | 11.0      |
| 51-----<br>Isknat             | 15      | 60      | 20      | 70      | ---     | 60      | ---         | 5.0       | ---       | ---       | ---       | 11.0      |
| 52-----<br>Justesen           | 25      | 65      | 25      | 75      | ---     | 60      | ---         | 5.0       | ---       | ---       | ---       | 12.0      |
| 53-----<br>Justesen           | 15      | 50      | 20      | 70      | ---     | 55      | ---         | 5.0       | ---       | ---       | ---       | 12.0      |
| 54-----<br>Justesen           | 10      | 45      | 20      | 55      | ---     | 50      | ---         | 4.0       | ---       | ---       | ---       | 10.0      |
| 64, 65-----<br>Little Wood    | ---     | 60      | ---     | 60      | ---     | 90      | 2.0         | 5.0       | ---       | ---       | ---       | 16.0      |
| 66, 67-----<br>Little Wood    | ---     | 50      | ---     | 55      | ---     | 80      | 1.5         | 5.0       | ---       | ---       | ---       | 10.0      |
| 68-----<br>Little Wood        | ---     | ---     | ---     | ---     | ---     | ---     | ---         | 5.0       | ---       | ---       | ---       | 11.0      |
| 69-----<br>Little Wood-Balaam | ---     | 53      | ---     | 59      | ---     | 68      | ---         | 4.6       | ---       | ---       | ---       | 9.0       |
| 70-----<br>Manard             | 15      | 50      | 18      | 55      | ---     | 50      | 1.5         | 3.5       | ---       | ---       | 2.0       | 6.0       |
| 71-----<br>Marshdale          | ---     | ---     | ---     | ---     | ---     | ---     | ---         | ---       | 3.5       | ---       | 8.0       | ---       |
| 72-----<br>Marshdale-Bruneel  | ---     | ---     | ---     | ---     | ---     | ---     | ---         | ---       | 3.5       | ---       | 8.0       | ---       |

See footnote at end of table.

TABLE 5.--YIELDS PER ACRE OF CROPS AND PASTURE--Continued

| Soil name and<br>map symbol   | Wheat |    | Barley |    | Oats |     | Alfalfa hay |      | Grass hay |      | Pasture |      |
|-------------------------------|-------|----|--------|----|------|-----|-------------|------|-----------|------|---------|------|
|                               | N     | I  | N      | I  | N    | I   | N           | I    | N         | I    | N       | I    |
|                               | Bu    | Bu | Bu     | Bu | Bu   | Bu  | Tons        | Tons | Tons      | Tons | AUM*    | AUM* |
| 73-----<br>McBiggam           | 20    | 65 | 25     | 75 | ---  | --- | 1.5         | 4.5  | ---       | ---  | ---     | 11.0 |
| 74-----<br>McCarey-Justesen   | 18    | 50 | 20     | 67 | ---  | --- | ---         | 3.0  | ---       | ---  | ---     | 9.0  |
| 76-----<br>McCarey-Molyneux   | 20    | 50 | 20     | 63 | ---  | --- | ---         | 2.6  | ---       | ---  | ---     | 9.0  |
| 78-----<br>Molyneux           | 25    | 65 | 25     | 75 | ---  | 60  | ---         | 5.0  | ---       | ---  | ---     | 12.0 |
| 79-----<br>Molyneux           | 20    | 65 | 25     | 75 | ---  | 60  | ---         | 5.0  | ---       | ---  | ---     | 12.0 |
| 80-----<br>Molyneux           | 20    | 50 | 20     | 60 | ---  | 45  | ---         | 4.0  | ---       | ---  | ---     | 12.0 |
| 87-----<br>Peevywell-Simonton | 20    | 55 | 26     | 64 | ---  | 55  | ---         | 3.6  | ---       | ---  | ---     | 9.0  |
| 89, 90-----<br>Picabo         | 40    | 65 | 50     | 80 | 40   | 60  | ---         | ---  | 2.5       | 4.0  | 12.0    | ---  |
| 102, 103-----<br>Simonton     | 30    | 60 | 40     | 75 | 30   | 60  | 2.0         | 3.7  | ---       | ---  | 3.0     | 12.0 |

\* Animal-unit-month: The amount of forage or feed required to feed one animal unit (one cow, one horse, one mule, five sheep, or five goats) for 30 days.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES

(Only the soils that support rangeland vegetation suitable for grazing are listed)

| Soil name and<br>map symbol | Range site   | Total production                   |                          | Characteristic vegetation  | Compo-<br>sition                                  |
|-----------------------------|--|------------------------------------|--------------------------|--|---|
|                             |  | Kind of year                       | Dry<br>weight<br>Lb/acre |  |   |
| 2*:<br>Adios-----           | 01lay002i, Shallow Loamy 8-12"<br>Ppt, Artrw/agsp. | Favorable<br>Normal<br>Unfavorable | 650<br>550<br>300        | Wyoming big sagebrush-----<br>Bluebunch wheatgrass-----<br>Thurber needlegrass-----<br>Bottlebrush squirreltail-----<br>Sandberg bluegrass-----<br>Phlox-----<br>Tapertip hawksbeard-----<br>Lupine-----<br>Rabbitbrush-----                             | 25<br>15<br>15<br>5<br>5<br>5<br>5<br>5<br>5      |
| Gooding-----                | 010ay026i, Loamy 11-13" Ppt,<br>Artrw/agsp.        | Favorable<br>Normal<br>Unfavorable | 1,000<br>700<br>500      | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Arrowleaf balsamroot-----<br>Sandberg bluegrass-----<br>Idaho fescue-----<br>Thurber needlegrass-----<br>Bottlebrush squirreltail-----<br>Nevada bluegrass-----                               | 25<br>20<br>10<br>5<br>5<br>5<br>5<br>5           |
| Bostrum-----                | 010ay006i, Clayey 11-14" Ppt,<br>Arlo/agsp.        | Favorable<br>Normal<br>Unfavorable | 800<br>600<br>450        | Alkali sagebrush-----<br>Bluebunch wheatgrass-----<br>Sandberg bluegrass-----<br>Idaho fescue-----<br>Bottlebrush squirreltail-----<br>Thurber needlegrass-----<br>Hood phlox-----<br>Narrowleaf pussytoes-----  | 25<br>20<br>10<br>5<br>5<br>5<br>5<br>5           |
| 3*:<br>Adios-----           | 01lay002i, Shallow Loamy 8-12"<br>Ppt, Artrw/agsp. | Favorable<br>Normal<br>Unfavorable | 650<br>550<br>300        | Wyoming big sagebrush-----<br>Bluebunch wheatgrass-----<br>Thurber needlegrass-----<br>Bottlebrush squirreltail-----<br>Sandberg bluegrass-----<br>Phlox-----<br>Tapertip hawksbeard-----<br>Lupine-----<br>Rabbitbrush-----                             | 25<br>15<br>15<br>5<br>5<br>5<br>5<br>5<br>5      |
| Adios, cool-----            | 010ay025i, Loamy Slope 11-13"<br>Ppt, Artrw/agsp.  | Favorable<br>Normal<br>Unfavorable | 1,050<br>750<br>500      | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Lettermann needlegrass-----<br>Bottlebrush squirreltail-----<br>Sandberg bluegrass-----<br>Phlox-----<br>Tapertip hawksbeard-----<br>Lupine-----<br>Rabbitbrush-----<br>Nevada bluegrass----- | 25<br>15<br>10<br>5<br>5<br>5<br>5<br>5<br>5<br>5 |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site   | Total production                   |                          | Characteristic vegetation   | Compo-<br>sition                        |
|-----------------------------|--|------------------------------------|--------------------------|---|---|
|                             |  | Kind of year                       | Dry<br>weight<br>Lb/acre |   |   |
| 4, 5-----<br>Balaam         | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp.        | Favorable<br>Normal<br>Unfavorable | 900<br>750<br>650        | Basin big sagebrush-----<br>Bluebunch wheatgrass-----<br>Basin wildrye-----<br>Antelope bitterbrush-----<br>Thurber needlegrass-----<br>Indian ricegrass-----<br>Arrowleaf balsamroot-----<br>Lupine----- | 30<br>20<br>10<br>5<br>5<br>5<br>5<br>5 |
| 6*:<br>Balaam-----          | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp.        | Favorable<br>Normal<br>Unfavorable | 900<br>750<br>650        | Basin big sagebrush-----<br>Bluebunch wheatgrass-----<br>Basin wildrye-----<br>Antelope bitterbrush-----<br>Thurber needlegrass-----<br>Indian ricegrass-----<br>Arrowleaf balsamroot-----<br>Lupine----- | 30<br>20<br>10<br>5<br>5<br>5<br>5<br>5 |
| Adamson-----                | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp.        | Favorable<br>Normal<br>Unfavorable | 1,000<br>850<br>750      | Bluebunch wheatgrass-----<br>Basin big sagebrush-----<br>Basin wildrye-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush-----<br>Prairie junegrass-----<br>Thurber needlegrass-----               | 30<br>25<br>10<br>5<br>5<br>5<br>5      |
| 9, 10-----<br>Bancroft      | 010ay023i, Loamy 12-16" Ppt,<br>Artr4/feid.        | Favorable<br>Normal<br>Unfavorable | 1,000<br>800<br>550      | Idaho fescue-----<br>Threetip sagebrush-----<br>Bluebunch wheatgrass-----<br>Thurber needlegrass-----<br>Western wheatgrass-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush-----                | 25<br>25<br>10<br>10<br>5<br>5<br>5     |
| 11-----<br>Bickett          | 010ay027i, Wet Meadow-----                         | Favorable<br>Normal<br>Unfavorable | 4,000<br>3,500<br>3,000  | Tufted hairgrass-----<br>Nebraska sedge-----<br>Sedge-----<br>Rush-----<br>Common cattail-----<br>Willow-----   | 25<br>15<br>15<br>10<br>5<br>5          |
| 12*:<br>Blackspar-----      | 010ay007i, Shallow Stony 8-16"<br>Ppt, Arar8/agsp. | Favorable<br>Normal<br>Unfavorable | 400<br>250<br>200        | Low sagebrush-----<br>Sandberg bluegrass-----<br>Bluebunch wheatgrass-----<br>Bottlebrush squirreltail-----<br>Thurber needlegrass-----<br>Hood phlox-----  | 25<br>20<br>20<br>5<br>5<br>5           |
| Rock outcrop.               |  |                                    |                          |   |   |
| 13*:<br>Blackspot-----      | 012xy001i, Limy Gravelly 8-13"<br>Ppt, Ararn/agsp. | Favorable<br>Normal<br>Unfavorable | 700<br>500<br>400        | Black sagebrush-----<br>Bluebunch wheatgrass-----<br>Sandberg bluegrass-----<br>Bottlebrush squirreltail-----<br>Milkvetch-----<br>Low larkspur-----<br>Arrowleaf balsamroot-----                         | 30<br>25<br>10<br>5<br>5<br>5<br>5      |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site  | Total production |                          | Characteristic vegetation     | Compo-<br>sition |
|-----------------------------|---|------------------|--------------------------|-------------------------------|------------------|
|                             |   | Kind of year     | Dry<br>weight<br>Lb/acre |                               |                  |
| 13*:<br>Prudy-----          | 010ay014i, Steep Slope 16-20"<br>Ppt, Arva2/syor2/agsp. | Favorable        | 1,300                    | Mountain big sagebrush-----   | 30               |
|                             |   | Normal           | 1,100                    | Bluebunch wheatgrass-----     | 25               |
|                             |   | Unfavorable      | 900                      | Nevada bluegrass-----         | 10               |
|                             |   |                  |                          | Mountain snowberry-----       | 5                |
|                             |   |                  |                          | Idaho fescue-----             | 5                |
|                             |   |                  |                          | Arrowleaf balsamroot-----     | 5                |
|                             |   |                  |                          | Lupine-----                   | 5                |
| 14*:<br>Bostrum-----        | 010ay006i, Clayey 11-14" Ppt,<br>Arlo/agsp.             | Favorable        | 800                      | Alkali sagebrush-----         | 25               |
|                             |   | Normal           | 600                      | Bluebunch wheatgrass-----     | 20               |
|                             |   | Unfavorable      | 450                      | Sandberg bluegrass-----       | 10               |
|                             |   |                  |                          | Idaho fescue-----             | 5                |
|                             |   |                  |                          | Bottlebrush squirreltail----- | 5                |
|                             |   |                  |                          | Thurber needlegrass-----      | 5                |
|                             |   |                  |                          | Hood phlox-----               | 5                |
|                             |   |                  |                          | Narrowleaf pussytoes-----     | 5                |
| Yutru-----                  | 010ay006i, Clayey 11-14" Ppt,<br>Arlo/agsp.             | Favorable        | 550                      | Bluebunch wheatgrass-----     | 25               |
|                             |   | Normal           | 400                      | Alkali sagebrush-----         | 25               |
|                             |   | Unfavorable      | 300                      | Sandberg bluegrass-----       | 10               |
|                             |   |                  |                          | Phlox-----                    | 5                |
|                             |   |                  |                          | Bottlebrush squirreltail----- | 5                |
|                             |   |                  |                          | Narrowleaf pussytoes-----     | 5                |
|                             |   |                  |                          | Threetip sagebrush-----       | 5                |
| Hamrub-----                 | 010ay026i, Loamy 11-13" Ppt,<br>Artrw/agsp.             | Favorable        | 1,100                    | Bluebunch wheatgrass-----     | 30               |
|                             |   | Normal           | 950                      | Wyoming big sagebrush-----    | 25               |
|                             |   | Unfavorable      | 700                      | Sandberg bluegrass-----       | 5                |
|                             |   |                  |                          | Thurber needlegrass-----      | 5                |
|                             |   |                  |                          | Bottlebrush squirreltail----- | 5                |
|                             |   |                  |                          | Hood phlox-----               | 5                |
| 20-----<br>Bruneel          | 010ay028i, Semiwet Meadow-----                          | Favorable        | 4,000                    | Sedge-----                    | 20               |
|                             |   | Normal           | 2,250                    | Slender wheatgrass-----       | 15               |
|                             |   | Unfavorable      | 1,600                    | Tufted hairgrass-----         | 10               |
|                             |   |                  |                          | Basin wildrye-----            | 10               |
|                             |   |                  |                          | Spike trisetum-----           | 5                |
|                             |   |                  |                          | Rush-----                     | 5                |
|                             |   |                  |                          | Clover-----                   | 5                |
| 23*:<br>Cox-----            | 01lay003i, Shallow Fractured<br>8-12" Ppt, Artrt/agsp.  | Favorable        | 600                      | Bluebunch wheatgrass-----     | 25               |
|                             |   | Normal           | 450                      | Basin big sagebrush-----      | 25               |
|                             |   | Unfavorable      | 200                      | Sandberg bluegrass-----       | 10               |
|                             |   |                  |                          | Thurber needlegrass-----      | 10               |
|                             |   |                  |                          | Arrowleaf balsamroot-----     | 10               |
|                             |   |                  |                          | Lupine-----                   | 5                |
|                             |   |                  |                          | Tapertip hawksbeard-----      | 5                |
| Rehfield-----               | 01lay014i, Sand 8-12" Ppt,<br>Artrt/orhy/stco4.         | Favorable        | 800                      | Basin big sagebrush-----      | 25               |
|                             |   | Normal           | 650                      | Needleandthread-----          | 20               |
|                             |   | Unfavorable      | 450                      | Indian ricegrass-----         | 15               |
|                             |   |                  |                          | Bluebunch wheatgrass-----     | 5                |
|                             |   |                  |                          | Sandberg bluegrass-----       | 5                |
|                             |   |                  |                          | Bottlebrush squirreltail----- | 5                |
|                             |   |                  |                          | Tall gray rabbitbrush-----    | 5                |
|                             |   |                  |                          | Low larkspur-----             | 5                |
|                             |   |                  |                          | Thurber needlegrass-----      | 5                |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and map symbol | Range site                                       | Total production |                       | Characteristic vegetation     | Composition |
|--------------------------|--|------------------|-----------------------|-------------------------------|-------------|
|                          |  | Kind of year     | Dry weight<br>Lb/acre |                               |             |
| 23*:<br>Rock outcrop.    |  |                  |                       |                               |             |
| 24*:<br>Deerhorn-----    | O1lay009i, Loamy 8-12" Ppt,<br>Artrt/agsp.       | Favorable        | 1,000                 | Bluebunch wheatgrass-----     | 35          |
|                          |  | Normal           | 750                   | Basin big sagebrush-----      | 20          |
|                          |  | Unfavorable      | 600                   | Sandberg bluegrass-----       | 10          |
|                          |  |                  |                       | Arrowleaf balsamroot-----     | 5           |
|                          |  |                  |                       | Tapertip hawksbeard-----      | 5           |
| Rehfield-----            | O1lay009i, Loamy 8-12" Ppt,<br>Artrt/agsp.       | Favorable        | 1,100                 | Bluebunch wheatgrass-----     | 25          |
|                          |  | Normal           | 700                   | Basin big sagebrush-----      | 20          |
|                          |  | Unfavorable      | 500                   | Arrowleaf balsamroot-----     | 10          |
|                          |  |                  |                       | Thurber needlegrass-----      | 10          |
|                          |  |                  |                       | Indian ricegrass-----         | 5           |
|                          |  |                  |                       | Needleandthread-----          | 5           |
|                          |  |                  |                       | Sandberg bluegrass-----       | 5           |
|                          |  |                  |                       | Bottlebrush squirreltail----- | 5           |
|                          |  |                  |                       | Tall green rabbitbrush-----   | 5           |
|                          |  |                  |                       | Low larkspur-----             | 5           |
| Rock outcrop.            |  |                  |                       |                               |             |
| 25*:<br>Deerhorn-----    | O1lay009i, Loamy 8-12" Ppt,<br>Artrt/agsp.       | Favorable        | 1,000                 | Bluebunch wheatgrass-----     | 35          |
|                          |  | Normal           | 750                   | Basin big sagebrush-----      | 20          |
|                          |  | Unfavorable      | 600                   | Sandberg bluegrass-----       | 10          |
|                          |  |                  |                       | Arrowleaf balsamroot-----     | 5           |
|                          |  |                  |                       | Tapertip hawksbeard-----      | 5           |
| Wildors-----             | O1lay011i, Stony Loam 10-12"<br>Ppt, Artrt/agsp. | Favorable        | 750                   | Bluebunch wheatgrass-----     | 30          |
|                          |  | Normal           | 500                   | Basin big sagebrush-----      | 20          |
|                          |  | Unfavorable      | 250                   | Thurber needlegrass-----      | 10          |
|                          |  |                  |                       | Bottlebrush squirreltail----- | 5           |
|                          |  |                  |                       | Sandberg bluegrass-----       | 5           |
|                          |  |                  |                       | Tall gray rabbitbrush-----    | 5           |
|                          |  |                  |                       | Gray horsebrush-----          | 5           |
|                          |  |                  |                       | Lupine-----                   | 5           |
| 26*:<br>Deerhorn-----    | O1lay009i, Loamy 8-12" Ppt,<br>Artrt/agsp.       | Favorable        | 1,000                 | Bluebunch wheatgrass-----     | 35          |
|                          |  | Normal           | 750                   | Basin big sagebrush-----      | 20          |
|                          |  | Unfavorable      | 600                   | Sandberg bluegrass-----       | 10          |
|                          |  |                  |                       | Arrowleaf balsamroot-----     | 5           |
|                          |  |                  |                       | Tapertip hawksbeard-----      | 5           |
| Wildors-----             | O1lay011i, Stony Loam 10-12"<br>Ppt, Artrt/agsp. | Favorable        | 750                   | Bluebunch wheatgrass-----     | 30          |
|                          |  | Normal           | 500                   | Basin big sagebrush-----      | 20          |
|                          |  | Unfavorable      | 250                   | Thurber needlegrass-----      | 10          |
|                          |  |                  |                       | Bottlebrush squirreltail----- | 5           |
|                          |  |                  |                       | Sandberg bluegrass-----       | 5           |
|                          |  |                  |                       | Tall gray rabbitbrush-----    | 5           |
|                          |  |                  |                       | Gray horsebrush-----          | 5           |
|                          |  |                  |                       | Lupine-----                   | 5           |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site   | Total production                   |                          | Characteristic vegetation  | Compo-<br>sition                                      |
|-----------------------------|--|------------------------------------|--------------------------|--|---|
|                             |  | Kind of year                       | Dry<br>weight<br>Lb/acre |  |   |
| 26*:<br>Trevino-----        | 01lay002i, Shallow Loamy 8-12"<br>Ppt, Artrw/agsp.             | Favorable<br>Normal<br>Unfavorable | 600<br>400<br>250        | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Sandberg bluegrass-----<br>Thurber needlegrass-----<br>Arrowleaf balsamroot-----<br>Tapertip hawksbeard-----<br>Indian ricegrass-----<br>Bottlebrush squirreltail-----  | 25<br>15<br>10<br>10<br>5<br>5<br>5<br>5              |
| 27*:<br>Dollarhide-----     | 010ay010i, North Slope<br>Fractured 16-22" Ppt,<br>Arva2/feid. | Favorable<br>Normal<br>Unfavorable | 850<br>750<br>600        | Idaho fescue-----<br>Mountain big sagebrush-----<br>Mountain snowberry-----<br>Serviceberry-----<br>Common chokecherry-----<br>Prairie junegrass-----<br>Bluebunch wheatgrass-----<br>Rabbitbrush-----<br>Lupine-----<br>Tapertip hawksbeard-----<br>Arrowleaf balsamroot----- | 25<br>10<br>5<br>5<br>5<br>5<br>5<br>5<br>5<br>5<br>5 |
| Rock outcrop.               |  |                                    |                          |  |   |
| 28, 29-----<br>Drage        | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp.                    | Favorable<br>Normal<br>Unfavorable | 1,100<br>850<br>700      | Bluebunch wheatgrass-----<br>Basin big sagebrush-----<br>Basin wildrye-----<br>Antelope bitterbrush-----<br>Needlegrass-----<br>Nevada bluegrass-----<br>Sandberg bluegrass-----<br>Arrowleaf balsamroot-----  | 25<br>20<br>10<br>5<br>5<br>5<br>5<br>5               |
| 30-----<br>Drage            | 010ay005i, Gravelly Loam<br>12-16" Ppt, Arva2/feid.            | Favorable<br>Normal<br>Unfavorable | 1,050<br>800<br>550      | Mountain big sagebrush-----<br>Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Antelope bitterbrush-----<br>Needlegrass-----<br>Nevada bluegrass-----<br>Sandberg bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----   | 20<br>15<br>15<br>5<br>5<br>5<br>5<br>5<br>5          |
| 32*:<br>Earcree-----        | 010ay013i, North Slope Loamy<br>18-24" Ppt, Arva2/syor2/fei.   | Favorable<br>Normal<br>Unfavorable | 2,400<br>1,750<br>1,250  | Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Mountain snowberry-----<br>Mountain big sagebrush-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Antelope bitterbrush-----  | 25<br>15<br>15<br>10<br>5<br>5<br>5                   |
| Lockman.                    |  |                                    |                          |  |   |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site   | Total production |                          | Characteristic vegetation   | Compo-<br>sition |
|-----------------------------|--|------------------|--------------------------|-----------------------------|------------------|
|                             |  | Kind of year     | Dry<br>weight<br>Lb/acre |                             |                  |
| 33*:<br>Earcree-----        | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.        | Favorable        | 1,700                    | Idaho fescue-----           | 25               |
|                             |  | Normal           | 1,300                    | Mountain big sagebrush----- | 15               |
|                             |  | Unfavorable      | 900                      | Bluebunch wheatgrass-----   | 10               |
|                             |  |                  |                          | Nevada bluegrass-----       | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----   | 5                |
|                             |  |                  |                          | Lupine-----                 | 5                |
|                             |  |                  |                          | Antelope bitterbrush-----   | 5                |
|                             |  |                  |                          | Mountain snowberry-----     | 5                |
| Moonstone-----              | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.                    | Favorable        | 1,500                    | Bluebunch wheatgrass-----   | 30               |
|                             |  | Normal           | 1,000                    | Idaho fescue-----           | 15               |
|                             |  | Unfavorable      | 700                      | Sandberg bluegrass-----     | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----   | 5                |
|                             |  |                  |                          | Mountain big sagebrush----- | 5                |
|                             |  |                  |                          | Antelope bitterbrush-----   | 5                |
|                             |  |                  |                          | Nevada bluegrass-----       | 5                |
| 34*:<br>Earcree-----        | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.        | Favorable        | 1,700                    | Idaho fescue-----           | 25               |
|                             |  | Normal           | 1,300                    | Mountain big sagebrush----- | 15               |
|                             |  | Unfavorable      | 900                      | Bluebunch wheatgrass-----   | 10               |
|                             |  |                  |                          | Nevada bluegrass-----       | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----   | 5                |
|                             |  |                  |                          | Lupine-----                 | 5                |
|                             |  |                  |                          | Antelope bitterbrush-----   | 5                |
|                             |  |                  |                          | Mountain snowberry-----     | 5                |
| Moonstone-----              | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp.  | Favorable        | 1,100                    | Bluebunch wheatgrass-----   | 35               |
|                             |  | Normal           | 800                      | Mountain big sagebrush----- | 15               |
|                             |  | Unfavorable      | 450                      | Sandberg bluegrass-----     | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----   | 5                |
|                             |  |                  |                          | Antelope bitterbrush-----   | 5                |
|                             |  |                  |                          | Mountain snowberry-----     | 5                |
|                             |  |                  |                          | Basin wildrye-----          | 5                |
| 35*:<br>Elkcreek-----       | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp.  | Favorable        | 1,200                    | Bluebunch wheatgrass-----   | 45               |
|                             |  | Normal           | 900                      | Mountain big sagebrush----- | 15               |
|                             |  | Unfavorable      | 600                      | Thurber needlegrass-----    | 10               |
|                             |  |                  |                          | Idaho fescue-----           | 5                |
|                             |  |                  |                          | Sandberg bluegrass-----     | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----   | 5                |
|                             |  |                  |                          | Basin wildrye-----          | 5                |
|                             |  |                  |                          | Antelope bitterbrush-----   | 5                |
|                             |  |                  |                          | Tapertip hawksbeard-----    | 5                |
| Gaib-----                   | 010ay021i, South Slope<br>Fractured 12-16" Ppt,<br>Arva2/agsp. | Favorable        | 600                      | Mountain big sagebrush----- | 30               |
|                             |  | Normal           | 400                      | Bluebunch wheatgrass-----   | 20               |
|                             |  | Unfavorable      | 300                      | Sandberg bluegrass-----     | 10               |
|                             |  |                  |                          | Thurber needlegrass-----    | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----   | 5                |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site  | Total production                   |                          | Characteristic vegetation  | Compo-<br>sition                         |
|-----------------------------|---|------------------------------------|--------------------------|--|--|
|                             |   | Kind of year                       | Dry<br>weight<br>Lb/acre |  |  |
| 36*:<br>Elkcreek-----       | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.                   | Favorable<br>Normal<br>Unfavorable | 1,400<br>1,100<br>700    | Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Sandberg bluegrass-----<br>Arrowleaf balsamroot-----<br>Basin wildrye-----<br>Antelope bitterbrush-----<br>Tapertip hawksbeard----- | 35<br>20<br>15<br>10<br>5<br>5<br>5<br>5 |
| Polecreek-----              | 010ay001i, Stony Clay 12-16"<br>Ppt, Arlo/feid.               | Favorable<br>Normal<br>Unfavorable | 700<br>500<br>300        | Idaho fescue-----<br>Alkali sagebrush-----<br>Sandberg bluegrass-----<br>Bottlebrush squirreltail-----<br>Thurber needlegrass-----<br>Hood phlox-----  | 30<br>20<br>10<br>5<br>5<br>5            |
| 37*:<br>Elksel-----         | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 1,100<br>900<br>600      | Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Antelope bitterbrush-----<br>Sandberg bluegrass-----<br>Basin wildrye-----<br>Nevada bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----          | 25<br>25<br>5<br>5<br>5<br>5<br>5<br>5   |
| Friedman-----               | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.       | Favorable<br>Normal<br>Unfavorable | 1,700<br>1,300<br>900    | Idaho fescue-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Antelope bitterbrush-----<br>Mountain snowberry-----<br>Prairie junegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----          | 25<br>15<br>10<br>5<br>5<br>5<br>5<br>5  |
| Starhope-----               | 010ay018i, South Slope Clayey<br>12-16" Ppt, Arar8/agsp.      | Favorable<br>Normal<br>Unfavorable | 700<br>500<br>400        | Low sagebrush-----<br>Bluebunch wheatgrass-----<br>Bluegrass-----<br>Lupine-----<br>Sandberg bluegrass-----<br>Arrowleaf balsamroot-----   | 40<br>15<br>10<br>10<br>10<br>5          |
| 38*:<br>Elksel-----         | 010ay025i, Loamy Slope 11-13"<br>Ppt, Artrw/agsp.             | Favorable<br>Normal<br>Unfavorable | 1,000<br>800<br>600      | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Nevada bluegrass-----<br>Sandberg bluegrass-----<br>Bottlebrush squirreltail-----<br>Antelope bitterbrush-----<br>Lupine-----<br>Hood phlox-----          | 25<br>25<br>5<br>5<br>5<br>5<br>5<br>5   |
| Peevywell-----              | 010ay025i, Loamy Slope 11-13"<br>Ppt, Artrw/agsp.             | Favorable<br>Normal<br>Unfavorable | 1,000<br>800<br>600      | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Nevada bluegrass-----<br>Sandberg bluegrass-----<br>Bottlebrush squirreltail-----<br>Antelope bitterbrush-----<br>Lupine-----<br>Hood phlox-----          | 25<br>25<br>5<br>5<br>5<br>5<br>5<br>5   |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site  | Total production |               | Characteristic vegetation     | Compo-<br>sition |
|-----------------------------|---|------------------|---------------|-------------------------------|------------------|
|                             |   | Kind of year     | Dry<br>weight |                               |                  |
|                             |   |                  | Lb/acre       |                               | Pct              |
| 38*:<br>Furshur-----        | 010ay018i, South Slope Clayey<br>12-16" Ppt, Arar8/agsp.      | Favorable        | 700           | Low sagebrush-----            | 30               |
|                             |   | Normal           | 500           | Sandberg bluegrass-----       | 15               |
|                             |   | Unfavorable      | 400           | Bluebunch wheatgrass-----     | 10               |
|                             |   |                  |               | Alkali sagebrush-----         | 5                |
|                             |   |                  |               | Bottlebrush squirreltail----- | 5                |
|                             |   |                  |               | Hood phlox-----               | 5                |
|                             |   |                  |               | Longleaf phlox-----           | 5                |
|                             |   |                  |               | Eriogonum-----                | 5                |
|                             |   |                  |               | Dwarf green rabbitbrush-----  | 5                |
|                             |   |                  |               |                               |                  |
| 39*:<br>Elksel-----         | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable        | 1,100         | Mountain big sagebrush-----   | 25               |
|                             |   | Normal           | 900           | Bluebunch wheatgrass-----     | 25               |
|                             |   | Unfavorable      | 600           | Antelope bitterbrush-----     | 5                |
|                             |   |                  |               | Sandberg bluegrass-----       | 5                |
|                             |   |                  |               | Basin wildrye-----            | 5                |
|                             |   |                  |               | Nevada bluegrass-----         | 5                |
|                             |   |                  |               | Arrowleaf balsamroot-----     | 5                |
|                             |   |                  |               | Lupine-----                   | 5                |
|                             |   |                  |               |                               |                  |
|                             |   |                  |               |                               |                  |
| Starhope-----               | 010ay018i, South Slope Clayey<br>12-16" Ppt, Arar8/agsp.      | Favorable        | 700           | Low sagebrush-----            | 40               |
|                             |   | Normal           | 500           | Bluebunch wheatgrass-----     | 15               |
|                             |   | Unfavorable      | 400           | Bluegrass-----                | 10               |
|                             |   |                  |               | Lupine-----                   | 10               |
|                             |   |                  |               | Sandberg bluegrass-----       | 10               |
|                             |   |                  |               | Arrowleaf balsamroot-----     | 5                |
| Rock outcrop.               |   |                  |               |                               |                  |
| 40*:<br>Friedman-----       | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.       | Favorable        | 1,700         | Idaho fescue-----             | 25               |
|                             |   | Normal           | 1,300         | Mountain big sagebrush-----   | 15               |
|                             |   | Unfavorable      | 900           | Bluebunch wheatgrass-----     | 10               |
|                             |   |                  |               | Antelope bitterbrush-----     | 5                |
|                             |   |                  |               | Mountain snowberry-----       | 5                |
|                             |   |                  |               | Prairie junegrass-----        | 5                |
|                             |   |                  |               | Arrowleaf balsamroot-----     | 5                |
|                             |   |                  |               | Lupine-----                   | 5                |
| Elksel-----                 | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable        | 1,100         | Mountain big sagebrush-----   | 25               |
|                             |   | Normal           | 900           | Bluebunch wheatgrass-----     | 25               |
|                             |   | Unfavorable      | 600           | Antelope bitterbrush-----     | 5                |
|                             |   |                  |               | Sandberg bluegrass-----       | 5                |
|                             |   |                  |               | Basin wildrye-----            | 5                |
|                             |   |                  |               | Nevada bluegrass-----         | 5                |
|                             |   |                  |               | Arrowleaf balsamroot-----     | 5                |
|                             |   |                  |               | Lupine-----                   | 5                |
| Winridge-----               | 010ay012i, North Slope Clayey<br>16-20" Ppt, Arar8/feid.      | Favorable        | 900           | Low sagebrush-----            | 35               |
|                             |   | Normal           | 750           | Idaho fescue-----             | 20               |
|                             |   | Unfavorable      | 650           | Nevada bluegrass-----         | 10               |
|                             |   |                  |               | Hood phlox-----               | 5                |
|                             |   |                  |               | Wyeth eriogonum-----          | 5                |
|                             |   |                  |               | Bluebunch wheatgrass-----     | 5                |
|                             |   |                  |               | Arrowleaf balsamroot-----     | 5                |
|                             |   |                  |               | Bottlebrush squirreltail----- | 5                |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES---Continued

| Soil name and map symbol | Range site   | Total production                   |                       | Characteristic vegetation  | Composition                              |
|--------------------------|--|------------------------------------|-----------------------|--|--|
|                          |  | Kind of year                       | Dry weight<br>Lb/acre |  |  |
| 41*:<br>Gaib-----        | 010ay021i, South Slope<br>Fractured 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 600<br>400<br>300     | Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Sandberg bluegrass-----<br>Thurber needlegrass-----<br>Arrowleaf balsamroot-----   | 30<br>20<br>10<br>5<br>5                 |
| Rock outcrop.            |  |                                    |                       |  |  |
| 42-----<br>Gimlett       | 010ay005i, Gravelly Loam<br>12-16" Ppt, Arva2/feid.            | Favorable<br>Normal<br>Unfavorable | 1,000<br>750<br>550   | Mountain big sagebrush-----<br>Idaho fescue-----<br>Western needlegrass-----<br>Antelope bitterbrush-----<br>Arrowleaf balsamroot-----<br>Lupine-----  | 30<br>20<br>5<br>5<br>5<br>5             |
| 43*:<br>Gooding-----     | 010ay026i, Loamy 11-13" Ppt,<br>Artrw/agsp.                    | Favorable<br>Normal<br>Unfavorable | 1,000<br>700<br>500   | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Arrowleaf balsamroot-----<br>Sandberg bluegrass-----<br>Idaho fescue-----<br>Thurber needlegrass-----<br>Bottlebrush squirreltail-----<br>Nevada bluegrass----- | 25<br>20<br>10<br>5<br>5<br>5<br>5<br>5  |
| Gooding, eroded---       | 010ay006i, Clayey 11-14" Ppt,<br>Arlo/agsp.                    | Favorable<br>Normal<br>Unfavorable | 650<br>500<br>300     | Bluebunch wheatgrass-----<br>Alkali sagebrush-----<br>Sandberg bluegrass-----<br>Idaho fescue-----<br>Longleaf phlox-----<br>Lupine-----<br>Threetip sagebrush-----<br>Tall green rabbitbrush-----                         | 25<br>25<br>15<br>5<br>5<br>5<br>5<br>5  |
| Hamrub-----              | 010ay026i, Loamy 11-13" Ppt,<br>Artrw/agsp.                    | Favorable<br>Normal<br>Unfavorable | 1,100<br>950<br>700   | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Sandberg bluegrass-----<br>Thurber needlegrass-----<br>Bottlebrush squirreltail-----<br>Hood phlox-----   | 30<br>25<br>5<br>5<br>5<br>5             |
| 44-----<br>Goodington    | 010ay019i, Loamy 12-16" Ppt,<br>Arva2/agsp.                    | Favorable<br>Normal<br>Unfavorable | 1,200<br>1,000<br>700 | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Idaho fescue-----<br>Western needlegrass-----<br>Bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Bottlebrush squirreltail-----                   | 25<br>20<br>10<br>10<br>5<br>5<br>5<br>5 |
| 45*:<br>Goodington-----  | 010ay019i, Loamy 12-16" Ppt,<br>Arva2/agsp.                    | Favorable<br>Normal<br>Unfavorable | 1,200<br>1,000<br>700 | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Idaho fescue-----<br>Western needlegrass-----<br>Bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Bottlebrush squirreltail-----                   | 25<br>20<br>10<br>10<br>5<br>5<br>5<br>5 |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site                                      | Total production |                          | Characteristic vegetation     | Compo-<br>sition |
|-----------------------------|---|------------------|--------------------------|-------------------------------|------------------|
|                             |   | Kind of year     | Dry<br>weight<br>Lb/acre |                               | Pct              |
| 45*:<br>Manard-----         | 010ay001i, Stony Clay 12-16"<br>Ppt, Arlo/feid. | Favorable        | 550                      | Idaho fescue-----             | 25               |
|                             |   | Normal           | 450                      | Alkali sagebrush-----         | 25               |
|                             |   | Unfavorable      | 300                      | Narrowleaf pussytoes-----     | 10               |
|                             |   |                  |                          | Sandberg bluegrass-----       | 5                |
|                             |   |                  |                          | Bottlebrush squirreltail----- | 5                |
|                             |   |                  |                          | Western needlegrass-----      | 5                |
|                             |   |                  |                          | Hood phlox-----               | 5                |
| 46-----<br>Hapur            | 010ay027i, Wet Meadow-----                      | Favorable        | 4,000                    | Sedge-----                    | 20               |
|                             |   | Normal           | 2,800                    | Tufted hairgrass-----         | 15               |
|                             |   | Unfavorable      | 2,000                    | Nebraska sedge-----           | 15               |
|                             |   |                  |                          | Rush-----                     | 5                |
|                             |   |                  |                          | Basin wildrye-----            | 5                |
|                             |   |                  |                          | Cinquefoil-----               | 5                |
|                             |   |                  |                          | Groundsel-----                | 5                |
|                             |   |                  |                          | Shrubby cinquefoil-----       | 5                |
|                             |   |                  |                          | Willow-----                   | 5                |
|                             |   |                  |                          | Silver sagebrush-----         | 5                |
| 47*:<br>Hapur-----          | 010ay027i, Wet Meadow-----                      | Favorable        | 4,000                    | Sedge-----                    | 20               |
|                             |   | Normal           | 2,800                    | Tufted hairgrass-----         | 15               |
|                             |   | Unfavorable      | 2,000                    | Nebraska sedge-----           | 15               |
|                             |   |                  |                          | Rush-----                     | 5                |
|                             |   |                  |                          | Basin wildrye-----            | 5                |
|                             |   |                  |                          | Cinquefoil-----               | 5                |
|                             |   |                  |                          | Groundsel-----                | 5                |
|                             |   |                  |                          | Shrubby cinquefoil-----       | 5                |
|                             |   |                  |                          | Willow-----                   | 5                |
|                             |   |                  |                          | Silver sagebrush-----         | 5                |
| Bickett-----                | 010ay027i, Wet Meadow-----                      | Favorable        | 4,000                    | Tufted hairgrass-----         | 25               |
|                             |   | Normal           | 3,500                    | Nebraska sedge-----           | 15               |
|                             |   | Unfavorable      | 3,000                    | Sedge-----                    | 15               |
|                             |   |                  |                          | Rush-----                     | 10               |
|                             |   |                  |                          | Common cattail-----           | 5                |
|                             |   |                  |                          | Willow-----                   | 5                |
| 48*:<br>Hapur-----          | 010ay027i, Wet Meadow-----                      | Favorable        | 4,000                    | Sedge-----                    | 20               |
|                             |   | Normal           | 2,800                    | Tufted hairgrass-----         | 15               |
|                             |   | Unfavorable      | 2,000                    | Nebraska sedge-----           | 15               |
|                             |   |                  |                          | Rush-----                     | 5                |
|                             |   |                  |                          | Basin wildrye-----            | 5                |
|                             |   |                  |                          | Cinquefoil-----               | 5                |
|                             |   |                  |                          | Groundsel-----                | 5                |
|                             |   |                  |                          | Shrubby cinquefoil-----       | 5                |
|                             |   |                  |                          | Willow-----                   | 5                |
|                             |   |                  |                          | Silver sagebrush-----         | 5                |
| Picabo-----                 | 010ay028i, Semiwet Meadow-----                  | Favorable        | 2,600                    | Sedge-----                    | 20               |
|                             |   | Normal           | 2,100                    | Tufted hairgrass-----         | 15               |
|                             |   | Unfavorable      | 1,600                    | Basin wildrye-----            | 10               |
|                             |   |                  |                          | Shrubby cinquefoil-----       | 5                |
|                             |   |                  |                          | Rocky Mountain iris-----      | 5                |
|                             |   |                  |                          | Cinquefoil-----               | 5                |
|                             |   |                  |                          | Inland saltgrass-----         | 5                |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site  | Total production                   |                          | Characteristic vegetation  | Compo-<br>sition                                      |
|-----------------------------|---|------------------------------------|--------------------------|--|---|
|                             |   | Kind of year                       | Dry<br>weight<br>Lb/acre |  |   |
| 49-----<br>Hutton           | 010ay028i, Semiwet Meadow----                                     | Favorable<br>Normal<br>Unfavorable | 3,500<br>2,000<br>1,600  | Sedge-----<br>Tufted hairgrass-----<br>Slender wheatgrass-----<br>Basin wildrye-----<br>Mountain brome-----<br>Rush-----<br>Willow-----<br>Bluegrass-----<br>Shrubby cinquefoil-----   | 25<br>15<br>15<br>10<br>5<br>5<br>5<br>5<br>5         |
| 53, 54, 55-----<br>Justesen | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp.                       | Favorable<br>Normal<br>Unfavorable | 1,100<br>900<br>750      | Basin big sagebrush-----<br>Bluebunch wheatgrass-----<br>Basin wildrye-----<br>Thurber needlegrass-----<br>Nerved bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Bottlebrush squirreltail-----  | 25<br>25<br>10<br>5<br>5<br>5<br>5<br>5               |
| 56*:<br>Ketchum.            |   |                                    |                          |  |   |
| Dollarhide-----             | 010ay010i, North Slope<br>Fractured 16-22" Ppt,<br>Arva2/feid.    | Favorable<br>Normal<br>Unfavorable | 850<br>750<br>600        | Idaho fescue-----<br>Mountain big sagebrush-----<br>Mountain snowberry-----<br>Serviceberry-----<br>Common chokecherry-----<br>Prairie junegrass-----<br>Bluebunch wheatgrass-----<br>Rabbitbrush-----<br>Lupine-----<br>Tapertip hawksbeard-----<br>Arrowleaf balsamroot----- | 25<br>10<br>5<br>5<br>5<br>5<br>5<br>5<br>5<br>5<br>5 |
| 57*:<br>Ketchum.            |   |                                    |                          |  |   |
| Povey-----                  | 010ay013i, North Slope Loamy<br>18-24" Ppt, Arva2/syor2/<br>fied. | Favorable<br>Normal<br>Unfavorable | 2,000<br>1,500<br>1,200  | Idaho fescue-----<br>Mountain snowberry-----<br>Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Common chokecherry-----<br>Prairie junegrass-----<br>Slender wheatgrass-----<br>Lupine-----<br>Arrowleaf balsamroot-----   | 20<br>15<br>15<br>10<br>5<br>5<br>5<br>5<br>5         |
| 58*:<br>Laurentzen-----     | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.                       | Favorable<br>Normal<br>Unfavorable | 1,400<br>1,100<br>700    | Bluebunch wheatgrass-----<br>Idaho fescue-----<br>Mountain big sagebrush-----<br>Sandberg bluegrass-----<br>Arrowleaf balsamroot-----<br>Thurber needlegrass-----<br>Antelope bitterbrush-----   | 25<br>20<br>15<br>10<br>5<br>5<br>5                   |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and map symbol                    | Range site  | Total production                   |                         | Characteristic vegetation   | Composition                             |
|---|---|------------------------------------|-------------------------|---|---|
|   |   | Kind of year                       | Dry weight<br>Lb/acre   |   | Pct                                     |
| 58*:<br>Mulshoe-----                        | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.               | Favorable<br>Normal<br>Unfavorable | 1,200<br>950<br>700     | Mountain big sagebrush-----<br>Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Antelope bitterbrush-----<br>Sandberg bluegrass-----<br>Basin wildrye-----<br>Arrowleaf balsamroot-----<br>Nevada bluegrass----- | 25<br>20<br>15<br>5<br>5<br>5<br>5<br>5 |
| 60*:<br>Lava flows.<br><br>Cinderhurst----- | 010ay020i, Mixed Shrubs 12-16"<br>Ppt, Arva2/pone3.       | Favorable<br>Normal<br>Unfavorable | 450<br>300<br>100       | Mountain big sagebrush-----<br>Antelope bitterbrush-----<br>Mountain snowberry-----<br>Common chokecherry-----<br>Penstemon-----<br>Wyeth eriogonum-----<br>Fernbush-----<br>Nevada bluegrass-----                | 55<br>5<br>5<br>5<br>5<br>5<br>5<br>5   |
| 61*:<br>Lavacreek-----                      | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.   | Favorable<br>Normal<br>Unfavorable | 1,400<br>1,200<br>1,000 | Idaho fescue-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Mountain snowberry-----<br>Common chokecherry-----<br>Prairie junegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----         | 20<br>15<br>15<br>5<br>5<br>5<br>5<br>5 |
| Dollarhide-----                             | 012xy025i, Shallow Subalpine<br>12-24" Ppt, Arart/feid.   | Favorable<br>Normal<br>Unfavorable | 650<br>400<br>175       | Idaho fescue-----<br>Hotsprings sagebrush-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Lupine-----   | 30<br>25<br>5<br>5<br>5                 |
| 62*:<br>Lavacreek-----                      | 012xy024i, Subalpine Slope<br>Loamy 20"+ Ppt, Artrs/feid. | Favorable<br>Normal<br>Unfavorable | 1,600<br>1,400<br>1,000 | Idaho fescue-----<br>Lupine-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Prairie junegrass-----  | 25<br>25<br>15<br>10<br>5               |
| Dollarhide-----                             | 012xy025i, Shallow Subalpine<br>12-24" Ppt, Artrt/feid.   | Favorable<br>Normal<br>Unfavorable | 650<br>400<br>175       | Idaho fescue-----<br>Hotsprings sagebrush-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Lupine-----   | 30<br>25<br>5<br>5<br>5                 |
| 63*:<br>Lavacreek-----                      | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.   | Favorable<br>Normal<br>Unfavorable | 1,400<br>1,200<br>1,000 | Idaho fescue-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Mountain snowberry-----<br>Common chokecherry-----<br>Prairie junegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----         | 20<br>15<br>15<br>5<br>5<br>5<br>5<br>5 |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site  | Total production                   |                          | Characteristic vegetation  | Compo-<br>sition                        |
|-----------------------------|---|------------------------------------|--------------------------|--|---|
|                             |   | Kind of year                       | Dry<br>weight<br>Lb/acre |  |   |
| 63*:<br>Vitale-----         | 010ay009i, South Slope<br>gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 1,100<br>800<br>450      | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Mountain snowberry-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush-----<br>Nevada bluegrass-----<br>Lupine-----<br>Basin wildrye-----          | 30<br>25<br>5<br>5<br>5<br>5<br>5<br>5  |
| 67-----<br>Little Wood      | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp.                   | Favorable<br>Normal<br>Unfavorable | 1,100<br>800<br>500      | Bluebunch wheatgrass-----<br>Basin big sagebrush-----<br>Basin wildrye-----<br>Sandberg bluegrass-----<br>Idaho fescue-----<br>Arrowleaf balsamroot-----<br>Mountain big sagebrush-----<br>Antelope bitterbrush----- | 20<br>20<br>10<br>5<br>5<br>5<br>5<br>5 |
| 68-----<br>Little Wood      | 010ay005i, Gravelly Loam<br>12-16" Ppt, Arva2/feid.           | Favorable<br>Normal<br>Unfavorable | 900<br>750<br>500        | Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Idaho fescue-----<br>Sandberg bluegrass-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush-----<br>Needlegrass-----<br>Nevada bluegrass-----      | 20<br>15<br>15<br>5<br>5<br>5<br>5<br>5 |
| 70-----<br>Manard           | 010ay017i, Clayey 12-16" Ppt,<br>Arlo/feid.                   | Favorable<br>Normal<br>Unfavorable | 750<br>600<br>300        | Alkali sagebrush-----<br>Idaho fescue-----<br>Nevada bluegrass-----<br>Narrowleaf pussytoes-----<br>Bottlebrush squirreltail-----<br>Western needlegrass-----<br>Hood phlox-----                                     | 25<br>20<br>10<br>10<br>5<br>5<br>5     |
| 71-----<br>Marshdale        | 010ay027i, Wet Meadow-----                                    | Favorable<br>Normal<br>Unfavorable | 4,500<br>3,600<br>3,000  | Sedge-----<br>Tufted hairgrass-----<br>Nebraska sedge-----<br>Slender wheatgrass-----<br>Rush-----<br>Willow-----<br>Bluegrass-----  | 30<br>15<br>15<br>10<br>5<br>5<br>5     |
| 72*:<br>Marshdale-----      | 010ay027i, Wet Meadow-----                                    | Favorable<br>Normal<br>Unfavorable | 4,500<br>3,600<br>3,000  | Sedge-----<br>Tufted hairgrass-----<br>Nebraska sedge-----<br>Slender wheatgrass-----<br>Rush-----<br>Willow-----<br>Bluegrass-----  | 30<br>15<br>15<br>10<br>5<br>5<br>5     |
| Bruneel-----                | 010ay028i, Semiwet Meadow-----                                | Favorable<br>Normal<br>Unfavorable | 4,000<br>2,250<br>1,600  | Sedge-----<br>Slender wheatgrass-----<br>Tufted hairgrass-----<br>Basin wildrye-----<br>Spike trisetum-----<br>Rush-----<br>Clover-----  | 20<br>15<br>10<br>10<br>5<br>5<br>5     |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site                                  | Total production                   |                          | Characteristic vegetation   | Compo-<br>sition                         |
|-----------------------------|---|------------------------------------|--------------------------|---|--|
|                             |   | Kind of year                       | Dry<br>weight<br>Lb/acre |   |  |
| 73-----<br>McBiggam         | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid. | Favorable<br>Normal<br>Unfavorable | 1,600<br>1,200<br>900    | Mountain big sagebrush-----<br>Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Arrowleaf balsamroot-----<br>Rabbitbrush-----<br>Eriogonum-----<br>Prairie junegrass-----<br>Lupine-----                     | 20<br>20<br>15<br>10<br>5<br>5<br>5<br>5 |
| 74*:<br>McCarey-----        | 011by011i, Loamy 12-16" Ppt,<br>Artr4/agsp. | Favorable<br>Normal<br>Unfavorable | 1,500<br>1,000<br>600    | Bluebunch wheatgrass-----<br>Threetip sagebrush-----<br>Nevada bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Antelope bitterbrush-----<br>Western wheatgrass-----<br>Prairie junegrass-----   | 25<br>25<br>5<br>5<br>5<br>5<br>5<br>5   |
| Justesen-----               | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp. | Favorable<br>Normal<br>Unfavorable | 1,100<br>900<br>750      | Basin big sagebrush-----<br>Bluebunch wheatgrass-----<br>Basin wildrye-----<br>Thurber needlegrass-----<br>Nerved bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Bottlebrush squirreltail----- | 25<br>25<br>10<br>5<br>5<br>5<br>5<br>5  |
| 75*:<br>McCarey-----        | 011by011i, Loamy 12-16" Ppt,<br>Artr4/agsp. | Favorable<br>Normal<br>Unfavorable | 1,500<br>1,000<br>600    | Bluebunch wheatgrass-----<br>Threetip sagebrush-----<br>Nevada bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Antelope bitterbrush-----<br>Western wheatgrass-----<br>Prairie junegrass-----   | 25<br>25<br>5<br>5<br>5<br>5<br>5<br>5   |
| Justesen-----               | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp. | Favorable<br>Normal<br>Unfavorable | 1,100<br>900<br>750      | Basin big sagebrush-----<br>Bluebunch wheatgrass-----<br>Basin wildrye-----<br>Thurber needlegrass-----<br>Nerved bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Bottlebrush squirreltail----- | 25<br>25<br>10<br>5<br>5<br>5<br>5<br>5  |
| Rock outcrop.               |   |                                    |                          |   |  |
| 76*:<br>McCarey-----        | 011by011i, Loamy 12-16" Ppt,<br>Artr4/agsp. | Favorable<br>Normal<br>Unfavorable | 1,500<br>1,000<br>600    | Bluebunch wheatgrass-----<br>Threetip sagebrush-----<br>Nevada bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Antelope bitterbrush-----<br>Western wheatgrass-----<br>Prairie junegrass-----   | 25<br>25<br>5<br>5<br>5<br>5<br>5<br>5   |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site                                  | Total production                   |                          | Characteristic vegetation  | Compo-<br>sition                                   |
|-----------------------------|---|------------------------------------|--------------------------|--|--|
|                             |   | Kind of year                       | Dry<br>weight<br>Lb/acre |  |  |
| 76*:<br>Molyneux-----       | 010ay023i, Loamy 12-16" Ppt,<br>Artr4/feid. | Favorable<br>Normal<br>Unfavorable | 1,050<br>800<br>550      | Idaho fescue-----<br>Threetip sagebrush-----<br>Bluebunch wheatgrass-----<br>Basin big sagebrush-----<br>Prairie junegrass-----<br>Basin wildrye-----<br>Lupine-----<br>Antelope bitterbrush-----  | 30<br>20<br>10<br>5<br>5<br>5<br>5<br>5            |
| 77*:<br>McCarey-----        | 010ay026i, Loamy 11-13" Ppt,<br>Artrw/agsp. | Favorable<br>Normal<br>Unfavorable | 1,500<br>1,000<br>600    | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Nevada bluegrass-----<br>Arrowleaf balsamroot-----<br>Lupine-----<br>Antelope bitterbrush-----<br>Western wheatgrass-----<br>Prairie junegrass-----   | 25<br>20<br>5<br>5<br>5<br>5<br>5<br>5             |
| Pedleford-----              | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp. | Favorable<br>Normal<br>Unfavorable | 1,100<br>800<br>600      | Bluebunch wheatgrass-----<br>Basin big sagebrush-----<br>Nevada bluegrass-----<br>Basin wildrye-----<br>Sandberg bluegrass-----<br>Prairie junegrass-----<br>Bottlebrush squirreltail-----<br>Lupine-----<br>Tall green rabbitbrush-----<br>Thurber needlegrass----- | 20<br>20<br>10<br>10<br>5<br>5<br>5<br>5<br>5<br>5 |
| 80-----<br>Molyneux         | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid. | Favorable<br>Normal<br>Unfavorable | 1,500<br>1,000<br>700    | Mountain big sagebrush-----<br>Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Prairie junegrass-----<br>Lupine-----<br>Needlegrass-----   | 25<br>20<br>20<br>5<br>5<br>5                      |
| 81*:<br>Moonstone-----      | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid. | Favorable<br>Normal<br>Unfavorable | 1,500<br>1,000<br>700    | Bluebunch wheatgrass-----<br>Idaho fescue-----<br>Sandberg bluegrass-----<br>Arrowleaf balsamroot-----<br>Mountain big sagebrush-----<br>Antelope bitterbrush-----<br>Nevada bluegrass-----  | 30<br>15<br>5<br>5<br>5<br>5<br>5                  |
| Bauscher-----               | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid. | Favorable<br>Normal<br>Unfavorable | 1,400<br>1,100<br>500    | Idaho fescue-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Sandberg bluegrass-----<br>Bottlebrush squirreltail-----<br>Bulbous oniongrass-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush-----                                       | 25<br>20<br>15<br>5<br>5<br>5<br>5<br>5            |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site  | Total production |                                 | Characteristic vegetation     | Compo-<br>sition |
|-----------------------------|---|------------------|---------------------------------|-------------------------------|------------------|
|                             |   | Kind of year     | Dry<br>weight<br><u>Lb/acre</u> |                               | <u>Pct</u>       |
| 82*:<br>Moonstone-----      | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable        | 1,100                           | Bluebunch wheatgrass-----     | 35               |
|                             |   | Normal           | 800                             | Mountain big sagebrush-----   | 15               |
|                             |   | Unfavorable      | 450                             | Sandberg bluegrass-----       | 5                |
|                             |   |                  |                                 | Arrowleaf balsamroot-----     | 5                |
|                             |   |                  |                                 | Antelope bitterbrush-----     | 5                |
|                             |   |                  |                                 | Mountain snowberry-----       | 5                |
|                             |   |                  |                                 | Basin wildrye-----            | 5                |
| Earcree-----                | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.       | Favorable        | 1,700                           | Idaho fescue-----             | 25               |
|                             |   | Normal           | 1,300                           | Mountain big sagebrush-----   | 15               |
|                             |   | Unfavorable      | 900                             | Bluebunch wheatgrass-----     | 10               |
|                             |   |                  |                                 | Nevada bluegrass-----         | 5                |
|                             |   |                  |                                 | Arrowleaf balsamroot-----     | 5                |
|                             |   |                  |                                 | Lupine-----                   | 5                |
|                             |   |                  |                                 | Antelope bitterbrush-----     | 5                |
|                             |   |                  |                                 | Mountain snowberry-----       | 5                |
| 83*:<br>Muldoon-----        | 010ay019i, Loamy 12-16" Ppt,<br>Arva2/agsp.                   | Favorable        | 1,200                           | Mountain big sagebrush-----   | 35               |
|                             |   | Normal           | 1,000                           | Bluebunch wheatgrass-----     | 30               |
|                             |   | Unfavorable      | 900                             | Bluegrass-----                | 10               |
|                             |   |                  |                                 | Idaho fescue-----             | 5                |
|                             |   |                  |                                 | Lupine-----                   | 5                |
|                             |   |                  |                                 | Arrowleaf balsamroot-----     | 5                |
| Peevywell-----              | 010ay017i, Clayey 12-16" Ppt,<br>Arlo/feid.                   | Favorable        | 800                             | Alkali sagebrush-----         | 25               |
|                             |   | Normal           | 650                             | Idaho fescue-----             | 25               |
|                             |   | Unfavorable      | 400                             | Bluebunch wheatgrass-----     | 10               |
|                             |   |                  |                                 | Low sagebrush-----            | 5                |
|                             |   |                  |                                 | Nevada bluegrass-----         | 5                |
|                             |   |                  |                                 | Bottlebrush squirreltail----- | 5                |
|                             |   |                  |                                 | Lupine-----                   | 5                |
|                             |   |                  |                                 | Phlox-----                    | 5                |
| 84*:<br>Mulshoe-----        | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.                   | Favorable        | 1,200                           | Mountain big sagebrush-----   | 25               |
|                             |   | Normal           | 950                             | Idaho fescue-----             | 20               |
|                             |   | Unfavorable      | 700                             | Bluebunch wheatgrass-----     | 15               |
|                             |   |                  |                                 | Antelope bitterbrush-----     | 5                |
|                             |   |                  |                                 | Sandberg bluegrass-----       | 5                |
|                             |   |                  |                                 | Basin wildrye-----            | 5                |
|                             |   |                  |                                 | Arrowleaf balsamroot-----     | 5                |
|                             |   |                  |                                 | Nevada bluegrass-----         | 5                |
| Gaib-----                   | 010ay007i, Shallow Stony 8-16"<br>Ppt, Arar8/agsp.            | Favorable        | 350                             | Low sagebrush-----            | 30               |
|                             |   | Normal           | 250                             | Bluebunch wheatgrass-----     | 20               |
|                             |   | Unfavorable      | 200                             | Sandberg bluegrass-----       | 10               |
|                             |   |                  |                                 | Thurber needlegrass-----      | 5                |
|                             |   |                  |                                 | Arrowleaf balsamroot-----     | 5                |
| Rock outcrop.               |   |                  |                                 |                               |                  |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site   | Total production |                          | Characteristic vegetation     | Compo-<br>sition |
|-----------------------------|--|------------------|--------------------------|-------------------------------|------------------|
|                             |  | Kind of year     | Dry<br>weight<br>Lb/acre |                               | Pct              |
| 85*:<br>Mulshoe-----        | 010ay019i, Loamy 12-16" Ppt,<br>Arva2/agsp.                    | Favorable        | 1,000                    | Bluebunch wheatgrass-----     | 30               |
|                             |  | Normal           | 800                      | Mountain big sagebrush-----   | 20               |
|                             |  | Unfavorable      | 600                      | Needlegrass-----              | 15               |
|                             |  |                  |                          | Antelope bitterbrush-----     | 5                |
|                             |  |                  |                          | Sandberg bluegrass-----       | 5                |
|                             |  |                  |                          | Basin wildrye-----            | 5                |
|                             |  |                  |                          | Lupine-----                   | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----     | 5                |
| Gaib-----                   | 010ay021i, South Slope<br>Fractured 12-16" Ppt,<br>Arva2/agsp. | Favorable        | 600                      | Mountain big sagebrush-----   | 30               |
|                             |  | Normal           | 400                      | Bluebunch wheatgrass-----     | 20               |
|                             |  | Unfavorable      | 300                      | Sandberg bluegrass-----       | 10               |
|                             |  |                  |                          | Thurber needlegrass-----      | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----     | 5                |
| Winu-----                   | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.        | Favorable        | 1,200                    | Mountain big sagebrush-----   | 25               |
|                             |  | Normal           | 1,000                    | Idaho fescue-----             | 20               |
|                             |  | Unfavorable      | 750                      | Bluebunch wheatgrass-----     | 10               |
|                             |  |                  |                          | Basin wildrye-----            | 5                |
|                             |  |                  |                          | Nevada bluegrass-----         | 5                |
|                             |  |                  |                          | Western wheatgrass-----       | 5                |
|                             |  |                  |                          | Antelope bitterbrush-----     | 5                |
|                             |  |                  |                          | Rabbitbrush-----              | 5                |
|                             |  |                  |                          | Arrowleaf balsamroot-----     | 5                |
| 86*:<br>Pagari-----         | 010ay022i, Loamy 12-16" Ppt,<br>Artrt/agsp.                    | Favorable        | 800                      | Basin big sagebrush-----      | 20               |
|                             |  | Normal           | 550                      | Bluebunch wheatgrass-----     | 20               |
|                             |  | Unfavorable      | 300                      | Basin wildrye-----            | 10               |
|                             |  |                  |                          | Antelope bitterbrush-----     | 5                |
|                             |  |                  |                          | Spiny horsebrush-----         | 5                |
|                             |  |                  |                          | Tall gray rabbitbrush-----    | 5                |
|                             |  |                  |                          | Thurber needlegrass-----      | 5                |
|                             |  |                  |                          | Western wheatgrass-----       | 5                |
|                             |  |                  |                          | Indian ricegrass-----         | 5                |
|                             |  |                  |                          | Sandberg bluegrass-----       | 5                |
|                             |  |                  |                          | Lupine-----                   | 5                |
|                             |  |                  |                          |                               |                  |
| Rehfield-----               | 01lay014i, Sand 8-12" Ppt,<br>Artrt/orhy/stco4.                | Favorable        | 800                      | Basin big sagebrush-----      | 25               |
|                             |  | Normal           | 650                      | Needleandthread-----          | 20               |
|                             |  | Unfavorable      | 450                      | Indian ricegrass-----         | 15               |
|                             |  |                  |                          | Bluebunch wheatgrass-----     | 5                |
|                             |  |                  |                          | Sandberg bluegrass-----       | 5                |
|                             |  |                  |                          | Bottlebrush squirreltail----- | 5                |
|                             |  |                  |                          | Tall gray rabbitbrush-----    | 5                |
|                             |  |                  |                          | Low larkspur-----             | 5                |
|                             |  |                  |                          | Thurber needlegrass-----      | 5                |
| 87*, 88*:<br>Peevywell----- | 010ay017i, Clayey 12-16" Ppt,<br>Arlo/feid.                    | Favorable        | 800                      | Alkali sagebrush-----         | 25               |
|                             |  | Normal           | 650                      | Idaho fescue-----             | 25               |
|                             |  | Unfavorable      | 400                      | Bluebunch wheatgrass-----     | 10               |
|                             |  |                  |                          | Low sagebrush-----            | 5                |
|                             |  |                  |                          | Nevada bluegrass-----         | 5                |
|                             |  |                  |                          | Bottlebrush squirreltail----- | 5                |
|                             |  |                  |                          | Lupine-----                   | 5                |
|                             |  |                  |                          | Phlox-----                    | 5                |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol                                       | Range site  | Total production |                          | Characteristic vegetation   | Compo-<br>sition |
|---|---|------------------|--------------------------|-----------------------------|------------------|
|   |   | Kind of year     | Dry<br>weight<br>Lb/acre |                             |                  |
| 87*, 88*:<br>Simonton-----  | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.                       | Favorable        | 1,300                    | Idaho fescue-----           | 25               |
|   |   | Normal           | 900                      | Bluebunch wheatgrass-----   | 25               |
|   |   | Unfavorable      | 700                      | Mountain big sagebrush----- | 20               |
|   |   |                  |                          | Arrowleaf balsamroot-----   | 5                |
|   |   |                  |                          | Lupine-----                 | 5                |
| 89, 90-----<br>Picabo   | 010ay028i, Semiwet Meadow-----                                    | Favorable        | 2,600                    | Sedge-----                  | 20               |
|   |   | Normal           | 2,100                    | Tufted hairgrass-----       | 15               |
|   |   | Unfavorable      | 1,600                    | Basin wildrye-----          | 10               |
|   |   |                  |                          | Shrubby cinquefoil-----     | 5                |
|   |   |                  |                          | Rocky Mountain iris-----    | 5                |
|   |   |                  |                          | Cinquefoil-----             | 5                |
|   |   |                  |                          | Inland saltgrass-----       | 5                |
| 92*:<br>Povey-----  | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.           | Favorable        | 1,200                    | Idaho fescue-----           | 30               |
|   |   | Normal           | 1,000                    | Mountain big sagebrush----- | 15               |
|   |   | Unfavorable      | 750                      | Bluebunch wheatgrass-----   | 10               |
|   |   |                  |                          | Mountain snowberry-----     | 5                |
|   |   |                  |                          | Sandberg bluegrass-----     | 5                |
|   |   |                  |                          | Lupine-----                 | 5                |
|   |   |                  |                          | Arrowleaf balsamroot-----   | 5                |
| Dollarhide-----   | 012xy025i, Shallow Subalpine<br>12-24" Ppt, Artrt/feid.           | Favorable        | 650                      | Idaho fescue-----           | 30               |
|   |   | Normal           | 400                      | Hotsprings sagebrush-----   | 25               |
|   |   | Unfavorable      | 175                      | Mountain big sagebrush----- | 5                |
|   |   |                  |                          | Bluebunch wheatgrass-----   | 5                |
|   |   |                  |                          | Lupine-----                 | 5                |
| 93*:<br>Povey-----  | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.           | Favorable        | 1,200                    | Idaho fescue-----           | 30               |
|   |   | Normal           | 1,000                    | Mountain big sagebrush----- | 15               |
|   |   | Unfavorable      | 750                      | Bluebunch wheatgrass-----   | 10               |
|   |   |                  |                          | Mountain snowberry-----     | 5                |
|   |   |                  |                          | Sandberg bluegrass-----     | 5                |
|   |   |                  |                          | Lupine-----                 | 5                |
|   |   |                  |                          | Arrowleaf balsamroot-----   | 5                |
| Rock outcrop.<br>94*:<br>Povey very<br>gravelly silt<br>loam----- | 010ay013i, North Slope Loamy<br>18-24" Ppt, Arva2/syor2/<br>fied. | Favorable        | 2,000                    | Idaho fescue-----           | 20               |
|   |   | Normal           | 1,500                    | Mountain snowberry-----     | 15               |
|   |   | Unfavorable      | 1,200                    | Bluebunch wheatgrass-----   | 15               |
|   |   |                  |                          | Mountain big sagebrush----- | 10               |
|   |   |                  |                          | Common chokecherry-----     | 5                |
|   |   |                  |                          | Prairie junegrass-----      | 5                |
|   |   |                  |                          | Slender wheatgrass-----     | 5                |
|   |   |                  |                          | Lupine-----                 | 5                |
|   |   |                  |                          | Arrowleaf balsamroot-----   | 5                |
|   |   |                  |                          |                             |                  |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol         | Range site  | Total production                   |                          | Characteristic vegetation   | Compo-<br>sition                                   |
|-------------------------------------|---|------------------------------------|--------------------------|---|--|
|                                     |   | Kind of year                       | Dry<br>weight<br>Lb/acre |   | Pct  |
| 94*:<br>Povey gravelly<br>loam----- | 010ay015i, South Slope Loamy<br>16-20" Ppt, Arva2/feid.       | Favorable<br>Normal<br>Unfavorable | 1,400<br>1,200<br>1,000  | Mountain big sagebrush-----<br>Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Mountain snowberry-----<br>Common chokecherry-----<br>Prairie junegrass-----<br>Slender wheatgrass-----<br>Lupine-----<br>Arrowleaf balsamroot-----  | 20<br>15<br>15<br>5<br>5<br>5<br>5<br>5<br>5       |
| 95*:<br>Povey-----                  | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.       | Favorable<br>Normal<br>Unfavorable | 1,200<br>1,000<br>750    | Idaho fescue-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Mountain snowberry-----<br>Sandberg bluegrass-----<br>Lupine-----<br>Arrowleaf balsamroot-----   | 30<br>15<br>10<br>5<br>5<br>5<br>5                 |
| Vitale-----                         | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 1,100<br>800<br>450      | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Mountain snowberry-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush-----<br>Nevada bluegrass-----<br>Lupine-----<br>Basin wildrye-----   | 30<br>25<br>5<br>5<br>5<br>5<br>5<br>5             |
| 96*:<br>Rehfield-----               | 01lay009i, Loamy 8-12" Ppt,<br>Artrt/agsp.                    | Favorable<br>Normal<br>Unfavorable | 1,100<br>700<br>500      | Bluebunch wheatgrass-----<br>Basin big sagebrush-----<br>Arrowleaf balsamroot-----<br>Thurber needlegrass-----<br>Indian ricegrass-----<br>Needleandthread-----<br>Sandberg bluegrass-----<br>Bottlebrush squirreltail-----<br>Tall green rabbitbrush-----<br>Low larkspur----- | 25<br>20<br>10<br>10<br>5<br>5<br>5<br>5<br>5<br>5 |
| Gooding-----                        | 010ay026i, Loamy 11-13" Ppt,<br>Artrw/agsp.                   | Favorable<br>Normal<br>Unfavorable | 1,000<br>700<br>500      | Bluebunch wheatgrass-----<br>Wyoming big sagebrush-----<br>Arrowleaf balsamroot-----<br>Sandberg bluegrass-----<br>Idaho fescue-----<br>Thurber needlegrass-----<br>Bottlebrush squirreltail-----<br>Nevada bluegrass-----  | 25<br>20<br>10<br>5<br>5<br>5<br>5<br>5            |
| 98*:<br>Rock outcrop.               |   |                                    |                          |   |  |
| Adios-----                          | 01lay002i, Shallow Loamy 8-12"<br>Ppt, Artrw/agsp.            | Favorable<br>Normal<br>Unfavorable | 650<br>550<br>300        | Wyoming big sagebrush-----<br>Bluebunch wheatgrass-----<br>Thurber needlegrass-----<br>Bottlebrush squirreltail-----<br>Sandberg bluegrass-----<br>Phlox-----<br>Tapertip hawksbeard-----<br>Lupine-----<br>Rabbitbrush-----  | 25<br>15<br>15<br>5<br>5<br>5<br>5<br>5<br>5       |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and map symbol | Range site  | Total production                   |                       | Characteristic vegetation  | Composition                                  |
|--------------------------|---|------------------------------------|-----------------------|--|--|
|                          |   | Kind of year                       | Dry weight<br>Lb/acre |  | Pct  |
| 99-----<br>Rockybar      | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 800<br>650<br>350     | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Arrowleaf balsamroot-----<br>Idaho fescue-----<br>Nevada bluegrass-----<br>Lupine-----<br>Tall green rabbitbrush-----<br>Low sagebrush-----                        | 35<br>20<br>10<br>5<br>5<br>5<br>5<br>5      |
| 101*:<br>Rubbleland.     |   |                                    |                       |  |  |
| Milligan-----            | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 1,000<br>700<br>450   | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Mountain snowberry-----<br>Common chokecherry-----<br>Antelope bitterbrush-----<br>Arrowleaf balsamroot-----<br>Nevada bluegrass-----<br>Basin wildrye-----        | 30<br>25<br>5<br>5<br>5<br>5<br>5<br>5       |
| 104*:<br>Simonton-----   | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.                   | Favorable<br>Normal<br>Unfavorable | 1,300<br>900<br>700   | Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Arrowleaf balsamroot-----<br>Lupine-----  | 25<br>25<br>20<br>5<br>5                     |
| Bauscher-----            | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.                   | Favorable<br>Normal<br>Unfavorable | 1,400<br>1,100<br>500 | Idaho fescue-----<br>Mountain big sagebrush-----<br>Bluebunch wheatgrass-----<br>Sandberg bluegrass-----<br>Bottlebrush squirreltail-----<br>Bulbous oniongrass-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush----- | 25<br>20<br>15<br>5<br>5<br>5<br>5<br>5      |
| 105*:<br>Starhope-----   | 010ay019i, Loamy 12-16" Ppt,<br>Arva2/agsp.                   | Favorable<br>Normal<br>Unfavorable | 1,200<br>1,000<br>700 | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Needlegrass-----<br>Bluegrass-----<br>Arrowleaf balsamroot-----<br>Idaho fescue-----<br>Lupine-----  | 30<br>20<br>15<br>10<br>5<br>5<br>5          |
| Furshur-----             | 010ay001i, Stony Clay 12-16"<br>Ppt, Arlo/feid.               | Favorable<br>Normal<br>Unfavorable | 800<br>600<br>450     | Idaho fescue-----<br>Alkali sagebrush-----<br>Bluebunch wheatgrass-----<br>Antelope bitterbrush-----<br>Bottlebrush squirreltail-----<br>Sandberg bluegrass-----<br>Hood phlox-----<br>Longleaf phlox-----<br>Eriogonum-----   | 25<br>20<br>10<br>5<br>5<br>5<br>5<br>5<br>5 |

See footnote at end of table.



TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and map symbol | Range site  | Total production                   |                       | Characteristic vegetation   | Composition                             |
|--------------------------|---|------------------------------------|-----------------------|---|---|
|                          |   | Kind of year                       | Dry weight<br>Lb/acre |   |   |
| 106*:<br>Starhope-----   | 010ay019i, Loamy 12-16" Ppt,<br>Arva2/agsp.                   | Favorable<br>Normal<br>Unfavorable | 1,200<br>1,000<br>700 | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Needlegrass-----<br>Bluegrass-----<br>Arrowleaf balsamroot-----<br>Idaho fescue-----<br>Lupine-----   | 30<br>20<br>15<br>10<br>5<br>5<br>5     |
| Peevywell-----           | 010ay017i, Clayey 12-16" Ppt,<br>Arlo/feid.                   | Favorable<br>Normal<br>Unfavorable | 800<br>650<br>400     | Alkali sagebrush-----<br>Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Low sagebrush-----<br>Nevada bluegrass-----<br>Bottlebrush squirreltail-----<br>Lupine-----<br>Phlox-----                                    | 25<br>25<br>10<br>5<br>5<br>5<br>5<br>5 |
| Smelter-----             | 010ay004i, Loamy 12-16" Ppt,<br>Arva2/feid.                   | Favorable<br>Normal<br>Unfavorable | 1,100<br>850<br>700   | Mountain big sagebrush-----<br>Idaho fescue-----<br>Bluebunch wheatgrass-----<br>Lupine-----<br>Basin wildrye-----<br>Arrowleaf balsamroot-----<br>Nevada bluegrass-----  | 25<br>25<br>20<br>5<br>5<br>5<br>5      |
| 107*:<br>Vitale-----     | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 1,100<br>800<br>450   | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Mountain snowberry-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush-----<br>Nevada bluegrass-----<br>Lupine-----<br>Basin wildrye-----             | 30<br>25<br>5<br>5<br>5<br>5<br>5<br>5  |
| Blackspar-----           | 010ay007i, Shallow Stony 8-16"<br>Ppt, Arar8/agsp.            | Favorable<br>Normal<br>Unfavorable | 400<br>250<br>200     | Low sagebrush-----<br>Sandberg bluegrass-----<br>Bluebunch wheatgrass-----<br>Bottlebrush squirreltail-----<br>Thurber needlegrass-----<br>Hood phlox-----  | 25<br>20<br>20<br>5<br>5<br>5           |
| 108*:<br>Vitale-----     | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 1,100<br>800<br>450   | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Mountain snowberry-----<br>Arrowleaf balsamroot-----<br>Antelope bitterbrush-----<br>Nevada bluegrass-----<br>Lupine-----<br>Basin wildrye-----             | 30<br>25<br>5<br>5<br>5<br>5<br>5<br>5  |
| Milligan-----            | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp. | Favorable<br>Normal<br>Unfavorable | 1,000<br>700<br>450   | Bluebunch wheatgrass-----<br>Mountain big sagebrush-----<br>Mountain snowberry-----<br>Common chokecherry-----<br>Antelope bitterbrush-----<br>Arrowleaf balsamroot-----<br>Nevada bluegrass-----<br>Basin wildrye----- | 30<br>25<br>5<br>5<br>5<br>5<br>5<br>5  |

See footnote at end of table.

TABLE 6.--RANGELAND PRODUCTIVITY AND CHARACTERISTIC PLANT COMMUNITIES--Continued

| Soil name and<br>map symbol | Range site   | Total production |                                 | Characteristic vegetation   | Compo-<br>sition |
|-----------------------------|--|------------------|---------------------------------|-----------------------------|------------------|
|                             |  | Kind of year     | Dry<br>weight<br><u>Lb/acre</u> |                             |                  |
| 109*:<br>Vitale-----        | 010ay009i, South Slope<br>Gravelly 12-16" Ppt,<br>Arva2/agsp.  | Favorable        | 1,100                           | Bluebunch wheatgrass-----   | 30               |
|                             |  | Normal           | 800                             | Mountain big sagebrush----- | 25               |
|                             |  | Unfavorable      | 450                             | Mountain snowberry-----     | 5                |
|                             |  |                  |                                 | Arrowleaf balsamroot-----   | 5                |
|                             |  |                  |                                 | Antelope bitterbrush-----   | 5                |
|                             |  |                  |                                 | Nevada bluegrass-----       | 5                |
|                             |  |                  |                                 | Lupine-----                 | 5                |
|                             |  |                  |                                 | Basin wildrye-----          | 5                |
| Povey-----                  | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.        | Favorable        | 1,200                           | Idaho fescue-----           | 30               |
|                             |  | Normal           | 1,000                           | Mountain big sagebrush----- | 15               |
|                             |  | Unfavorable      | 750                             | Bluebunch wheatgrass-----   | 10               |
|                             |  |                  |                                 | Mountain snowberry-----     | 5                |
|                             |  |                  |                                 | Sandberg bluegrass-----     | 5                |
|                             |  |                  |                                 | Lupine-----                 | 5                |
|                             |  |                  |                                 | Arrowleaf balsamroot-----   | 5                |
| 110*:<br>Winu-----          | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.        | Favorable        | 1,200                           | Mountain big sagebrush----- | 25               |
|                             |  | Normal           | 1,000                           | Idaho fescue-----           | 20               |
|                             |  | Unfavorable      | 750                             | Bluebunch wheatgrass-----   | 10               |
|                             |  |                  |                                 | Basin wildrye-----          | 5                |
|                             |  |                  |                                 | Nevada bluegrass-----       | 5                |
|                             |  |                  |                                 | Western wheatgrass-----     | 5                |
|                             |  |                  |                                 | Antelope bitterbrush-----   | 5                |
|                             |  |                  |                                 | Rabbitbrush-----            | 5                |
|                             |  |                  |                                 | Arrowleaf balsamroot-----   | 5                |
| Rock outcrop.               |  |                  |                                 |                             |                  |
| 111*:<br>Winu-----          | 010ay008i, North Slope Loamy<br>16-20" Ppt, Arva2/feid.        | Favorable        | 1,200                           | Mountain big sagebrush----- | 25               |
|                             |  | Normal           | 1,000                           | Idaho fescue-----           | 20               |
|                             |  | Unfavorable      | 750                             | Bluebunch wheatgrass-----   | 10               |
|                             |  |                  |                                 | Basin wildrye-----          | 5                |
|                             |  |                  |                                 | Nevada bluegrass-----       | 5                |
|                             |  |                  |                                 | Western wheatgrass-----     | 5                |
|                             |  |                  |                                 | Antelope bitterbrush-----   | 5                |
|                             |  |                  |                                 | Rabbitbrush-----            | 5                |
|                             |  |                  |                                 | Arrowleaf balsamroot-----   | 5                |
| Gaib-----                   | 010ay021i, South Slope<br>Fractured 12-16" Ppt,<br>Arva2/agsp. | Favorable        | 600                             | Mountain big sagebrush----- | 30               |
|                             |  | Normal           | 400                             | Bluebunch wheatgrass-----   | 20               |
|                             |  | Unfavorable      | 300                             | Sandberg bluegrass-----     | 10               |
|                             |  |                  |                                 | Thurber needlegrass-----    | 5                |
|                             |  |                  |                                 | Arrowleaf balsamroot-----   | 5                |

\* See description of the map unit for composition and behavior characteristics of the map unit.



TABLE 7.--WINDBREAKS AND ENVIRONMENTAL PLANTINGS

(The symbol < means less than; > means more than. Absence of an entry indicates that trees generally do not grow to the given height on that soil. Only the soils suitable for windbreaks and environmental plantings are listed)

| Soil name and map symbol    | Trees having predicted 20-year average height, in feet, of--                        |  |   |   |               |
|-----------------------------|---|--|---|---|---------------|
|                             | <8  | 8-15   | 16-25   | 26-35   | >35           |
| 1-----<br>Adamson           | Siberian peashrub   | Nanking cherry,<br>blue spruce.  | Rocky Mountain<br>juniper, golden<br>willow, Douglas<br>fir, mountainash,<br>Scotch pine. | Russian olive,<br>idahybrid poplar.                   | Black locust. |
| 4, 5-----<br>Balaam         | Siberian peashrub   | Black locust,<br>Nanking cherry.   | Rocky Mountain<br>juniper, golden<br>willow, Douglas<br>fir, Scotch pine.                 | Russian olive,<br>blue spruce,<br>idahybrid poplar.   | ---           |
| 7*:<br>Balaam-----          | European privet,<br>honeysuckle.  | Siberian peashrub,<br>lilac, Nanking<br>cherry, Rocky<br>Mountain juniper. | Golden willow,<br>Scotch pine,<br>Norway spruce,<br>blue spruce.                          | Russian olive,<br>idahybrid poplar.                   | ---           |
| Adamson-----                | European privet---  | Siberian peashrub,<br>lilac, Nanking<br>cherry, Rocky<br>Mountain juniper. | Golden willow,<br>Scotch pine,<br>Norway spruce,<br>honeysuckle, blue<br>spruce.          | Russian olive,<br>idahybrid poplar.                   | ---           |
| 8*:<br>Balaam-----          | Siberian peashrub   | Black locust,<br>Nanking cherry.   | Rocky Mountain<br>juniper, golden<br>willow, Douglas<br>fir, Scotch pine.                 | Russian olive,<br>blue spruce,<br>idahybrid poplar.   | ---           |
| Adamson-----                | Siberian peashrub   | Blue spruce,<br>Nanking cherry.  | Rocky Mountain<br>juniper, golden<br>willow, Douglas<br>fir, Scotch pine,<br>mountainash. | Russian olive,<br>idahybrid poplar.                   | Black locust. |
| Riverwash.                  |   |  |   |   |               |
| 9, 10-----<br>Bancroft      | Siberian peashrub,<br>Nanking cherry,<br>Peking<br>cotoneaster,<br>European privet. | Rocky Mountain<br>juniper.   | Scotch pine,<br>Norway spruce,<br>blue spruce.  | Russian olive,<br>golden willow,<br>idahybrid poplar. | ---           |
| 15, 16, 17-----<br>Bringmee | European privet,<br>honeysuckle.  | Siberian peashrub,<br>Nanking cherry,<br>Rocky Mountain<br>juniper, lilac. | Golden willow,<br>blue spruce,<br>Norway spruce,<br>Scotch pine.                          | Russian olive,<br>idahybrid poplar.                   | ---           |
| 18*:<br>Bringmee-----       | European privet,<br>honeysuckle.  | Siberian peashrub,<br>Nanking cherry,<br>Rocky Mountain<br>juniper, lilac. | Golden willow,<br>blue spruce,<br>Norway spruce,<br>Scotch pine.                          | Russian olive,<br>idahybrid poplar.                   | ---           |

See footnote at end of table.

TABLE 7.--WINDBREAKS AND ENVIRONMENTAL PLANTINGS--Continued

| Soil name and map symbol  | Trees having predicted 20-year average height, in feet, of-- |   |  |                                     |               |
|---------------------------|--|---|--|-------------------------------------|---------------|
|                           | <8   | 8-15  | 16-25  | 26-35                               | >35           |
| 18*:<br>Hutton-----       | Lilac, honeysuckle   | Siberian peashrub,<br>Nanking cherry.   | Golden willow,<br>Rocky Mountain<br>juniper, green<br>ash, Norway<br>spruce. | Idahybrid poplar                    | ---           |
| 19*:<br>Bringmee-----     | European privet,<br>honeysuckle.                             | Siberian peashrub,<br>Nanking cherry,<br>Rocky Mountain<br>juniper, lilac.      | Golden willow,<br>blue spruce,<br>Norway spruce,<br>Scotch pine.             | Russian olive,<br>idahybrid poplar. | ---           |
| Little Wood-----          | Honeysuckle-----   | Nanking cherry,<br>lilac, Rocky<br>Mountain juniper.                            | Green ash, Norway<br>spruce, Russian<br>olive.                               | ---                                 | ---           |
| 20-----<br>Bruneel        | Lilac, honeysuckle   | Siberian peashrub,<br>Nanking cherry.   | Golden willow,<br>Rocky Mountain<br>juniper, green<br>ash, Norway<br>spruce. | Idahybrid poplar                    | ---           |
| 21, 22-----<br>Carey Lake | Lilac, honeysuckle   | Siberian peashrub,<br>Nanking cherry.   | Golden willow,<br>Rocky Mountain<br>juniper, green<br>ash, Norway<br>spruce. | Idahybrid poplar                    | ---           |
| 28, 29-----<br>Drage      | Siberian peashrub  | Russian olive,<br>Rocky Mountain<br>juniper, Nanking<br>cherry, blue<br>spruce. | Golden willow,<br>Douglas fir,<br>Sitka<br>mountainash,<br>Scotch pine.      | Idahybrid poplar                    | Black locust. |
| 31-----<br>Drage          | Siberian peashrub  | Russian olive,<br>Rocky Mountain<br>juniper, Nanking<br>cherry, blue<br>spruce. | Golden willow,<br>Douglas fir,<br>Sitka<br>mountainash,<br>Scotch pine.      | Idahybrid poplar                    | Black locust. |
| 42-----<br>Gimlett        | Honeysuckle-----   | Lilac, Rocky<br>Mountain juniper,<br>Nanking cherry.                            | Russian olive,<br>Norway spruce.   | ---                                 | ---           |
| 44-----<br>Goodington     | Siberian peashrub,<br>black locust.                          | Nanking cherry----  | Sitka mountainash,<br>golden willow,<br>Scotch pine.                         | Russian olive-----                  | ---           |
| 45*:<br>Goodington-----   | Siberian peashrub,<br>black locust.                          | Nanking cherry----  | Sitka mountainash,<br>golden willow,<br>Scotch pine.                         | Russian olive-----                  | ---           |
| Manard-----               | Peking<br>cotoneaster,<br>European privet.                   | Lilac, black<br>locust, Rocky<br>Mountain juniper.                              | Russian olive,<br>golden willow.   | ---                                 | ---           |

See footnote at end of table.



TABLE 7.--WINDBREAKS AND ENVIRONMENTAL PLANTINGS--Continued

| Soil name and<br>map symbol        | Trees having predicted 20-year average height, in feet, of-- |  |  |   |  |
|------------------------------------|--|--|--|---|--|
|                                    | <8   | 8-15   | 16-25  | 26-35   | >35  |
| 46-----<br>Hapur                   | Honeysuckle-----   | Siberian peashrub  | Golden willow,<br>green ash.   | ---   | ---  |
| 47*:<br>Hapur-----<br>Bickett.     | Honeysuckle-----   | Siberian peashrub  | Golden willow,<br>green ash.   | ---   | ---  |
| 48*:<br>Hapur-----                 | Honeysuckle-----   | Siberian peashrub  | Golden willow,<br>green ash.   | ---   | ---  |
| Picabo-----                        | Honeysuckle-----   | Lilac, Siberian<br>peashrub, Nanking<br>cherry.  | Golden willow,<br>Norway spruce,<br>green ash.                               | Idahybrid poplar                                    | ---  |
| 49-----<br>Hutton                  | Lilac, honeysuckle   | Siberian peashrub,<br>Nanking cherry.  | Golden willow,<br>Rocky Mountain<br>juniper, green<br>ash, Norway<br>spruce. | Idahybrid poplar                                    | ---  |
| 50-----<br>Hutton Variant          | European privet,<br>honeysuckle.                             | Lilac, Siberian<br>peashrub, Nanking<br>cherry, Rocky<br>Mountain juniper.             | Golden willow,<br>Scotch pine, blue<br>spruce, Norway<br>spruce.             | Russian olive,<br>idahybrid poplar.                 | ---  |
| 51-----<br>Isknat                  | European privet,<br>honeysuckle.                             | Lilac, Siberian<br>peashrub, Nanking<br>cherry, Rocky<br>Mountain juniper.             | Golden willow,<br>Scotch pine, blue<br>spruce, Norway<br>spruce.             | Russian olive,<br>idahybrid poplar.                 | ---  |
| 52, 53-----<br>Justesen            | ---  | Rocky Mountain<br>juniper, lilac,<br>Tatarian<br>honeysuckle,<br>Siberian<br>peashrub. | Nanking cherry,<br>Scotch pine,<br>Norway spruce,<br>golden willow.          | ---   | Black locust,<br>idahybrid poplar,<br>Russian olive. |
| 64, 65, 66, 67-----<br>Little Wood | Honeysuckle-----   | Nanking cherry,<br>lilac, Rocky<br>Mountain juniper.                                   | Green ash, Norway<br>spruce, Russian<br>olive.                               | ---   | ---  |
| 68-----<br>Little Wood             | European privet,<br>honeysuckle.                             | Lilac, Siberian<br>peashrub, Nanking<br>cherry, Rocky<br>Mountain juniper.             | Golden willow,<br>Scotch pine, blue<br>spruce, Norway<br>spruce.             | Russian olive,<br>idahybrid poplar.                 | ---  |
| 69*:<br>Little Wood-----           | Honeysuckle-----   | Nanking cherry,<br>lilac, Rocky<br>Mountain juniper.                                   | Green ash, Norway<br>spruce, Russian<br>olive.                               | ---   | ---  |
| Balaam-----                        | Siberian peashrub  | Black locust,<br>Nanking cherry.   | Rocky Mountain<br>juniper, golden<br>willow, Douglas<br>fir, Scotch pine.    | Russian olive,<br>blue spruce,<br>idahybrid poplar. | ---  |
| 70-----<br>Manard                  | Peking<br>cotoneaster,<br>European privet.                   | Lilac, black<br>locust, Rocky<br>Mountain juniper.                                     | Russian olive,<br>golden willow.   | ---   | ---  |

See footnote at end of table.

TABLE 7.--WINDBREAKS AND ENVIRONMENTAL PLANTINGS--Continued

| Soil name and map symbol  | Trees having predicted 20-year average height, in feet, of-- |   |   |                                  |               |
|---------------------------|--|---|---|----------------------------------|---------------|
|                           | <8   | 8-15  | 16-25   | 26-35                            | >35           |
| 71-----<br>Marshdale      | Honeysuckle-----   | Lilac, Siberian peashrub, Nanking cherry.                                       | Golden willow, Norway spruce, green ash.  | Idahybrid poplar                 | ---           |
| 72*:<br>Marshdale-----    | Honeysuckle-----   | Lilac, Siberian peashrub, Nanking cherry.                                       | Golden willow, Norway spruce, green ash.  | Idahybrid poplar                 | ---           |
| Bruneel-----              | Lilac, honeysuckle   | Siberian peashrub, Nanking cherry.  | Golden willow, Rocky Mountain juniper, green ash, Norway spruce.                    | Idahybrid poplar                 | ---           |
| 73-----<br>McBiggam       | European privet, honeysuckle.                                | Siberian peashrub, lilac, Nanking cherry, Rocky Mountain juniper, black locust. | Golden willow, Scotch pine, Norway spruce.  | Russian olive, idahybrid poplar. | ---           |
| 78, 79-----<br>Molyneux   | Siberian peashrub  | Nanking cherry, blue spruce.  | Rocky Mountain juniper, golden willow, Douglas fir, Sitka mountainash, Scotch pine. | Russian olive, idahybrid poplar. | Black locust. |
| 87*:<br>Peevywell-----    | Siberian peashrub, black locust.                             | Nanking cherry----  | Sitka mountainash, golden willow, Scotch pine.                                      | Russian olive-----               | ---           |
| Simonton-----             | Nanking cherry, cotoneaster, European privet.                | Siberian peashrub, lilac, Tatarian honeysuckle.                                 | Scotch pine, Norway spruce, green ash, blue spruce.                                 | Cottonwood, golden willow.       | ---           |
| 89, 90-----<br>Picabo     | Honeysuckle-----   | Lilac, Siberian peashrub, Nanking cherry.                                       | Golden willow, Norway spruce, green ash.  | Idahybrid poplar                 | ---           |
| 102, 103-----<br>Simonton | Nanking cherry, Peking cotoneaster, European privet.         | Siberian peashrub, lilac, Tatarian honeysuckle.                                 | Scotch pine, Norway spruce, green ash, blue spruce.                                 | Cottonwood, golden willow.       | ---           |

\* See description of the map unit for composition and behavior characteristics of the map unit.



TABLE 8.--RECREATIONAL DEVELOPMENT

(Some terms that describe restrictive soil features are defined in the Glossary. See text for definitions of "slight," "moderate," and "severe." Absence of an entry indicates that the soil was not rated)

| Soil name and map symbol | Camp areas                           | Picnic areas                         | Playgrounds                        | Paths and trails          | Golf fairways  |
|--------------------------|--------------------------------------|--------------------------------------|------------------------------------|---------------------------|--|
| 1-----<br>Adamson        | Severe:<br>flooding.                 | Moderate:<br>dusty.                  | Moderate:<br>dusty.                | Moderate:<br>dusty.       | Moderate:<br>droughty.                                 |
| 2*:<br>Adios-----        | Severe:<br>percs slowly.             | Severe:<br>percs slowly.             | Severe:<br>slope,<br>percs slowly. | Slight-----               | Moderate:<br>large stones,<br>slope,<br>depth to rock. |
| Gooding-----             | Moderate:<br>slope,<br>percs slowly. | Moderate:<br>slope,<br>percs slowly. | Severe:<br>slope.                  | Severe:<br>erodes easily. | Moderate:<br>slope.                                    |
| Bostrum-----             | Moderate:<br>slope,<br>large stones. | Moderate:<br>slope,<br>large stones. | Severe:<br>slope.                  | Moderate:<br>dusty.       | Moderate:<br>slope,<br>depth to rock.                  |
| 3*:<br>Adios-----        | Severe:<br>slope,<br>percs slowly.   | Severe:<br>slope,<br>percs slowly.   | Severe:<br>slope,<br>percs slowly. | Moderate:<br>slope.       | Severe:<br>slope.                                      |
| Adios, cool-----         | Severe:<br>slope,<br>percs slowly.   | Severe:<br>slope,<br>percs slowly.   | Severe:<br>slope,<br>percs slowly. | Moderate:<br>slope.       | Severe:<br>slope.                                      |
| 4-----<br>Balaam         | Moderate:<br>small stones.           | Moderate:<br>small stones.           | Severe:<br>small stones.           | Slight-----               | Moderate:<br>small stones,<br>droughty.                |
| 5-----<br>Balaam         | Severe:<br>small stones.             | Severe:<br>small stones.             | Severe:<br>small stones.           | Severe:<br>small stones.  | Severe:<br>small stones.                               |
| 6*:<br>Balaam-----       | Severe:<br>small stones.             | Severe:<br>small stones.             | Severe:<br>small stones.           | Severe:<br>small stones.  | Severe:<br>small stones.                               |
| Adamson-----             | Severe:<br>flooding.                 | Slight-----                          | Slight-----                        | Slight-----               | Moderate:<br>droughty.                                 |
| 7*:<br>Balaam-----       | Severe:<br>flooding.                 | Moderate:<br>small stones.           | Severe:<br>small stones.           | Slight-----               | Severe:<br>droughty.                                   |
| Adamson-----             | Severe:<br>flooding.                 | Slight-----                          | Slight-----                        | Slight-----               | Moderate:<br>droughty.                                 |
| 8*:<br>Balaam-----       | Severe:<br>flooding.                 | Moderate:<br>small stones.           | Severe:<br>small stones.           | Slight-----               | Severe:<br>droughty.                                   |
| Adamson-----             | Severe:<br>flooding.                 | Slight-----                          | Moderate:<br>flooding.             | Slight-----               | Moderate:<br>droughty,<br>flooding.                    |
| Riverwash.               |                                      |                                      |                                    |                           |  |

See footnote at end of table.

TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and map symbol                    | Camp areas   | Picnic areas   | Playgrounds  | Paths and trails                     | Golf fairways  |
|---|--|--|--|--------------------------------------|--|
| 9-----<br>Bancroft                          | Moderate:<br>dusty.                                  | Moderate:<br>dusty.                                  | Moderate:<br>slope,<br>dusty.                        | Moderate:<br>dusty.                  | Slight.  |
| 10-----<br>Bancroft                         | Moderate:<br>dusty.                                  | Moderate:<br>dusty.                                  | Severe:<br>slope.                                    | Moderate:<br>dusty.                  | Slight.  |
| 11-----<br>Bickett                          | Severe:<br>flooding,<br>ponding,<br>excess humus.    | Severe:<br>ponding,<br>excess humus.                 | Severe:<br>excess humus,<br>ponding,<br>flooding.    | Severe:<br>ponding,<br>excess humus. | Severe:<br>ponding,<br>flooding,<br>excess humus.      |
| 12*:<br>Blackspar-----<br><br>Rock outcrop. | Severe:<br>slope,<br>large stones,<br>small stones.  | Severe:<br>slope,<br>large stones,<br>small stones.  | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>large stones,<br>slope.   | Severe:<br>small stones,<br>large stones,<br>droughty. |
| 13*:<br>Blackspot-----                      | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope.                    | Severe:<br>small stones,<br>slope,<br>depth to rock.   |
| Prudy-----                                  | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                    | Severe:<br>slope.                                      |
| 14*:<br>Bostrum-----                        | Moderate:<br>large stones,<br>percs slowly.          | Moderate:<br>large stones,<br>percs slowly.          | Moderate:<br>slope,<br>small stones.                 | Moderate:<br>dusty.                  | Moderate:<br>depth to rock.                            |
| Yutru-----                                  | Moderate:<br>percs slowly.                           | Moderate:<br>too clayey.                             | Moderate:<br>too clayey,<br>percs slowly.            | Moderate:<br>too clayey.             | Severe:<br>too clayey.                                 |
| Hamrub-----                                 | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                           | Severe:<br>slope.                                    | Slight-----                          | Slight.  |
| 15-----<br>Bringmee                         | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                           | Moderate:<br>small stones,<br>percs slowly.          | Slight-----                          | Slight.  |
| 16-----<br>Bringmee                         | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                           | Moderate:<br>slope,<br>small stones.                 | Slight-----                          | Slight.  |
| 17-----<br>Bringmee                         | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                           | Severe:<br>slope.                                    | Slight-----                          | Slight.  |
| 18*:<br>Bringmee-----                       | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                           | Moderate:<br>slope,<br>small stones.                 | Slight-----                          | Slight.  |
| Hutton-----                                 | Severe:<br>flooding,<br>percs slowly.                | Severe:<br>percs slowly.                             | Severe:<br>percs slowly.                             | Moderate:<br>wetness.                | Moderate:<br>wetness,<br>flooding.                     |

See footnote at end of table.



TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and<br>map symbol | Camp areas                                  | Picnic areas                                | Playgrounds   | Paths and trails                | Golf fairways                                   |
|-----------------------------|---|---|---|---------------------------------|---|
| 19*:<br>Bringmee-----       | Moderate:<br>small stones,<br>percs slowly. | Moderate:<br>small stones,<br>percs slowly. | Severe:<br>small stones.                            | Slight-----                     | Moderate:<br>small stones.                      |
| Little Wood-----            | Severe:<br>small stones.                    | Severe:<br>small stones.                    | Severe:<br>small stones.                            | Moderate:<br>dusty.             | Severe:<br>small stones.                        |
| 20-----<br>Bruneel          | Severe:<br>flooding,<br>wetness.            | Moderate:<br>wetness,<br>dusty.             | Severe:<br>wetness.                                 | Moderate:<br>wetness,<br>dusty. | Moderate:<br>wetness,<br>droughty,<br>flooding. |
| 21-----<br>Carey Lake       | Moderate:<br>dusty.                         | Moderate:<br>dusty.                         | Moderate:<br>small stones,<br>dusty.                | Moderate:<br>dusty.             | Slight.   |
| 22-----<br>Carey Lake       | Moderate:<br>dusty.                         | Moderate:<br>dusty.                         | Moderate:<br>slope,<br>small stones,<br>dusty.      | Moderate:<br>dusty.             | Slight.   |
| 23*:<br>Cox-----            | Severe:<br>depth to rock.                   | Severe:<br>depth to rock.                   | Severe:<br>large stones,<br>slope,<br>small stones. | Severe:<br>large stones.        | Severe:<br>large stones,<br>thin layer.         |
| Rehfield-----               | Slight-----                                 | Slight-----                                 | Moderate:<br>slope,<br>small stones.                | Slight-----                     | Slight.   |
| Rock outcrop.               |   |   |   |                                 |   |
| 24*:<br>Deerhorn-----       | Moderate:<br>slope.                         | Moderate:<br>slope.                         | Severe:<br>slope.                                   | Slight-----                     | Moderate:<br>slope,<br>depth to rock.           |
| Rehfield-----               | Slight-----                                 | Slight-----                                 | Moderate:<br>slope,<br>small stones.                | Slight-----                     | Slight.   |
| Rock outcrop.               |   |   |   |                                 |   |
| 25*:<br>Deerhorn-----       | Slight-----                                 | Slight-----                                 | Moderate:<br>slope,<br>depth to rock.               | Slight-----                     | Moderate:<br>depth to rock.                     |
| Wildors-----                | Moderate:<br>large stones.                  | Moderate:<br>large stones.                  | Severe:<br>large stones.                            | Severe:<br>large stones.        | Severe:<br>large stones.                        |
| 26*:<br>Deerhorn-----       | Moderate:<br>slope.                         | Moderate:<br>slope.                         | Severe:<br>slope.                                   | Slight-----                     | Moderate:<br>slope,<br>depth to rock.           |
| Wildors-----                | Moderate:<br>slope,<br>large stones.        | Moderate:<br>slope,<br>large stones.        | Severe:<br>large stones,<br>slope.                  | Severe:<br>large stones.        | Severe:<br>large stones.                        |

See footnote at end of table.

TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and map symbol | Camp areas   | Picnic areas   | Playgrounds  | Paths and trails                   | Golf fairways                                     |
|--------------------------|--|--|--|------------------------------------|---|
| 26*:<br>Trevino-----     | Severe:<br>large stones,<br>depth to rock.           | Severe:<br>large stones,<br>depth to rock.           | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>large stones.           | Severe:<br>large stones,<br>depth to rock.        |
| 27*:<br>Dollarhide-----  | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>small stones,<br>slope.                |
| Rock outcrop.            |  |  |  |                                    |   |
| 28-----<br>Drage         | Moderate:<br>small stones,<br>dusty.                 | Moderate:<br>small stones,<br>dusty.                 | Severe:<br>slope,<br>small stones.                   | Moderate:<br>dusty.                | Moderate:<br>small stones,<br>large stones.       |
| 29, 30-----<br>Drage     | Moderate:<br>slope,<br>small stones,<br>dusty.       | Moderate:<br>slope,<br>small stones,<br>dusty.       | Severe:<br>slope,<br>small stones.                   | Moderate:<br>dusty.                | Moderate:<br>small stones,<br>large stones.       |
| 31-----<br>Drage         | Severe:<br>small stones.                             | Severe:<br>small stones.                             | Severe:<br>small stones.                             | Moderate:<br>dusty.                | Severe:<br>small stones.                          |
| 32*:<br>Earcrec-----     | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                 |
| Lockman-----             | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                  | Severe:<br>slope.                                 |
| 33*:<br>Earcrec-----     | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Moderate:<br>slope.                | Severe:<br>slope.                                 |
| Moonstone-----           | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Moderate:<br>slope.                | Severe:<br>slope.                                 |
| 34*:<br>Earcrec-----     | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                 |
| Moonstone-----           | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                 |
| 35*:<br>Elkcreek-----    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                  | Severe:<br>slope.                                 |
| Gaib-----                | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones. | Severe:<br>small stones,<br>slope,<br>thin layer. |

See footnote at end of table.



TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and map symbol | Camp areas  | Picnic areas  | Playgrounds  | Paths and trails                   | Golf fairways  |
|--------------------------|---|---|--|------------------------------------|--|
| 36*:<br>Elkcreek-----    | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>slope.                                    | Severe:<br>slope,<br>dusty.        | Severe:<br>slope.                                    |
| Polecreek-----           | Severe:<br>depth to rock.                           | Severe:<br>depth to rock.                           | Severe:<br>large stones,<br>slope,<br>depth to rock. | Severe:<br>large stones.           | Severe:<br>large stones,<br>thin layer.              |
| 37*:<br>Elksel-----      | Severe:<br>slope,<br>large stones.                  | Severe:<br>slope,<br>large stones.                  | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>slope.                  | Severe:<br>large stones,<br>slope.                   |
| Friedman-----            | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>large stones,<br>slope.                   | Severe:<br>slope.                  | Severe:<br>slope.                                    |
| Starhope-----            | Severe:<br>slope,<br>large stones,<br>percs slowly. | Severe:<br>slope,<br>large stones,<br>percs slowly. | Severe:<br>slope,<br>small stones,<br>percs slowly.  | Severe:<br>large stones,<br>slope. | Severe:<br>large stones,<br>slope.                   |
| 38*:<br>Elksel-----      | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                    |
| Peevywell-----           | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>slope.                  | Severe:<br>slope.                                    |
| Furshur-----             | Severe:<br>slope,<br>small stones,<br>percs slowly. | Severe:<br>slope,<br>small stones,<br>percs slowly. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope.                  | Severe:<br>small stones,<br>slope,<br>depth to rock. |
| 39*:<br>Elksel-----      | Severe:<br>slope,<br>large stones.                  | Severe:<br>slope,<br>large stones.                  | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>slope.                  | Severe:<br>large stones,<br>slope.                   |
| Starhope-----            | Severe:<br>slope,<br>large stones,<br>percs slowly. | Severe:<br>slope,<br>large stones,<br>percs slowly. | Severe:<br>slope,<br>small stones,<br>percs slowly.  | Severe:<br>large stones,<br>slope. | Severe:<br>large stones,<br>slope.                   |
| Rock outcrop.            |   |   |  |                                    |  |
| 40*:<br>Friedman-----    | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>large stones,<br>slope.                   | Severe:<br>slope.                  | Severe:<br>slope.                                    |

See footnote at end of table.

TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and<br>map symbol | Camp areas   | Picnic areas   | Playgrounds  | Paths and trails                     | Golf fairways                                     |
|-----------------------------|--|--|--|--------------------------------------|---|
| 40*:<br>Elksel-----         | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>slope.                    | Severe:<br>large stones,<br>slope.                |
| Winridge-----               | Severe:<br>slope,<br>percs slowly.                   | Severe:<br>slope,<br>percs slowly.                   | Severe:<br>slope,<br>percs slowly.                   | Severe:<br>slope.                    | Severe:<br>slope.                                 |
| 41*:<br>Gaib-----           | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones.   | Severe:<br>small stones,<br>slope,<br>thin layer. |
| Rock outcrop.               |  |  |  |                                      |   |
| 42-----<br>Gimlett          | Severe:<br>small stones.                             | Severe:<br>small stones.                             | Severe:<br>small stones.                             | Severe:<br>small stones.             | Severe:<br>small stones,<br>droughty.             |
| 43*:<br>Gooding-----        | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                           | Severe:<br>slope.                                    | Slight-----                          | Slight.   |
| Gooding, eroded-----        | Severe:<br>large stones.                             | Severe:<br>large stones.                             | Severe:<br>large stones.                             | Slight-----                          | Severe:<br>large stones.                          |
| Hamrub-----                 | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                           | Severe:<br>slope.                                    | Slight-----                          | Slight.   |
| 44-----<br>Goodington       | Moderate:<br>percs slowly,<br>dusty.                 | Moderate:<br>percs slowly,<br>dusty.                 | Moderate:<br>slope,<br>percs slowly,<br>dusty.       | Moderate:<br>dusty.                  | Slight.   |
| 45*:<br>Goodington-----     | Moderate:<br>percs slowly,<br>dusty.                 | Moderate:<br>percs slowly,<br>dusty.                 | Moderate:<br>slope,<br>percs slowly,<br>dusty.       | Moderate:<br>dusty.                  | Slight.   |
| Manard-----                 | Moderate:<br>large stones,<br>percs slowly.          | Moderate:<br>large stones,<br>percs slowly.          | Severe:<br>large stones.                             | Moderate:<br>dusty.                  | Moderate:<br>large stones,<br>depth to rock.      |
| 46-----<br>Hapur            | Severe:<br>flooding,<br>wetness.                     | Severe:<br>wetness.                                  | Severe:<br>wetness,<br>flooding.                     | Severe:<br>wetness.                  | Severe:<br>wetness,<br>flooding.                  |
| 47*:<br>Hapur-----          | Severe:<br>flooding,<br>wetness.                     | Severe:<br>wetness.                                  | Severe:<br>wetness,<br>flooding.                     | Severe:<br>wetness.                  | Severe:<br>wetness,<br>flooding.                  |
| Bickett-----                | Severe:<br>flooding,<br>ponding,<br>excess humus.    | Severe:<br>ponding,<br>excess humus.                 | Severe:<br>excess humus,<br>ponding,<br>flooding.    | Severe:<br>ponding,<br>excess humus. | Severe:<br>ponding,<br>flooding,<br>excess humus. |

See footnote at end of table.



TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and map symbol  | Camp areas   | Picnic areas   | Playgrounds                                 | Paths and trails              | Golf fairways                           |
|---------------------------|--|--|---|-------------------------------|---|
| 48*:<br>Hapur-----        | Severe:<br>flooding,<br>wetness.                     | Severe:<br>wetness.                                  | Severe:<br>wetness,<br>flooding.            | Severe:<br>wetness.           | Severe:<br>wetness,<br>flooding.        |
| Picabo-----               | Severe:<br>flooding.                                 | Moderate:<br>wetness,<br>excess salt.                | Moderate:<br>wetness,<br>flooding.          | Moderate:<br>dusty.           | Moderate:<br>excess salt,<br>flooding.  |
| 49-----<br>Hutton         | Severe:<br>flooding,<br>percs slowly.                | Severe:<br>percs slowly.                             | Severe:<br>percs slowly.                    | Moderate:<br>wetness.         | Moderate:<br>wetness,<br>flooding.      |
| 50-----<br>Hutton Variant | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                           | Moderate:<br>small stones,<br>percs slowly. | Slight-----                   | Slight.                                 |
| 51-----<br>Isknat         | Moderate:<br>small stones,<br>percs slowly.          | Moderate:<br>small stones,<br>percs slowly.          | Severe:<br>small stones.                    | Slight-----                   | Moderate:<br>small stones,<br>droughty. |
| 52-----<br>Justesen       | Moderate:<br>dusty.                                  | Moderate:<br>dusty.                                  | Moderate:<br>slope,<br>dusty.               | Moderate:<br>dusty.           | Slight.                                 |
| 53-----<br>Justesen       | Moderate:<br>dusty.                                  | Moderate:<br>dusty.                                  | Severe:<br>slope.                           | Moderate:<br>dusty.           | Slight.                                 |
| 54-----<br>Justesen       | Moderate:<br>slope,<br>dusty.                        | Moderate:<br>slope,<br>dusty.                        | Severe:<br>slope.                           | Moderate:<br>dusty.           | Moderate:<br>slope.                     |
| 55-----<br>Justesen       | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                           | Moderate:<br>slope,<br>dusty. | Severe:<br>slope.                       |
| 56*:<br>Ketchum-----      | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope,<br>small stones.          | Severe:<br>slope.             | Severe:<br>small stones,<br>slope.      |
| Dollarhide-----           | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones.          | Severe:<br>slope.             | Severe:<br>small stones,<br>slope.      |
| 57*:<br>Ketchum-----      | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope,<br>small stones.          | Severe:<br>slope.             | Severe:<br>small stones,<br>slope.      |
| Povey-----                | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.          | Severe:<br>slope.             | Moderate:<br>small stones,<br>droughty. |
| 58*:<br>Laurentzen-----   | Moderate:<br>slope,<br>dusty.                        | Moderate:<br>slope,<br>dusty.                        | Severe:<br>slope.                           | Moderate:<br>dusty.           | Moderate:<br>slope.                     |

See footnote at end of table.

TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and<br>map symbol    | Camp areas  | Picnic areas  | Playgrounds  | Paths and trails                   | Golf fairways  |
|--------------------------------|---|---|--|------------------------------------|--|
| 58*:<br>Mulshoe-----           | Severe:<br>slope.   | Severe:<br>slope.   | Severe:<br>large stones,<br>slope,<br>small stones.    | Severe:<br>large stones.           | Severe:<br>large stones,<br>slope.                       |
| 59*.<br>Lava flows             |   |   |  |                                    |  |
| 60*:<br>Lava flows.            |   |   |  |                                    |  |
| Cinderhurst-----               | Severe:<br>large stones,<br>small stones,<br>depth to rock. | Severe:<br>large stones,<br>small stones,<br>depth to rock. | Severe:<br>large stones,<br>slope,<br>small stones.    | Severe:<br>large stones.           | Severe:<br>small stones,<br>large stones,<br>thin layer. |
| 61*, 62*:<br>Lavacreek-----    | Severe:<br>slope,<br>small stones.                          | Severe:<br>slope,<br>small stones.                          | Severe:<br>slope,<br>small stones.                     | Severe:<br>slope.                  | Severe:<br>small stones,<br>slope.                       |
| Dollarhide-----                | Severe:<br>slope,<br>small stones,<br>depth to rock.        | Severe:<br>slope,<br>small stones,<br>depth to rock.        | Severe:<br>slope,<br>small stones.                     | Severe:<br>slope.                  | Severe:<br>small stones,<br>slope.                       |
| 63*:<br>Lavacreek-----         | Severe:<br>slope,<br>small stones.                          | Severe:<br>slope,<br>small stones.                          | Severe:<br>slope,<br>small stones.                     | Severe:<br>slope.                  | Severe:<br>small stones,<br>slope.                       |
| Vitale-----                    | Severe:<br>slope,<br>small stones.                          | Severe:<br>slope,<br>small stones.                          | Severe:<br>slope,<br>small stones.                     | Severe:<br>slope,<br>small stones. | Severe:<br>small stones,<br>slope.                       |
| 64, 65-----<br>Little Wood     | Moderate:<br>small stones,<br>dusty.                        | Moderate:<br>small stones,<br>dusty.                        | Severe:<br>small stones.                               | Moderate:<br>dusty.                | Moderate:<br>small stones,<br>droughty.                  |
| 66, 67, 68-----<br>Little Wood | Severe:<br>small stones.                                    | Severe:<br>small stones.                                    | Severe:<br>small stones.                               | Moderate:<br>dusty.                | Severe:<br>small stones.                                 |
| 69*:<br>Little Wood-----       | Moderate:<br>small stones.                                  | Severe:<br>small stones.                                    | Severe:<br>small stones.                               | Moderate:<br>dusty.                | Severe:<br>small stones.                                 |
| Balaam-----                    | Severe:<br>small stones.                                    | Moderate:<br>small stones.                                  | Severe:<br>small stones.                               | Slight-----                        | Moderate:<br>small stones,<br>droughty.                  |
| 70-----<br>Manard              | Moderate:<br>percs slowly,<br>dusty.                        | Moderate:<br>percs slowly,<br>dusty.                        | Moderate:<br>slope,<br>small stones,<br>depth to rock. | Moderate:<br>dusty.                | Moderate:<br>depth to rock.                              |
| 71-----<br>Marshdale           | Severe:<br>flooding,<br>wetness.                            | Severe:<br>wetness.   | Severe:<br>wetness,<br>flooding.                       | Severe:<br>wetness.                | Severe:<br>wetness,<br>flooding.                         |

See footnote at end of table.



TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and map symbol | Camp areas                         | Picnic areas                       | Playgrounds   | Paths and trails                     | Golf fairways                                       |
|--------------------------|------------------------------------|------------------------------------|---|--------------------------------------|---|
| 72*:<br>Marshdale-----   | Severe:<br>flooding,<br>wetness.   | Severe:<br>wetness.                | Severe:<br>wetness,<br>flooding.                      | Severe:<br>wetness,                  | Severe:<br>wetness,<br>flooding.                    |
| Bruneel-----             | Severe:<br>flooding,<br>wetness.   | Moderate:<br>wetness,<br>dusty.    | Severe:<br>wetness.                                   | Moderate:<br>wetness,<br>dusty.      | Moderate:<br>wetness,<br>droughty,<br>flooding.     |
| 73-----<br>McBiggam      | Moderate:<br>percs slowly.         | Moderate:<br>percs slowly.         | Moderate:<br>slope,<br>small stones,<br>percs slowly. | Slight-----                          | Slight.   |
| 74*:<br>McCarey-----     | Moderate:<br>dusty.                | Moderate:<br>dusty.                | Moderate:<br>slope,<br>depth to rock,<br>dusty.       | Moderate:<br>dusty.                  | Moderate:<br>depth to rock.                         |
| Justesen-----            | Moderate:<br>dusty.                | Moderate:<br>dusty.                | Moderate:<br>slope,<br>dusty.                         | Moderate:<br>dusty.                  | Slight.   |
| 75*:<br>McCarey-----     | Moderate:<br>slope,<br>dusty.      | Moderate:<br>slope,<br>dusty.      | Severe:<br>slope.                                     | Severe:<br>erodes easily.            | Moderate:<br>slope,<br>depth to rock.               |
| Justesen-----            | Moderate:<br>slope,<br>dusty.      | Moderate:<br>slope,<br>dusty.      | Severe:<br>slope.                                     | Moderate:<br>dusty.                  | Moderate:<br>slope.                                 |
| Rock outcrop.            |                                    |                                    |   |                                      |   |
| 76*:<br>McCarey-----     | Moderate:<br>dusty.                | Moderate:<br>dusty.                | Moderate:<br>slope,<br>depth to rock,<br>dusty.       | Moderate:<br>dusty.                  | Moderate:<br>depth to rock.                         |
| Molyneux-----            | Moderate:<br>dusty.                | Moderate:<br>dusty.                | Moderate:<br>slope,<br>dusty.                         | Moderate:<br>dusty.                  | Slight.   |
| 77*:<br>McCarey-----     | Severe:<br>slope.                  | Severe:<br>slope.                  | Severe:<br>slope.                                     | Severe:<br>erodes easily.            | Severe:<br>slope.                                   |
| Pedleford-----           | Severe:<br>slope,<br>small stones. | Severe:<br>slope,<br>small stones. | Severe:<br>large stones,<br>slope,<br>small stones.   | Moderate:<br>large stones,<br>slope. | Severe:<br>small stones,<br>large stones,<br>slope. |
| 78-----<br>Molyneux      | Moderate:<br>dusty.                | Moderate:<br>dusty.                | Moderate:<br>slope,<br>dusty.                         | Moderate:<br>dusty.                  | Slight.   |
| 79-----<br>Molyneux      | Moderate:<br>dusty.                | Moderate:<br>dusty.                | Severe:<br>slope.                                     | Moderate:<br>dusty.                  | Slight.   |

See footnote at end of table.

TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and map symbol | Camp areas   | Picnic areas   | Playgrounds  | Paths and trails                   | Golf fairways                                       |
|--------------------------|--|--|--|------------------------------------|---|
| 80-----<br>Molyneux      | Moderate:<br>slope,<br>dusty.                        | Moderate:<br>slope,<br>dusty.                        | Severe:<br>slope.                                    | Moderate:<br>dusty.                | Moderate:<br>slope.                                 |
| 81*:<br>Moonstone-----   | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Moderate:<br>slope.                | Severe:<br>slope.                                   |
| Bauscher-----            | Moderate:<br>slope,<br>dusty.                        | Moderate:<br>slope,<br>dusty.                        | Severe:<br>slope.                                    | Moderate:<br>dusty.                | Moderate:<br>slope.                                 |
| 82*:<br>Moonstone-----   | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                   |
| Earcree-----             | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                   |
| 83*:<br>Muldoon-----     | Moderate:<br>slope,<br>percs slowly.                 | Moderate:<br>slope,<br>percs slowly.                 | Severe:<br>slope.                                    | Slight-----                        | Moderate:<br>slope.                                 |
| Peevywell-----           | Moderate:<br>slope,<br>percs slowly.                 | Moderate:<br>slope,<br>percs slowly.                 | Severe:<br>slope.                                    | Severe:<br>erodes easily.          | Moderate:<br>large stones,<br>slope,<br>thin layer. |
| 84*:<br>Mulshoe-----     | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>large stones.           | Severe:<br>large stones,<br>slope.                  |
| Gaib-----                | Severe:<br>slope,<br>depth to rock.                  | Severe:<br>slope,<br>depth to rock.                  | Severe:<br>slope,<br>depth to rock.                  | Moderate:<br>slope,<br>dusty.      | Severe:<br>slope,<br>thin layer.                    |
| Rock outcrop.            |  |  |  |                                    |   |
| 85*:<br>Mulshoe-----     | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>large stones,<br>slope. | Severe:<br>large stones,<br>slope.                  |
| Gaib-----                | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones. | Severe:<br>small stones,<br>slope,<br>thin layer.   |
| Winu-----                | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                   |

See footnote at end of table.



TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and<br>map symbol                   | Camp areas   | Picnic areas   | Playgrounds   | Paths and trails          | Golf fairways   |
|---|--|--|---|---------------------------|---|
| 86*:<br>Pagari-----                           | Severe:<br>large stones.                             | Severe:<br>large stones.                               | Severe:<br>large stones,<br>slope,<br>small stones.   | Severe:<br>large stones.  | Severe:<br>large stones.                                |
| Rehfield-----                                 | Slight-----  | Slight-----  | Moderate:<br>slope,<br>small stones.                  | Slight-----               | Slight.   |
| 87*:<br>Peevywell-----                        | Moderate:<br>percs slowly.                           | Moderate:<br>percs slowly.                             | Moderate:<br>slope,<br>small stones,<br>cemented pan. | Slight-----               | Moderate:<br>large stones,<br>thin layer.               |
| Simonton-----                                 | Moderate:<br>dusty.                                  | Moderate:<br>dusty.                                    | Moderate:<br>slope,<br>small stones.                  | Moderate:<br>dusty.       | Slight.   |
| 88*:<br>Peevywell-----                        | Severe:<br>slope.                                    | Severe:<br>slope.                                      | Severe:<br>slope.                                     | Severe:<br>erodes easily. | Severe:<br>slope.                                       |
| Simonton-----                                 | Moderate:<br>slope,<br>dusty.                        | Moderate:<br>slope,<br>dusty.                          | Severe:<br>slope.                                     | Moderate:<br>dusty.       | Moderate:<br>slope.                                     |
| 89-----<br>Picabo                             | Severe:<br>flooding.                                 | Moderate:<br>wetness,<br>excess salt.                  | Moderate:<br>wetness,<br>flooding.                    | Moderate:<br>dusty.       | Moderate:<br>excess salt,<br>flooding.                  |
| 90-----<br>Picabo                             | Severe:<br>flooding.                                 | Moderate:<br>wetness,<br>small stones,<br>excess salt. | Severe:<br>small stones.                              | Moderate:<br>dusty.       | Moderate:<br>excess salt,<br>small stones,<br>flooding. |
| 91*.<br>Pits, gravel                          |  |  |   |                           |   |
| 92*:<br>Povey-----                            | Severe:<br>slope.                                    | Severe:<br>slope.                                      | Severe:<br>slope,<br>small stones.                    | Severe:<br>slope.         | Moderate:<br>small stones,<br>droughty.                 |
| Dollarhide-----                               | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock.   | Severe:<br>slope,<br>small stones.                    | Severe:<br>slope.         | Severe:<br>small stones,<br>slope.                      |
| 93*:<br>Povey-----                            | Severe:<br>slope.                                    | Severe:<br>slope.                                      | Severe:<br>slope,<br>small stones.                    | Severe:<br>slope.         | Moderate:<br>small stones,<br>droughty.                 |
| Rock outcrop.                                 |  |  |   |                           |   |
| 94*:<br>Povey very gravelly<br>silt loam----- | Severe:<br>slope.                                    | Severe:<br>slope.                                      | Severe:<br>slope,<br>small stones.                    | Severe:<br>slope.         | Severe:<br>small stones.                                |

See footnote at end of table.

TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and map symbol      | Camp areas  | Picnic areas  | Playgrounds   | Paths and trails                   | Golf fairways                                       |
|-------------------------------|---|---|---|------------------------------------|---|
| 94*:<br>Povey gravelly loam-- | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope.                  | Moderate:<br>small stones,<br>droughty.             |
| 95*:<br>Povey-----            | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope.                  | Moderate:<br>small stones,<br>droughty.             |
| Vitale-----                   | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones. | Severe:<br>small stones,<br>slope.                  |
| 96*:<br>Rehfield-----         | Moderate:<br>slope.                                 | Moderate:<br>slope.                                 | Severe:<br>slope.                                   | Slight-----                        | Moderate:<br>slope.                                 |
| Gooding-----                  | Moderate:<br>slope,<br>percs slowly.                | Moderate:<br>slope,<br>percs slowly.                | Severe:<br>slope.                                   | Severe:<br>erodes easily.          | Moderate:<br>slope.                                 |
| 97*.<br>Riverwash             |   |   |   |                                    |   |
| 98*:<br>Rock outcrop.         |   |   |   |                                    |   |
| Adios-----                    | Severe:<br>slope,<br>percs slowly.                  | Severe:<br>slope,<br>percs slowly.                  | Severe:<br>slope,<br>percs slowly.                  | Severe:<br>slope.                  | Severe:<br>slope.                                   |
| 99-----<br>Rockybar           | Severe:<br>slope,<br>large stones,<br>small stones. | Severe:<br>slope,<br>large stones,<br>small stones. | Severe:<br>large stones,<br>slope,<br>small stones. | Severe:<br>large stones.           | Severe:<br>small stones,<br>large stones,<br>slope. |
| 100*.<br>Rubbleland           |   |   |   |                                    |   |
| 101*:<br>Rubbleland.          |   |   |   |                                    |   |
| Milligan-----                 | Severe:<br>slope,<br>large stones.                  | Severe:<br>slope,<br>large stones.                  | Severe:<br>large stones,<br>slope,<br>small stones. | Severe:<br>large stones,<br>slope. | Severe:<br>large stones,<br>slope.                  |
| 102-----<br>Simonton          | Moderate:<br>dusty.                                 | Moderate:<br>dusty.                                 | Moderate:<br>slope,<br>small stones.                | Moderate:<br>dusty.                | Slight.   |
| 103-----<br>Simonton          | Moderate:<br>dusty.                                 | Moderate:<br>dusty.                                 | Severe:<br>slope.                                   | Moderate:<br>dusty.                | Slight.   |
| 104*:<br>Simonton-----        | Moderate:<br>slope,<br>dusty.                       | Moderate:<br>slope,<br>dusty.                       | Severe:<br>slope.                                   | Moderate:<br>dusty.                | Moderate:<br>slope.                                 |

See footnote at end of table.



TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and<br>map symbol | Camp areas  | Picnic areas  | Playgrounds  | Paths and trails                   | Golf fairways  |
|-----------------------------|---|---|--|------------------------------------|--|
| 104*:<br>Bauscher-----      | Moderate:<br>slope,<br>dusty.                       | Moderate:<br>slope,<br>dusty.                       | Severe:<br>slope.                                    | Moderate:<br>dusty.                | Moderate:<br>slope.                                    |
| 105*:<br>Starhope-----      | Severe:<br>percs slowly.                            | Severe:<br>percs slowly.                            | Severe:<br>slope,<br>percs slowly.                   | Slight-----                        | Moderate:<br>slope,<br>thin layer.                     |
| Furshur-----                | Severe:<br>small stones,<br>percs slowly.           | Severe:<br>small stones,<br>percs slowly.           | Severe:<br>slope,<br>small stones,<br>depth to rock. | Slight-----                        | Severe:<br>small stones,<br>depth to rock.             |
| 106*:<br>Starhope-----      | Severe:<br>slope,<br>percs slowly.                  | Severe:<br>slope,<br>percs slowly.                  | Severe:<br>slope,<br>percs slowly.                   | Moderate:<br>slope.                | Severe:<br>slope.                                      |
| Peevywell-----              | Moderate:<br>slope,<br>percs slowly.                | Moderate:<br>slope,<br>percs slowly.                | Severe:<br>slope.                                    | Severe:<br>erodes easily.          | Moderate:<br>large stones,<br>slope,<br>thin layer.    |
| Smelter-----                | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>slope.                                    | Moderate:<br>slope.                | Severe:<br>slope.                                      |
| 107*:<br>Vitale-----        | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope,<br>small stones. | Severe:<br>small stones,<br>slope.                     |
| Blackspar-----              | Severe:<br>slope,<br>large stones,<br>small stones. | Severe:<br>slope,<br>large stones,<br>small stones. | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>large stones,<br>slope. | Severe:<br>small stones,<br>large stones,<br>droughty. |
| 108*:<br>Vitale-----        | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope,<br>small stones. | Severe:<br>small stones,<br>slope.                     |
| Milligan-----               | Severe:<br>slope,<br>large stones.                  | Severe:<br>slope,<br>large stones.                  | Severe:<br>large stones,<br>slope,<br>small stones.  | Severe:<br>large stones,<br>slope. | Severe:<br>large stones,<br>slope.                     |
| 109*:<br>Vitale-----        | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones.                  | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope,<br>small stones. | Severe:<br>small stones,<br>slope.                     |
| Povey-----                  | Severe:<br>slope.                                   | Severe:<br>slope.                                   | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Moderate:<br>small stones,<br>droughty.                |

See footnote at end of table.

TABLE 8.--RECREATIONAL DEVELOPMENT--Continued

| Soil name and<br>map symbol             | Camp areas   | Picnic areas   | Playgrounds  | Paths and trails                   | Golf fairways                                     |
|---|--|--|--|------------------------------------|---|
| 110*:<br>Winu-----<br><br>Rock outcrop. | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                 |
| 111*:<br>Winu-----                      | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope,<br>small stones.                   | Severe:<br>slope.                  | Severe:<br>slope.                                 |
| Gaib-----                               | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones,<br>depth to rock. | Severe:<br>slope,<br>small stones. | Severe:<br>small stones,<br>slope,<br>thin layer. |

\* See description of the map unit for composition and behavior characteristics of the map unit.



TABLE 9.--BUILDING SITE DEVELOPMENT

(Some terms that describe restrictive soil features are defined in the Glossary. See text for definitions of "slight," "moderate," and "severe." Absence of an entry indicates that the soil was not rated. The information in this table indicates the dominant soil condition but does not eliminate the need for onsite investigation)

| Soil name and map symbol | Shallow excavations                                  | Dwellings without basements                            | Dwellings with basements                             | Small commercial buildings         | Local roads and streets                                  | Lawns and landscaping                                  |
|--------------------------|--|--|--|------------------------------------|--|--|
| 1-----<br>Adamson        | Severe:<br>cutbanks cave.                            | Severe:<br>flooding.                                   | Severe:<br>flooding.                                 | Severe:<br>flooding.               | Moderate:<br>flooding,<br>frost action.                  | Moderate:<br>droughty.                                 |
| 2*:<br>Adios-----        | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>shrink-swell.                               | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>shrink-swell,<br>slope. | Severe:<br>low strength,<br>shrink-swell.                | Moderate:<br>large stones,<br>slope,<br>depth to rock. |
| Gooding-----             | Moderate:<br>depth to rock,<br>too clayey,<br>slope. | Severe:<br>shrink-swell.                               | Severe:<br>shrink-swell.                             | Severe:<br>shrink-swell,<br>slope. | Severe:<br>shrink-swell,<br>low strength.                | Moderate:<br>slope.                                    |
| Bostrum-----             | Severe:<br>depth to rock.                            | Moderate:<br>shrink-swell,<br>slope,<br>depth to rock. | Severe:<br>depth to rock.                            | Severe:<br>slope.                  | Severe:<br>low strength.                                 | Moderate:<br>slope,<br>depth to rock.                  |
| 3*:<br>Adios-----        | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>shrink-swell,<br>slope.                     | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>shrink-swell,<br>slope. | Severe:<br>low strength,<br>slope,<br>shrink-swell.      | Severe:<br>slope.                                      |
| Adios, cool-----         | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>shrink-swell,<br>slope.                     | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>shrink-swell,<br>slope. | Severe:<br>low strength,<br>slope,<br>shrink-swell.      | Severe:<br>slope.                                      |
| 4-----<br>Balaam         | Severe:<br>cutbanks cave.                            | Slight-----  | Slight-----  | Slight-----                        | Slight-----  | Moderate:<br>small stones,<br>droughty.                |
| 5-----<br>Balaam         | Severe:<br>cutbanks cave.                            | Slight-----  | Slight-----  | Slight-----                        | Slight-----  | Severe:<br>small stones.                               |
| 6*:<br>Balaam-----       | Severe:<br>cutbanks cave.                            | Slight-----  | Slight-----  | Slight-----                        | Slight-----  | Severe:<br>small stones.                               |
| Adamson-----             | Severe:<br>cutbanks cave.                            | Severe:<br>flooding.                                   | Severe:<br>flooding.                                 | Severe:<br>flooding.               | Moderate:<br>flooding,<br>frost action.                  | Moderate:<br>droughty.                                 |
| 7*:<br>Balaam-----       | Severe:<br>cutbanks cave.                            | Severe:<br>flooding.                                   | Severe:<br>flooding.                                 | Severe:<br>flooding.               | Moderate:<br>flooding,<br>large stones.                  | Severe:<br>droughty.                                   |
| Adamson-----             | Severe:<br>cutbanks cave.                            | Severe:<br>flooding.                                   | Severe:<br>flooding.                                 | Severe:<br>flooding.               | Moderate:<br>flooding,<br>frost action,<br>large stones. | Moderate:<br>droughty.                                 |

See footnote at end of table.

TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol | Shallow excavations                                  | Dwellings without basements                          | Dwellings with basements                             | Small commercial buildings                             | Local roads and streets                              | Lawns and landscaping                                  |
|--------------------------|--|--|--|--|--|--|
| 8*:<br>Balaam-----       | Severe:<br>cutbanks cave.                            | Severe:<br>flooding.                                 | Severe:<br>flooding.                                 | Severe:<br>flooding.                                   | Severe:<br>flooding.                                 | Severe:<br>droughty.                                   |
| Adamson-----             | Severe:<br>cutbanks cave.                            | Severe:<br>flooding.                                 | Severe:<br>flooding.                                 | Severe:<br>flooding.                                   | Severe:<br>flooding.                                 | Moderate:<br>droughty,<br>flooding.                    |
| Riverwash.               |  |  |  |  |  |  |
| 9-----<br>Bancroft.      | Severe:<br>cutbanks cave.                            | Slight-----  | Slight-----  | Slight-----  | Severe:<br>low strength,<br>frost action.            | Slight.  |
| 10-----<br>Bancroft      | Severe:<br>cutbanks cave.                            | Slight-----  | Slight-----  | Moderate:<br>slope.                                    | Severe:<br>low strength,<br>frost action.            | Slight.  |
| 11-----<br>Bickett       | Severe:<br>ponding.                                  | Severe:<br>flooding,<br>ponding.                     | Severe:<br>flooding,<br>ponding.                     | Severe:<br>flooding,<br>ponding.                       | Severe:<br>low strength,<br>ponding,<br>flooding.    | Severe:<br>ponding,<br>flooding,<br>excess humus.      |
| 12*:<br>Blackspar-----   | Severe:<br>depth to rock,<br>large stones,<br>slope. | Severe:<br>slope,<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope,<br>depth to rock,<br>large stones.   | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>small stones,<br>large stones,<br>droughty. |
| Rock outcrop.            |  |  |  |  |  |  |
| 13*:<br>Blackspot-----   | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>slope,<br>cemented pan.                   | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>slope,<br>cemented pan.                     | Severe:<br>cemented pan,<br>slope.                   | Severe:<br>small stones,<br>slope,<br>depth to rock.   |
| Prudy-----               | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                      | Severe:<br>slope.                                    | Severe:<br>slope.                                      |
| 14*:<br>Bostrum-----     | Severe:<br>depth to rock.                            | Moderate:<br>shrink-swell,<br>depth to rock.         | Severe:<br>depth to rock.                            | Moderate:<br>shrink-swell,<br>slope,<br>depth to rock. | Severe:<br>low strength.                             | Moderate:<br>depth to rock.                            |
| Yutru-----               | Moderate:<br>too clayey.                             | Severe:<br>shrink-swell.                             | Slight-----  | Severe:<br>shrink-swell.                               | Severe:<br>shrink-swell,<br>low strength.            | Severe:<br>too clayey.                                 |
| Hamrub-----              | Moderate:<br>depth to rock,<br>cemented pan.         | Moderate:<br>shrink-swell.                           | Moderate:<br>depth to rock,<br>cemented pan.         | Moderate:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength.                             | Slight.  |
| 15, 16-----<br>Bringmee  | Severe:<br>cutbanks cave.                            | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell.                             | Severe:<br>low strength.                             | Slight.  |
| 17-----<br>Bringmee      | Severe:<br>cutbanks cave.                            | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength.                             | Slight.  |

See footnote at end of table.



TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol  | Shallow excavations                        | Dwellings without basements                            | Dwellings with basements                          | Small commercial buildings                             | Local roads and streets                                | Lawns and landscaping                           |
|---------------------------|--|--|---|--|--|---|
| 18*:<br>Bringmee-----     | Severe:<br>cutbanks cave.                  | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell.                        | Moderate:<br>shrink-swell.                             | Severe:<br>low strength.                               | Slight.   |
| Hutton-----               | Severe:<br>wetness.                        | Severe:<br>flooding,<br>shrink-swell.                  | Severe:<br>flooding,<br>wetness,<br>shrink-swell. | Severe:<br>flooding,<br>shrink-swell.                  | Severe:<br>low strength,<br>flooding,<br>frost action. | Moderate:<br>wetness,<br>flooding.              |
| 19*:<br>Bringmee-----     | Severe:<br>cutbanks cave.                  | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell.                        | Moderate:<br>shrink-swell.                             | Severe:<br>low strength.                               | Moderate:<br>small stones.                      |
| Little Wood-----          | Severe:<br>cutbanks cave.                  | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell.                        | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell,<br>frost action.            | Severe:<br>small stones.                        |
| 20-----<br>Bruneel        | Severe:<br>cutbanks cave,<br>wetness.      | Severe:<br>flooding,<br>wetness.                       | Severe:<br>flooding,<br>wetness.                  | Severe:<br>flooding,<br>wetness.                       | Severe:<br>flooding,<br>frost action.                  | Moderate:<br>wetness,<br>droughty,<br>flooding. |
| 21, 22-----<br>Carey Lake | Moderate:<br>wetness.                      | Slight-----  | Moderate:<br>wetness.                             | Slight-----  | Moderate:<br>low strength,<br>frost action.            | Slight.   |
| 23*:<br>Cox-----          | Severe:<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>large stones.             | Severe:<br>depth to rock,<br>large stones.        | Severe:<br>slope,<br>depth to rock,<br>large stones.   | Severe:<br>depth to rock,<br>large stones.             | Severe:<br>large stones,<br>thin layer.         |
| Rehfield-----             | Severe:<br>cutbanks cave.                  | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell.                        | Moderate:<br>shrink-swell,<br>slope.                   | Moderate:<br>frost action,<br>shrink-swell.            | Slight.   |
| Rock outcrop.             |  |  |   |  |  |   |
| 24*:<br>Deerhorn-----     | Severe:<br>depth to rock.                  | Moderate:<br>shrink-swell,<br>slope,<br>depth to rock. | Severe:<br>depth to rock.                         | Severe:<br>slope.                                      | Moderate:<br>depth to rock,<br>shrink-swell,<br>slope. | Moderate:<br>slope,<br>depth to rock.           |
| Rehfield-----             | Severe:<br>cutbanks cave.                  | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell.                        | Moderate:<br>shrink-swell,<br>slope.                   | Moderate:<br>frost action,<br>shrink-swell.            | Slight.   |
| Rock outcrop.             |  |  |   |  |  |   |
| 25*:<br>Deerhorn-----     | Severe:<br>depth to rock.                  | Moderate:<br>shrink-swell,<br>depth to rock.           | Severe:<br>depth to rock.                         | Moderate:<br>shrink-swell,<br>slope,<br>depth to rock. | Moderate:<br>depth to rock,<br>shrink-swell.           | Moderate:<br>depth to rock.                     |
| Wildors-----              | Severe:<br>depth to rock,<br>large stones. | Severe:<br>large stones.                               | Severe:<br>depth to rock,<br>large stones.        | Severe:<br>large stones.                               | Severe:<br>large stones.                               | Severe:<br>large stones.                        |

See footnote at end of table.

TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol  | Shallow excavations                        | Dwellings without basements                            | Dwellings with basements                   | Small commercial buildings                            | Local roads and streets                                | Lawns and landscaping                       |
|---------------------------|--|--|--|---|--|---|
| 26*:<br>Deerhorn-----     | Severe:<br>depth to rock.                  | Moderate:<br>shrink-swell,<br>slope,<br>depth to rock. | Severe:<br>depth to rock.                  | Severe:<br>slope.                                     | Moderate:<br>depth to rock,<br>shrink-swell,<br>slope. | Moderate:<br>slope,<br>depth to rock.       |
| Wildors-----              | Severe:<br>depth to rock,<br>large stones. | Severe:<br>large stones.                               | Severe:<br>depth to rock,<br>large stones. | Severe:<br>slope,<br>large stones.                    | Severe:<br>large stones.                               | Severe:<br>large stones.                    |
| Trevino-----              | Severe:<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>large stones.             | Severe:<br>depth to rock,<br>large stones. | Severe:<br>slope,<br>depth to rock,<br>large stones.  | Severe:<br>depth to rock,<br>large stones.             | Severe:<br>large stones,<br>depth to rock.  |
| 27*:<br>Dollarhide-----   | Severe:<br>depth to rock,<br>slope.        | Severe:<br>slope,<br>depth to rock.                    | Severe:<br>depth to rock,<br>slope.        | Severe:<br>slope,<br>depth to rock.                   | Severe:<br>depth to rock,<br>slope.                    | Severe:<br>small stones,<br>slope.          |
| Rock outcrop.             |  |  |  |   |  |   |
| 28-----<br>Drage          | Moderate:<br>large stones.                 | Moderate:<br>shrink-swell,<br>large stones.            | Moderate:<br>large stones.                 | Moderate:<br>shrink-swell,<br>slope,<br>large stones. | Moderate:<br>shrink-swell,<br>frost action.            | Moderate:<br>small stones,<br>large stones. |
| 29, 30-----<br>Drage      | Moderate:<br>large stones,<br>slope.       | Moderate:<br>shrink-swell,<br>slope,<br>large stones.  | Moderate:<br>slope,<br>large stones.       | Severe:<br>slope.                                     | Moderate:<br>shrink-swell,<br>slope,<br>frost action.  | Moderate:<br>small stones,<br>large stones. |
| 31-----<br>Drage          | Moderate:<br>large stones.                 | Moderate:<br>shrink-swell,<br>large stones.            | Moderate:<br>large stones.                 | Moderate:<br>shrink-swell,<br>large stones.           | Moderate:<br>shrink-swell,<br>frost action.            | Severe:<br>small stones.                    |
| 32*:<br>Earcree-----      | Severe:<br>cutbanks cave,<br>slope.        | Severe:<br>slope.                                      | Severe:<br>slope.                          | Severe:<br>slope.                                     | Severe:<br>slope.                                      | Severe:<br>slope.                           |
| Lockman-----              | Severe:<br>cutbanks cave,<br>slope.        | Severe:<br>slope.                                      | Severe:<br>slope.                          | Severe:<br>slope.                                     | Severe:<br>slope.                                      | Severe:<br>slope.                           |
| 33*, 34*:<br>Earcree----- | Severe:<br>cutbanks cave,<br>slope.        | Severe:<br>slope.                                      | Severe:<br>slope.                          | Severe:<br>slope.                                     | Severe:<br>slope.                                      | Severe:<br>slope.                           |
| Moonstone-----            | Severe:<br>slope.                          | Severe:<br>slope.                                      | Severe:<br>slope.                          | Severe:<br>slope.                                     | Severe:<br>slope.                                      | Severe:<br>slope.                           |
| 35*:<br>Elkcreek-----     | Severe:<br>depth to rock,<br>slope.        | Severe:<br>slope.                                      | Severe:<br>depth to rock,<br>slope.        | Severe:<br>slope.                                     | Severe:<br>slope.                                      | Severe:<br>slope.                           |

See footnote at end of table.



TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol | Shallow excavations                                  | Dwellings without basements                          | Dwellings with basements                             | Small commercial buildings                           | Local roads and streets                                     | Lawns and landscaping                               |
|--------------------------|--|--|--|--|---|---|
| 35*:<br>Gaib-----        | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope,<br>depth to rock.                  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope,<br>depth to rock.                  | Severe:<br>depth to rock,<br>slope.                         | Severe:<br>small stones,<br>slope,<br>thin layer.   |
| 36*:<br>Elkcreek-----    | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>slope.   | Severe:<br>slope.                                   |
| Polecreek-----           | Severe:<br>depth to rock,<br>large stones.           | Severe:<br>depth to rock,<br>large stones.           | Severe:<br>depth to rock,<br>large stones.           | Severe:<br>slope,<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>large stones.                  | Severe:<br>large stones,<br>thin layer.             |
| 37*:<br>Elksel-----      | Severe:<br>large stones,<br>slope.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>low strength,<br>slope,<br>large stones.         | Severe:<br>large stones,<br>slope.                  |
| Friedman-----            | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.   | Severe:<br>slope.                                   |
| Starhope-----            | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>depth to rock,<br>slope,<br>shrink-swell. | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength,<br>slope,<br>shrink-swell.         | Severe:<br>large stones,<br>slope.                  |
| 38*:<br>Elksel-----      | Severe:<br>slope.                                    | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>slope,<br>shrink-swell.                   | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>slope,<br>shrink-swell.                          | Severe:<br>slope.                                   |
| Peevywell-----           | Severe:<br>cemented pan,<br>slope.                   | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>cemented pan,<br>slope,<br>shrink-swell.  | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength,<br>slope,<br>frost action.         | Severe:<br>slope.                                   |
| Furshur-----             | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>shrink-swell,<br>slope,<br>depth to rock. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>shrink-swell,<br>slope,<br>depth to rock. | Severe:<br>depth to rock,<br>cemented pan,<br>low strength. | Severe:<br>small stones,<br>slope,<br>depth to rock |
| 39*:<br>Elksel-----      | Severe:<br>large stones,<br>slope.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>low strength,<br>slope,<br>large stones.         | Severe:<br>large stones,<br>slope.                  |
| Starhope-----            | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>depth to rock,<br>slope,<br>shrink-swell. | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength,<br>slope,<br>shrink-swell.         | Severe:<br>large stones,<br>slope.                  |
| Rock outcrop.            |  |  |  |  |   |   |
| 40*:<br>Friedman-----    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.   | Severe:<br>slope.                                   |

See footnote at end of table.

TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol | Shallow excavations                          | Dwellings without basements                  | Dwellings with basements                     | Small commercial buildings                             | Local roads and streets                             | Lawns and landscaping                             |
|--------------------------|--|--|--|--|---|---|
| 40*:<br>Elksel-----      | Severe:<br>large stones,<br>slope.           | Severe:<br>slope,<br>large stones.           | Severe:<br>slope,<br>large stones.           | Severe:<br>slope,<br>large stones.                     | Severe:<br>low strength,<br>slope,<br>large stones. | Severe:<br>large stones,<br>slope.                |
| Winridge-----            | Severe:<br>depth to rock,<br>slope.          | Severe:<br>slope.                            | Severe:<br>depth to rock,<br>slope.          | Severe:<br>slope.                                      | Severe:<br>slope.                                   | Severe:<br>slope.                                 |
| 41*:<br>Gaib-----        | Severe:<br>depth to rock,<br>slope.          | Severe:<br>slope,<br>depth to rock.          | Severe:<br>depth to rock,<br>slope.          | Severe:<br>slope,<br>depth to rock.                    | Severe:<br>depth to rock,<br>slope.                 | Severe:<br>small stones,<br>slope,<br>thin layer. |
| Rock outcrop.            |  |  |  |  |   |   |
| 42-----<br>Gimlett       | Severe:<br>cutbanks cave.                    | Moderate:<br>large stones.                   | Moderate:<br>large stones.                   | Moderate:<br>large stones.                             | Moderate:<br>large stones.                          | Severe:<br>small stones,<br>droughty.             |
| 43*:<br>Gooding-----     | Moderate:<br>depth to rock,<br>too clayey.   | Severe:<br>shrink-swell.                     | Severe:<br>shrink-swell.                     | Severe:<br>shrink-swell.                               | Severe:<br>shrink-swell,<br>low strength.           | Slight.   |
| Gooding, eroded--        | Moderate:<br>depth to rock,<br>too clayey.   | Severe:<br>shrink-swell.                     | Severe:<br>shrink-swell.                     | Severe:<br>shrink-swell.                               | Severe:<br>shrink-swell,<br>low strength.           | Severe:<br>large stones.                          |
| Hamrub-----              | Moderate:<br>depth to rock,<br>cemented pan. | Moderate:<br>shrink-swell.                   | Moderate:<br>depth to rock,<br>cemented pan. | Moderate:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength.                            | Slight.   |
| 44-----<br>Goodington    | Moderate:<br>depth to rock,<br>too clayey.   | Severe:<br>shrink-swell.                     | Moderate:<br>depth to rock,<br>shrink-swell. | Severe:<br>shrink-swell.                               | Severe:<br>low strength,<br>shrink-swell.           | Slight.   |
| 45*:<br>Goodington-----  | Moderate:<br>depth to rock,<br>too clayey.   | Severe:<br>shrink-swell.                     | Moderate:<br>depth to rock,<br>shrink-swell. | Severe:<br>shrink-swell.                               | Severe:<br>low strength,<br>shrink-swell.           | Slight.   |
| Manard-----              | Severe:<br>depth to rock,<br>cemented pan.   | Moderate:<br>shrink-swell,<br>depth to rock. | Severe:<br>depth to rock,<br>cemented pan.   | Moderate:<br>shrink-swell,<br>slope,<br>depth to rock. | Severe:<br>low strength.                            | Moderate:<br>large stones,<br>depth to rock.      |
| 46-----<br>Hapur         | Severe:<br>cutbanks cave,<br>wetness.        | Severe:<br>flooding,<br>wetness.             | Severe:<br>flooding,<br>wetness.             | Severe:<br>flooding,<br>wetness.                       | Severe:<br>low strength,<br>wetness,<br>flooding.   | Severe:<br>wetness,<br>flooding.                  |
| 47*:<br>Hapur-----       | Severe:<br>cutbanks cave,<br>wetness.        | Severe:<br>flooding,<br>wetness.             | Severe:<br>flooding,<br>wetness.             | Severe:<br>flooding,<br>wetness.                       | Severe:<br>low strength,<br>wetness,<br>flooding.   | Severe:<br>wetness,<br>flooding.                  |

See footnote at end of table.



TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol  | Shallow excavations                   | Dwellings without basements           | Dwellings with basements                          | Small commercial buildings            | Local roads and streets                                | Lawns and landscaping                             |
|---------------------------|---------------------------------------|---------------------------------------|---|---------------------------------------|--|---|
| 47*:<br>Bickett-----      | Severe:<br>ponding.                   | Severe:<br>flooding,<br>ponding.      | Severe:<br>flooding,<br>ponding.                  | Severe:<br>flooding,<br>ponding.      | Severe:<br>low strength,<br>ponding,<br>flooding.      | Severe:<br>ponding,<br>flooding,<br>excess humus. |
| 48*:<br>Hapur-----        | Severe:<br>cutbanks cave,<br>wetness. | Severe:<br>flooding,<br>wetness.      | Severe:<br>flooding,<br>wetness.                  | Severe:<br>flooding,<br>wetness.      | Severe:<br>low strength,<br>wetness,<br>flooding.      | Severe:<br>wetness,<br>flooding.                  |
| Picabo-----               | Severe:<br>wetness.                   | Severe:<br>flooding.                  | Severe:<br>flooding,<br>wetness.                  | Severe:<br>flooding.                  | Severe:<br>flooding,<br>frost action.                  | Moderate:<br>excess salt,<br>flooding.            |
| 49-----<br>Hutton         | Severe:<br>wetness.                   | Severe:<br>flooding,<br>shrink-swell. | Severe:<br>flooding,<br>wetness,<br>shrink-swell. | Severe:<br>flooding,<br>shrink-swell. | Severe:<br>low strength,<br>flooding,<br>frost action. | Moderate:<br>wetness,<br>flooding.                |
| 50-----<br>Hutton Variant | Severe:<br>cutbanks cave.             | Moderate:<br>shrink-swell.            | Slight-----                                       | Moderate:<br>shrink-swell.            | Moderate:<br>shrink-swell,<br>frost action.            | Slight.   |
| 51-----<br>Isknat         | Severe:<br>cutbanks cave.             | Moderate:<br>shrink-swell.            | Slight-----                                       | Moderate:<br>shrink-swell.            | Moderate:<br>shrink-swell,<br>frost action.            | Moderate:<br>small stones,<br>droughty.           |
| 52-----<br>Justesen       | Slight-----                           | Slight-----                           | Slight-----                                       | Slight-----                           | Moderate:<br>frost action.                             | Slight.   |
| 53-----<br>Justesen       | Slight-----                           | Slight-----                           | Slight-----                                       | Moderate:<br>slope.                   | Moderate:<br>frost action.                             | Slight.   |
| 54-----<br>Justesen       | Moderate:<br>slope.                   | Moderate:<br>slope.                   | Moderate:<br>slope.                               | Severe:<br>slope.                     | Moderate:<br>slope,<br>frost action.                   | Moderate:<br>slope.                               |
| 55-----<br>Justesen       | Severe:<br>slope.                     | Severe:<br>slope.                     | Severe:<br>slope.                                 | Severe:<br>slope.                     | Severe:<br>slope.                                      | Severe:<br>slope.                                 |
| 56*:<br>Ketchum-----      | Severe:<br>slope.                     | Severe:<br>slope.                     | Severe:<br>slope.                                 | Severe:<br>slope.                     | Severe:<br>slope.                                      | Severe:<br>small stones,<br>slope.                |
| Dollarhide-----           | Severe:<br>depth to rock,<br>slope.   | Severe:<br>slope,<br>depth to rock.   | Severe:<br>depth to rock,<br>slope.               | Severe:<br>slope,<br>depth to rock.   | Severe:<br>depth to rock,<br>slope.                    | Severe:<br>small stones,<br>slope.                |
| 57*:<br>Ketchum-----      | Severe:<br>slope.                     | Severe:<br>slope.                     | Severe:<br>slope.                                 | Severe:<br>slope.                     | Severe:<br>slope.                                      | Severe:<br>small stones,<br>slope.                |
| Povey-----                | Severe:<br>slope.                     | Severe:<br>slope.                     | Severe:<br>slope.                                 | Severe:<br>slope.                     | Severe:<br>slope.                                      | Moderate:<br>small stones,<br>droughty.           |

See footnote at end of table.

TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol    | Shallow excavations                        | Dwellings without basements                | Dwellings with basements                               | Small commercial buildings                           | Local roads and streets                     | Lawns and landscaping                                    |
|-----------------------------|--|--|--|--|---|--|
| 58*:<br>Laurentzen-----     | Moderate:<br>depth to rock,<br>slope.      | Moderate:<br>shrink-swell,<br>slope.       | Moderate:<br>depth to rock,<br>slope,<br>shrink-swell. | Severe:<br>slope.                                    | Severe:<br>low strength,<br>frost action.   | Moderate:<br>slope.                                      |
| Mulshoe-----                | Severe:<br>depth to rock.                  | Severe:<br>slope,<br>large stones.         | Severe:<br>depth to rock,<br>slope.                    | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.          | Severe:<br>large stones,<br>slope.                       |
| 59*:<br>Lava flows          |  |  |  |  |   |  |
| 60*:<br>Lava flows.         |  |  |  |  |   |  |
| Cinderhurst-----            | Severe:<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>large stones.             | Severe:<br>slope,<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>large stones.  | Severe:<br>small stones,<br>large stones,<br>thin layer. |
| 61*, 62*:<br>Lavacreek----- | Severe:<br>slope.                          | Severe:<br>slope.                          | Severe:<br>slope.                                      | Severe:<br>slope.                                    | Severe:<br>slope.                           | Severe:<br>small stones,<br>slope.                       |
| Dollarhide-----             | Severe:<br>depth to rock,<br>slope.        | Severe:<br>slope,<br>depth to rock.        | Severe:<br>depth to rock,<br>slope.                    | Severe:<br>slope,<br>depth to rock.                  | Severe:<br>depth to rock,<br>slope.         | Severe:<br>small stones,<br>slope.                       |
| 63*:<br>Lavacreek-----      | Severe:<br>slope.                          | Severe:<br>slope.                          | Severe:<br>slope.                                      | Severe:<br>slope.                                    | Severe:<br>slope.                           | Severe:<br>small stones,<br>slope.                       |
| Vitale-----                 | Severe:<br>depth to rock,<br>slope.        | Severe:<br>slope.                          | Severe:<br>depth to rock,<br>slope.                    | Severe:<br>slope.                                    | Severe:<br>slope.                           | Severe:<br>small stones,<br>slope.                       |
| 64, 65-----<br>Little Wood  | Severe:<br>cutbanks cave.                  | Moderate:<br>shrink-swell.                 | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell,<br>frost action. | Moderate:<br>small stones,<br>droughty.                  |
| 66, 67-----<br>Little Wood  | Severe:<br>cutbanks cave.                  | Moderate:<br>shrink-swell.                 | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell,<br>frost action. | Severe:<br>small stones.                                 |
| 68-----<br>Little Wood      | Severe:<br>cutbanks cave.                  | Moderate:<br>large stones.                 | Moderate:<br>large stones.                             | Moderate:<br>large stones.                           | Moderate:<br>frost action,<br>large stones. | Severe:<br>small stones.                                 |
| 69*:<br>Little Wood-----    | Severe:<br>cutbanks cave.                  | Moderate:<br>shrink-swell.                 | Moderate:<br>shrink-swell.                             | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell,<br>frost action. | Severe:<br>small stones.                                 |
| Balaam-----                 | Severe:<br>cutbanks cave.                  | Slight-----                                | Slight-----  | Slight-----  | Slight-----                                 | Moderate:<br>small stones,<br>droughty.                  |

See footnote at end of table.



TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol | Shallow excavations                   | Dwellings without basements           | Dwellings with basements                   | Small commercial buildings            | Local roads and streets                                | Lawns and landscaping                           |
|--------------------------|---------------------------------------|---------------------------------------|--|---------------------------------------|--|---|
| 70-----<br>Manard        | Severe:<br>depth to rock.             | Severe:<br>shrink-swell.              | Severe:<br>depth to rock,<br>shrink-swell. | Severe:<br>shrink-swell.              | Severe:<br>shrink-swell,<br>low strength.              | Moderate:<br>depth to rock.                     |
| 71-----<br>Marshdale     | Severe:<br>cutbanks cave,<br>wetness. | Severe:<br>flooding,<br>wetness.      | Severe:<br>flooding,<br>wetness.           | Severe:<br>flooding,<br>wetness.      | Severe:<br>wetness,<br>flooding,<br>frost action.      | Severe:<br>wetness,<br>flooding.                |
| 72*:<br>Marshdale-----   | Severe:<br>cutbanks cave,<br>wetness. | Severe:<br>flooding,<br>wetness.      | Severe:<br>flooding,<br>wetness.           | Severe:<br>flooding,<br>wetness.      | Severe:<br>wetness,<br>flooding,<br>frost action.      | Severe:<br>wetness,<br>flooding.                |
| Bruneel-----             | Severe:<br>cutbanks cave,<br>wetness. | Severe:<br>flooding,<br>wetness.      | Severe:<br>flooding,<br>wetness.           | Severe:<br>flooding,<br>wetness.      | Severe:<br>flooding,<br>frost action.                  | Moderate:<br>wetness,<br>droughty,<br>flooding. |
| 73-----<br>McBiggam      | Moderate:<br>too clayey.              | Moderate:<br>shrink-swell.            | Severe:<br>shrink-swell.                   | Moderate:<br>shrink-swell,<br>slope.  | Severe:<br>low strength,<br>frost action.              | Slight.   |
| 74*:<br>McCarey-----     | Severe:<br>depth to rock.             | Moderate:<br>depth to rock.           | Severe:<br>depth to rock.                  | Moderate:<br>slope,<br>depth to rock. | Moderate:<br>depth to rock,<br>frost action.           | Moderate:<br>depth to rock.                     |
| Justesen-----            | Slight-----                           | Slight-----                           | Slight-----                                | Moderate:<br>slope.                   | Moderate:<br>frost action.                             | Slight.   |
| 75*:<br>McCarey-----     | Severe:<br>depth to rock.             | Moderate:<br>slope,<br>depth to rock. | Severe:<br>depth to rock.                  | Severe:<br>slope.                     | Moderate:<br>depth to rock,<br>slope,<br>frost action. | Moderate:<br>slope,<br>depth to rock.           |
| Justesen-----            | Moderate:<br>slope.                   | Moderate:<br>slope.                   | Moderate:<br>slope.                        | Severe:<br>slope.                     | Moderate:<br>slope,<br>frost action.                   | Moderate:<br>slope.                             |
| Rock outcrop.            |                                       |                                       |  |                                       |  |   |
| 76*:<br>McCarey-----     | Severe:<br>depth to rock.             | Moderate:<br>depth to rock.           | Severe:<br>depth to rock.                  | Moderate:<br>slope,<br>depth to rock. | Moderate:<br>depth to rock,<br>frost action.           | Moderate:<br>depth to rock.                     |
| Molyneux-----            | Slight-----                           | Moderate:<br>shrink-swell.            | Moderate:<br>shrink-swell.                 | Moderate:<br>shrink-swell,<br>slope.  | Moderate:<br>low strength,<br>frost action.            | Slight.   |
| 77*:<br>McCarey-----     | Severe:<br>depth to rock,<br>slope.   | Severe:<br>slope.                     | Severe:<br>depth to rock,<br>slope.        | Severe:<br>slope.                     | Severe:<br>slope.                                      | Severe:<br>slope.                               |

See footnote at end of table.

TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol | Shallow excavations                                 | Dwellings without basements                           | Dwellings with basements                              | Small commercial buildings           | Local roads and streets                               | Lawns and landscaping                               |
|--------------------------|---|---|---|--------------------------------------|---|---|
| 77*:<br>Pedleford-----   | Severe:<br>depth to rock,<br>slope.                 | Severe:<br>slope.                                     | Severe:<br>depth to rock,<br>slope.                   | Severe:<br>slope.                    | Severe:<br>slope.                                     | Severe:<br>small stones,<br>large stones,<br>slope. |
| 78-----<br>Molyneux      | Slight-----   | Moderate:<br>shrink-swell.                            | Moderate:<br>shrink-swell.                            | Moderate:<br>shrink-swell.           | Moderate:<br>low strength,<br>frost action.           | Slight.   |
| 79-----<br>Molyneux      | Slight-----   | Moderate:<br>shrink-swell.                            | Moderate:<br>shrink-swell.                            | Moderate:<br>shrink-swell,<br>slope. | Moderate:<br>low strength,<br>frost action.           | Slight.   |
| 80-----<br>Molyneux      | Moderate:<br>slope.                                 | Moderate:<br>shrink-swell,<br>slope.                  | Moderate:<br>slope,<br>shrink-swell.                  | Severe:<br>slope.                    | Moderate:<br>low strength,<br>slope,<br>frost action. | Moderate:<br>slope.                                 |
| 81*:<br>Moonstone-----   | Severe:<br>slope.                                   | Severe:<br>slope.                                     | Severe:<br>slope.                                     | Severe:<br>slope.                    | Severe:<br>slope.                                     | Severe:<br>slope.                                   |
| Bauscher-----            | Moderate:<br>slope.                                 | Moderate:<br>shrink-swell,<br>slope.                  | Moderate:<br>slope,<br>shrink-swell.                  | Severe:<br>slope.                    | Moderate:<br>shrink-swell,<br>slope,<br>frost action. | Moderate:<br>slope.                                 |
| 82*:<br>Moonstone-----   | Severe:<br>slope.                                   | Severe:<br>slope.                                     | Severe:<br>slope.                                     | Severe:<br>slope.                    | Severe:<br>slope.                                     | Severe:<br>slope.                                   |
| Earcree-----             | Severe:<br>cutbanks cave,<br>slope.                 | Severe:<br>slope.                                     | Severe:<br>slope.                                     | Severe:<br>slope.                    | Severe:<br>slope.                                     | Severe:<br>slope.                                   |
| 83*:<br>Muldoon-----     | Moderate:<br>cemented pan,<br>too clayey,<br>slope. | Moderate:<br>shrink-swell,<br>slope.                  | Moderate:<br>cemented pan,<br>slope,<br>shrink-swell. | Severe:<br>slope.                    | Severe:<br>low strength.                              | Moderate:<br>slope.                                 |
| Peevywell-----           | Severe:<br>cemented pan.                            | Moderate:<br>shrink-swell,<br>slope,<br>cemented pan. | Severe:<br>cemented pan.                              | Severe:<br>slope.                    | Severe:<br>low strength.                              | Moderate:<br>large stones,<br>slope,<br>thin layer. |
| 84*:<br>Mulshoe-----     | Severe:<br>depth to rock.                           | Severe:<br>slope,<br>large stones.                    | Severe:<br>depth to rock,<br>slope.                   | Severe:<br>slope,<br>large stones.   | Severe:<br>slope,<br>large stones.                    | Severe:<br>large stones,<br>slope.                  |
| Gaib-----                | Severe:<br>depth to rock,<br>slope.                 | Severe:<br>slope,<br>depth to rock.                   | Severe:<br>depth to rock,<br>slope.                   | Severe:<br>slope,<br>depth to rock.  | Severe:<br>depth to rock,<br>slope.                   | Severe:<br>slope,<br>thin layer.                    |
| Rock outcrop.            |   |   |   |                                      |   |   |

See footnote at end of table.



TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol | Shallow excavations                 | Dwellings without basements                 | Dwellings with basements             | Small commercial buildings                            | Local roads and streets                               | Lawns and landscaping                                  |
|--------------------------|-------------------------------------|---|--------------------------------------|---|---|--|
| 85*:<br>Mulshoe-----     | Severe:<br>depth to rock.           | Severe:<br>slope,<br>large stones.          | Severe:<br>depth to rock,<br>slope.  | Severe:<br>slope,<br>large stones.                    | Severe:<br>slope,<br>large stones.                    | Severe:<br>large stone<br>slope.                       |
| Gaib-----                | Severe:<br>depth to rock,<br>slope. | Severe:<br>slope,<br>depth to rock.         | Severe:<br>depth to rock,<br>slope.  | Severe:<br>slope,<br>depth to rock.                   | Severe:<br>depth to rock,<br>slope.                   | Severe:<br>small stone<br>slope,<br>thin layer.        |
| Winu-----                | Severe:<br>depth to rock,<br>slope. | Severe:<br>slope.                           | Severe:<br>depth to rock,<br>slope.  | Severe:<br>slope.                                     | Severe:<br>slope.                                     | Severe:<br>slope.                                      |
| 86*:<br>Pagari-----      | Severe:<br>large stones.            | Severe:<br>large stones.                    | Severe:<br>large stones.             | Severe:<br>slope,<br>large stones.                    | Severe:<br>large stones.                              | Severe:<br>large stones.                               |
| Rehfield-----            | Severe:<br>cutbanks cave.           | Moderate:<br>shrink-swell.                  | Moderate:<br>shrink-swell.           | Moderate:<br>shrink-swell,<br>slope.                  | Moderate:<br>frost action,<br>shrink-swell.           | Slight.  |
| 87*:<br>Peevywell-----   | Severe:<br>cemented pan.            | Moderate:<br>shrink-swell,<br>cemented pan. | Severe:<br>cemented pan.             | Moderate:<br>shrink-swell,<br>slope,<br>cemented pan. | Severe:<br>low strength.                              | Moderate:<br>large stones<br>thin layer.               |
| Simonton-----            | Severe:<br>cutbanks cave.           | Moderate:<br>shrink-swell.                  | Moderate:<br>shrink-swell.           | Moderate:<br>shrink-swell,<br>slope.                  | Moderate:<br>frost action,<br>shrink-swell.           | Slight.  |
| 88*:<br>Peevywell-----   | Severe:<br>cemented pan,<br>slope.  | Severe:<br>slope.                           | Severe:<br>cemented pan,<br>slope.   | Severe:<br>slope.                                     | Severe:<br>low strength,<br>slope.                    | Severe:<br>slope.                                      |
| Simonton-----            | Severe:<br>cutbanks cave.           | Moderate:<br>shrink-swell,<br>slope.        | Moderate:<br>slope,<br>shrink-swell. | Severe:<br>slope.                                     | Moderate:<br>slope,<br>frost action,<br>shrink-swell. | Moderate:<br>slope.                                    |
| 89-----<br>Picabo        | Severe:<br>wetness.                 | Severe:<br>flooding.                        | Severe:<br>flooding,<br>wetness.     | Severe:<br>flooding.                                  | Severe:<br>flooding,<br>frost action.                 | Moderate:<br>excess salt,<br>flooding.                 |
| 90-----<br>Picabo        | Severe:<br>wetness.                 | Severe:<br>flooding.                        | Severe:<br>flooding,<br>wetness.     | Severe:<br>flooding.                                  | Severe:<br>flooding,<br>frost action.                 | Moderate:<br>excess salt,<br>small stones<br>flooding. |
| 91*.<br>Pits, gravel     |                                     |   |                                      |   |   |  |

See footnote at end of table.

TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol                         | Shallow excavations                                  | Dwellings without basements          | Dwellings with basements                             | Small commercial buildings          | Local roads and streets                               | Lawns and landscaping                               |
|--|--|--------------------------------------|--|-------------------------------------|---|---|
| 92*:<br>Povey-----                               | Severe:<br>slope.                                    | Severe:<br>slope.                    | Severe:<br>slope.                                    | Severe:<br>slope.                   | Severe:<br>slope.                                     | Moderate:<br>small stones,<br>droughty.             |
| Dollarhide-----                                  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope,<br>depth to rock.  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope,<br>depth to rock. | Severe:<br>depth to rock,<br>slope.                   | Severe:<br>small stones,<br>slope.                  |
| 93*:<br>Povey-----                               | Severe:<br>slope.                                    | Severe:<br>slope.                    | Severe:<br>slope.                                    | Severe:<br>slope.                   | Severe:<br>slope.                                     | Moderate:<br>small stones,<br>droughty.             |
| Rock outcrop.                                    |  |                                      |  |                                     |   |   |
| 94*:<br>Povey very<br>gravelly silt<br>loam----- | Severe:<br>slope.                                    | Severe:<br>slope.                    | Severe:<br>slope.                                    | Severe:<br>slope.                   | Severe:<br>slope.                                     | Severe:<br>small stones.                            |
| Povey gravelly<br>loam-----                      | Severe:<br>slope.                                    | Severe:<br>slope.                    | Severe:<br>slope.                                    | Severe:<br>slope.                   | Severe:<br>slope.                                     | Moderate:<br>small stones,<br>droughty.             |
| 95*:<br>Povey-----                               | Severe:<br>slope.                                    | Severe:<br>slope.                    | Severe:<br>slope.                                    | Severe:<br>slope.                   | Severe:<br>slope.                                     | Moderate:<br>small stones,<br>droughty.             |
| Vitale-----                                      | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                    | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                   | Severe:<br>slope.                                     | Severe:<br>small stones,<br>slope.                  |
| 96*:<br>Rehfield-----                            | Severe:<br>cutbanks cave.                            | Moderate:<br>shrink-swell,<br>slope. | Moderate:<br>slope,<br>shrink-swell.                 | Severe:<br>slope.                   | Moderate:<br>slope,<br>frost action,<br>shrink-swell. | Moderate:<br>slope.                                 |
| Gooding-----                                     | Moderate:<br>depth to rock,<br>too clayey,<br>slope. | Severe:<br>shrink-swell.             | Severe:<br>shrink-swell.                             | Severe:<br>shrink-swell,<br>slope.  | Severe:<br>shrink-swell,<br>low strength.             | Moderate:<br>slope.                                 |
| 97*.<br>Riverwash                                |  |                                      |  |                                     |   |   |
| 98*:<br>Rock outcrop.                            |  |                                      |  |                                     |   |   |
| Adios-----                                       | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>shrink-swell,<br>slope.   | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>shrink-swell,<br>slope.  | Severe:<br>low strength,<br>slope,<br>shrink-swell.   | Severe:<br>slope.                                   |
| 99-----<br>Rockybar                              | Severe:<br>large stones,<br>slope.                   | Severe:<br>slope,<br>large stones.   | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.  | Severe:<br>slope,<br>large stones.                    | Severe:<br>small stones,<br>large stones,<br>slope. |

See footnote at end of table.



TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and map symbol | Shallow excavations                                  | Dwellings without basements                           | Dwellings with basements                             | Small commercial buildings                           | Local roads and streets                                     | Lawns and landscaping                              |
|--------------------------|--|---|--|--|---|--|
| 100*.<br>Rubbleland      |  |   |  |  |   |  |
| 101*:<br>Rubbleland.     |  |   |  |  |   |  |
| Milligan-----            | Severe:<br>depth to rock,<br>large stones,<br>slope. | Severe:<br>slope,<br>large stones.                    | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.                          | Severe:<br>large stones<br>slope.                  |
| 102-----<br>Simonton     | Severe:<br>cutbanks cave.                            | Moderate:<br>shrink-swell.                            | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell.                           | Moderate:<br>frost action,<br>shrink-swell.                 | Slight.  |
| 103-----<br>Simonton     | Severe:<br>cutbanks cave.                            | Moderate:<br>shrink-swell.                            | Moderate:<br>shrink-swell.                           | Moderate:<br>shrink-swell,<br>slope.                 | Moderate:<br>frost action,<br>shrink-swell.                 | Slight.  |
| 104*:<br>Simonton-----   | Severe:<br>cutbanks cave.                            | Moderate:<br>shrink-swell,<br>slope.                  | Moderate:<br>slope,<br>shrink-swell.                 | Severe:<br>slope.                                    | Moderate:<br>slope,<br>frost action,<br>shrink-swell.       | Moderate:<br>slope.                                |
| Bauscher-----            | Moderate:<br>slope.                                  | Moderate:<br>shrink-swell,<br>slope.                  | Moderate:<br>slope,<br>shrink-swell.                 | Severe:<br>slope.                                    | Moderate:<br>shrink-swell,<br>slope,<br>frost action.       | Moderate:<br>slope.                                |
| 105*:<br>Starhope-----   | Severe:<br>depth to rock.                            | Severe:<br>shrink-swell.                              | Severe:<br>depth to rock,<br>shrink-swell.           | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength,<br>shrink-swell.                   | Moderate:<br>slope,<br>thin layer.                 |
| Furshur-----             | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>shrink-swell,<br>depth to rock.            | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>shrink-swell,<br>slope,<br>depth to rock. | Severe:<br>depth to rock,<br>cemented pan,<br>low strength. | Severe:<br>small stones<br>depth to roc            |
| 106*:<br>Starhope-----   | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>shrink-swell,<br>slope.                    | Severe:<br>depth to rock,<br>slope,<br>shrink-swell. | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength,<br>slope,<br>shrink-swell.         | Severe:<br>slope.                                  |
| Peevywell-----           | Severe:<br>cemented pan.                             | Moderate:<br>shrink-swell,<br>slope,<br>cemented pan. | Severe:<br>cemented pan.                             | Severe:<br>slope.                                    | Severe:<br>low strength.                                    | Moderate:<br>large stones<br>slope,<br>thin layer. |
| Smelter-----             | Severe:<br>slope.                                    | Severe:<br>shrink-swell,<br>slope.                    | Severe:<br>slope.                                    | Severe:<br>shrink-swell,<br>slope.                   | Severe:<br>low strength,<br>slope,<br>shrink-swell.         | Severe:<br>slope.                                  |
| 107*:<br>Vitale-----     | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                     | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>slope.   | Severe:<br>small stones<br>slope.                  |

See footnote at end of table.

TABLE 9.--BUILDING SITE DEVELOPMENT--Continued

| Soil name and<br>map symbol | Shallow<br>excavations                               | Dwellings<br>without<br>basements                    | Dwellings<br>with<br>basements                       | Small<br>commercial<br>buildings                     | Local roads<br>and streets                           | Lawns and<br>landscaping                               |
|-----------------------------|--|--|--|--|--|--|
| 107*:<br>Blackspar-----     | Severe:<br>depth to rock,<br>large stones,<br>slope. | Severe:<br>slope,<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope,<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>small stones,<br>large stones,<br>droughty. |
| 108*:<br>Vitale-----        | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>small stones,<br>slope.                     |
| Milligan-----               | Severe:<br>depth to rock,<br>large stones,<br>slope. | Severe:<br>slope,<br>large stones.                   | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope,<br>large stones.                   | Severe:<br>slope,<br>large stones.                   | Severe:<br>large stones,<br>slope.                     |
| 109*:<br>Vitale-----        | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>small stones,<br>slope.                     |
| Povey-----                  | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Moderate:<br>small stones,<br>droughty.                |
| 110*:<br>Winu-----          | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                      |
| Rock outcrop.               |  |  |  |  |  |  |
| 111*:<br>Winu-----          | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>slope.                                      |
| Gaib-----                   | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope,<br>depth to rock.                  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>slope,<br>depth to rock.                  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>small stones,<br>slope,<br>thin layer.      |

\* See description of the map unit for composition and behavior characteristics of the map unit.



TABLE 10.--SANITARY FACILITIES

(Some terms that describe restrictive soil features are defined in the Glossary. See text for definitions of "slight," "good," and other terms. Absence of an entry indicates that the soil was not rated. The information in this table indicates the dominant soil condition but does not eliminate the need for onsite investigation)

| Soil name and map symbol | Septic tank absorption fields                        | Sewage lagoon areas                                  | Trench sanitary landfill                             | Area sanitary landfill                               | Daily cover for landfill                                |
|--------------------------|--|--|--|--|---|
| 1-----<br>Adamson        | Severe:<br>poor filter.                              | Severe:<br>seepage.                                  | Severe:<br>seepage,<br>too sandy.                    | Severe:<br>seepage.                                  | Poor:<br>seepage,<br>too sandy,<br>small stones.        |
| 2*:<br>Adios-----        | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>depth to rock,<br>cemented pan.           | Poor:<br>depth to rock,<br>too clayey,<br>hard to pack. |
| Gooding-----             | Severe:<br>percs slowly.                             | Severe:<br>slope.                                    | Severe:<br>depth to rock.                            | Moderate:<br>slope.                                  | Poor:<br>hard to pack.                                  |
| Bostrum-----             | Severe:<br>depth to rock,<br>percs slowly.           | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock.                            | Severe:<br>depth to rock.                            | Poor:<br>depth to rock.                                 |
| 3*:<br>Adios-----        | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Poor:<br>depth to rock,<br>too clayey,<br>hard to pack. |
| Adios, cool-----         | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Poor:<br>depth to rock,<br>too clayey,<br>hard to pack. |
| 4, 5-----<br>Balaam      | Severe:<br>poor filter.                              | Severe:<br>seepage.                                  | Severe:<br>seepage,<br>too sandy.                    | Severe:<br>seepage.                                  | Poor:<br>seepage,<br>too sandy,<br>small stones.        |
| 6*:<br>Balaam-----       | Severe:<br>poor filter.                              | Severe:<br>seepage.                                  | Severe:<br>seepage,<br>too sandy.                    | Severe:<br>seepage.                                  | Poor:<br>seepage,<br>too sandy,<br>small stones.        |
| Adamson-----             | Severe:<br>poor filter.                              | Severe:<br>seepage.                                  | Severe:<br>seepage,<br>too sandy.                    | Severe:<br>seepage.                                  | Poor:<br>seepage,<br>too sandy,<br>small stones.        |
| 7*:<br>Balaam-----       | Severe:<br>poor filter.                              | Severe:<br>seepage.                                  | Severe:<br>seepage,<br>too sandy,<br>large stones.   | Severe:<br>seepage.                                  | Poor:<br>seepage,<br>too sandy,<br>small stones.        |
| Adamson-----             | Severe:<br>poor filter.                              | Severe:<br>seepage.                                  | Severe:<br>seepage,<br>too sandy,<br>large stones.   | Severe:<br>seepage.                                  | Poor:<br>too sandy,<br>large stones.                    |

See footnote at end of table.

TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and<br>map symbol | Septic tank<br>absorption<br>fields                  | Sewage lagoon<br>areas                                 | Trench<br>sanitary<br>landfill                         | Area<br>sanitary<br>landfill                         | Daily cover<br>for landfill                        |
|-----------------------------|--|--|--|--|--|
| 8*:<br>Balaam-----          | Severe:<br>flooding,<br>poor filter.                 | Severe:<br>seepage,<br>flooding.                       | Severe:<br>flooding,<br>seepage,<br>too sandy.         | Severe:<br>flooding,<br>seepage.                     | Poor:<br>seepage,<br>too sandy,<br>small stones.   |
| Adamson-----                | Severe:<br>flooding,<br>poor filter.                 | Severe:<br>seepage,<br>flooding.                       | Severe:<br>flooding,<br>seepage,<br>wetness.           | Severe:<br>flooding,<br>seepage.                     | Poor:<br>seepage,<br>too sandy,<br>large stones.   |
| Riverwash.                  |  |  |  |  |  |
| 9, 10-----<br>Bancroft      | Moderate:<br>percs slowly.                           | Moderate:<br>seepage,<br>slope.                        | Moderate:<br>too clayey.                               | Slight-----  | Fair:<br>too clayey.                               |
| 11-----<br>Bickett          | Severe:<br>flooding,<br>ponding,<br>percs slowly.    | Severe:<br>flooding,<br>excess humus,<br>ponding.      | Severe:<br>flooding,<br>ponding.                       | Severe:<br>flooding,<br>ponding.                     | Poor:<br>ponding.                                  |
| 12*:<br>Blackspar-----      | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones.   | Severe:<br>depth to rock,<br>slope,<br>large stones.   | Severe:<br>depth to rock,<br>slope.                  | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| Rock outcrop.               |  |  |  |  |  |
| 13*:<br>Blackspot-----      | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>seepage,<br>depth to rock,<br>cemented pan. | Severe:<br>depth to rock,<br>cemented pan,<br>seepage. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| Prudy-----                  | Severe:<br>slope.                                    | Severe:<br>slope.                                      | Severe:<br>depth to rock,<br>cemented pan,<br>slope.   | Severe:<br>slope.                                    | Poor:<br>slope.                                    |
| 14*:<br>Bostrum-----        | Severe:<br>depth to rock,<br>percs slowly.           | Severe:<br>depth to rock.                              | Severe:<br>depth to rock.                              | Severe:<br>depth to rock.                            | Poor:<br>depth to rock.                            |
| Yutru-----                  | Severe:<br>percs slowly.                             | Moderate:<br>slope,<br>large stones.                   | Moderate:<br>large stones.                             | Slight-----  | Fair:<br>large stones.                             |
| Hamrub-----                 | Severe:<br>percs slowly.                             | Severe:<br>slope.                                      | Severe:<br>depth to rock,<br>cemented pan.             | Moderate:<br>depth to rock,<br>cemented pan.         | Fair:<br>depth to rock,<br>too clayey.             |
| 15, 16, 17-----<br>Bringmee | Severe:<br>percs slowly.                             | Severe:<br>seepage.                                    | Severe:<br>seepage.                                    | Slight-----  | Fair:<br>too clayey,<br>thin layer.                |

See footnote at end of table.



TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and map symbol | Septic tank absorption fields                               | Sewage lagoon areas                                  | Trench sanitary landfill                               | Area sanitary landfill                       | Daily cover for landfill                         |
|--------------------------|---|--|--|--|--|
| 18*:<br>Bringmee-----    | Severe:<br>percs slowly.                                    | Severe:<br>seepage.                                  | Severe:<br>seepage.                                    | Slight-----                                  | Fair:<br>too clayey,<br>thin layer.              |
| Hutton-----              | Severe:<br>flooding,<br>wetness,<br>percs slowly.           | Severe:<br>flooding,<br>wetness.                     | Severe:<br>flooding,<br>wetness,<br>too clayey.        | Severe:<br>flooding,<br>wetness.             | Poor:<br>too clayey,<br>hard to pack.            |
| 19*:<br>Bringmee-----    | Severe:<br>percs slowly.                                    | Severe:<br>seepage.                                  | Severe:<br>seepage.                                    | Slight-----                                  | Fair:<br>too clayey,<br>thin layer.              |
| Little Wood-----         | Severe:<br>poor filter.                                     | Severe:<br>seepage.                                  | Severe:<br>seepage.                                    | Severe:<br>seepage.                          | Poor:<br>small stones.                           |
| 20-----<br>Bruneel       | Severe:<br>flooding,<br>wetness,<br>poor filter.            | Severe:<br>seepage,<br>flooding,<br>wetness.         | Severe:<br>flooding,<br>seepage,<br>wetness.           | Severe:<br>flooding,<br>seepage,<br>wetness. | Poor:<br>seepage,<br>too sandy,<br>small stones. |
| 21-----<br>Carey Lake    | Moderate:<br>wetness,<br>percs slowly.                      | Moderate:<br>seepage.                                | Severe:<br>wetness.                                    | Slight-----                                  | Fair:<br>too clayey.                             |
| 22-----<br>Carey Lake    | Moderate:<br>wetness,<br>percs slowly.                      | Moderate:<br>seepage,<br>slope.                      | Severe:<br>wetness.                                    | Slight-----                                  | Fair:<br>too clayey.                             |
| 23*:<br>Cox-----         | Severe:<br>depth to rock,<br>large stones.                  | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>seepage,<br>large stones. | Severe:<br>depth to rock,<br>seepage.        | Poor:<br>area reclaim,<br>large stones.          |
| Rehfield-----            | Moderate:<br>percs slowly.                                  | Moderate:<br>seepage,<br>slope.                      | Slight-----  | Slight-----                                  | Good.  |
| Rock outcrop.            |   |  |  |  |  |
| 24*:<br>Deerhorn-----    | Severe:<br>depth to rock,<br>cemented pan,<br>percs slowly. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock.                              | Severe:<br>depth to rock,<br>cemented pan.   | Poor:<br>depth to rock.                          |
| Rehfield-----            | Moderate:<br>percs slowly.                                  | Moderate:<br>seepage,<br>slope.                      | Slight-----  | Slight-----                                  | Good.  |
| Rock outcrop.            |   |  |  |  |  |
| 25*:<br>Deerhorn-----    | Severe:<br>depth to rock,<br>cemented pan,<br>percs slowly. | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>depth to rock.                              | Severe:<br>depth to rock,<br>cemented pan.   | Poor:<br>depth to rock.                          |

See footnote at end of table.

TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and<br>map symbol | Septic tank<br>absorption<br>fields                         | Sewage lagoon<br>areas                               | Trench<br>sanitary<br>landfill                  | Area<br>sanitary<br>landfill                    | Daily cover<br>for landfill                        |
|-----------------------------|---|--|---|---|--|
| 25*:<br>Wildors-----        | Severe:<br>depth to rock,<br>cemented pan,<br>large stones. | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>depth to rock,<br>large stones.      | Severe:<br>depth to rock,<br>cemented pan.      | Poor:<br>area reclaim,<br>large stones.            |
| 26*:<br>Deerhorn-----       | Severe:<br>depth to rock,<br>cemented pan,<br>percs slowly. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock.                       | Severe:<br>depth to rock,<br>cemented pan.      | Poor:<br>depth to rock.                            |
| Wildors-----                | Severe:<br>depth to rock,<br>cemented pan,<br>large stones. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>large stones.      | Severe:<br>depth to rock,<br>cemented pan.      | Poor:<br>area reclaim,<br>large stones.            |
| Trevino-----                | Severe:<br>depth to rock,<br>large stones.                  | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>large stones.      | Moderate:<br>slope.                             | Poor:<br>depth to rock.                            |
| 27*:<br>Dollarhide-----     | Severe:<br>depth to rock,<br>slope.                         | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>depth to rock,<br>large stones,<br>slope. |
| Rock outcrop.               |   |  |   |   |  |
| 28-----<br>Drage            | Severe:<br>percs slowly.                                    | Moderate:<br>seepage,<br>slope.                      | Moderate:<br>large stones.                      | Slight-----                                     | Poor:<br>small stones.                             |
| 29, 30-----<br>Drage        | Severe:<br>percs slowly.                                    | Severe:<br>slope.                                    | Moderate:<br>slope,<br>large stones.            | Moderate:<br>slope.                             | Poor:<br>small stones.                             |
| 31-----<br>Drage            | Severe:<br>percs slowly.                                    | Moderate:<br>seepage.                                | Moderate:<br>large stones.                      | Slight-----                                     | Poor:<br>small stones.                             |
| 32*:<br>Earcree-----        | Severe:<br>slope.   | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage,<br>slope.                   | Severe:<br>seepage,<br>slope.                   | Poor:<br>slope.                                    |
| Lockman-----                | Severe:<br>slope.   | Severe:<br>seepage,<br>slope.                        | Severe:<br>depth to rock,<br>seepage,<br>slope. | Severe:<br>seepage,<br>slope.                   | Poor:<br>slope.                                    |
| 33*, 34*:<br>Earcree-----   | Severe:<br>slope.   | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage,<br>slope.                   | Severe:<br>seepage,<br>slope.                   | Poor:<br>slope.                                    |
| Moonstone-----              | Severe:<br>depth to rock,<br>slope.                         | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>area reclaim,<br>slope.                   |

See footnote at end of table.



TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and map symbol | Septic tank absorption fields                        | Sewage lagoon areas                                  | Trench sanitary landfill                             | Area sanitary landfill                               | Daily cover for landfill                                |
|--------------------------|--|--|--|--|---|
| 35*:<br>Elkcreek-----    | Severe:<br>depth to rock,<br>percs slowly,<br>slope. | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope.                  | Poor:<br>depth to rock,<br>slope.                       |
| Gaib-----                | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.                  | Poor:<br>area reclaim,<br>large stones,<br>slope.       |
| 36*:<br>Elkcreek-----    | Severe:<br>depth to rock,<br>percs slowly,<br>slope. | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope.                  | Poor:<br>depth to rock,<br>slope.                       |
| Polecreek-----           | Severe:<br>depth to rock,<br>large stones.           | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>too clayey.             | Severe:<br>depth to rock.                            | Poor:<br>area reclaim,<br>too clayey,<br>hard to pack.  |
| 37*:<br>Elksel-----      | Severe:<br>percs slowly,<br>slope,<br>large stones.  | Severe:<br>slope,<br>large stones.                   | Severe:<br>depth to rock,<br>slope,<br>too clayey.   | Severe:<br>slope.                                    | Poor:<br>too clayey,<br>hard to pack,<br>large stones.  |
| Friedman-----            | Severe:<br>percs slowly,<br>slope.                   | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope,<br>too clayey.   | Severe:<br>slope.                                    | Poor:<br>too clayey,<br>small stones,<br>slope.         |
| Starhope-----            | Severe:<br>depth to rock,<br>percs slowly,<br>slope. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>too clayey.   | Severe:<br>depth to rock,<br>slope.                  | Poor:<br>area reclaim,<br>too clayey,<br>hard to pack.  |
| 38*:<br>Elksel-----      | Severe:<br>percs slowly,<br>slope.                   | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>slope.                                    | Poor:<br>too clayey,<br>small stones,<br>slope.         |
| Peevywell-----           | Severe:<br>cemented pan,<br>percs slowly,<br>slope.  | Severe:<br>cemented pan,<br>slope.                   | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>cemented pan,<br>slope.                   | Poor:<br>area reclaim,<br>too clayey,<br>hard to pack.  |
| Furshur-----             | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Poor:<br>depth to rock,<br>too clayey,<br>hard to pack. |
| 39*:<br>Elksel-----      | Severe:<br>percs slowly,<br>slope,<br>large stones.  | Severe:<br>slope,<br>large stones.                   | Severe:<br>depth to rock,<br>slope,<br>too clayey.   | Severe:<br>slope.                                    | Poor:<br>too clayey,<br>hard to pack,<br>large stones.  |

See footnote at end of table.

TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and<br>map symbol | Septic tank<br>absorption<br>fields                  | Sewage lagoon<br>areas                                 | Trench<br>sanitary<br>landfill                       | Area<br>sanitary<br>landfill                 | Daily cover<br>for landfill                            |
|-----------------------------|--|--|--|--|--|
| 39*:<br>Starhope-----       | Severe:<br>depth to rock,<br>percs slowly,<br>slope. | Severe:<br>depth to rock,<br>slope,<br>large stones.   | Severe:<br>depth to rock,<br>slope,<br>too clayey.   | Severe:<br>depth to rock,<br>slope.          | Poor:<br>area reclaim,<br>too clayey,<br>hard to pack. |
| Rock outcrop.               |  |  |  |  |  |
| 40*:<br>Friedman-----       | Severe:<br>percs slowly,<br>slope.                   | Severe:<br>slope.                                      | Severe:<br>depth to rock,<br>slope,<br>too clayey.   | Severe:<br>slope.                            | Poor:<br>too clayey,<br>small stones,<br>slope.        |
| Elksel-----                 | Severe:<br>percs slowly,<br>slope,<br>large stones.  | Severe:<br>slope,<br>large stones.                     | Severe:<br>depth to rock,<br>slope,<br>too clayey.   | Severe:<br>slope.                            | Poor:<br>too clayey,<br>hard to pack,<br>large stones. |
| Winridge-----               | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope.                    | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope.          | Poor:<br>area reclaim,<br>small stones,<br>slope.      |
| 41*:<br>Gaib-----           | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope,<br>large stones.   | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.          | Poor:<br>area reclaim,<br>large stones,<br>slope.      |
| Rock outcrop.               |  |  |  |  |  |
| 42-----<br>Gimlett          | Severe:<br>poor filter.                              | Severe:<br>seepage.                                    | Severe:<br>seepage,<br>large stones.                 | Severe:<br>seepage.                          | Poor:<br>seepage,<br>small stones.                     |
| 43*:<br>Gooding-----        | Severe:<br>percs slowly.                             | Severe:<br>slope.                                      | Severe:<br>depth to rock.                            | Slight-----                                  | Poor:<br>hard to pack.                                 |
| Gooding, eroded----         | Severe:<br>percs slowly.                             | Moderate:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock.                            | Slight-----                                  | Poor:<br>hard to pack.                                 |
| Hamrub-----                 | Severe:<br>percs slowly.                             | Severe:<br>slope.                                      | Severe:<br>depth to rock,<br>cemented pan.           | Moderate:<br>depth to rock,<br>cemented pan. | Fair:<br>depth to rock,<br>too clayey.                 |
| 44-----<br>Goodington       | Severe:<br>percs slowly.                             | Moderate:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock.                            | Moderate:<br>depth to rock.                  | Poor:<br>thin layer.                                   |
| 45*:<br>Goodington-----     | Severe:<br>percs slowly.                             | Moderate:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock.                            | Moderate:<br>depth to rock.                  | Poor:<br>thin layer.                                   |

See footnote at end of table.



TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and map symbol  | Septic tank absorption fields                               | Sewage lagoon areas                               | Trench sanitary landfill                        | Area sanitary landfill                       | Daily cover for landfill                         |
|---------------------------|---|---|---|--|--|
| 45*:<br>Manard-----       | Severe:<br>depth to rock,<br>cemented pan,<br>percs slowly. | Severe:<br>depth to rock,<br>cemented pan.        | Severe:<br>depth to rock,<br>cemented pan.      | Severe:<br>depth to rock,<br>cemented pan.   | Poor:<br>depth to rock.                          |
| 46-----<br>Hapur          | Severe:<br>flooding,<br>wetness,<br>percs slowly.           | Severe:<br>seepage,<br>flooding,<br>wetness.      | Severe:<br>flooding,<br>seepage,<br>wetness.    | Severe:<br>flooding,<br>seepage,<br>wetness. | Poor:<br>wetness.                                |
| 47*:<br>Hapur-----        | Severe:<br>flooding,<br>wetness,<br>percs slowly.           | Severe:<br>seepage,<br>flooding,<br>wetness.      | Severe:<br>flooding,<br>seepage,<br>wetness.    | Severe:<br>flooding,<br>seepage,<br>wetness. | Poor:<br>wetness.                                |
| Bickett-----              | Severe:<br>flooding,<br>ponding,<br>percs slowly.           | Severe:<br>flooding,<br>excess humus,<br>ponding. | Severe:<br>flooding,<br>ponding.                | Severe:<br>flooding,<br>ponding.             | Poor:<br>ponding.                                |
| 48*:<br>Hapur-----        | Severe:<br>flooding,<br>wetness,<br>percs slowly.           | Severe:<br>seepage,<br>flooding,<br>wetness.      | Severe:<br>flooding,<br>seepage,<br>wetness.    | Severe:<br>flooding,<br>seepage,<br>wetness. | Poor:<br>wetness.                                |
| Picabo-----               | Severe:<br>flooding,<br>wetness.                            | Severe:<br>flooding,<br>wetness.                  | Severe:<br>flooding,<br>seepage,<br>wetness.    | Severe:<br>flooding,<br>wetness.             | Fair:<br>wetness.                                |
| 49-----<br>Hutton         | Severe:<br>flooding,<br>wetness,<br>percs slowly.           | Severe:<br>flooding,<br>wetness.                  | Severe:<br>flooding,<br>wetness,<br>too clayey. | Severe:<br>flooding,<br>wetness.             | Poor:<br>too clayey,<br>hard to pack.            |
| 50-----<br>Hutton Variant | Severe:<br>percs slowly,<br>poor filter.                    | Severe:<br>seepage.                               | Severe:<br>seepage,<br>too sandy.               | Severe:<br>seepage.                          | Poor:<br>seepage,<br>too sandy,<br>small stones. |
| 51-----<br>Isknat         | Severe:<br>percs slowly,<br>poor filter.                    | Severe:<br>seepage.                               | Severe:<br>seepage,<br>too sandy.               | Severe:<br>seepage.                          | Poor:<br>seepage,<br>too sandy,<br>small stones. |
| 52, 53-----<br>Justesen   | Moderate:<br>percs slowly.                                  | Moderate:<br>seepage,<br>slope.                   | Slight-----                                     | Slight-----                                  | Good.  |
| 54-----<br>Justesen       | Moderate:<br>percs slowly,<br>slope.                        | Severe:<br>slope.                                 | Moderate:<br>slope.                             | Moderate:<br>slope.                          | Fair:<br>slope.                                  |
| 55-----<br>Justesen       | Severe:<br>slope.   | Severe:<br>slope.                                 | Severe:<br>slope.                               | Severe:<br>slope.                            | Poor:<br>slope.                                  |

See footnote at end of table.

TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and map symbol    | Septic tank absorption fields              | Sewage lagoon areas                                  | Trench sanitary landfill                             | Area sanitary landfill                          | Daily cover for landfill                           |
|-----------------------------|--|--|--|---|--|
| 56*:<br>Ketchum-----        | Severe:<br>slope.                          | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage,<br>slope.                   | Poor:<br>small stones,<br>slope.                   |
| Dollarhide-----             | Severe:<br>depth to rock,<br>slope.        | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>depth to rock,<br>large stones,<br>slope. |
| 57*:<br>Ketchum-----        | Severe:<br>slope.                          | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage,<br>slope.                   | Poor:<br>small stones,<br>slope.                   |
| Povey-----                  | Severe:<br>slope.                          | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope.                               | Poor:<br>large stones,<br>slope.                   |
| 58*:<br>Laurentzen-----     | Severe:<br>percs slowly.                   | Severe:<br>slope.                                    | Severe:<br>depth to rock.                            | Moderate:<br>depth to rock,<br>slope.           | Fair:<br>area reclaim,<br>too clayey,<br>slope.    |
| Mulshoe-----                | Severe:<br>depth to rock,<br>slope.        | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| 59*.<br>Lava flows          |  |  |  |   |  |
| 60*:<br>Lava flows.         |  |  |  |   |  |
| Cinderhurst-----            | Severe:<br>depth to rock,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>large stones.           | Severe:<br>depth to rock.                       | Poor:<br>area reclaim.                             |
| 61*, 62*:<br>Lavacreek----- | Severe:<br>slope.                          | Severe:<br>seepage,<br>slope.                        | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>slope.                               | Poor:<br>small stones,<br>slope.                   |
| Dollarhide-----             | Severe:<br>depth to rock,<br>slope.        | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>depth to rock,<br>large stones,<br>slope. |
| 63*:<br>Lavacreek-----      | Severe:<br>slope.                          | Severe:<br>seepage,<br>slope.                        | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>slope.                               | Poor:<br>small stones,<br>slope.                   |

See footnote at end of table.



TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and map symbol           | Septic tank absorption fields                               | Sewage lagoon areas                                  | Trench sanitary landfill                             | Area sanitary landfill                       | Daily cover for landfill                           |
|------------------------------------|---|--|--|--|--|
| 63*:<br>Vitale-----                | Severe:<br>depth to rock,<br>slope.                         | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.          | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| 64, 65, 66, 67-----<br>Little Wood | Severe:<br>poor filter.                                     | Severe:<br>seepage.                                  | Severe:<br>seepage.                                  | Severe:<br>seepage.                          | Poor:<br>small stones.                             |
| 68-----<br>Little Wood             | Severe:<br>poor filter.                                     | Severe:<br>seepage.                                  | Severe:<br>seepage,<br>too sandy,<br>large stones.   | Severe:<br>seepage.                          | Poor:<br>seepage,<br>too sandy,<br>small stones.   |
| 69*:<br>Little Wood-----           | Severe:<br>poor filter.                                     | Severe:<br>seepage.                                  | Severe:<br>seepage.                                  | Severe:<br>seepage.                          | Poor:<br>small stones.                             |
| Balaam-----                        | Severe:<br>poor filter.                                     | Severe:<br>seepage.                                  | Severe:<br>seepage,<br>too sandy.                    | Severe:<br>seepage.                          | Poor:<br>seepage,<br>too sandy,<br>small stones.   |
| 70-----<br>Manard                  | Severe:<br>depth to rock,<br>cemented pan,<br>percs slowly. | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>depth to rock.                            | Severe:<br>depth to rock,<br>cemented pan.   | Poor:<br>depth to rock,<br>hard to pack.           |
| 71-----<br>Marshdale               | Severe:<br>flooding,<br>wetness.                            | Severe:<br>seepage,<br>flooding,<br>wetness.         | Severe:<br>flooding,<br>seepage,<br>wetness.         | Severe:<br>flooding,<br>wetness.             | Poor:<br>wetness.                                  |
| 72*:<br>Marshdale-----             | Severe:<br>flooding,<br>wetness.                            | Severe:<br>seepage,<br>flooding,<br>wetness.         | Severe:<br>flooding,<br>seepage,<br>wetness.         | Severe:<br>flooding,<br>wetness.             | Poor:<br>wetness.                                  |
| Bruneel-----                       | Severe:<br>flooding,<br>wetness,<br>poor filter.            | Severe:<br>seepage,<br>flooding,<br>wetness.         | Severe:<br>flooding,<br>seepage,<br>wetness.         | Severe:<br>flooding,<br>seepage,<br>wetness. | Poor:<br>seepage,<br>too sandy,<br>small stones.   |
| 73-----<br>McBiggam                | Severe:<br>percs slowly.                                    | Moderate:<br>slope.                                  | Severe:<br>too clayey.                               | Slight-----                                  | Poor:<br>too clayey,<br>hard to pack.              |
| 74*:<br>McCarey-----               | Severe:<br>depth to rock.                                   | Severe:<br>depth to rock.                            | Severe:<br>depth to rock.                            | Severe:<br>depth to rock.                    | Poor:<br>depth to rock.                            |
| Justesen-----                      | Moderate:<br>percs slowly.                                  | Moderate:<br>seepage,<br>slope.                      | Slight-----  | Slight-----                                  | Good.  |

See footnote at end of table.

TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and<br>map symbol        | Septic tank<br>absorption<br>fields  | Sewage lagoon<br>areas                               | Trench<br>sanitary<br>landfill                       | Area<br>sanitary<br>landfill                    | Daily cover<br>for landfill                        |
|------------------------------------|--------------------------------------|--|--|---|--|
| 75*:<br>McCarey-----               | Severe:<br>depth to rock.            | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock.                            | Severe:<br>depth to rock.                       | Poor:<br>depth to rock.                            |
| Justesen-----<br><br>Rock outcrop. | Moderate:<br>percs slowly,<br>slope. | Severe:<br>slope.                                    | Moderate:<br>slope.                                  | Moderate:<br>slope.                             | Fair:<br>slope.                                    |
| 76*:<br>McCarey-----               | Severe:<br>depth to rock.            | Severe:<br>depth to rock.                            | Severe:<br>depth to rock.                            | Severe:<br>depth to rock.                       | Poor:<br>depth to rock.                            |
| Molyneux-----                      | Severe:<br>percs slowly.             | Moderate:<br>seepage,<br>slope.                      | Moderate:<br>too clayey.                             | Slight-----                                     | Fair:<br>too clayey.                               |
| 77*:<br>McCarey-----               | Severe:<br>depth to rock,<br>slope.  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>slope.                  |
| Pedleford-----                     | Severe:<br>depth to rock,<br>slope.  | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| 78, 79-----<br>Molyneux            | Severe:<br>percs slowly.             | Moderate:<br>seepage,<br>slope.                      | Moderate:<br>too clayey.                             | Slight-----                                     | Fair:<br>too clayey.                               |
| 80-----<br>Molyneux                | Severe:<br>percs slowly.             | Severe:<br>slope.                                    | Moderate:<br>slope,<br>too clayey.                   | Moderate:<br>slope.                             | Fair:<br>too clayey,<br>slope.                     |
| 81*:<br>Moonstone-----             | Severe:<br>depth to rock,<br>slope.  | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>area reclaim,<br>slope.                   |
| Bauscher-----                      | Severe:<br>percs slowly.             | Severe:<br>seepage,<br>slope.                        | Severe:<br>depth to rock,<br>seepage.                | Severe:<br>seepage.                             | Fair:<br>depth to rock,<br>small stones,<br>slope. |
| 82*:<br>Moonstone-----             | Severe:<br>depth to rock,<br>slope.  | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>area reclaim,<br>slope.                   |
| Earcree-----                       | Severe:<br>slope.                    | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage,<br>slope.                   | Poor:<br>slope.                                    |

See footnote at end of table.



TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and map symbol | Septic tank absorption fields             | Sewage lagoon areas                                  | Trench sanitary landfill                             | Area sanitary landfill                          | Daily cover for landfill                           |
|--------------------------|---|--|--|---|--|
| 83*:<br>Muldoon-----     | Severe:<br>percs slowly.                  | Severe:<br>slope.                                    | Severe:<br>cemented pan,<br>too clayey.              | Moderate:<br>cemented pan,<br>slope.            | Poor:<br>too clayey.                               |
| Peevywell-----           | Severe:<br>cemented pan,<br>percs slowly. | Severe:<br>seepage,<br>cemented pan,<br>slope.       | Severe:<br>cemented pan,<br>seepage.                 | Severe:<br>cemented pan.                        | Poor:<br>area reclaim,<br>small stones.            |
| 84*:<br>Mulshoe-----     | Severe:<br>depth to rock,<br>slope.       | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| Gaib-----                | Severe:<br>depth to rock,<br>slope.       | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>area reclaim,<br>large stones,<br>slope.  |
| Rock outcrop.            |   |  |  |   |  |
| 85*:<br>Mulshoe-----     | Severe:<br>depth to rock,<br>slope.       | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| Gaib-----                | Severe:<br>depth to rock,<br>slope.       | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>area reclaim,<br>large stones,<br>slope.  |
| Winu-----                | Severe:<br>depth to rock,<br>slope.       | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>area reclaim,<br>slope.                   |
| 86*:<br>Pagari-----      | Severe:<br>large stones.                  | Severe:<br>seepage,<br>slope,<br>large stones.       | Severe:<br>depth to rock,<br>large stones.           | Severe:<br>seepage.                             | Poor:<br>large stones.                             |
| Rehfield-----            | Moderate:<br>percs slowly.                | Moderate:<br>seepage,<br>slope.                      | Slight-----  | Slight-----                                     | Good.  |
| 87*:<br>Peevywell-----   | Severe:<br>cemented pan,<br>percs slowly. | Severe:<br>seepage,<br>cemented pan.                 | Severe:<br>cemented pan,<br>seepage.                 | Severe:<br>cemented pan.                        | Poor:<br>area reclaim,<br>small stones.            |
| Simonton-----            | Severe:<br>percs slowly.                  | Severe:<br>seepage.                                  | Severe:<br>seepage.                                  | Severe:<br>seepage.                             | Fair:<br>too clayey.                               |

See footnote at end of table.

TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and map symbol                      | Septic tank absorption fields                       | Sewage lagoon areas                                  | Trench sanitary landfill                             | Area sanitary landfill                          | Daily cover for landfill                           |
|---|---|--|--|---|--|
| 88*:<br>Peevywell-----                        | Severe:<br>cemented pan,<br>percs slowly,<br>slope. | Severe:<br>seepage,<br>cemented pan,<br>slope.       | Severe:<br>cemented pan,<br>seepage,<br>slope.       | Severe:<br>cemented pan,<br>slope.              | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| Simonton-----                                 | Severe:<br>percs slowly.                            | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage.                                  | Severe:<br>seepage.                             | Fair:<br>too clayey,<br>slope.                     |
| 89, 90-----<br>Picabo                         | Severe:<br>flooding,<br>wetness.                    | Severe:<br>flooding,<br>wetness.                     | Severe:<br>flooding,<br>seepage,<br>wetness.         | Severe:<br>flooding,<br>wetness.                | Fair:<br>wetness.                                  |
| 91*.<br>Pits, gravel                          |   |  |  |   |  |
| 92*:<br>Povey-----                            | Severe:<br>slope.                                   | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope.                               | Poor:<br>large stones,<br>slope.                   |
| Dollarhide-----                               | Severe:<br>depth to rock,<br>slope.                 | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>depth to rock,<br>large stones,<br>slope. |
| 93*:<br>Povey-----                            | Severe:<br>slope.                                   | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope.                               | Poor:<br>large stones,<br>slope.                   |
| Rock outcrop.                                 |   |  |  |   |  |
| 94*:<br>Povey very gravelly<br>silt loam----- | Severe:<br>slope.                                   | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope.                               | Poor:<br>large stones,<br>slope.                   |
| Povey gravelly<br>loam-----                   | Severe:<br>slope.                                   | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope.                               | Poor:<br>large stones,<br>slope.                   |
| 95*:<br>Povey-----                            | Severe:<br>slope.                                   | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope.                               | Poor:<br>large stones,<br>slope.                   |
| Vitale-----                                   | Severe:<br>depth to rock,<br>slope.                 | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>small stones,<br>slope. |

See footnote at end of table.



TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and<br>map symbol | Septic tank<br>absorption<br>fields                  | Sewage lagoon<br>areas                               | Trench<br>sanitary<br>landfill                       | Area<br>sanitary<br>landfill                         | Daily cover<br>for landfill                             |
|-----------------------------|--|--|--|--|---|
| 96*:<br>Rehfield-----       | Moderate:<br>percs slowly,<br>slope.                 | Severe:<br>slope.                                    | Moderate:<br>slope.                                  | Moderate:<br>slope.                                  | Fair:<br>slope.   |
| Gooding-----                | Severe:<br>percs slowly.                             | Severe:<br>slope.                                    | Severe:<br>depth to rock.                            | Moderate:<br>slope.                                  | Poor:<br>hard to pack.                                  |
| 97*.<br>Riverwash           |  |  |  |  |   |
| 98*:<br>Rock outcrop.       |  |  |  |  |   |
| Adios-----                  | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Poor:<br>depth to rock,<br>too clayey,<br>hard to pack. |
| 99-----<br>Rockybar         | Severe:<br>slope,<br>large stones.                   | Severe:<br>seepage,<br>slope,<br>large stones.       | Severe:<br>seepage,<br>slope,<br>large stones.       | Severe:<br>seepage,<br>slope.                        | Poor:<br>small stones,<br>slope.                        |
| 100*.<br>Rubbleland         |  |  |  |  |   |
| 101*:<br>Rubbleland.        |  |  |  |  |   |
| Milligan-----               | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Poor:<br>area reclaim,<br>large stones,<br>slope.       |
| 102, 103-----<br>Simonton   | Severe:<br>percs slowly.                             | Severe:<br>seepage.                                  | Severe:<br>seepage.                                  | Severe:<br>seepage.                                  | Fair:<br>too clayey.                                    |
| 104*:<br>Simonton-----      | Severe:<br>percs slowly.                             | Severe:<br>seepage,<br>slope.                        | Severe:<br>seepage.                                  | Severe:<br>seepage.                                  | Fair:<br>too clayey,<br>slope.                          |
| Bauscher-----               | Severe:<br>percs slowly.                             | Severe:<br>seepage,<br>slope.                        | Severe:<br>depth to rock,<br>seepage.                | Severe:<br>seepage.                                  | Fair:<br>depth to rock,<br>small stones,<br>slope.      |
| 105*:<br>Starhope-----      | Severe:<br>depth to rock,<br>percs slowly.           | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>too clayey.             | Severe:<br>depth to rock.                            | Poor:<br>area reclaim,<br>too clayey,<br>hard to pack.  |
| Furshur-----                | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>depth to rock,<br>cemented pan.           | Severe:<br>depth to rock,<br>cemented pan.           | Poor:<br>depth to rock,<br>too clayey,<br>hard to pack. |

See footnote at end of table.

TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and map symbol | Septic tank absorption fields                        | Sewage lagoon areas                                  | Trench sanitary landfill                             | Area sanitary landfill                          | Daily cover for landfill                               |
|--------------------------|--|--|--|---|--|
| 106*:<br>Starhope-----   | Severe:<br>depth to rock,<br>percs slowly,<br>slope. | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope,<br>too clayey.   | Severe:<br>depth to rock,<br>slope.             | Poor:<br>area reclaim,<br>too clayey,<br>hard to pack. |
| Peevywell-----           | Severe:<br>cemented pan,<br>percs slowly.            | Severe:<br>seepage,<br>cemented pan,<br>slope.       | Severe:<br>cemented pan,<br>seepage.                 | Severe:<br>cemented pan.                        | Poor:<br>area reclaim,<br>small stones.                |
| Smelter-----             | Severe:<br>percs slowly,<br>slope.                   | Severe:<br>slope.                                    | Severe:<br>slope,<br>too clayey.                     | Severe:<br>slope.                               | Poor:<br>too clayey,<br>slope.                         |
| 107*:<br>Vitale-----     | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>small stones,<br>slope.     |
| Blackspar-----           | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>small stones,<br>slope.     |
| 108*:<br>Vitale-----     | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>small stones,<br>slope.     |
| Milligan-----            | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>area reclaim,<br>large stones,<br>slope.      |
| 109*:<br>Vitale-----     | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope.             | Poor:<br>depth to rock,<br>small stones,<br>slope.     |
| Povey-----               | Severe:<br>slope.                                    | Severe:<br>slope.                                    | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>slope.                               | Poor:<br>large stones,<br>slope.                       |
| 110*:<br>Winu-----       | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>area reclaim,<br>slope.                       |
| Rock outcrop.            |  |  |  |   |  |
| 111*:<br>Winu-----       | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope.      | Severe:<br>depth to rock,<br>seepage,<br>slope. | Poor:<br>area reclaim,<br>slope.                       |

See footnote at end of table.



TABLE 10.--SANITARY FACILITIES--Continued

| Soil name and<br>map symbol | Septic tank<br>absorption<br>fields | Sewage lagoon<br>areas                               | Trench<br>sanitary<br>landfill                       | Area<br>sanitary<br>landfill        | Daily cover<br>for landfill                       |
|-----------------------------|-------------------------------------|--|--|-------------------------------------|---|
| 111*:<br>Gaib-----          | Severe:<br>depth to rock,<br>slope. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope,<br>large stones. | Severe:<br>depth to rock,<br>slope. | Poor:<br>area reclaim,<br>large stones,<br>slope. |

\* See description of the map unit for composition and behavior characteristics of the map unit.

TABLE 11.--CONSTRUCTION MATERIALS

(Some terms that describe restrictive soil features are defined in the Glossary. See text for definitions of "good," "fair," and other terms. Absence of an entry indicates that the soil was not rated. The information in this table indicates the dominant soil condition but does not eliminate the need for onsite investigation)

| Soil name and map symbol | Roadfill                                 | Sand  | Gravel                       | Topsoil   |
|--------------------------|--|---|------------------------------|---|
| 1-----<br>Adamson        | Good-----                                | Probable-----                                 | Probable-----                | Poor:<br>small stones,<br>area reclaim.               |
| 2*:<br>Adios-----        | Poor:<br>depth to rock,<br>low strength. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines. | Poor:<br>small stones.                                |
| Gooding-----             | Poor:<br>shrink-swell,<br>low strength.  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines. | Poor:<br>too clayey.                                  |
| Bostrum-----             | Poor:<br>depth to rock,<br>low strength. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines. | Poor:<br>too clayey,<br>small stones.                 |
| 3*:<br>Adios-----        | Poor:<br>depth to rock,<br>low strength. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines. | Poor:<br>small stones,<br>slope.                      |
| Adios, cool-----         | Poor:<br>depth to rock,<br>low strength. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines. | Poor:<br>small stones,<br>slope.                      |
| 4, 5-----<br>Balaam      | Good-----                                | Improbable:<br>small stones.                  | Probable-----                | Poor:<br>too sandy,<br>small stones,<br>area reclaim. |
| 6*:<br>Balaam-----       | Good-----                                | Improbable:<br>small stones.                  | Probable-----                | Poor:<br>too sandy,<br>small stones,<br>area reclaim. |
| Adamson-----             | Good-----                                | Probable-----                                 | Probable-----                | Poor:<br>small stones,<br>area reclaim.               |
| 7*:<br>Balaam-----       | Fair:<br>large stones.                   | Improbable:<br>small stones,<br>large stones. | Improbable:<br>large stones. | Poor:<br>too sandy,<br>small stones,<br>area reclaim. |
| Adamson-----             | Fair:<br>large stones.                   | Improbable:<br>large stones.                  | Improbable:<br>large stones. | Poor:<br>too sandy,<br>large stones,<br>area reclaim. |

See footnote at end of table.



TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and<br>map symbol | Roadfill   | Sand  | Gravel  | Topsoil   |
|-----------------------------|--|---|---|---|
| 8*:<br>Balaam-----          | Fair:<br>large stones.                             | Improbable:<br>small stones,<br>large stones. | Improbable:<br>large stones.                  | Poor:<br>too sandy,<br>small stones,<br>area reclaim.     |
| Adamson-----                | Fair:<br>large stones.                             | Improbable:<br>large stones.                  | Improbable:<br>large stones.                  | Poor:<br>too sandy,<br>large stones,<br>area reclaim.     |
| Riverwash.                  |  |   |   |   |
| 9, 10-----<br>Bancroft      | Good-----  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>area reclaim.                                    |
| 11-----<br>Bickett          | Poor:<br>wetness.                                  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>excess humus,<br>wetness.                        |
| 12*:<br>Blackspar-----      | Poor:<br>depth to rock,<br>large stones,<br>slope. | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>depth to rock,<br>small stones,<br>slope.        |
| Rock outcrop.               |  |   |   |   |
| 13*:<br>Blackspot-----      | Poor:<br>depth to rock,<br>slope.                  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>depth to rock,<br>cemented pan,<br>small stones. |
| Prudy-----                  | Poor:<br>slope.                                    | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                          |
| 14*:<br>Bostrum-----        | Poor:<br>depth to rock,<br>low strength.           | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>too clayey,<br>small stones.                     |
| Yutru-----                  | Good-----  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>too clayey,<br>area reclaim,<br>small stones.    |
| Hamrub-----                 | Poor:<br>low strength.                             | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Good.   |
| 15, 16, 17-----<br>Bringmee | Good-----  | Probable-----                                 | Probable-----                                 | Poor:<br>area reclaim.                                    |
| 18*:<br>Bringmee-----       | Good-----  | Probable-----                                 | Probable-----                                 | Poor:<br>area reclaim.                                    |
| Hutton-----                 | Poor:<br>low strength,<br>shrink-swell.            | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>thin layer.                                      |

See footnote at end of table.

TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and map symbol  | Roadfill                                | Sand  | Gravel  | Topsoil   |
|---------------------------|---|---|---|---|
| 19*:<br>Bringmee-----     | Good-----                               | Probable-----                                 | Probable-----                                 | Poor:<br>small stones,<br>area reclaim.                 |
| Little Wood-----          | Good-----                               | Improbable:<br>small stones.                  | Probable-----                                 | Poor:<br>small stones,<br>area reclaim.                 |
| 20-----<br>Bruneel        | Fair:<br>wetness.                       | Probable-----                                 | Probable-----                                 | Poor:<br>too sandy,<br>small stones,<br>area reclaim.   |
| 21, 22-----<br>Carey Lake | Good-----                               | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>too clayey,<br>small stones.                   |
| 23*:<br>Cox-----          | Poor:<br>area reclaim,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>large stones.                 |
| Rehfield-----             | Good-----                               | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>too sandy,<br>small stones,<br>area reclaim.   |
| Rock outcrop.             |   |   |   |   |
| 24*:<br>Deerhorn-----     | Poor:<br>depth to rock.                 | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>depth to rock,<br>cemented pan,<br>too clayey. |
| Rehfield-----             | Good-----                               | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>small stones,<br>area reclaim.                 |
| Rock outcrop.             |   |   |   |   |
| 25*:<br>Deerhorn-----     | Poor:<br>depth to rock.                 | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>depth to rock,<br>cemented pan,<br>too clayey. |
| Wildors-----              | Poor:<br>area reclaim,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>large stones.                                  |
| 26*:<br>Deerhorn-----     | Poor:<br>depth to rock.                 | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>depth to rock,<br>cemented pan,<br>too clayey. |
| Wildors-----              | Poor:<br>area reclaim,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>large stones.                                  |

See footnote at end of table.



TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and map symbol     | Roadfill                                 | Sand  | Gravel  | Topsoil  |
|------------------------------|--|---|---|--|
| 26*:<br>Trevino-----         | Poor:<br>depth to rock,<br>large stones. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>depth to rock,<br>large stones.           |
| 27*:<br>Dollarhide-----      | Poor:<br>depth to rock,<br>slope.        | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| Rock outcrop.                |  |   |   |  |
| 28, 29, 30, 31-----<br>Drage | Fair:<br>large stones.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>area reclaim.            |
| 32*:<br>Earcree-----         | Poor:<br>slope.                          | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| Lockman-----                 | Poor:<br>slope.                          | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| 33*:<br>Earcree-----         | Fair:<br>slope.                          | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| Moonstone-----               | Poor:<br>area reclaim.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| 34*:<br>Earcree-----         | Poor:<br>slope.                          | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| Moonstone-----               | Poor:<br>area reclaim,<br>slope.         | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| 35*:<br>Elkcreek-----        | Poor:<br>depth to rock,<br>slope.        | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>large stones,<br>slope.                   |
| Gaib-----                    | Poor:<br>area reclaim,<br>slope.         | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| 36*:<br>Elkcreek-----        | Poor:<br>depth to rock.                  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>large stones,<br>slope.                   |

See footnote at end of table.

TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and map symbol | Roadfill   | Sand  | Gravel  | Topsoil   |
|--------------------------|--|---|---|---|
| 36*:<br>Polecreek-----   | Poor:<br>area reclaim,<br>large stones.            | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>large stones.                   |
| 37*:<br>Elksel-----      | Poor:<br>low strength,<br>large stones,<br>slope.  | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>too clayey,<br>large stones,<br>area reclaim.    |
| Friedman-----            | Poor:<br>slope.                                    | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>area reclaim,<br>slope.         |
| Starhope-----            | Poor:<br>area reclaim,<br>low strength,<br>slope.  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>large stones,<br>slope.                          |
| 38*:<br>Elksel-----      | Poor:<br>slope,<br>shrink-swell.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>area reclaim,<br>slope.         |
| Peevywell-----           | Poor:<br>area reclaim,<br>low strength,<br>slope.  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                          |
| Furshur-----             | Poor:<br>depth to rock,<br>low strength,<br>slope. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>depth to rock,<br>cemented pan,<br>small stones. |
| 39*:<br>Elksel-----      | Poor:<br>low strength,<br>large stones,<br>slope.  | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>too clayey,<br>large stones,<br>area reclaim.    |
| Starhope-----            | Poor:<br>area reclaim,<br>low strength,<br>slope.  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>large stones,<br>slope.                          |
| Rock outcrop.            |  |   |   |   |
| 40*:<br>Friedman-----    | Poor:<br>slope.                                    | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>area reclaim,<br>slope.         |
| Elksel-----              | Poor:<br>low strength,<br>large stones,<br>slope.  | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>too clayey,<br>large stones,<br>area reclaim.    |

See footnote at end of table.



TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and map symbol | Roadfill                                 | Sand                         | Gravel                       | Topsoil   |
|--------------------------|--|------------------------------|------------------------------|---|
| 40*:<br>Winridge-----    | Poor:<br>area reclaim,<br>slope.         | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>small stones,<br>slope.                  |
| 41*:<br>Gaib-----        | Poor:<br>area reclaim,<br>slope.         | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>area reclaim,<br>small stones,<br>slope. |
| Rock outcrop.            |  |                              |                              |   |
| 42-----<br>Gimlett       | Fair:<br>large stones.                   | Probable-----                | Probable-----                | Poor:<br>small stones,<br>area reclaim.           |
| 43*:<br>Gooding-----     | Poor:<br>shrink-swell,<br>low strength.  | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>too clayey.                              |
| Gooding, eroded-----     | Poor:<br>shrink-swell,<br>low strength.  | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>too clayey,<br>small stones.             |
| Hamrub-----              | Poor:<br>low strength.                   | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Good.   |
| 44-----<br>Goodington    | Poor:<br>low strength.                   | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>thin layer.                              |
| 45*:<br>Goodington-----  | Poor:<br>low strength.                   | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>thin layer.                              |
| Manard-----              | Poor:<br>depth to rock,<br>low strength. | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>large stones.                            |
| 46-----<br>Hapur         | Poor:<br>wetness.                        | Probable-----                | Probable-----                | Poor:<br>wetness.                                 |
| 47*:<br>Hapur-----       | Poor:<br>wetness.                        | Probable-----                | Probable-----                | Poor:<br>wetness.                                 |
| Bickett-----             | Poor:<br>wetness.                        | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>excess humus,<br>wetness.                |
| 48*:<br>Hapur-----       | Poor:<br>wetness.                        | Probable-----                | Probable-----                | Poor:<br>wetness.                                 |
| Picabo-----              | Fair:<br>wetness.                        | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>small stones.                            |

See footnote at end of table.

TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and<br>map symbol | Roadfill                                 | Sand  | Gravel  | Topsoil  |
|-----------------------------|--|---|---|--|
| 49-----<br>Hutton           | Poor:<br>low strength,<br>shrink-swell.  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>thin layer.                                   |
| 50-----<br>Hutton Variant   | Good-----                                | Improbable:<br>small stones.                  | Probable-----                                 | Poor:<br>too clayey,<br>small stones,<br>area reclaim. |
| 51-----<br>Isknat           | Good-----                                | Improbable:<br>small stones.                  | Probable-----                                 | Poor:<br>too clayey,<br>small stones,<br>area reclaim. |
| 52, 53-----<br>Justesen     | Good-----                                | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>too clayey,<br>small stones.                  |
| 54-----<br>Justesen         | Good-----                                | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>too clayey,<br>small stones,<br>slope.        |
| 55-----<br>Justesen         | Fair:<br>slope.                          | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>slope.  |
| 56*:<br>Ketchum-----        | Poor:<br>slope.                          | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>area reclaim,<br>slope.      |
| Dollarhide-----             | Poor:<br>depth to rock,<br>slope.        | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>depth to rock,<br>small stones,<br>slope.     |
| 57*:<br>Ketchum-----        | Poor:<br>slope.                          | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>area reclaim,<br>slope.      |
| Povey-----                  | Poor:<br>slope.                          | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>small stones,<br>slope.      |
| 58*:<br>Laurentzen-----     | Poor:<br>low strength.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>slope.  |
| Mulshoe-----                | Poor:<br>depth to rock,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>large stones,<br>slope.                       |
| 59*.<br>Lava flows          |  |   |   |  |
| 60*:<br>Lava flows.         |  |   |   |  |

See footnote at end of table.



TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and<br>map symbol     | Roadfill  | Sand  | Gravel  | Topsoil   |
|---------------------------------|---|---|---|---|
| 60*:<br>Cinderhurst-----        | Poor:<br>area reclaim,<br>large stones.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim,<br>large stones.               |
| 61*, 62*:<br>Lavacreek-----     | Poor:<br>slope.   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>area reclaim,<br>slope.     |
| Dollarhide-----                 | Poor:<br>depth to rock,<br>slope.                         | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>depth to rock,<br>small stones,<br>slope.    |
| 63*:<br>Lavacreek-----          | Poor:<br>slope.   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>area reclaim,<br>slope.     |
| Vitale-----                     | Poor:<br>depth to rock,<br>slope.                         | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                      |
| 64, 65, 66, 67--<br>Little Wood | Good-----   | Improbable:<br>small stones.                  | Probable-----                                 | Poor:<br>small stones,<br>area reclaim.               |
| 68-----<br>Little Wood          | Fair:<br>large stones.                                    | Improbable:<br>small stones,<br>large stones. | Improbable:<br>large stones.                  | Poor:<br>small stones,<br>area reclaim.               |
| 69*:<br>Little Wood-----        | Good-----   | Improbable:<br>small stones.                  | Probable-----                                 | Poor:<br>small stones,<br>area reclaim.               |
| Balaam-----                     | Good-----   | Improbable:<br>small stones.                  | Probable-----                                 | Poor:<br>too sandy,<br>small stones,<br>area reclaim. |
| 70-----<br>Manard               | Poor:<br>depth to rock,<br>shrink-swell,<br>low strength. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>thin layer.                                  |
| 71-----<br>Marshdale            | Poor:<br>wetness.   | Probable-----                                 | Probable-----                                 | Poor:<br>wetness.                                     |
| 72*:<br>Marshdale-----          | Poor:<br>wetness.   | Probable-----                                 | Probable-----                                 | Poor:<br>wetness.                                     |

See footnote at end of table.

TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and<br>map symbol | Roadfill                                | Sand                         | Gravel                       | Topsoil   |
|-----------------------------|---|------------------------------|------------------------------|---|
| 72*:<br>Bruneel-----        | Fair:<br>wetness.                       | Probable-----                | Probable-----                | Poor:<br>too sandy,<br>small stones,<br>area reclaim. |
| 73-----<br>McBiggam         | Poor:<br>low strength,<br>shrink-swell. | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>small stones,<br>thin layer.                 |
| 74*:<br>McCarey-----        | Poor:<br>depth to rock.                 | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>depth to rock,<br>small stones.              |
| Justesen-----               | Good-----                               | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>too clayey,<br>small stones.                 |
| 75*:<br>McCarey-----        | Poor:<br>depth to rock.                 | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>depth to rock,<br>small stones,<br>slope.    |
| Justesen-----               | Good-----                               | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>too clayey,<br>small stones,<br>slope.       |
| Rock outcrop.               |   |                              |                              |   |
| 76*:<br>McCarey-----        | Poor:<br>depth to rock.                 | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>depth to rock,<br>small stones.              |
| Molyneux-----               | Fair:<br>shrink-swell.                  | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>small stones,<br>area reclaim.               |
| 77*:<br>McCarey-----        | Poor:<br>depth to rock.                 | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>slope.                                       |
| Pedleford-----              | Poor:<br>area reclaim.                  | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Poor:<br>small stones,<br>slope.                      |
| 78, 79-----<br>Molyneux     | Fair:<br>shrink-swell.                  | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>small stones,<br>area reclaim.               |
| 80-----<br>Molyneux         | Fair:<br>shrink-swell.                  | Improbable:<br>excess fines. | Improbable:<br>excess fines. | Fair:<br>small stones,<br>area reclaim,<br>slope.     |

See footnote at end of table.



TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and map symbol | Roadfill                                 | Sand  | Gravel  | Topsoil   |
|--------------------------|--|---|---|---|
| 81*:<br>Moonstone-----   | Poor:<br>area reclaim.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                      |
| Bauscher-----            | Fair:<br>depth to rock,<br>shrink-swell. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones.                                |
| 82*:<br>Moonstone-----   | Poor:<br>area reclaim,<br>slope.         | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                      |
| Earcree-----             | Poor:<br>slope.                          | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                      |
| 83*:<br>Muldoon-----     | Poor:<br>low strength.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim,<br>small stones.               |
| Peevywell-----           | Poor:<br>area reclaim.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim.                                |
| 84*:<br>Mulshoe-----     | Poor:<br>depth to rock,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>large stones,<br>slope.                      |
| Gaib-----                | Poor:<br>area reclaim.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim,<br>small stones,<br>slope.     |
| Rock outcrop.            |  |   |   |   |
| 85*:<br>Mulshoe-----     | Poor:<br>depth to rock.                  | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>large stones,<br>slope.                      |
| Gaib-----                | Poor:<br>area reclaim,<br>slope.         | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim,<br>small stones,<br>slope.     |
| Winu-----                | Poor:<br>area reclaim,<br>slope.         | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                      |
| 86*:<br>Pagari-----      | Poor:<br>large stones.                   | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>large stones,<br>area reclaim.               |
| Rehfield-----            | Good-----                                | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>too sandy,<br>small stones,<br>area reclaim. |

See footnote at end of table.

TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and<br>map symbol                   | Roadfill                          | Sand  | Gravel  | Topsoil  |
|---|-----------------------------------|---|---|--|
| 87*:<br>Peevywell-----                        | Poor:<br>area reclaim.            | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim.                             |
| Simonton-----                                 | Good-----                         | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>small stones.                             |
| 88*:<br>Peevywell-----                        | Poor:<br>area reclaim.            | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim,<br>slope.                   |
| Simonton-----                                 | Good-----                         | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>small stones,<br>slope.                   |
| 89, 90-----<br>Picabo                         | Fair:<br>wetness.                 | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>small stones.                             |
| 91*.<br>Pits, gravel                          |                                   |   |   |  |
| 92*:<br>Povey-----                            | Poor:<br>slope.                   | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| Dollarhide-----                               | Poor:<br>depth to rock,<br>slope. | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| 93*:<br>Povey-----                            | Poor:<br>slope.                   | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| Rock outcrop.                                 |                                   |   |   |  |
| 94*:<br>Povey very gravelly<br>silt loam----- | Poor:<br>slope.                   | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| Povey gravelly loam--                         | Poor:<br>slope.                   | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| 95*:<br>Povey-----                            | Poor:<br>slope.                   | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| Vitale-----                                   | Poor:<br>depth to rock,<br>slope. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |

See footnote at end of table.



TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and<br>map symbol | Roadfill   | Sand  | Gravel  | Topsoil   |
|-----------------------------|--|---|---|---|
| 96*:<br>Rehfield-----       | Good-----  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>small stones,<br>area reclaim.                   |
| Gooding-----                | Poor:<br>shrink-swell,<br>low strength.            | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>too clayey.                                      |
| 97*.<br>Riverwash           |  |   |   |   |
| 98*:<br>Rock outcrop.       |  |   |   |   |
| Adios-----                  | Poor:<br>depth to rock,<br>low strength,<br>slope. | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                          |
| 99-----<br>Rockybar         | Poor:<br>large stones.                             | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>large stones,<br>area reclaim,<br>slope.         |
| 100*.<br>Rubbleland         |  |   |   |   |
| 101*:<br>Rubbleland.        |  |   |   |   |
| Milligan-----               | Poor:<br>area reclaim,<br>large stones,<br>slope.  | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>small stones,<br>slope.                          |
| 102, 103-----<br>Simonton   | Good-----  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>small stones.                                    |
| 104*:<br>Simonton-----      | Good-----  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Fair:<br>small stones,<br>slope.                          |
| Bauscher-----               | Fair:<br>depth to rock,<br>shrink-swell.           | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones.                                    |
| 105*:<br>Starhope-----      | Poor:<br>area reclaim,<br>low strength.            | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>large stones.                                    |
| Furshur-----                | Poor:<br>depth to rock,<br>low strength.           | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>depth to rock,<br>cemented pan,<br>small stones. |

See footnote at end of table.

TABLE 11.--CONSTRUCTION MATERIALS--Continued

| Soil name and map symbol | Roadfill   | Sand  | Gravel  | Topsoil  |
|--------------------------|--|---|---|--|
| 106*:<br>Starhope-----   | Poor:<br>area reclaim,<br>low strength.            | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>large stones,<br>slope.                   |
| Peevywell-----           | Poor:<br>area reclaim.                             | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim.                             |
| Smelter-----             | Poor:<br>low strength.                             | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>thin layer,<br>slope.                     |
| 107*:<br>Vitale-----     | Poor:<br>depth to rock,<br>slope.                  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| Blackspar-----           | Poor:<br>depth to rock,<br>large stones,<br>slope. | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>depth to rock,<br>small stones,<br>slope. |
| 108*:<br>Vitale-----     | Poor:<br>depth to rock,<br>slope.                  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| Milligan-----            | Poor:<br>area reclaim,<br>large stones,<br>slope.  | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>small stones,<br>slope.                   |
| 109*:<br>Vitale-----     | Poor:<br>depth to rock,<br>slope.                  | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| Povey-----               | Poor:<br>slope.                                    | Improbable:<br>excess fines,<br>large stones. | Improbable:<br>excess fines,<br>large stones. | Poor:<br>area reclaim,<br>small stones,<br>slope.  |
| 110*:<br>Winu-----       | Poor:<br>area reclaim,<br>slope.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| Rock outcrop.            |  |   |   |  |
| 111*:<br>Winu-----       | Poor:<br>area reclaim,<br>slope.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>small stones,<br>slope.                   |
| Gaib-----                | Poor:<br>area reclaim,<br>slope.                   | Improbable:<br>excess fines.                  | Improbable:<br>excess fines.                  | Poor:<br>area reclaim,<br>small stones,<br>slope.  |

\* See description of the map unit for composition and behavior characteristics of the map unit.



TABLE 12.--WATER MANAGEMENT

(Some terms that describe restrictive soil features are defined in the Glossary. See text for definitions of "slight," "moderate," and "severe." Absence of an entry indicates that the soil was not evaluated. The information in this table indicates the dominant soil condition but does not eliminate the need for onsite investigation)

| Soil name and map symbol | Limitations for--    |                                     |                             | Features affecting-- |  |  |
|--------------------------|----------------------|-------------------------------------|-----------------------------|----------------------|--|--|
|                          | Pond reservoir areas | Embankments, dikes, and levees      | Aquifer-fed excavated ponds | Drainage             | Irrigation                                 | Terraces and diversions                |
| 1-----<br>Adamson        | Severe: seepage.     | Severe: seepage.                    | Severe: no water.           | Deep to water        | Droughty-----                              | Too sandy.                             |
| 2*:<br>Adios-----        | Severe: slope.       | Severe: thin layer.                 | Severe: no water.           | Deep to water        | Percs slowly, depth to rock, cemented pan. | Slope, depth to rock, cemented pan     |
| Gooding-----             | Severe: slope.       | Moderate: thin layer, hard to pack. | Severe: no water.           | Deep to water        | Slope, percs slowly, erodes easily.        | Slope, erodes easily, percs slowly     |
| Bostrum-----             | Severe: slope.       | Severe: thin layer.                 | Severe: no water.           | Deep to water        | Slope, percs slowly, depth to rock.        | Slope, large stones, depth to rock     |
| 3*:<br>Adios-----        | Severe: slope.       | Severe: thin layer.                 | Severe: no water.           | Deep to water        | Percs slowly, depth to rock, cemented pan. | Slope, depth to rock, cemented pan.    |
| Adios, cool-----         | Severe: slope.       | Severe: thin layer.                 | Severe: no water.           | Deep to water        | Percs slowly, depth to rock, cemented pan. | Slope, depth to rock, cemented pan.    |
| 4-----<br>Balaam         | Severe: seepage.     | Severe: seepage.                    | Severe: no water.           | Deep to water        | Droughty, soil blowing.                    | Large stones, too sandy, soil blowing. |
| 5-----<br>Balaam         | Severe: seepage.     | Severe: seepage.                    | Severe: no water.           | Deep to water        | Slope, droughty.                           | Large stones, too sandy.               |
| 6*:<br>Balaam-----       | Severe: seepage.     | Severe: seepage.                    | Severe: no water.           | Deep to water        | Droughty-----                              | Large stones, too sandy.               |
| Adamson-----             | Severe: seepage.     | Severe: seepage.                    | Severe: no water.           | Deep to water        | Droughty, soil blowing.                    | Too sandy, soil blowing.               |
| 7*:<br>Balaam-----       | Severe: seepage.     | Severe: seepage, large stones.      | Severe: no water.           | Deep to water        | Large stones, droughty, soil blowing.      | Large stones, too sandy, soil blowing. |
| Adamson-----             | Severe: seepage.     | Severe: seepage.                    | Severe: no water.           | Deep to water        | Large stones, droughty, soil blowing.      | Large stones, too sandy, soil blowing. |
| 8*:<br>Balaam-----       | Severe: seepage.     | Severe: seepage, large stones.      | Severe: no water.           | Deep to water        | Large stones, droughty, soil blowing.      | Large stones, too sandy, soil blowing. |

See footnote at end of table.

TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol                                  | Limitations for--                              |                                  |                             | Features affecting--         |                                       |  |
|---|--|----------------------------------|-----------------------------|------------------------------|---------------------------------------|--|
|   | Pond reservoir areas                           | Embankments, dikes, and levees   | Aquifer-fed excavated ponds | Drainage                     | Irrigation                            | Terraces and diversions                |
| 8*:<br>Adamson-----<br><br>Riverwash.                     | Severe:<br>seepage.                            | Severe:<br>seepage.              | Severe:<br>cutbanks cave.   | Deep to water                | Large stones, droughty, soil blowing. | Large stones, too sandy, soil blowing. |
| 9-----<br>Bancroft  | Moderate:<br>seepage.                          | Moderate:<br>thin layer, piping. | Severe:<br>no water.        | Deep to water                | Erodes easily                         | Erodes easily.                         |
| 10-----<br>Bancroft                                       | Moderate:<br>seepage, slope.                   | Moderate:<br>thin layer, piping. | Severe:<br>no water.        | Deep to water                | Slope, erodes easily.                 | Erodes easily.                         |
| 11-----<br>Bickett  | Moderate:<br>seepage.                          | Severe:<br>ponding.              | Severe:<br>slow refill.     | Ponding, flooding, subsides. | Ponding, flooding.                    | Ponding.                               |
| 12*:<br>Blackspar-----<br><br>Rock outcrop.               | Severe:<br>depth to rock, slope.               | Severe:<br>large stones.         | Severe:<br>no water.        | Deep to water                | Slope, large stones, droughty.        | Slope, large stones, depth to rock.    |
| 13*:<br>Blackspot-----<br><br>Prudy-----                  | Severe:<br>depth to rock, cemented pan, slope. | Severe:<br>seepage.              | Severe:<br>no water.        | Deep to water                | Slope, droughty, depth to rock.       | Slope, large stones, depth to rock.    |
|   | Severe:<br>slope.                              | Severe:<br>piping.               | Severe:<br>no water.        | Deep to water                | Droughty, slope.                      | Slope.                                 |
| 14*:<br>Bostrum-----<br><br>Yutru-----<br><br>Hamrub----- | Moderate:<br>depth to rock, slope.             | Severe:<br>thin layer.           | Severe:<br>no water.        | Deep to water                | Slope, percs slowly, depth to rock.   | Large stones, depth to rock.           |
|   | Moderate:<br>slope.                            | Severe:<br>piping.               | Severe:<br>no water.        | Deep to water                | Slope, slow intake, percs slowly.     | Large stones, erodes easily.           |
|   | Moderate:<br>seepage, depth to rock, slope.    | Moderate:<br>thin layer, piping. | Severe:<br>no water.        | Deep to water                | Percs slowly, slope, erodes easily.   | Erodes easily.                         |
| 15-----<br>Bringmee                                       | Severe:<br>seepage.                            | Moderate:<br>thin layer.         | Severe:<br>no water.        | Deep to water                | Favorable-----                        | Favorable.                             |
| 16, 17-----<br>Bringmee                                   | Severe:<br>seepage.                            | Moderate:<br>thin layer.         | Severe:<br>no water.        | Deep to water                | Slope-----                            | Favorable.                             |
| 18*:<br>Bringmee-----                                     | Severe:<br>seepage.                            | Moderate:<br>thin layer.         | Severe:<br>no water.        | Deep to water                | Favorable-----                        | Favorable.                             |

See footnote at end of table.



TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol | Limitations for--                                      |                                      |                             | Features affecting--                        |   |  |
|--------------------------|--|--------------------------------------|-----------------------------|---|---|--|
|                          | Pond reservoir areas                                   | Embankments, dikes, and levees       | Aquifer-fed excavated ponds | Drainage                                    | Irrigation                                  | Terraces and diversions                  |
| 18*:<br>Hutton-----      | Slight-----  | Severe:<br>wetness.                  | Severe:<br>slow refill.     | Percs slowly,<br>flooding,<br>frost action. | Wetness,<br>percs slowly.                   | Wetness,<br>percs slowly.                |
| 19*:<br>Bringmee-----    | Severe:<br>seepage.                                    | Moderate:<br>thin layer.             | Severe:<br>no water.        | Deep to water                               | Favorable-----                              | Favorable.                               |
| Little Wood-----         | Severe:<br>seepage.                                    | Severe:<br>thin layer.               | Severe:<br>no water.        | Deep to water                               | Droughty-----                               | Favorable.                               |
| 20-----<br>Bruneel       | Severe:<br>seepage.                                    | Severe:<br>seepage,<br>wetness.      | Severe:<br>cutbanks cave.   | Flooding,<br>large stones,<br>frost action. | Wetness,<br>droughty,<br>flooding.          | Wetness,<br>too sandy.                   |
| 21-----<br>Carey Lake    | Moderate:<br>seepage.                                  | Severe:<br>piping.                   | Severe:<br>no water.        | Deep to water                               | Favorable-----                              | Erodes easily.                           |
| 22-----<br>Carey Lake    | Moderate:<br>seepage,<br>slope.                        | Severe:<br>piping.                   | Severe:<br>no water.        | Deep to water                               | Slope-----                                  | Erodes easily.                           |
| 23*:<br>Cox-----         | Severe:<br>depth to rock,<br>slope.                    | Severe:<br>seepage,<br>large stones. | Severe:<br>no water.        | Deep to water                               | Large stones,<br>droughty,<br>soil blowing. | Slope,<br>large stones,<br>depth to rock |
| Rehfield-----            | Moderate:<br>seepage,<br>slope.                        | Severe:<br>piping.                   | Severe:<br>no water.        | Deep to water                               | Fast intake,<br>soil blowing,<br>slope.     | Soil blowing.                            |
| Rock outcrop.            |  |                                      |                             |   |   |  |
| 24*:<br>Deerhorn-----    | Severe:<br>slope.                                      | Severe:<br>thin layer.               | Severe:<br>no water.        | Deep to water                               | Slope,<br>soil blowing,<br>depth to rock.   | Slope,<br>depth to rock<br>cemented pan. |
| Rehfield-----            | Moderate:<br>seepage,<br>slope.                        | Severe:<br>piping.                   | Severe:<br>no water.        | Deep to water                               | Soil blowing,<br>slope.                     | Soil blowing.                            |
| Rock outcrop.            |  |                                      |                             |   |   |  |
| 25*:<br>Deerhorn-----    | Moderate:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>thin layer.               | Severe:<br>no water.        | Deep to water                               | Slope,<br>soil blowing,<br>depth to rock.   | Depth to rock,<br>cemented pan.          |
| Wildors-----             | Moderate:<br>seepage,<br>depth to rock,<br>slope.      | Severe:<br>piping,<br>large stones.  | Severe:<br>no water.        | Deep to water                               | Large stones,<br>droughty,<br>soil blowing. | Large stones,<br>depth to rock           |
| 26*:<br>Deerhorn-----    | Severe:<br>slope.                                      | Severe:<br>thin layer.               | Severe:<br>no water.        | Deep to water                               | Slope,<br>soil blowing,<br>depth to rock.   | Slope,<br>depth to rock<br>cemented pan. |

See footnote at end of table.

TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol  | Limitations for--                   |   |                             | Features affecting-- |  |   |
|---------------------------|-------------------------------------|---|-----------------------------|----------------------|--|---|
|                           | Pond reservoir areas                | Embankments, dikes, and levees                  | Aquifer-fed excavated ponds | Drainage             | Irrigation                                   | Terraces and diversions                   |
| 26*:<br>Wildors-----      | Severe:<br>slope.                   | Severe:<br>piping,<br>large stones.             | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>soil blowing.  | Slope,<br>large stones,<br>depth to rock. |
| Trevino-----              | Severe:<br>depth to rock,<br>slope. | Severe:<br>piping,<br>large stones.             | Severe:<br>no water.        | Deep to water        | Slope,<br>large stones,<br>depth to rock.    | Slope,<br>large stones,<br>depth to rock. |
| 27*:<br>Dollarhide-----   | Severe:<br>depth to rock,<br>slope. | Severe:<br>seepage,<br>large stones.            | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| Rock outcrop.             |                                     |   |                             |                      |  |   |
| 28-----<br>Drage          | Moderate:<br>seepage,<br>slope.     | Moderate:<br>large stones.                      | Severe:<br>no water.        | Deep to water        | Slope,<br>large stones,<br>droughty.         | Large stones.                             |
| 29, 30-----<br>Drage      | Severe:<br>slope.                   | Moderate:<br>large stones.                      | Severe:<br>no water.        | Deep to water        | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones.                   |
| 31-----<br>Drage          | Moderate:<br>seepage.               | Moderate:<br>large stones.                      | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty.                   | Large stones.                             |
| 32*:<br>Earcree-----      | Severe:<br>seepage,<br>slope.       | Moderate:<br>thin layer,<br>seepage.            | Severe:<br>no water.        | Deep to water        | Droughty,<br>soil blowing,<br>slope.         | Slope,<br>soil blowing.                   |
| Lockman-----              | Severe:<br>seepage,<br>slope.       | Severe:<br>seepage.                             | Severe:<br>no water.        | Deep to water        | Slope-----                                   | Slope,<br>too sandy.                      |
| 33*, 34*:<br>Earcree----- | Severe:<br>seepage,<br>slope.       | Moderate:<br>thin layer,<br>seepage.            | Severe:<br>no water.        | Deep to water        | Droughty,<br>soil blowing,<br>slope.         | Slope,<br>soil blowing.                   |
| Moonstone-----            | Severe:<br>seepage,<br>slope.       | Moderate:<br>thin layer,<br>seepage,<br>piping. | Severe:<br>no water.        | Deep to water        | Droughty,<br>depth to rock,<br>slope.        | Slope,<br>depth to rock.                  |
| 35*:<br>Elkcreek-----     | Severe:<br>slope.                   | Severe:<br>thin layer.                          | Severe:<br>no water.        | Deep to water        | Depth to rock,<br>slope.                     | Slope,<br>large stones,<br>depth to rock. |
| Gaib-----                 | Severe:<br>depth to rock,<br>slope. | Severe:<br>large stones.                        | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| 36*:<br>Elkcreek-----     | Severe:<br>slope.                   | Severe:<br>thin layer.                          | Severe:<br>no water.        | Deep to water        | Depth to rock,<br>slope.                     | Slope,<br>large stones,<br>depth to rock. |

See footnote at end of table.



TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol | Limitations for--                                    |   |                             | Features affecting-- |  |   |
|--------------------------|--|---|-----------------------------|----------------------|--|---|
|                          | Pond reservoir areas                                 | Embankments, dikes, and levees            | Aquifer-fed excavated ponds | Drainage             | Irrigation                                       | Terraces and diversions                   |
| 36*:<br>Polecreek-----   | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>percs slowly.      | Slope,<br>large stones,<br>depth to rock  |
| 37*:<br>Elksel-----      | Severe:<br>slope.                                    | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water        | Slope,<br>large stones,<br>droughty.             | Slope,<br>large stones,<br>percs slowly.  |
| Friedman-----            | Severe:<br>slope.                                    | Moderate:<br>thin layer,<br>large stones. | Severe:<br>no water.        | Deep to water        | Percs slowly,<br>slope.                          | Slope,<br>large stones,<br>percs slowly.  |
| Starhope-----            | Severe:<br>slope.                                    | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>percs slowly.      | Slope,<br>large stones,<br>depth to rock  |
| 38*:<br>Elksel-----      | Severe:<br>slope.                                    | Moderate:<br>thin layer,<br>large stones. | Severe:<br>no water.        | Deep to water        | Droughty,<br>percs slowly,<br>slope.             | Slope,<br>large stones,<br>percs slowly.  |
| Peevywell-----           | Severe:<br>slope.                                    | Severe:<br>thin layer.                    | Severe:<br>no water.        | Deep to water        | Percs slowly,<br>cemented pan,<br>slope.         | Slope,<br>cemented pan,<br>percs slowly.  |
| Furshur-----             | Severe:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>hard to pack.                  | Severe:<br>no water.        | Deep to water        | Percs slowly,<br>depth to rock,<br>cemented pan. | Slope,<br>depth to rock,<br>cemented pan. |
| 39*:<br>Elksel-----      | Severe:<br>slope.                                    | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water        | Slope,<br>large stones,<br>droughty.             | Slope,<br>large stones,<br>percs slowly.  |
| Starhope-----            | Severe:<br>slope.                                    | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>percs slowly.      | Slope,<br>large stones,<br>depth to rock  |
| Rock outcrop.            |  |   |                             |                      |  |   |
| 40*:<br>Friedman-----    | Severe:<br>slope.                                    | Moderate:<br>thin layer,<br>large stones. | Severe:<br>no water.        | Deep to water        | Percs slowly,<br>slope.                          | Slope,<br>large stones,<br>percs slowly.  |
| Elksel-----              | Severe:<br>slope.                                    | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water        | Slope,<br>large stones,<br>droughty.             | Slope,<br>large stones,<br>percs slowly.  |
| Winridge-----            | Severe:<br>slope.                                    | Severe:<br>thin layer.                    | Severe:<br>no water.        | Deep to water        | Large stones,<br>percs slowly,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock  |
| 41*:<br>Gaib-----        | Severe:<br>depth to rock,<br>slope.                  | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>depth to rock.     | Slope,<br>large stones,<br>depth to rock  |

See footnote at end of table.

TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol | Limitations for--                                      |   |   | Features affecting--               |  |                                 |
|--------------------------|--|---|---|------------------------------------|--|---------------------------------|
|                          | Pond reservoir areas                                   | Embankments, dikes, and levees            | Aquifer-fed excavated ponds               | Drainage                           | Irrigation                                       | Terraces and diversions         |
| 41*:<br>Rock outcrop.    |  |   |   |                                    |  |                                 |
| 42-----<br>Gimlett       | Severe:<br>seepage.                                    | Severe:<br>seepage.                       | Severe:<br>no water.                      | Deep to water                      | Large stones,<br>droughty.                       | Large stones,<br>too sandy.     |
| 43*:<br>Gooding-----     | Moderate:<br>depth to rock,<br>cemented pan,<br>slope. | Moderate:<br>thin layer,<br>hard to pack. | Severe:<br>no water.                      | Deep to water                      | Slope,<br>percs slowly,<br>erodes easily.        | Erodes easily,<br>percs slowly. |
| Gooding, eroded--        | Moderate:<br>depth to rock,<br>cemented pan,<br>slope. | Moderate:<br>thin layer,<br>hard to pack. | Severe:<br>no water.                      | Deep to water                      | Slope,<br>percs slowly.                          | Percs slowly.                   |
| Hamrub-----              | Moderate:<br>seepage,<br>depth to rock,<br>slope.      | Moderate:<br>thin layer,<br>piping.       | Severe:<br>no water.                      | Deep to water                      | Percs slowly,<br>slope,<br>erodes easily.        | Erodes easily.                  |
| 44-----<br>Goodington    | Moderate:<br>depth to rock,<br>slope.                  | Moderate:<br>thin layer,<br>piping.       | Severe:<br>no water.                      | Deep to water                      | Percs slowly,<br>slope,<br>erodes easily.        | Erodes easily.                  |
| 45*:<br>Goodington-----  | Moderate:<br>depth to rock,<br>slope.                  | Moderate:<br>thin layer,<br>piping.       | Severe:<br>no water.                      | Deep to water                      | Percs slowly,<br>slope,<br>erodes easily.        | Erodes easily.                  |
| Manard-----              | Moderate:<br>depth to rock,<br>cemented pan,<br>slope. | Severe:<br>thin layer.                    | Severe:<br>no water.                      | Deep to water                      | Percs slowly,<br>depth to rock,<br>cemented pan. | Large stones,<br>depth to rock. |
| 46-----<br>Hapur         | Severe:<br>seepage.                                    | Severe:<br>wetness.                       | Severe:<br>slow refill,<br>cutbanks cave. | Flooding,<br>frost action.         | Wetness,<br>erodes easily,<br>flooding.          | Erodes easily,<br>wetness.      |
| 47*:<br>Hapur-----       | Severe:<br>seepage.                                    | Severe:<br>wetness.                       | Severe:<br>slow refill,<br>cutbanks cave. | Flooding,<br>frost action.         | Wetness,<br>erodes easily,<br>flooding.          | Erodes easily,<br>wetness.      |
| Bickett-----             | Moderate:<br>seepage.                                  | Severe:<br>ponding.                       | Severe:<br>slow refill.                   | Ponding,<br>flooding,<br>subsides. | Ponding,<br>flooding.                            | Ponding.                        |
| 48*:<br>Hapur-----       | Severe:<br>seepage.                                    | Severe:<br>wetness.                       | Severe:<br>slow refill,<br>cutbanks cave. | Flooding,<br>frost action.         | Wetness,<br>erodes easily,<br>flooding.          | Erodes easily,<br>wetness.      |
| Picabo-----              | Moderate:<br>seepage.                                  | Severe:<br>piping.                        | Severe:<br>cutbanks cave.                 | Flooding,<br>frost action.         | Wetness,<br>erodes easily,<br>flooding.          | Erodes easily,<br>wetness.      |

See footnote at end of table.



TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol    | Limitations for--                   |   |                             | Features affecting--                        |  |   |
|-----------------------------|-------------------------------------|---|-----------------------------|---|--|---|
|                             | Pond reservoir areas                | Embankments, dikes, and levees                  | Aquifer-fed excavated ponds | Drainage                                    | Irrigation                                   | Terraces and diversions                   |
| 49-----<br>Hutton           | Slight-----                         | Severe:<br>wetness.                             | Severe:<br>slow refill.     | Percs slowly,<br>flooding,<br>frost action. | Wetness,<br>percs slowly.                    | Wetness,<br>percs slowly.                 |
| 50-----<br>Hutton Variant   | Severe:<br>seepage.                 | Severe:<br>seepage.                             | Severe:<br>no water.        | Deep to water                               | Percs slowly---                              | Too sandy.                                |
| 51-----<br>Isknat           | Severe:<br>seepage.                 | Severe:<br>seepage.                             | Severe:<br>no water.        | Deep to water                               | Droughty,<br>percs slowly.                   | Large stones,<br>too sandy.               |
| 52, 53-----<br>Justesen     | Moderate:<br>seepage,<br>slope.     | Severe:<br>piping.                              | Severe:<br>no water.        | Deep to water                               | Slope-----                                   | Erodes easily.                            |
| 54, 55-----<br>Justesen     | Severe:<br>slope.                   | Severe:<br>piping.                              | Severe:<br>no water.        | Deep to water                               | Slope-----                                   | Slope,<br>erodes easily.                  |
| 56*:<br>Ketchum-----        | Severe:<br>seepage,<br>slope.       | Severe:<br>seepage.                             | Severe:<br>no water.        | Deep to water                               | Slope,<br>droughty.                          | Slope,<br>large stones.                   |
| Dollarhide-----             | Severe:<br>depth to rock,<br>slope. | Severe:<br>seepage,<br>large stones.            | Severe:<br>no water.        | Deep to water                               | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| 57*:<br>Ketchum-----        | Severe:<br>seepage,<br>slope.       | Severe:<br>seepage.                             | Severe:<br>no water.        | Deep to water                               | Slope,<br>droughty.                          | Slope,<br>large stones.                   |
| Povey-----                  | Severe:<br>slope.                   | Severe:<br>large stones.                        | Severe:<br>no water.        | Deep to water                               | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones.                   |
| 58*:<br>Laurentzen-----     | Severe:<br>slope.                   | Moderate:<br>thin layer,<br>piping.             | Severe:<br>no water.        | Deep to water                               | Slope-----                                   | Slope,<br>erodes easily.                  |
| Mulshoe-----                | Severe:<br>slope.                   | Severe:<br>large stones.                        | Severe:<br>no water.        | Deep to water                               | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| 59*.<br>Lava flows          |                                     |   |                             |   |  |   |
| 60*:<br>Lava flows.         |                                     |   |                             |   |  |   |
| Cinderhurst-----            | Severe:<br>depth to rock,<br>slope. | Severe:<br>large stones.                        | Severe:<br>no water.        | Deep to water                               | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| 61*, 62*:<br>Lavacreek----- | Severe:<br>slope.                   | Moderate:<br>thin layer,<br>seepage,<br>piping. | Severe:<br>no water.        | Deep to water                               | Large stones,<br>droughty,<br>slope.         | Slope,<br>large stones.                   |

See footnote at end of table.

TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol  | Limitations for--                      |  |                             | Features affecting--                  |  |  |
|---------------------------|--|--|-----------------------------|---------------------------------------|--|--|
|                           | Pond reservoir areas                   | Embankments, dikes, and levees         | Aquifer-fed excavated ponds | Drainage                              | Irrigation                             | Terraces and diversions                |
| 61*, 62*: Dollarhide----- | Severe: depth to rock, slope.          | Severe: seepage, large stones.         | Severe: no water.           | Deep to water                         | Large stones, droughty, depth to rock. | Slope, large stones, depth to rock.    |
| 63*: Lavacreek-----       | Severe: slope.                         | Moderate: thin layer, seepage, piping. | Severe: no water.           | Deep to water                         | Large stones, droughty, slope.         | Slope, large stones.                   |
| Vitale-----               | Severe: slope.                         | Severe: large stones.                  | Severe: no water.           | Deep to water                         | Slope, large stones, depth to rock.    | Slope, large stones, depth to rock.    |
| 64----- Little Wood       | Severe: seepage.                       | Severe: thin layer.                    | Severe: no water.           | Deep to water                         | Droughty-----                          | Favorable.                             |
| 65----- Little Wood       | Severe: seepage.                       | Severe: thin layer.                    | Severe: no water.           | Deep to water                         | Slope, droughty.                       | Favorable.                             |
| 66----- Little Wood       | Severe: seepage.                       | Severe: thin layer.                    | Severe: no water.           | Deep to water                         | Droughty-----                          | Favorable.                             |
| 67----- Little Wood       | Severe: seepage.                       | Severe: thin layer.                    | Severe: no water.           | Deep to water                         | Slope, droughty.                       | Favorable.                             |
| 68----- Little Wood       | Severe: seepage.                       | Severe: seepage, large stones.         | Severe: no water.           | Deep to water                         | Large stones, droughty.                | Large stones, too sandy.               |
| 69*: Little Wood-----     | Severe: seepage.                       | Severe: thin layer.                    | Severe: no water.           | Deep to water                         | Droughty-----                          | Favorable.                             |
| Balaam-----               | Severe: seepage.                       | Severe: seepage.                       | Severe: no water.           | Deep to water                         | Droughty, soil blowing.                | Large stones, too sandy, soil blowing. |
| 70----- Manard            | Moderate: depth to rock, cemented pan. | Severe: thin layer.                    | Severe: no water.           | Deep to water                         | Percs slowly, depth to rock.           | Depth to rock, cemented pan.           |
| 71----- Marshdale         | Moderate: seepage.                     | Severe: piping, wetness.               | Severe: cutbanks cave.      | Flooding, frost action.               | Wetness, flooding.                     | Wetness.                               |
| 72*: Marshdale-----       | Moderate: seepage.                     | Severe: piping, wetness.               | Severe: cutbanks cave.      | Flooding, frost action.               | Wetness, flooding.                     | Wetness.                               |
| Bruneel-----              | Severe: seepage.                       | Severe: seepage, wetness.              | Severe: cutbanks cave.      | Flooding, large stones, frost action. | Wetness, droughty, flooding.           | Wetness, too sandy.                    |
| 73----- McBiggam          | Moderate: slope.                       | Moderate: hard to pack.                | Severe: no water.           | Deep to water                         | Percs slowly, slope, erodes easily.    | Erodes easily, percs slowly.           |

See footnote at end of table.



TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol | Limitations for--                        |  |                             | Features affecting-- |  |                                     |
|--------------------------|--|--|-----------------------------|----------------------|--|-------------------------------------|
|                          | Pond reservoir areas                     | Embankments, dikes, and levees         | Aquifer-fed excavated ponds | Drainage             | Irrigation                             | Terraces and diversions             |
| 74*:<br>McCarey-----     | Moderate: seepage, depth to rock, slope. | Severe: piping.                        | Severe: no water.           | Deep to water        | Depth to rock, slope, erodes easily.   | Depth to rock, erodes easily.       |
| Justesen-----            | Moderate: seepage, slope.                | Severe: piping.                        | Severe: no water.           | Deep to water        | Slope-----                             | Erodes easily.                      |
| 75*:<br>McCarey-----     | Severe: slope.                           | Severe: piping.                        | Severe: no water.           | Deep to water        | Depth to rock, slope, erodes easily.   | Slope, depth to rock erodes easily. |
| Justesen-----            | Severe: slope.                           | Severe: piping.                        | Severe: no water.           | Deep to water        | Slope-----                             | Slope, erodes easily.               |
| Rock outcrop.            |  |  |                             |                      |  |                                     |
| 76*:<br>McCarey-----     | Moderate: seepage, depth to rock, slope. | Severe: piping.                        | Severe: no water.           | Deep to water        | Depth to rock, slope, erodes easily.   | Depth to rock, erodes easily.       |
| Molyneux-----            | Moderate: slope.                         | Moderate: piping.                      | Severe: no water.           | Deep to water        | Slope-----                             | Favorable.                          |
| 77*:<br>McCarey-----     | Severe: slope.                           | Severe: piping.                        | Severe: no water.           | Deep to water        | Depth to rock, slope, erodes easily.   | Slope, depth to rock erodes easily. |
| Pedleford-----           | Severe: slope.                           | Severe: large stones.                  | Severe: no water.           | Deep to water        | Large stones, droughty, depth to rock. | Slope, large stones, depth to rock. |
| 78, 79-----<br>Molyneux  | Moderate: slope.                         | Moderate: piping.                      | Severe: no water.           | Deep to water        | Slope-----                             | Favorable.                          |
| 80-----<br>Molyneux      | Severe: slope.                           | Moderate: piping.                      | Severe: no water.           | Deep to water        | Slope-----                             | Slope.                              |
| 81*:<br>Moonstone-----   | Severe: seepage, slope.                  | Moderate: thin layer, seepage, piping. | Severe: no water.           | Deep to water        | Droughty, depth to rock, slope.        | Slope, depth to rock.               |
| Bauscher-----            | Severe: seepage, slope.                  | Severe: thin layer.                    | Severe: no water.           | Deep to water        | Slope-----                             | Slope.                              |
| 82*:<br>Moonstone-----   | Severe: seepage, slope.                  | Moderate: thin layer, seepage, piping. | Severe: no water.           | Deep to water        | Droughty, depth to rock, slope.        | Slope, depth to rock.               |

See footnote at end of table.

TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol | Limitations for--                                |                                      |                             | Features affecting-- |  |   |
|--------------------------|--|--------------------------------------|-----------------------------|----------------------|--|---|
|                          | Pond reservoir areas                             | Embankments, dikes, and levees       | Aquifer-fed excavated ponds | Drainage             | Irrigation                                   | Terraces and diversions                   |
| 82*:<br>Earcree-----     | Severe:<br>seepage,<br>slope.                    | Moderate:<br>thin layer,<br>seepage. | Severe:<br>no water.        | Deep to water        | Droughty,<br>soil blowing,<br>slope.         | Slope,<br>soil blowing.                   |
| 83*:<br>Muldoon-----     | Severe:<br>slope.                                | Moderate:<br>thin layer,<br>piping.  | Severe:<br>no water.        | Deep to water        | Slope-----                                   | Slope,<br>large stones.                   |
| Peevywell-----           | Severe:<br>slope.                                | Severe:<br>seepage.                  | Severe:<br>no water.        | Deep to water        | Percs slowly,<br>cemented pan,<br>slope.     | Slope,<br>large stones,<br>cemented pan.  |
| 84*:<br>Mulshoe-----     | Severe:<br>slope.                                | Severe:<br>large stones.             | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| Gaib-----                | Severe:<br>depth to rock,<br>slope.              | Severe:<br>large stones.             | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| Rock outcrop.            |  |                                      |                             |                      |  |   |
| 85*:<br>Mulshoe-----     | Severe:<br>slope.                                | Severe:<br>large stones.             | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| Gaib-----                | Severe:<br>depth to rock,<br>slope.              | Severe:<br>large stones.             | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| Winu-----                | Severe:<br>seepage,<br>slope.                    | Moderate:<br>thin layer.             | Severe:<br>no water.        | Deep to water        | Depth to rock,<br>slope.                     | Slope,<br>depth to rock.                  |
| 86*:<br>Pagari-----      | Severe:<br>slope.                                | Severe:<br>seepage,<br>large stones. | Severe:<br>no water.        | Deep to water        | Large stones,<br>droughty,<br>slope.         | Slope,<br>large stones.                   |
| Rehfield-----            | Moderate:<br>seepage,<br>slope.                  | Severe:<br>piping.                   | Severe:<br>no water.        | Deep to water        | Fast intake,<br>soil blowing,<br>slope.      | Soil blowing.                             |
| 87*:<br>Peevywell-----   | Moderate:<br>seepage,<br>cemented pan,<br>slope. | Severe:<br>seepage.                  | Severe:<br>no water.        | Deep to water        | Percs slowly,<br>cemented pan,<br>slope.     | Large stones,<br>cemented pan.            |
| Simonton-----            | Severe:<br>seepage.                              | Severe:<br>piping.                   | Severe:<br>no water.        | Deep to water        | Rooting depth,<br>slope.                     | Erodes easily.                            |
| 88*:<br>Peevywell-----   | Severe:<br>slope.                                | Severe:<br>seepage.                  | Severe:<br>no water.        | Deep to water        | Percs slowly,<br>cemented pan,<br>slope.     | Slope,<br>large stones,<br>cemented pan.  |

See footnote at end of table.



TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol                         | Limitations for--                   |   |                             | Features affecting--       |  |   |
|--|-------------------------------------|---|-----------------------------|----------------------------|--|---|
|  | Pond reservoir areas                | Embankments, dikes, and levees            | Aquifer-fed excavated ponds | Drainage                   | Irrigation                                   | Terraces and diversions                   |
| 88*:<br>Simonton-----                            | Severe:<br>seepage,<br>slope.       | Severe:<br>piping.                        | Severe:<br>no water.        | Deep to water              | Rooting depth,<br>slope.                     | Slope,<br>erodes easily                   |
| 89-----<br>Picabo                                | Moderate:<br>seepage.               | Severe:<br>piping.                        | Severe:<br>cutbanks cave.   | Flooding,<br>frost action. | Wetness,<br>erodes easily,<br>flooding.      | Erodes easily,<br>wetness.                |
| 90-----<br>Picabo                                | Moderate:<br>seepage.               | Severe:<br>piping.                        | Severe:<br>cutbanks cave.   | Flooding,<br>frost action. | Wetness,<br>flooding.                        | Erodes easily,<br>wetness.                |
| 91*.<br>Pits, gravel                             |                                     |   |                             |                            |  |   |
| 92*:<br>Povey-----                               | Severe:<br>slope.                   | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water              | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones.                   |
| Dollarhide-----                                  | Severe:<br>depth to rock,<br>slope. | Severe:<br>seepage,<br>large stones.      | Severe:<br>no water.        | Deep to water              | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock  |
| 93*:<br>Povey-----                               | Severe:<br>slope.                   | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water              | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones.                   |
| Rock outcrop.                                    |                                     |   |                             |                            |  |   |
| 94*:<br>Povey very<br>gravelly silt<br>loam----- | Severe:<br>slope.                   | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water              | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones.                   |
| Povey gravelly<br>loam-----                      | Severe:<br>slope.                   | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water              | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones.                   |
| 95*:<br>Povey-----                               | Severe:<br>slope.                   | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water              | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones.                   |
| Vitale-----                                      | Severe:<br>slope.                   | Severe:<br>large stones.                  | Severe:<br>no water.        | Deep to water              | Slope,<br>large stones,<br>depth to rock.    | Slope,<br>large stones,<br>depth to rock  |
| 96*:<br>Rehfield-----                            | Severe:<br>slope.                   | Severe:<br>piping.                        | Severe:<br>no water.        | Deep to water              | Soil blowing,<br>slope.                      | Slope,<br>soil blowing.                   |
| Gooding-----                                     | Severe:<br>slope.                   | Moderate:<br>thin layer,<br>hard to pack. | Severe:<br>no water.        | Deep to water              | Slope,<br>percs slowly,<br>erodes easily.    | Slope,<br>erodes easily,<br>percs slowly. |
| 97*.<br>Riverwash                                |                                     |   |                             |                            |  |   |

See footnote at end of table.

TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and map symbol  | Limitations for--                           |                                       |                             | Features affecting-- |  |                                     |
|---------------------------|---|---------------------------------------|-----------------------------|----------------------|--|-------------------------------------|
|                           | Pond reservoir areas                        | Embankments, dikes, and levees        | Aquifer-fed excavated ponds | Drainage             | Irrigation                                 | Terraces and diversions             |
| 98*:<br>Rock outcrop.     |   |                                       |                             |                      |  |                                     |
| Adios-----                | Severe: slope.                              | Severe: thin layer.                   | Severe: no water.           | Deep to water        | Percs slowly, depth to rock, cemented pan. | Slope, depth to rock, cemented pan. |
| 99-----<br>Rockybar       | Severe: seepage, slope.                     | Severe: large stones.                 | Severe: no water.           | Deep to water        | Large stones, droughty, slope.             | Slope, large stones.                |
| 100*.<br>Rubbleland       |   |                                       |                             |                      |  |                                     |
| 101*:<br>Rubbleland.      |   |                                       |                             |                      |  |                                     |
| Milligan-----             | Severe: seepage, slope.                     | Severe: large stones.                 | Severe: no water.           | Deep to water        | Large stones, droughty, depth to rock.     | Slope, large stones, depth to rock. |
| 102, 103-----<br>Simonton | Severe: seepage.                            | Severe: piping.                       | Severe: no water.           | Deep to water        | Rooting depth, slope.                      | Erodes easily.                      |
| 104*:<br>Simonton-----    | Severe: seepage, slope.                     | Severe: piping.                       | Severe: no water.           | Deep to water        | Rooting depth, slope.                      | Slope, erodes easily.               |
| Bauscher-----             | Severe: seepage, slope.                     | Severe: thin layer.                   | Severe: no water.           | Deep to water        | Slope-----                                 | Slope.                              |
| 105*:<br>Starhope-----    | Severe: slope.                              | Moderate: hard to pack, large stones. | Severe: no water.           | Deep to water        | Large stones, percs slowly.                | Slope, large stones, depth to rock. |
| Furshur-----              | Severe: depth to rock, cemented pan, slope. | Severe: hard to pack.                 | Severe: no water.           | Deep to water        | Percs slowly, depth to rock, cemented pan. | Slope, depth to rock, cemented pan. |
| 106*:<br>Starhope-----    | Severe: slope.                              | Moderate: hard to pack, large stones. | Severe: no water.           | Deep to water        | Large stones, percs slowly.                | Slope, large stones, depth to rock. |
| Peevywell-----            | Severe: slope.                              | Severe: seepage.                      | Severe: no water.           | Deep to water        | Percs slowly, cemented pan, slope.         | Slope, large stones, cemented pan.  |
| Smelter-----              | Severe: slope.                              | Slight-----                           | Severe: no water.           | Deep to water        | Percs slowly, slope.                       | Slope.                              |
| 107*:<br>Vitale-----      | Severe: slope.                              | Severe: large stones.                 | Severe: no water.           | Deep to water        | Slope, large stones, depth to rock.        | Slope, large stones, depth to rock. |

See footnote at end of table.



TABLE 12.--WATER MANAGEMENT--Continued

| Soil name and<br>map symbol | Limitations for--                   |                                      |                                   | Features affecting-- |  |   |
|-----------------------------|-------------------------------------|--------------------------------------|-----------------------------------|----------------------|--|---|
|                             | Pond<br>reservoir<br>areas          | Embankments,<br>dikes, and<br>levees | Aquifer-fed<br>excavated<br>ponds | Drainage             | Irrigation                                   | Terraces<br>and<br>diversions             |
| 107*:<br>Blackspar-----     | Severe:<br>depth to rock,<br>slope. | Severe:<br>large stones.             | Severe:<br>no water.              | Deep to water        | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones,<br>depth to rock. |
| 108*:<br>Vitale-----        | Severe:<br>slope.                   | Severe:<br>large stones.             | Severe:<br>no water.              | Deep to water        | Slope,<br>large stones,<br>depth to rock.    | Slope,<br>large stones,<br>depth to rock. |
| Milligan-----               | Severe:<br>seepage,<br>slope.       | Severe:<br>large stones.             | Severe:<br>no water.              | Deep to water        | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |
| 109*:<br>Vitale-----        | Severe:<br>slope.                   | Severe:<br>large stones.             | Severe:<br>no water.              | Deep to water        | Slope,<br>large stones,<br>depth to rock.    | Slope,<br>large stones,<br>depth to rock. |
| Povey-----                  | Severe:<br>slope.                   | Severe:<br>large stones.             | Severe:<br>no water.              | Deep to water        | Slope,<br>large stones,<br>droughty.         | Slope,<br>large stones.                   |
| 110*:<br>Winu-----          | Severe:<br>seepage,<br>slope.       | Moderate:<br>thin layer.             | Severe:<br>no water.              | Deep to water        | Depth to rock,<br>slope.                     | Slope,<br>depth to rock.                  |
| Rock outcrop.               |                                     |                                      |                                   |                      |  |   |
| 111*:<br>Winu-----          | Severe:<br>seepage,<br>slope.       | Moderate:<br>thin layer.             | Severe:<br>no water.              | Deep to water        | Depth to rock,<br>slope.                     | Slope,<br>depth to rock.                  |
| Gaib-----                   | Severe:<br>depth to rock,<br>slope. | Severe:<br>large stones.             | Severe:<br>no water.              | Deep to water        | Large stones,<br>droughty,<br>depth to rock. | Slope,<br>large stones,<br>depth to rock. |

\* See description of the map unit for composition and behavior characteristics of the map unit.

TABLE 13.--ENGINEERING INDEX PROPERTIES

(The symbol &lt; means less than; &gt; means more than. Absence of an entry indicates that data were not estimated)

| Soil name and map symbol | Depth | USDA texture   | Classification |          | Frag-ments > 3 inches | Percentage passing sieve number-- |        |        |       | Liquid limit | Plas-ticity index |
|--------------------------|-------|--|----------------|----------|-----------------------|-----------------------------------|--------|--------|-------|--------------|-------------------|
|                          |       |  | Unified        | AASHTO   |                       | 4                                 | 10     | 40     | 200   |              |                   |
|                          | In    |  |                |          | Pct                   |                                   |        |        |       | Pct          |                   |
| Adamson                  | 0-5   | Loam-----  | CL-ML, ML      | A-4      | 0                     | 100                               | 90-100 | 80-95  | 60-75 | 20-30        | NP-10             |
|                          | 5-28  | Stratified loam to fine sandy loam.  | ML, CL-ML      | A-4      | 0                     | 95-100                            | 85-100 | 75-90  | 50-70 | 20-30        | NP-10             |
|                          | 28-61 | Very gravelly sand, very gravelly coarse sand, extremely gravelly coarse sand. | GP             | A-1      | 5-30                  | 20-40                             | 15-35  | 5-25   | 0-5   | ---          | NP                |
| 2*:                      |       |  |                |          |                       |                                   |        |        |       |              |                   |
| Adios-----               | 0-5   | Stony loam-----  | CL             | A-6      | 5-10                  | 85-100                            | 80-95  | 70-85  | 60-80 | 25-35        | 10-15             |
|                          | 5-23  | Clay, clay loam, gravelly clay.  | CL, CH         | A-7      | 0-15                  | 70-100                            | 65-100 | 60-90  | 55-80 | 40-60        | 20-35             |
|                          | 23-27 | Indurated-----   | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |
|                          | 27    | Weathered bedrock  | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |
| Gooding-----             | 0-9   | Silt loam-----   | ML             | A-4      | 0                     | 95-100                            | 90-100 | 80-95  | 75-90 | 25-30        | NP-10             |
|                          | 9-34  | Silty clay, clay, silty clay loam.   | CL, CH         | A-7      | 0                     | 90-100                            | 90-100 | 85-100 | 75-95 | 45-65        | 20-40             |
|                          | 34-49 | Silty clay loam, clay loam.  | CL, CH         | A-7      | 5-10                  | 90-100                            | 90-100 | 80-95  | 75-90 | 40-55        | 15-30             |
|                          | 49-62 | Cemented-----  | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |
|                          | 62    | Unweathered bedrock.   | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |
| Bostrum-----             | 0-4   | Cobbly silt loam   | CL-ML          | A-4      | 15-30                 | 75-100                            | 75-95  | 70-95  | 65-90 | 20-30        | 5-10              |
|                          | 4-28  | Silty clay, clay, silty clay loam.   | CL, CH         | A-7      | 0-10                  | 95-100                            | 95-100 | 85-100 | 75-95 | 40-60        | 20-35             |
|                          | 28-32 | Silty clay loam, clay loam.  | ML, CL         | A-6, A-7 | 0-10                  | 95-100                            | 95-100 | 80-100 | 70-95 | 35-45        | 10-20             |
|                          | 32-36 | Unweathered bedrock.   | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |
| 3*:                      |       |  |                |          |                       |                                   |        |        |       |              |                   |
| Adios-----               | 0-5   | Stony loam-----  | CL             | A-6      | 5-10                  | 85-100                            | 80-95  | 70-85  | 60-80 | 25-35        | 10-15             |
|                          | 5-23  | Clay, clay loam, gravelly clay.  | CL, CH         | A-7      | 0-15                  | 70-100                            | 65-100 | 60-90  | 55-80 | 40-60        | 20-35             |
|                          | 23-27 | Indurated-----   | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |
|                          | 27    | Weathered bedrock  | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |
| Adios, cool-----         | 0-7   | Loam-----  | CL             | A-6      | 0                     | 90-100                            | 85-95  | 70-85  | 55-75 | 25-35        | 10-15             |
|                          | 7-25  | Clay, clay loam, gravelly clay.  | CL, CH         | A-7      | 0-15                  | 70-100                            | 65-100 | 60-90  | 55-80 | 40-60        | 20-35             |
|                          | 25-28 | Indurated-----   | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |
|                          | 28-32 | Weathered bedrock  | ---            | ---      | ---                   | ---                               | ---    | ---    | ---   | ---          | ---               |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture   | Classification |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |       |       | Liquid<br>limit<br><br>Pct | Plas-<br>ticity<br>inde |
|--------------------------|-----------|--|----------------|----------|-----------------------------|--------------------------------------|--------|-------|-------|----------------------------|-------------------------|
|                          |           |  | Unified        | AASHTO   |                             | 4                                    | 10     | 40    | 200   |                            |                         |
|                          | <u>In</u> |  |                |          | <u>Pct</u>                  |                                      |        |       |       |                            |                         |
| 4-----<br>Balaam         | 0-14      | Gravelly sandy loam.   | SM, GM         | A-2, A-1 | 0-5                         | 55-80                                | 55-75  | 30-60 | 15-30 | 25-30                      | NP-5                    |
|                          | 14-21     | Very gravelly coarse sandy loam, very gravelly fine sandy loam.                | GM             | A-1, A-2 | 0-10                        | 45-60                                | 40-55  | 20-50 | 10-30 | ---                        | NP                      |
|                          | 21-61     | Extremely gravelly coarse sand, extremely gravelly loamy coarse sand.          | GP, GP-GM      | A-1      | 10-30                       | 20-35                                | 15-30  | 5-20  | 0-10  | ---                        | NP                      |
| 5-----<br>Balaam         | 0-14      | Very gravelly sandy loam.  | GM             | A-1      | 0-5                         | 40-55                                | 30-50  | 20-40 | 10-25 | 25-30                      | NP-5                    |
|                          | 14-21     | Very gravelly coarse sandy loam, very gravelly fine sandy loam.                | GM             | A-1, A-2 | 0-10                        | 45-60                                | 40-55  | 20-50 | 10-30 | ---                        | NP                      |
|                          | 21-61     | Extremely gravelly coarse sand, extremely gravelly loamy coarse sand.          | GP, GP-GM      | A-1      | 10-30                       | 20-35                                | 15-30  | 5-20  | 0-10  | ---                        | NP                      |
| 6*:<br>Balaam-----       | 0-21      | Very gravelly sandy loam.  | GM             | A-1      | 0-5                         | 40-55                                | 30-50  | 20-40 | 10-25 | 25-30                      | NP-5                    |
|                          | 21-35     | Very gravelly coarse sandy loam, very gravelly fine sandy loam.                | GM             | A-1, A-2 | 0-10                        | 45-60                                | 40-55  | 20-50 | 10-30 | ---                        | NP                      |
|                          | 35-63     | Extremely gravelly coarse sand, extremely gravelly loamy coarse sand.          | GP, GP-GM      | A-1      | 10-30                       | 20-35                                | 15-30  | 5-20  | 0-10  | ---                        | NP                      |
| Adamson-----             | 0-5       | Fine sandy loam  | SM, ML         | A-4      | 0                           | 100                                  | 90-100 | 80-90 | 40-70 | 20-25                      | NP-5                    |
|                          | 5-28      | Stratified loam to fine sandy loam.  | ML, CL-ML      | A-4      | 0                           | 95-100                               | 85-100 | 75-90 | 50-70 | 20-30                      | NP-10                   |
|                          | 28-61     | Very gravelly sand, very gravelly coarse sand, extremely gravelly coarse sand. | GP             | A-1      | 5-30                        | 20-40                                | 15-35  | 5-25  | 0-5   | ---                        | NP                      |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol             | Depth     | USDA texture  | Classification             |                  | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |        | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------------------|-----------|---|----------------------------|------------------|-----------------------------|--------------------------------------|--------|--------|--------|-----------------|--------------------------|
|                                      |           |   | Unified                    | AASHTO           |                             | 4                                    | 10     | 40     | 200    |                 |                          |
|                                      | <u>In</u> |   |                            |                  | <u>Pct</u>                  |                                      |        |        |        | <u>Pct</u>      |                          |
| 7*:<br>Balaam-----                   | 0-10      | Gravelly sandy loam.  | SM, GM                     | A-4, A-2         | 0                           | 60-80                                | 55-75  | 45-65  | 25-50  | 25-30           | NP-5                     |
|                                      | 10-17     | Very gravelly sandy loam, very cobbly sandy loam.                 | GM                         | A-1, A-2         | 5-40                        | 35-55                                | 35-55  | 25-45  | 10-30  | ---             | NP                       |
|                                      | 17-60     | Extremely cobbly loamy coarse sand, extremely cobbly coarse sand. | GP, GP-GM                  | A-1              | 50-65                       | 15-30                                | 10-30  | 5-20   | 0-10   | ---             | NP                       |
| Adamson-----                         | 0-9       | Fine sandy loam   | SM, ML,<br>SM-SC,<br>CL-ML | A-4              | 0                           | 90-100                               | 90-100 | 85-100 | 45-65  | 20-30           | NP-10                    |
|                                      | 9-22      | Very fine sandy loam.   | ML, CL-ML                  | A-4              | 0                           | 90-100                               | 90-100 | 85-95  | 55-75  | 20-30           | NP-10                    |
|                                      | 22-48     | Extremely cobbly loamy coarse sand, extremely cobbly coarse sand. | GM                         | A-1              | 50-70                       | 50-65                                | 45-60  | 20-35  | 5-20   | ---             | NP                       |
|                                      | 48-60     | Extremely stony coarse sand.                                      | GP-GM                      | A-1              | 60-80                       | 35-55                                | 30-50  | 15-30  | 5-10   | ---             | NP                       |
| 8*:<br>Balaam-----                   | 0-10      | Gravelly sandy loam.  | SM, GM                     | A-4, A-2         | 0                           | 60-80                                | 55-75  | 45-65  | 25-50  | 25-30           | NP-5                     |
|                                      | 10-17     | Very gravelly sandy loam, very cobbly sandy loam.                 | GM                         | A-1, A-2         | 5-30                        | 35-55                                | 35-55  | 25-45  | 10-30  | ---             | NP                       |
|                                      | 17-60     | Extremely cobbly loamy coarse sand, extremely cobbly coarse sand. | GP-GM, GP                  | A-1              | 50-65                       | 15-30                                | 10-30  | 5-20   | 0-10   | ---             | NP                       |
| Adamson-----                         | 0-9       | Fine sandy loam   | SM, ML,<br>SM-SC,<br>CL-ML | A-4              | 0                           | 90-100                               | 90-100 | 85-95  | 45-65  | 20-30           | NP-10                    |
|                                      | 9-22      | Very fine sandy loam.   | ML, CL-ML                  | A-4              | 0                           | 90-100                               | 90-100 | 85-100 | 55-75  | 20-30           | NP-10                    |
|                                      | 22-48     | Extremely cobbly loamy coarse sand, extremely cobbly coarse sand. | GM, GP-GM                  | A-1              | 50-70                       | 50-65                                | 45-60  | 20-35  | 5-20   | ---             | NP                       |
|                                      | 48-60     | Extremely stony coarse sand.                                      | GP-GM                      | A-1              | 60-80                       | 35-55                                | 30-50  | 15-30  | 5-10   | ---             | NP                       |
| Riverwash.<br>9, 10-----<br>Bancroft | 0-11      | Silt loam-----  | ML, CL-ML                  | A-4              | 0                           | 100                                  | 100    | 100    | 95-100 | 20-30           | NP-10                    |
|                                      | 11-42     | Silt loam, silty clay loam.                                       | CL                         | A-6              | 0                           | 100                                  | 100    | 100    | 95-100 | 30-40           | 10-20                    |
|                                      | 42-80     | Gravelly loam, gravelly loamy sand.                               | SM-SC, SM,<br>ML, CL-ML    | A-1, A-2,<br>A-4 | 0-10                        | 65-80                                | 60-75  | 40-70  | 20-60  | 15-25           | NP-10                    |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture   | Classification |                  | Frag-<br>ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-------|--|----------------|------------------|---------------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |       |  | Unified        | AASHTO           |                                 | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | In    |  |                |                  | Pct                             |                                      |        |        |       | Pct             |                          |
| 11-----<br>Bickett       | 0-6   | Mucky peat-----  | PT             | A-8              | 0                               | ---                                  | ---    | ---    | ---   | ---             | NP                       |
|                          | 6-11  | Muck-----  | PT, OL         | A-8              | 0                               | ---                                  | ---    | ---    | ---   | ---             | NP                       |
|                          | 11-40 | Silty clay loam,<br>silt loam.   | CL             | A-6              | 0                               | 90-100                               | 90-100 | 90-100 | 85-95 | 30-40           | 10-2                     |
|                          | 40-61 | Loam, clay loam,<br>gravelly fine<br>sandy loam.   | CL, GC         | A-6              | 0                               | 60-100                               | 55-90  | 50-85  | 45-75 | 25-35           | 10-2                     |
| 12*:<br>Blackspar-----   | 0-3   | Very cobbly loam   | GM, SM         | A-2, A-4         | 20-65                           | 45-85                                | 40-65  | 35-60  | 25-50 | 25-35           | NP-1                     |
|                          | 3-17  | Very cobbly loam,<br>extremely cobbly<br>loam, very<br>cobbly clay<br>loam.                | GC             | A-2, A-6         | 25-65                           | 35-65                                | 30-65  | 25-65  | 20-50 | 30-40           | 10-2                     |
|                          | 17    | Unweathered<br>bedrock.  | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          |       | Rock outcrop.  |                |                  |                                 |                                      |        |        |       |                 |                          |
| 13*:<br>Blackspot-----   | 0-7   | Very gravelly<br>loam.   | GM             | A-4, A-2         | 5-15                            | 45-60                                | 40-55  | 35-50  | 25-40 | 20-30           | NP-5                     |
|                          | 7-14  | Very gravelly<br>loam, extremely<br>gravelly loam,<br>extremely<br>gravelly sandy<br>loam. | GM             | A-1, A-2         | 10-20                           | 25-55                                | 25-50  | 15-45  | 10-30 | 20-30           | NP-5                     |
|                          | 14-19 | Indurated-----   | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 19    | Unweathered<br>bedrock.  | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Prudy-----               | 0-10  | Loam-----  | CL-ML, CL      | A-4, A-6         | 0                               | 100                                  | 85-100 | 65-85  | 50-80 | 25-35           | 5-15                     |
|                          | 10-42 | Loam, gravelly<br>loam, gravelly<br>fine sandy loam.                                       | ML, SM         | A-4, A-2,<br>A-6 | 0-15                            | 70-90                                | 65-90  | 50-85  | 30-60 | 30-40           | 5-15                     |
|                          | 42-50 | Indurated-----   | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 50    | Weathered bedrock  | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| 14*:<br>Bostrum-----     | 0-4   | Cobbly silt loam   | CL-ML          | A-4              | 15-30                           | 75-100                               | 75-95  | 70-95  | 65-90 | 20-30           | 5-10                     |
|                          | 4-32  | Silty clay, clay,<br>silty clay loam.  | CL, CH         | A-7              | 0-10                            | 95-100                               | 95-100 | 85-100 | 75-95 | 40-60           | 20-35                    |
|                          | 32-36 | Unweathered<br>bedrock.  | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Yutru-----               | 0-7   | Silty clay-----  | CL, CH         | A-7              | 0-5                             | 90-100                               | 90-100 | 85-95  | 80-90 | 45-60           | 25-40                    |
|                          | 7-35  | Clay, silty clay   | CL, CH         | A-7              | 0-25                            | 75-100                               | 75-100 | 65-100 | 60-95 | 45-55           | 25-35                    |
|                          | 35-63 | Silty clay loam,<br>clay loam.   | ML, CL         | A-6, A-7         | 0-25                            | 75-100                               | 75-100 | 70-100 | 65-95 | 35-45           | 10-20                    |
| Hamrub-----              | 0-10  | Silt loam-----   | CL-ML, ML      | A-4              | 0                               | 100                                  | 100    | 90-100 | 80-90 | 25-35           | 5-10                     |
|                          | 10-41 | Silt loam, silty<br>clay loam.   | CL             | A-6              | 0                               | 100                                  | 95-100 | 90-95  | 85-90 | 30-40           | 10-20                    |
|                          | 41-43 | Silt loam, loam  | CL-ML, ML      | A-4              | 0                               | 100                                  | 85-95  | 80-90  | 70-80 | 25-35           | 5-10                     |
|                          | 43-48 | Indurated-----   | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 48    | Unweathered<br>bedrock.  | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol    | Depth     | USDA texture   | Classification |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |       |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|-----------------------------|-----------|--|----------------|----------|-----------------------------|--------------------------------------|--------|-------|-------|-----------------|--------------------------|
|                             |           |  | Unified        | AASHTO   |                             | 4                                    | 10     | 40    | 200   |                 |                          |
|                             | <u>In</u> |  |                |          | <u>Pct</u>                  |                                      |        |       |       | <u>Pct</u>      |                          |
| 15, 16, 17-----<br>Bringmee | 0-7       | Loam-----  | CL             | A-6      | 0                           | 90-100                               | 85-100 | 75-90 | 55-70 | 25-35           | 10-15                    |
|                             | 7-47      | Loam, clay loam,<br>sandy clay loam.   | CL             | A-6, A-7 | 0                           | 75-90                                | 75-90  | 70-90 | 55-70 | 35-50           | 15-25                    |
|                             | 47-61     | Gravelly sandy<br>loam, very<br>gravelly loamy<br>coarse sand,<br>very gravelly<br>loamy sand. | GP-GM, GM      | A-1      | 15-25                       | 40-60                                | 35-60  | 20-40 | 10-25 | 20-25           | NP-5                     |
| 18*:<br>Bringmee-----       | 0-7       | Loam-----  | CL             | A-6      | 0                           | 90-100                               | 85-100 | 75-90 | 55-70 | 25-35           | 10-15                    |
|                             | 7-47      | Loam, clay loam,<br>sandy clay loam.   | CL             | A-6, A-7 | 0                           | 75-90                                | 75-90  | 70-90 | 55-70 | 35-50           | 15-25                    |
|                             | 47-61     | Gravelly sandy<br>loam, very<br>gravelly loamy<br>coarse sand,<br>very gravelly<br>loamy sand. | GP-GM, GM      | A-1      | 15-25                       | 40-60                                | 35-60  | 20-40 | 10-25 | 20-25           | NP-5                     |
| Hutton-----                 | 0-4       | Clay loam-----   | CL             | A-6      | 0                           | 95-100                               | 90-95  | 75-85 | 65-75 | 30-40           | 10-15                    |
|                             | 4-19      | Clay loam-----   | CL, ML         | A-6, A-7 | 0                           | 95-100                               | 90-95  | 85-90 | 80-85 | 35-45           | 10-20                    |
|                             | 19-62     | Clay, silty clay,<br>gravelly clay.  | CH, CL         | A-7      | 0-5                         | 70-100                               | 65-100 | 60-95 | 50-90 | 45-60           | 25-40                    |
| 19*:<br>Bringmee-----       | 0-11      | Gravelly loam----  | GC, SC         | A-6, A-2 | 0                           | 55-80                                | 50-75  | 40-70 | 25-50 | 25-35           | 10-15                    |
|                             | 11-33     | Loam, clay loam,<br>sandy clay loam.   | CL             | A-6, A-7 | 0                           | 75-90                                | 75-90  | 70-90 | 55-70 | 35-50           | 15-25                    |
|                             | 33-61     | Gravelly sandy<br>loam, very<br>gravelly loamy<br>coarse sand,<br>very gravelly<br>loamy sand. | GP-GM, GM      | A-1      | 15-25                       | 40-60                                | 35-60  | 20-40 | 10-25 | 20-25           | NP-5                     |
| Little Wood-----            | 0-13      | Very gravelly<br>loam.   | GM, GM-GC      | A-2, A-4 | 0-5                         | 45-55                                | 40-50  | 30-50 | 20-40 | 25-35           | 5-10                     |
|                             | 13-26     | Very gravelly<br>sandy clay loam,<br>very gravelly<br>loam, very<br>gravelly clay<br>loam.     | GC             | A-2      | 0-15                        | 45-55                                | 40-50  | 20-40 | 10-35 | 30-50           | 10-25                    |
|                             | 26-32     | Extremely<br>gravelly loamy<br>coarse sand,<br>extremely<br>gravelly coarse<br>sandy loam.     | GM, GP-GM      | A-1      | 5-20                        | 25-35                                | 20-30  | 10-20 | 5-15  | 15-20           | NP-5                     |
|                             | 32-61     | Extremely<br>gravelly loamy<br>coarse sand,<br>extremely<br>gravelly coarse<br>sand.           | GP, GP-GM      | A-1      | 5-20                        | 20-35                                | 15-30  | 5-20  | 0-10  | ---             | NP                       |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol  | Depth     | USDA texture   | Classification             |                  | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|---------------------------|-----------|--|----------------------------|------------------|-----------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                           |           |  | Unified                    | AASHTO           |                             | 4                                    | 10     | 40     | 200   |                 |                          |
|                           | <u>In</u> |  |                            |                  | <u>Pct</u>                  |                                      |        |        |       | <u>Pct</u>      |                          |
| 20-----<br>Bruneel        | 0-14      | Loam-----  | CL-ML, ML,<br>CL           | A-4, A-6         | 0                           | 95-100                               | 85-100 | 80-95  | 60-75 | 20-35           | NP-15                    |
|                           | 14-23     | Stratified loam<br>to fine sandy<br>loam.  | ML, CL-ML                  | A-4              | 0                           | 95-100                               | 80-100 | 75-90  | 50-75 | 20-30           | NP-10                    |
|                           | 23-61     | Very gravelly<br>loamy sand,<br>extremely<br>gravelly loamy<br>sand, extremely<br>gravelly coarse<br>sand. | GP, GP-GM                  | A-1              | 10-30                       | 25-40                                | 20-40  | 5-30   | 0-10  | ---             | NP                       |
| 21, 22-----<br>Carey Lake | 0-12      | Loam-----  | CL-ML                      | A-4              | 0                           | 90-100                               | 85-100 | 75-95  | 55-75 | 20-30           | 5-10                     |
|                           | 12-20     | Silt loam, loam,<br>clay loam.   | CL, ML                     | A-6, A-7         | 0                           | 90-100                               | 85-100 | 75-100 | 55-85 | 35-45           | 10-20                    |
|                           | 20-42     | Loam, clay loam,<br>fine sandy loam.   | CL-ML, CL                  | A-4, A-6         | 0                           | 90-100                               | 85-100 | 65-100 | 50-75 | 25-40           | 5-15                     |
|                           | 42-72     | Loam, fine sandy<br>loam, very fine<br>sandy loam.   | SM, ML                     | A-4, A-2         | 0                           | 75-100                               | 75-100 | 50-95  | 30-70 | 25-30           | NP-5                     |
| 23*:<br>Cox-----          | 0-3       | Very stony sandy<br>loam.  | SM                         | A-2, A-4         | 40-60                       | 65-85                                | 60-80  | 40-55  | 25-50 | 20-25           | NP-5                     |
|                           | 3-12      | Very cobbly fine<br>sandy loam, very<br>stony sandy<br>loam, extremely<br>stony sandy<br>loam.             | SM, GM                     | A-2, A-4,        | 40-65                       | 55-85                                | 50-80  | 30-70  | 15-45 | 20-35           | NP-10                    |
|                           | 12-16     | Unweathered<br>bedrock.  | ---                        | ---              | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Rehfield-----             | 0-3       | Loamy sand-----  | SM                         | A-2, A-1         | 0                           | 90-100                               | 85-100 | 45-75  | 15-30 | ---             | NP                       |
|                           | 3-42      | Sandy loam, loam,<br>sandy clay loam.  | SC, CL,<br>SM-SC,          | A-4, A-6         | 0-5                         | 100                                  | 90-100 | 55-85  | 35-55 | 25-40           | 5-15                     |
|                           | 42-67     | Gravelly loamy<br>sand, loamy<br>sand, very fine<br>sandy loam.  | CL-ML<br>SM                | A-1, A-2,<br>A-4 | 0-15                        | 75-100                               | 70-100 | 40-75  | 10-40 | 20-25           | NP-5                     |
| Rock outcrop.             |           |  |                            |                  |                             |                                      |        |        |       |                 |                          |
| 24*:<br>Deerhorn-----     | 0-9       | Fine sandy loam  | SM, ML                     | A-4              | 0                           | 100                                  | 100    | 70-85  | 40-55 | 20-25           | NP-5                     |
|                           | 9-21      | Loam, sandy clay<br>loam, sandy<br>loam.   | SC, CL                     | A-6              | 0                           | 100                                  | 100    | 80-95  | 45-65 | 25-35           | 10-15                    |
|                           | 21-24     | Indurated-----   | ---                        | ---              | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                           | 24-38     | Unweathered<br>bedrock.  | ---                        | ---              | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Rehfield-----             | 0-11      | Sandy loam-----  | SM                         | A-2, A-4         | 0                           | 90-100                               | 85-100 | 50-70  | 25-40 | 20-25           | NP-5                     |
|                           | 11-42     | Sandy loam, loam,<br>sandy clay loam.  | SC, CL,<br>SM-SC,<br>CL-ML | A-4, A-6         | 0-5                         | 100                                  | 90-100 | 55-85  | 35-55 | 25-40           | 5-15                     |
|                           | 42-67     | Gravelly loamy<br>sand, loamy<br>sand, very fine<br>sandy loam.  | SM                         | A-1, A-2,<br>A-4 | 0-15                        | 75-100                               | 70-100 | 40-75  | 10-40 | 20-25           | NP-5                     |
| Rock outcrop.             |           |  |                            |                  |                             |                                      |        |        |       |                 |                          |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture   | Classification  |                  | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-----------|--|-----------------|------------------|-----------------------------|--------------------------------------|-------|-------|-------|-----------------|--------------------------|
|                          |           |  | Unified         | AASHTO           |                             | 4                                    | 10    | 40    | 200   |                 |                          |
|                          | <u>In</u> |  |                 |                  | <u>Pct</u>                  |                                      |       |       |       | <u>Pct</u>      |                          |
| 25*:<br>Deerhorn-----    | 0-9       | Fine sandy loam  | SM, ML          | A-4              | 0                           | 100                                  | 100   | 70-85 | 40-55 | 20-25           | NP-5                     |
|                          | 9-21      | Loam, sandy clay<br>loam, sandy<br>loam.                               | SC, CL          | A-6              | 0                           | 100                                  | 100   | 80-95 | 45-65 | 25-35           | 10-15                    |
|                          | 21-24     | Indurated-----   | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
|                          | 24-28     | Unweathered<br>bedrock.  | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
| Wildors-----             | 0-9       | Very stony sandy<br>loam.  | SM              | A-2, A-4         | 50-70                       | 90-95                                | 85-90 | 50-65 | 25-45 | 20-25           | NP-5                     |
|                          | 9-21      | Very stony sandy<br>loam, very stony<br>loam, extremely<br>stony loam. | SM, ML          | A-1, A-2,<br>A-4 | 30-70                       | 70-75                                | 65-70 | 40-65 | 20-55 | 25-30           | NP-5                     |
|                          | 21-24     | Indurated-----   | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
|                          | 24-28     | Unweathered<br>bedrock.  | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
| 26*:<br>Deerhorn-----    | 0-8       | Fine sandy loam  | SM, ML          | A-4              | 0                           | 100                                  | 100   | 70-85 | 40-55 | 20-25           | NP-5                     |
|                          | 8-21      | Loam, sandy clay<br>loam, sandy<br>loam.                               | SC, CL          | A-6              | 0                           | 100                                  | 100   | 80-95 | 45-65 | 25-35           | 10-15                    |
|                          | 21-28     | Indurated-----   | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
|                          | 28-32     | Unweathered<br>bedrock.  | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
| Wildors-----             | 0-10      | Very stony sandy<br>loam.  | SM              | A-2, A-4         | 50-70                       | 90-95                                | 85-90 | 50-65 | 25-45 | 20-25           | NP-5                     |
|                          | 10-22     | Very stony sandy<br>loam, very stony<br>loam, extremely<br>stony loam. | SM, ML          | A-1, A-2,<br>A-4 | 30-70                       | 70-75                                | 65-70 | 40-65 | 20-55 | 25-30           | NP-5                     |
|                          | 22-24     | Indurated-----   | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
|                          | 24-28     | Unweathered<br>bedrock.  | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
| Trevino-----             | 0-12      | Extremely stony<br>silt loam.  | CL-ML,<br>GM-GC | A-4              | 60-75                       | 60-90                                | 55-85 | 50-80 | 40-75 | 20-30           | 5-10                     |
|                          | 12-16     | Unweathered<br>bedrock.  | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
| 27*:<br>Dollarhide-----  | 0-7       | Very gravelly<br>fine sandy loam.                                      | GM              | A-1, A-2         | 0-25                        | 40-55                                | 35-50 | 25-50 | 15-30 | 20-25           | NP-5                     |
|                          | 7-13      | Extremely cobbly<br>fine sandy loam,<br>extremely cobbly<br>loam.      | GM              | A-1, A-2         | 50-65                       | 40-50                                | 40-45 | 30-40 | 15-30 | 20-25           | NP-5                     |
|                          | 13        | Unweathered<br>bedrock.  | ---             | ---              | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                      |
| Rock outcrop.            |           |  |                 |                  |                             |                                      |       |       |       |                 |                          |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture  | Classification |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit | Plas-<br>ticit<br>index |
|--------------------------|-------|---|----------------|----------|-----------------------------|--------------------------------------|-------|-------|-------|-----------------|-------------------------|
|                          |       |   | Unified        | AASHTO   |                             | 4                                    | 10    | 40    | 200   |                 |                         |
|                          | In    |   |                |          | Pct                         |                                      |       |       |       | Pct             |                         |
| 28, 29-----<br>Drage     | 0-14  | Gravelly loam----   | CL, GC         | A-6      | 0-15                        | 65-90                                | 60-80 | 55-80 | 40-65 | 30-40           | 10-15                   |
|                          | 14-20 | Very gravelly<br>clay loam, very<br>gravelly sandy<br>clay loam.                                    | GC             | A-2, A-7 | 5-30                        | 40-60                                | 30-55 | 25-50 | 20-40 | 40-50           | 15-25                   |
|                          | 20-61 | Extremely<br>gravelly sandy<br>loam, extremely<br>gravelly loam,<br>extremely cobbly<br>sandy loam. | GC, GM-GC      | A-2      | 25-45                       | 30-40                                | 25-35 | 15-35 | 10-25 | 25-40           | 5-15                    |
| 30-----<br>Drage         | 0-14  | Gravelly loam----   | CL, GC         | A-6      | 0-15                        | 65-90                                | 60-80 | 55-80 | 40-65 | 30-40           | 10-15                   |
|                          | 14-30 | Very gravelly<br>clay loam, very<br>gravelly sandy<br>clay loam.                                    | GC             | A-2, A-7 | 5-30                        | 40-60                                | 30-55 | 25-50 | 20-40 | 40-50           | 15-25                   |
|                          | 30-61 | Extremely<br>gravelly sandy<br>loam, extremely<br>gravelly loam,<br>extremely cobbly<br>sandy loam. | GC, GM-GC      | A-2      | 25-45                       | 30-40                                | 25-35 | 15-35 | 10-25 | 25-40           | 5-15                    |
| 31-----<br>Drage         | 0-16  | Very gravelly<br>loam.  | GC, SC         | A-2      | 0-10                        | 60-80                                | 45-50 | 30-40 | 25-35 | 30-40           | 10-15                   |
|                          | 16-41 | Very gravelly<br>clay loam, very<br>gravelly sandy<br>clay loam.                                    | GC             | A-2, A-7 | 5-30                        | 40-60                                | 30-55 | 25-50 | 20-40 | 40-50           | 15-25                   |
|                          | 41-61 | Extremely<br>gravelly sandy<br>loam, extremely<br>gravelly loam,<br>extremely cobbly<br>sandy loam. | GC, GM-GC      | A-2      | 25-45                       | 30-40                                | 25-35 | 15-35 | 10-25 | 25-40           | 5-15                    |
| 32*:<br>Earcree-----     | 0-37  | Gravelly coarse<br>sandy loam.  | SM             | A-1, A-2 | 0                           | 75-95                                | 65-75 | 35-45 | 20-35 | 20-25           | NP-5                    |
|                          | 37-52 | Gravelly coarse<br>sandy loam,<br>gravelly sandy<br>loam, gravelly<br>loamy coarse<br>sand.         | SM, GM         | A-1, A-2 | 0                           | 60-80                                | 50-75 | 25-50 | 10-35 | 15-25           | NP-5                    |
|                          | 52-70 | Very gravelly<br>loamy coarse<br>sand.  | SM, GM         | A-1      | 0                           | 50-60                                | 40-50 | 20-30 | 10-20 | ---             | NP                      |
| Lockman-----             | 0-15  | Sandy loam-----   | SM             | A-2      | 0                           | 85-95                                | 80-90 | 45-65 | 25-35 | 15-25           | NP-5                    |
|                          | 15-23 | Gravelly sandy<br>loam, sandy<br>loam.  | SM             | A-2, A-4 | 0-5                         | 85-95                                | 70-90 | 45-70 | 25-40 | 15-25           | NP-5                    |
|                          | 23-44 | Gravelly sandy<br>loam, gravelly<br>loamy sand.   | SM             | A-1, A-2 | 0-5                         | 75-90                                | 60-75 | 40-65 | 15-30 | 15-25           | NP-5                    |
|                          | 44-58 | Weathered bedrock   | ---            | ---      | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                     |
|                          | 58    | Unweathered<br>bedrock.   | ---            | ---      | ---                         | ---                                  | ---   | ---   | ---   | ---             | ---                     |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture   | Classification |               | Frag-ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|--------------------------|-----------|--|----------------|---------------|------------------------------------|--------------------------------------|--------|--------|-------|------------------------|--------------------------|
|                          |           |  | Unified        | AASHTO        |                                    | 4                                    | 10     | 40     | 200   |                        |                          |
|                          | <u>In</u> |  |                |               |                                    |                                      |        |        |       |                        |                          |
| 33*:<br>Earcree-----     | 0-37      | Gravelly coarse sandy loam.  | SM             | A-1, A-2      | 0                                  | 75-95                                | 65-75  | 35-45  | 20-35 | 20-25                  | NP-5                     |
|                          | 37-52     | Gravelly coarse sandy loam, gravelly sandy loam, gravelly loamy coarse sand. | SM, GM         | A-1, A-2      | 0                                  | 60-80                                | 50-75  | 25-50  | 10-35 | 15-25                  | NP-5                     |
|                          | 52-70     | Very gravelly loamy coarse sand.   | SM, GM         | A-1           | 0                                  | 50-60                                | 40-50  | 20-30  | 10-20 | ---                    | NP                       |
| Moonstone-----           | 0-26      | Gravelly coarse sandy loam.  | SM             | A-1, A-2      | 0-5                                | 70-80                                | 65-75  | 45-50  | 20-30 | 20-25                  | NP-5                     |
|                          | 26-34     | Coarse sandy loam, gravelly coarse sandy loam.                               | SM             | A-1, A-2, A-4 | 0-5                                | 70-95                                | 65-90  | 45-70  | 20-50 | 20-25                  | NP-5                     |
|                          | 34        | Weathered bedrock  | ---            | ---           | ---                                | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| 34*:<br>Earcree-----     | 0-37      | Gravelly coarse sandy loam.  | SM             | A-1, A-2      | 0                                  | 75-95                                | 65-75  | 35-45  | 20-35 | 20-25                  | NP-5                     |
|                          | 37-52     | Gravelly coarse sandy loam, gravelly sandy loam, gravelly loamy coarse sand. | SM, GM         | A-1, A-2      | 0                                  | 60-80                                | 50-75  | 25-50  | 10-35 | 15-25                  | NP-5                     |
|                          | 52-70     | Very gravelly loamy coarse sand.   | SM, GM         | A-1           | 0                                  | 50-60                                | 40-50  | 20-30  | 10-20 | ---                    | NP                       |
| Moonstone-----           | 0-21      | Gravelly coarse sandy loam.  | SM             | A-1, A-2      | 0-5                                | 70-80                                | 65-75  | 45-50  | 20-30 | 20-25                  | NP-5                     |
|                          | 21-32     | Coarse sandy loam, gravelly coarse sandy loam.                               | SM             | A-1, A-2, A-4 | 0-5                                | 70-95                                | 65-90  | 45-70  | 20-50 | 20-25                  | NP-5                     |
|                          | 32-36     | Weathered bedrock  | ---            | ---           | ---                                | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| 35*:<br>Elkcreek-----    | 0-11      | Loam-----  | CL-ML          | A-4           | 0                                  | 90-100                               | 85-100 | 70-95  | 50-75 | 20-30                  | 5-10                     |
|                          | 11-34     | Clay loam, sandy clay loam, loam.  | CL, SC         | A-6           | 0-10                               | 90-100                               | 85-100 | 65-100 | 40-85 | 30-40                  | 10-15                    |
|                          | 34-38     | Unweathered bedrock.   | ---            | ---           | ---                                | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| Gaib-----                | 0-4       | Very gravelly loam.  | GM-GC, GC      | A-2, A-4, A-6 | 0-25                               | 30-55                                | 25-50  | 15-40  | 10-40 | 25-35                  | 5-15                     |
|                          | 4-12      | Very cobbly clay loam, very stony sandy clay loam.                           | GC, SC         | A-2, A-6, A-7 | 30-50                              | 55-70                                | 50-70  | 40-60  | 20-50 | 35-50                  | 15-25                    |
|                          | 12-16     | Unweathered bedrock.   | ---            | ---           | ---                                | ---                                  | ---    | ---    | ---   | ---                    | ---                      |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture  | Classification          |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-----------|---|-------------------------|----------|-----------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |           |   | Unified                 | AASHTO   |                             | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | <u>In</u> |   |                         |          | <u>Pct</u>                  |                                      |        |        |       | <u>Pct</u>      |                          |
| 36*:<br>Elkcreek-----    | 0-11      | Loam-----   | CL-ML                   | A-4      | 0                           | 90-100                               | 85-100 | 70-95  | 50-75 | 20-30           | 5-10                     |
|                          | 11-34     | Clay loam, sandy<br>clay loam, loam.  | CL, SC                  | A-6      | 0-10                        | 90-100                               | 85-100 | 65-100 | 40-85 | 30-40           | 10-15                    |
|                          | 34-38     | Unweathered<br>bedrock.   | ---                     | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Polecreek-----           | 0-4       | Very stony loam   | CL                      | A-6      | 30-60                       | 95-100                               | 75-90  | 60-80  | 55-75 | 30-35           | 15-20                    |
|                          | 4-6       | Very cobbly clay,<br>very cobbly<br>silty clay loam,<br>very cobbly clay<br>loam. | CL, CH, GC              | A-7, A-2 | 30-65                       | 45-75                                | 40-70  | 35-70  | 30-65 | 40-60           | 20-35                    |
|                          | 6-13      | Very gravelly<br>clay, very<br>cobbly clay.                                       | CL, CH, GC              | A-2, A-7 | 10-60                       | 40-80                                | 35-75  | 30-70  | 25-65 | 40-60           | 20-35                    |
|                          | 13        | Unweathered<br>bedrock.   | ---                     | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| 37*:<br>Elksel-----      | 0-10      | Very cobbly loam  | GC, CL                  | A-2, A-6 | 40-50                       | 55-90                                | 50-85  | 40-80  | 25-65 | 30-40           | 10-15                    |
|                          | 10-33     | Very cobbly clay<br>loam, very<br>cobbly clay,<br>extremely cobbly<br>clay.       | GC, CL, CH              | A-7      | 30-70                       | 50-75                                | 45-70  | 45-65  | 35-60 | 40-60           | 20-35                    |
|                          | 33-45     | Extremely cobbly<br>clay, extremely<br>cobbly sandy<br>clay.                      | GC                      | A-2      | 50-75                       | 40-50                                | 35-45  | 25-40  | 20-35 | 40-55           | 20-30                    |
|                          | 45        | Weathered bedrock   | ---                     | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Friedman-----            | 0-5       | Cobbly loam-----  | CL-ML, CL               | A-4, A-6 | 15-20                       | 85-95                                | 80-90  | 70-85  | 50-70 | 25-35           | 5-15                     |
|                          | 5-24      | Gravelly loam,<br>gravelly clay<br>loam.  | GC, GM-GC,<br>CL, CL-ML | A-6, A-4 | 10-15                       | 65-90                                | 60-90  | 60-80  | 45-70 | 25-40           | 5-20                     |
|                          | 24-47     | Very gravelly<br>clay, very<br>gravelly clay<br>loam.                             | GC                      | A-2      | 10-15                       | 35-55                                | 30-50  | 20-40  | 15-35 | 35-50           | 15-25                    |
|                          | 47-54     | Very gravelly<br>sandy clay loam.   | GM-GC, GC               | A-2      | 10-25                       | 40-60                                | 35-55  | 25-40  | 15-25 | 25-35           | 5-15                     |
|                          | 54        | Weathered bedrock   | ---                     | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Starhope-----            | 0-3       | Very cobbly clay<br>loam.   | CL, GC                  | A-6      | 30-55                       | 65-90                                | 60-85  | 55-85  | 40-65 | 30-40           | 10-20                    |
|                          | 3-19      | Clay loam, cobbly<br>clay, gravelly<br>clay loam.                                 | CH, CL                  | A-7      | 0-45                        | 70-100                               | 65-100 | 60-95  | 50-80 | 40-60           | 20-40                    |
|                          | 19-22     | Clay loam,<br>gravelly clay<br>loam.  | CL                      | A-6, A-7 | 0-10                        | 70-100                               | 65-100 | 65-95  | 50-75 | 35-45           | 15-25                    |
|                          | 22-26     | Unweathered<br>bedrock.   | ---                     | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture  | Classification          |                  | Frag-ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |        |       |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|--------------------------|-----------|---|-------------------------|------------------|------------------------------------|--------------------------------------|--------|-------|-------|------------------------|--------------------------|
|                          |           |   | Unified                 | AASHTO           |                                    | 4                                    | 10     | 40    | 200   |                        |                          |
|                          | <u>In</u> |   |                         |                  |                                    |                                      |        |       |       |                        |                          |
| 38*:<br>Elksel-----      | 0-12      | Gravelly loam----   | CL-ML, CL,<br>GM-GC, GC | A-4, A-6         | 0-10                               | 70-80                                | 60-75  | 50-70 | 40-60 | 20-40                  | 5-15                     |
|                          | 12-42     | Very gravelly<br>clay, extremely<br>gravelly clay.                          | GC                      | A-2              | 10-25                              | 40-50                                | 30-40  | 25-35 | 20-30 | 40-60                  | 20-35                    |
|                          | 42-54     | Cemented-----   | ---                     | ---              | ---                                | ---                                  | ---    | ---   | ---   | ---                    | ---                      |
|                          | 54        | Unweathered<br>bedrock.   | ---                     | ---              | ---                                | ---                                  | ---    | ---   | ---   | ---                    | ---                      |
| Peevywell-----           | 0-5       | Cobbly loam-----  | CL-ML, CL               | A-4, A-6         | 10-25                              | 80-90                                | 70-80  | 60-70 | 50-60 | 25-40                  | 5-15                     |
|                          | 5-13      | Gravelly loam,<br>gravelly clay<br>loam.                                    | CL                      | A-6              | 0-10                               | 65-80                                | 60-80  | 55-75 | 50-65 | 25-40                  | 10-20                    |
|                          | 13-31     | Gravelly clay,<br>clay.   | CL, CH                  | A-7              | 0-10                               | 65-85                                | 65-80  | 60-75 | 55-65 | 40-60                  | 20-35                    |
|                          | 31-40     | Indurated-----  | ---                     | ---              | ---                                | ---                                  | ---    | ---   | ---   | ---                    | ---                      |
|                          | 40        | Unweathered<br>bedrock.   | ---                     | ---              | ---                                | ---                                  | ---    | ---   | ---   | ---                    | ---                      |
| Furshur-----             | 0-2       | Very channery<br>loam.  | GC, GM-GC               | A-2, A-6,<br>A-4 | 0-10                               | 40-60                                | 35-55  | 25-50 | 20-40 | 20-30                  | 5-15                     |
|                          | 2-5       | Clay loam-----  | CL                      | A-6              | 0-10                               | 90-100                               | 85-95  | 60-85 | 50-65 | 30-40                  | 10-15                    |
|                          | 5-15      | Clay, gravelly<br>clay.   | CH                      | A-7              | 0-10                               | 70-90                                | 65-90  | 55-80 | 55-75 | 50-70                  | 30-45                    |
|                          | 15-20     | Indurated-----  | ---                     | ---              | ---                                | ---                                  | ---    | ---   | ---   | ---                    | ---                      |
|                          | 20        | Unweathered<br>bedrock.   | ---                     | ---              | ---                                | ---                                  | ---    | ---   | ---   | ---                    | ---                      |
| 39*:<br>Elksel-----      | 0-10      | Very cobbly loam  | GC, CL                  | A-2, A-6         | 40-50                              | 55-90                                | 50-85  | 40-80 | 25-65 | 30-40                  | 10-15                    |
|                          | 10-33     | Very cobbly clay<br>loam, very<br>cobbly clay,<br>extremely cobbly<br>clay. | GC, CL, CH              | A-7              | 30-70                              | 50-75                                | 45-70  | 45-65 | 35-60 | 40-60                  | 20-35                    |
|                          | 33-45     | Extremely cobbly<br>clay, extremely<br>cobbly sandy<br>clay.                | GC                      | A-2              | 50-75                              | 40-50                                | 35-45  | 25-40 | 20-35 | 40-55                  | 20-30                    |
|                          | 45        | Weathered bedrock   | ---                     | ---              | ---                                | ---                                  | ---    | ---   | ---   | ---                    | ---                      |
| Starhope-----            | 0-3       | Very cobbly clay<br>loam.   | CL, GC                  | A-6              | 30-55                              | 65-90                                | 60-85  | 55-85 | 40-65 | 30-40                  | 10-20                    |
|                          | 3-19      | Clay loam, cobbly<br>clay, gravelly<br>clay loam.                           | CH, CL                  | A-7              | 0-45                               | 70-100                               | 65-100 | 60-95 | 50-80 | 40-60                  | 20-40                    |
|                          | 19-22     | Clay loam,<br>gravelly clay<br>loam.  | CL                      | A-6, A-7         | 0-10                               | 70-100                               | 65-100 | 65-95 | 50-75 | 35-45                  | 15-25                    |
|                          | 22-26     | Unweathered<br>bedrock.   | ---                     | ---              | ---                                | ---                                  | ---    | ---   | ---   | ---                    | ---                      |
| Rock outcrop.            |           |   |                         |                  |                                    |                                      |        |       |       |                        |                          |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and<br>map symbol | Depth     | USDA texture  | Classification          |                  | Frag-<br>ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|-----------------------------|-----------|---|-------------------------|------------------|--|--------------------------------------|--------|--------|-------|------------------------|--------------------------|
|                             |           |   | Unified                 | AASHTO           |  | 4                                    | 10     | 40     | 200   |                        |                          |
| 40*:<br>Friedman-----       | <u>In</u> |   |                         |                  |  |                                      |        |        |       |                        |                          |
|                             | 0-5       | Cobbly loam-----  | CL-ML, CL               | A-4, A-6         | 15-20                                  | 85-95                                | 80-90  | 70-85  | 50-70 | 25-35                  | 5-15                     |
|                             | 5-24      | Gravelly loam,<br>gravelly clay<br>loam.                                    | GC, GM-GC,<br>CL, CL-ML | A-6, A-4         | 10-15                                  | 65-90                                | 60-90  | 60-80  | 45-70 | 25-40                  | 5-20                     |
|                             | 24-47     | Very gravelly<br>clay, very<br>gravelly clay<br>loam.                       | GC                      | A-2              | 10-15                                  | 35-55                                | 30-50  | 20-40  | 15-35 | 35-50                  | 15-25                    |
|                             | 47-54     | Very gravelly<br>sandy clay loam.   | GM-GC, GC               | A-2              | 10-25                                  | 40-60                                | 35-55  | 25-40  | 15-25 | 25-35                  | 5-15                     |
|                             | 54        | Weathered bedrock   | ---                     | ---              | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| Elksel-----                 | 0-10      | Very cobbly loam  | GC, CL                  | A-2, A-6         | 40-50                                  | 55-90                                | 50-85  | 40-80  | 25-65 | 30-40                  | 10-15                    |
|                             | 10-33     | Very cobbly clay<br>loam, very<br>cobbly clay,<br>extremely cobbly<br>clay. | GC, CL, CH              | A-7              | 30-70                                  | 50-75                                | 45-70  | 45-65  | 35-60 | 40-60                  | 20-35                    |
|                             | 33-45     | Extremely cobbly<br>clay, extremely<br>cobbly sandy<br>clay.                | GC                      | A-2              | 50-75                                  | 40-50                                | 35-45  | 25-40  | 20-35 | 40-55                  | 20-30                    |
|                             | 45        | Weathered bedrock   | ---                     | ---              | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| Winridge-----               | 0-4       | Clay loam-----  | CL, ML                  | A-6, A-7         | 0-5                                    | 90-100                               | 85-100 | 75-100 | 60-80 | 35-45                  | 10-20                    |
|                             | 4-16      | Clay, gravelly<br>clay, cobbly<br>clay.                                     | CL, CH                  | A-7              | 5-30                                   | 75-90                                | 70-90  | 65-90  | 50-85 | 45-70                  | 30-50                    |
|                             | 16-23     | Sandy clay loam,<br>gravelly clay<br>loam, cobbly<br>clay loam.             | GC, CL, SC              | A-6, A-7         | 5-35                                   | 55-100                               | 50-95  | 45-95  | 35-75 | 35-45                  | 15-25                    |
|                             | 23        | Unweathered<br>bedrock.   | ---                     | ---              | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| 41*:<br>Gaib-----           | 0-5       | Very gravelly<br>loam.  | GM-GC, GC               | A-2, A-4,<br>A-6 | 0-25                                   | 30-55                                | 25-50  | 15-40  | 10-40 | 25-35                  | 5-15                     |
|                             | 5-13      | Very cobbly clay<br>loam, very stony<br>sandy clay loam.                    | GC, SC                  | A-2, A-6,<br>A-7 | 30-50                                  | 55-70                                | 50-70  | 40-60  | 20-50 | 35-50                  | 15-25                    |
|                             | 13        | Unweathered<br>bedrock.   | ---                     | ---              | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| Rock outcrop.               |           |   |                         |                  |  |                                      |        |        |       |                        |                          |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture  | Classification |          | Frag-<br>ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-------|---|----------------|----------|---------------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |       |   | Unified        | AASHTO   |                                 | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | In    |   |                |          | Pct                             |                                      |        |        |       | Pct             |                          |
| 42-----<br>Gimlett       | 0-3   | Very gravelly sandy loam.   | GM, SM         | A-1      | 0-10                            | 40-65                                | 30-50  | 20-40  | 10-25 | 20-25           | NP-5                     |
|                          | 3-27  | Very gravelly sandy loam, very gravelly loam, very gravelly sandy clay loam.  | GM, GM-GC      | A-2, A-1 | 0-10                            | 35-55                                | 30-50  | 20-40  | 15-30 | 20-30           | NP-10                    |
|                          | 27-49 | Stratified extremely cobbly sandy loam to extremely cobbly loamy coarse sand. | GM, GP-GM      | A-1      | 50-65                           | 15-40                                | 15-35  | 10-25  | 5-15  | 15-25           | NP-5                     |
|                          | 49-63 | Extremely cobbly loamy coarse sand, extremely cobbly coarse sand.             | GP, GP-GM      | A-1      | 50-65                           | 20-40                                | 15-30  | 10-20  | 0-10  | ---             | NP                       |
| 43*:<br>Gooding-----     | 0-9   | Silt loam-----  | ML             | A-4      | 0                               | 95-100                               | 90-100 | 80-95  | 75-90 | 25-35           | NP-10                    |
|                          | 9-34  | Silty clay, clay, silty clay loam.  | CL, CH         | A-7      | 0                               | 90-100                               | 90-100 | 85-100 | 75-95 | 45-65           | 20-40                    |
|                          | 34-49 | Silty clay loam, clay loam.   | CL, CH         | A-7      | 5-10                            | 90-100                               | 90-100 | 80-95  | 75-90 | 40-55           | 15-30                    |
|                          | 49-62 | Cemented-----   | ---            | ---      | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Gooding, eroded-         | 62    | Unweathered bedrock.  | ---            | ---      | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 0-2   | Very cobbly clay loam.  | CL             | A-7      | 20-40                           | 65-85                                | 60-80  | 55-75  | 50-65 | 40-50           | 15-25                    |
|                          | 2-42  | Silty clay, clay, silty clay loam.  | CL, CH         | A-7      | 0                               | 90-100                               | 90-100 | 85-100 | 75-95 | 45-65           | 20-40                    |
|                          | 42-62 | Cemented-----   | ---            | ---      | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Hamrub-----              | 62-66 | Unweathered bedrock.  | ---            | ---      | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 0-10  | Silt loam-----  | CL-ML, ML      | A-4      | 0                               | 100                                  | 100    | 90-100 | 80-90 | 25-35           | 5-10                     |
|                          | 10-41 | Silt loam, silty clay loam.   | CL             | A-6      | 0                               | 100                                  | 95-100 | 90-95  | 85-90 | 30-40           | 10-20                    |
|                          | 41-43 | Silt loam, loam   | CL-ML, ML      | A-4      | 0                               | 100                                  | 85-95  | 80-90  | 70-80 | 25-35           | 5-10                     |
| 44-----<br>Goodington    | 43-48 | Indurated-----  | ---            | ---      | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 48    | Unweathered bedrock.  | ---            | ---      | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 0-10  | Silt loam-----  | CL-ML          | A-4      | 0                               | 100                                  | 100    | 95-100 | 70-90 | 25-30           | 5-10                     |
|                          | 10-26 | Silty clay, clay  | CL, CH         | A-7      | 0                               | 100                                  | 100    | 90-100 | 75-95 | 45-65           | 20-35                    |
| 45*:<br>Goodington-----  | 26-56 | Silty clay loam, silt loam.   | CL             | A-7      | 0-15                            | 100                                  | 95-100 | 95-100 | 85-95 | 40-50           | 15-25                    |
|                          | 56    | Unweathered bedrock.  | ---            | ---      | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 0-15  | Silt loam-----  | CL-ML          | A-4      | 0                               | 100                                  | 100    | 95-100 | 70-90 | 25-30           | 5-10                     |
|                          | 15-28 | Silty clay, clay  | CL, CH         | A-7      | 0                               | 100                                  | 100    | 90-100 | 75-95 | 45-65           | 20-35                    |
| 45*:<br>Goodington-----  | 28-48 | Silty clay loam, silt loam.   | CL             | A-7      | 0-15                            | 100                                  | 95-100 | 95-100 | 85-95 | 40-50           | 15-25                    |
|                          | 48-52 | Unweathered bedrock.  | ---            | ---      | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture  | Classification |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-------|---|----------------|----------|-----------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |       |   | Unified        | AASHTO   |                             | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | In    |   |                |          | Pct                         |                                      |        |        |       | Pct             |                          |
| 45*:<br>Manard-----      | 0-11  | Very stony silt loam.                                   | CL             | A-6      | 10-25                       | 90-100                               | 85-100 | 75-100 | 60-95 | 30-40           | 10-20                    |
|                          | 11-26 | Silty clay, clay  | CL, CH         | A-7      | 10-15                       | 90-100                               | 85-100 | 75-100 | 65-95 | 45-60           | 20-35                    |
|                          | 26-28 | Indurated-----  | ---            | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 28-32 | Unweathered bedrock.                                    | ---            | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| 46-----<br>Hapur         | 0-3   | Silt loam-----  | CL             | A-6      | 0                           | 100                                  | 95-100 | 90-100 | 80-95 | 30-40           | 10-15                    |
|                          | 3-30  | Silty clay loam, clay loam, loam.                       | CL             | A-6, A-7 | 0                           | 100                                  | 95-100 | 90-100 | 70-90 | 30-45           | 10-20                    |
|                          | 30-44 | Fine sandy loam   | SM-SC, SM      | A-4, A-2 | 0                           | 100                                  | 95-100 | 65-85  | 25-50 | 15-25           | NP-10                    |
|                          | 44-51 | Loamy fine sand   | SM             | A-2      | 0                           | 80-100                               | 75-100 | 60-80  | 20-30 | ---             | NP                       |
|                          | 51-63 | Very gravelly coarse sand, very gravelly loamy sand.    | GP, GP-GM, GM  | A-1      | 0-5                         | 30-50                                | 25-50  | 10-35  | 0-15  | ---             | NP                       |
| 47*:<br>Hapur-----       | 0-3   | Silt loam-----  | CL             | A-6      | 0                           | 100                                  | 95-100 | 90-100 | 80-95 | 30-40           | 10-15                    |
|                          | 3-30  | Silty clay loam, clay loam, loam.                       | CL             | A-6, A-7 | 0                           | 100                                  | 95-100 | 90-100 | 70-90 | 30-45           | 10-20                    |
|                          | 30-44 | Fine sandy loam   | SM-SC, SM      | A-4, A-2 | 0                           | 100                                  | 95-100 | 65-85  | 25-50 | 15-25           | NP-10                    |
|                          | 44-51 | Loamy fine sand   | SM             | A-2      | 0                           | 80-100                               | 75-100 | 60-80  | 20-30 | ---             | NP                       |
|                          | 51-63 | Very gravelly coarse sand, very gravelly loamy sand.    | GP, GP-GM, GM  | A-1      | 0-5                         | 30-50                                | 25-50  | 10-35  | 0-15  | ---             | NP                       |
| Bickett-----             | 0-6   | Mucky peat-----   | PT             | A-8      | 0                           | ---                                  | ---    | ---    | ---   | ---             | NP                       |
|                          | 6-11  | Muck-----   | PT, OL         | A-8      | 0                           | ---                                  | ---    | ---    | ---   | ---             | NP                       |
|                          | 11-40 | Silty clay loam, silt loam.                             | CL             | A-6      | 0                           | 90-100                               | 90-100 | 90-100 | 85-95 | 30-40           | 10-20                    |
|                          | 40-61 | Loam, clay loam, gravelly fine sandy loam.              | CL, GC         | A-6      | 0                           | 60-100                               | 55-90  | 50-85  | 45-75 | 25-35           | 10-20                    |
| 48*:<br>Hapur-----       | 0-3   | Silt loam-----  | CL             | A-6      | 0                           | 100                                  | 95-100 | 90-100 | 80-95 | 30-40           | 10-15                    |
|                          | 3-30  | Silty clay loam, clay loam, loam.                       | CL             | A-6, A-7 | 0                           | 100                                  | 95-100 | 90-100 | 70-90 | 30-45           | 10-20                    |
|                          | 30-44 | Fine sandy loam   | SM-SC, SM      | A-4, A-2 | 0                           | 100                                  | 95-100 | 65-85  | 25-50 | 15-25           | NP-10                    |
|                          | 44-51 | Loamy fine sand   | SM             | A-2      | 0                           | 80-100                               | 75-100 | 60-80  | 20-30 | ---             | NP                       |
|                          | 51-63 | Very gravelly coarse sand, very gravelly loamy sand.    | GP, GP-GM, GM  | A-1      | 0-5                         | 30-50                                | 25-50  | 10-35  | 0-15  | ---             | NP                       |
| Picabo-----              | 0-9   | Silt loam-----  | ML             | A-4      | 0                           | 95-100                               | 95-100 | 90-100 | 75-95 | ---             | NP                       |
|                          | 9-39  | Loam, silt loam   | ML             | A-5      | 0                           | 95-100                               | 95-100 | 95-100 | 75-95 | 40-50           | NP-5                     |
|                          | 39-51 | Gravelly silt loam.                                     | GM, SM, ML     | A-5      | 0                           | 70-80                                | 65-75  | 55-70  | 45-60 | 40-50           | NP-5                     |
|                          | 51-61 | Very fine sandy loam, silt loam.                        | ML             | A-4      | 0                           | 95-100                               | 95-100 | 90-95  | 65-90 | ---             | NP                       |
|                          | 61-72 | Stratified loamy sand to extremely gravelly loamy sand. | GM, SM         | A-1      | 0-10                        | 35-65                                | 30-60  | 20-45  | 10-20 | ---             | NP                       |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol  | Depth | USDA texture  | Classification          |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|---------------------------|-------|---|-------------------------|----------|-----------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                           |       |   | Unified                 | AASHTO   |                             | 4                                    | 10     | 40     | 200   |                 |                          |
|                           | In    |   |                         |          | Pct                         |                                      |        |        |       | Pct             |                          |
| 49-----<br>Hutton         | 0-4   | Clay loam-----  | CL                      | A-6      | 0                           | 95-100                               | 90-95  | 75-85  | 65-75 | 30-40           | 10-15                    |
|                           | 4-19  | Clay loam-----  | CL, ML                  | A-6, A-7 | 0                           | 95-100                               | 90-95  | 85-90  | 80-85 | 35-45           | 10-20                    |
|                           | 19-62 | Clay, silty clay,<br>gravelly clay.   | CH, CL                  | A-7      | 0-5                         | 70-100                               | 65-100 | 60-95  | 50-90 | 45-60           | 25-40                    |
| 50-----<br>Hutton Variant | 0-8   | Clay loam-----  | CL                      | A-6, A-7 | 0                           | 90-100                               | 85-100 | 70-90  | 60-80 | 35-45           | 15-25                    |
|                           | 8-24  | Clay, gravelly<br>clay.   | CL, CH                  | A-7      | 0                           | 80-100                               | 75-100 | 70-95  | 65-90 | 45-75           | 25-45                    |
|                           | 24-39 | Very gravelly<br>sandy clay loam,<br>very gravelly<br>sandy clay.   | GC                      | A-2      | 0-10                        | 30-55                                | 25-50  | 15-45  | 10-30 | 35-50           | 15-25                    |
|                           | 39-66 | Extremely<br>gravelly sandy<br>loam, extremely<br>gravelly coarse<br>sand.                                    | GP, GP-GM,<br>GM        | A-1      | 10-30                       | 15-30                                | 10-25  | 5-20   | 0-15  | ---             | NP                       |
| 51-----<br>Isknat         | 0-2   | Gravelly clay<br>loam.  | GM, GC,<br>CL, ML       | A-6, A-7 | 0                           | 60-80                                | 55-75  | 45-70  | 35-60 | 35-45           | 10-20                    |
|                           | 2-11  | Gravelly clay<br>loam.  | GC, CL, CH              | A-7      | 0                           | 55-75                                | 50-75  | 45-70  | 35-60 | 45-55           | 20-30                    |
|                           | 11-26 | Very gravelly<br>clay loam, very<br>gravelly sandy<br>clay loam, very<br>gravelly sandy<br>clay.              | GC                      | A-2      | 0-15                        | 35-55                                | 30-50  | 20-45  | 15-35 | 45-60           | 20-35                    |
|                           | 26-35 | Very gravelly<br>sandy clay loam,<br>extremely<br>gravelly sandy<br>clay loam.                                | GP-GC, GC               | A-2      | 15-25                       | 20-50                                | 15-45  | 10-40  | 5-25  | 30-45           | 10-20                    |
|                           | 35-61 | Extremely<br>gravelly sandy<br>loam, extremely<br>gravelly loamy<br>sand, extremely<br>cobbly coarse<br>sand. | GP, GP-GM,<br>GM        | A-1      | 25-55                       | 20-40                                | 15-40  | 5-35   | 0-15  | ---             | NP                       |
| 52, 53-----<br>Justesen   | 0-7   | Loam-----   | CL-ML                   | A-4      | 0                           | 100                                  | 95-100 | 80-95  | 55-75 | 25-30           | 5-10                     |
|                           | 7-24  | Loam, clay loam,<br>silty clay loam.  | CL                      | A-6, A-7 | 0                           | 100                                  | 95-100 | 85-100 | 65-85 | 35-45           | 15-25                    |
|                           | 24-62 | Fine sandy loam,<br>loam.   | CL-ML, ML,<br>SM-SC, SM | A-4      | 0                           | 90-100                               | 85-100 | 60-90  | 45-75 | 25-35           | 5-10                     |
| 54, 55-----<br>Justesen   | 0-14  | Loam-----   | CL-ML                   | A-4      | 0                           | 100                                  | 95-100 | 80-95  | 55-75 | 25-30           | 5-10                     |
|                           | 14-31 | Loam, clay loam,<br>silty clay loam.  | CL                      | A-6, A-7 | 0                           | 100                                  | 95-100 | 85-100 | 65-85 | 35-45           | 15-25                    |
|                           | 31-64 | Fine sandy loam,<br>loam.   | CL-ML, ML,<br>SM-SC, SM | A-4      | 0                           | 90-100                               | 85-100 | 60-90  | 45-75 | 25-35           | 5-10                     |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture   | Classification       |               | Frag-ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|--------------------------|-------|--|----------------------|---------------|------------------------------------|--------------------------------------|-------|-------|-------|------------------------|--------------------------|
|                          |       |  | Unified              | AASHTO        |                                    | 4                                    | 10    | 40    | 200   |                        |                          |
|                          | In    |  |                      |               |                                    |                                      |       |       |       |                        |                          |
| 56*:<br>Ketchum-----     | 0-3   | Very gravelly loam.  | GM-GC, GC            | A-2, A-4, A-6 | 5-20                               | 40-55                                | 35-50 | 30-50 | 20-40 | 25-35                  | 5-15                     |
|                          | 3-48  | Very gravelly loam, very gravelly sandy loam, very gravelly fine sandy loam. | GM, GM-GC            | A-1, A-2, A-4 | 10-20                              | 40-60                                | 35-55 | 20-55 | 10-40 | 20-30                  | NP-10                    |
|                          | 48-61 | Extremely gravelly fine sandy loam, extremely gravelly coarse sandy loam.    | GM                   | A-1           | 10-40                              | 30-45                                | 25-40 | 15-25 | 10-15 | 20-25                  | NP-5                     |
| Dollarhide-----          | 0-7   | Very gravelly fine sandy loam.   | GM                   | A-1, A-2      | 0-25                               | 40-55                                | 35-50 | 25-50 | 15-30 | 20-25                  | NP-5                     |
|                          | 7-13  | Extremely cobbly fine sandy loam, extremely cobbly loam.                     | GM                   | A-1, A-2      | 50-65                              | 40-50                                | 40-45 | 30-40 | 15-30 | 20-25                  | NP-5                     |
|                          | 13    | Unweathered bedrock.   | ---                  | ---           | ---                                | ---                                  | ---   | ---   | ---   | ---                    | ---                      |
| 57*:<br>Ketchum-----     | 0-3   | Very gravelly loam.  | GM-GC, GC            | A-2, A-4, A-6 | 5-20                               | 40-55                                | 35-50 | 30-50 | 20-40 | 25-35                  | 5-15                     |
|                          | 3-48  | Very gravelly loam, very gravelly sandy loam, very gravelly fine sandy loam. | GM, GM-GC            | A-1, A-2, A-4 | 10-20                              | 40-60                                | 35-55 | 20-55 | 10-40 | 20-30                  | NP-10                    |
|                          | 48-61 | Extremely gravelly fine sandy loam, extremely gravelly coarse sandy loam.    | GM                   | A-1           | 10-40                              | 30-45                                | 25-40 | 15-25 | 10-15 | 20-25                  | NP-5                     |
| Povey-----               | 0-4   | Gravelly loam----  | SM, GM, SM-SC, GM-GC | A-4           | 5-10                               | 60-85                                | 55-80 | 40-70 | 35-50 | 20-30                  | NP-10                    |
|                          | 4-25  | Very gravelly loam, very cobbly loam, extremely gravelly fine sandy loam.    | GM, GM-GC            | A-2, A-1      | 10-50                              | 30-60                                | 25-55 | 20-50 | 10-35 | 20-30                  | NP-10                    |
|                          | 25-50 | Very cobbly loam, extremely cobbly sandy loam, extremely cobbly loam.        | GM                   | A-1, A-2      | 40-70                              | 50-60                                | 45-55 | 30-45 | 20-35 | 20-25                  | NP-5                     |
|                          | 50-54 | Unweathered bedrock.   | ---                  | ---           | ---                                | ---                                  | ---   | ---   | ---   | ---                    | ---                      |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture  | Classification  |                  | Frag-<br>ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |       |        |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|--------------------------|-------|---|-----------------|------------------|--|--------------------------------------|-------|--------|-------|------------------------|--------------------------|
|                          |       |   | Unified         | AASHTO           |  | 4                                    | 10    | 40     | 200   |                        |                          |
| 58*:<br>Laurentzen-----  | In    |   |                 |                  |  |                                      |       |        |       |                        |                          |
|                          | 0-13  | Silt loam-----  | CL-ML, ML       | A-4              | 0                                      | 100                                  | 100   | 95-100 | 75-85 | 25-35                  | 5-10                     |
|                          | 13-63 | Loam, clay loam,<br>silty clay loam.  | CL              | A-6              | 0-5                                    | 100                                  | 100   | 95-100 | 75-90 | 30-40                  | 10-15                    |
|                          | 63    | Unweathered<br>bedrock.   | ---             | ---              | ---                                    | ---                                  | ---   | ---    | ---   | ---                    | ---                      |
| Mulshoe-----             | 0-10  | Very stony loam   | GM-GC,<br>CL-ML | A-4, A-2         | 30-60                                  | 50-80                                | 50-75 | 45-70  | 30-60 | 25-30                  | 5-10                     |
|                          | 10-23 | Very stony clay<br>loam, very<br>cobbly clay<br>loam, very<br>gravelly clay<br>loam.  | GC, CL          | A-6, A-2         | 15-65                                  | 35-85                                | 30-80 | 25-75  | 20-65 | 30-40                  | 10-15                    |
|                          | 23-28 | Weathered bedrock   | ---             | ---              | ---                                    | ---                                  | ---   | ---    | ---   | ---                    | ---                      |
|                          | 28    | Unweathered<br>bedrock.   | ---             | ---              | ---                                    | ---                                  | ---   | ---    | ---   | ---                    | ---                      |
| 59*.<br>Lava flows       |       |   |                 |                  |  |                                      |       |        |       |                        |                          |
| 60*:<br>Lava flows.      |       |   |                 |                  |  |                                      |       |        |       |                        |                          |
| Cinderhurst-----         | 0-3   | Extremely cobbly<br>silt loam.  | GM              | A-2, A-4,<br>A-5 | 55-70                                  | 50-60                                | 45-55 | 40-55  | 30-50 | 35-45                  | NP-5                     |
|                          | 3-8   | Very cobbly silt<br>loam, very<br>gravelly silt<br>loam, extremely<br>cobbly loam.    | ML, GM          | A-2, A-4,<br>A-5 | 25-65                                  | 50-90                                | 45-85 | 40-80  | 30-75 | 35-45                  | 5-10                     |
|                          | 8     | Unweathered<br>bedrock.   | ---             | ---              | ---                                    | ---                                  | ---   | ---    | ---   | ---                    | ---                      |
| 61*:<br>Lavacreek-----   | 0-23  | Very gravelly<br>silt loam.   | GM              | A-4, A-2,<br>A-5 | 0-15                                   | 45-60                                | 40-55 | 35-50  | 30-50 | 35-45                  | NP-5                     |
|                          | 23-41 | Very gravelly<br>silt loam, very<br>cobbly loam,<br>extremely cobbly<br>loam.         | GM, ML          | A-4, A-2         | 30-55                                  | 45-75                                | 40-70 | 30-65  | 25-65 | 25-35                  | NP-5                     |
|                          | 41-49 | Very gravelly<br>loam, extremely<br>gravelly loam,<br>extremely cobbly<br>sandy loam. | GM              | A-1, A-4,<br>A-2 | 40-55                                  | 30-65                                | 25-60 | 20-55  | 10-45 | 20-25                  | NP-5                     |
|                          | 49    | Unweathered<br>bedrock.   | ---             | ---              | ---                                    | ---                                  | ---   | ---    | ---   | ---                    | ---                      |
| Dollarhide-----          | 0-7   | Very gravelly<br>silt loam.   | GM              | A-2, A-4         | 0-25                                   | 40-55                                | 35-50 | 30-50  | 25-45 | 20-25                  | NP-5                     |
|                          | 7-16  | Extremely cobbly<br>fine sandy loam,<br>extremely cobbly<br>loam.                     | GM              | A-1, A-2         | 50-65                                  | 40-50                                | 40-45 | 30-40  | 15-30 | 20-25                  | NP-5                     |
|                          | 16-20 | Unweathered<br>bedrock.   | ---             | ---              | ---                                    | ---                                  | ---   | ---    | ---   | ---                    | ---                      |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and<br>map symbol | Depth     | USDA texture  | Classification |                  | Frag-<br>ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit | Plas-<br>tic<br>inde |
|-----------------------------|-----------|---|----------------|------------------|---------------------------------|--------------------------------------|-------|-------|-------|-----------------|----------------------|
|                             |           |   | Unified        | AASHTO           |                                 | 4                                    | 10    | 40    | 200   |                 |                      |
|                             | <u>In</u> |   |                |                  | <u>Pct</u>                      |                                      |       |       |       | <u>Pct</u>      |                      |
| 62*:<br>Lavacreek-----      | 0-9       | Very gravelly<br>silt loam.   | GM             | A-4, A-2,<br>A-5 | 0-15                            | 45-60                                | 40-55 | 35-50 | 30-50 | 35-45           | NP-5                 |
|                             | 9-38      | Very gravelly<br>silt loam, very<br>cobbly loam,<br>extremely cobbly<br>loam.         | GM, ML         | A-4, A-2         | 30-55                           | 45-75                                | 40-70 | 30-65 | 25-65 | 25-35           | NP-5                 |
|                             | 38-43     | Very gravelly<br>loam, extremely<br>gravelly loam,<br>extremely cobbly<br>sandy loam. | GM             | A-1, A-4,<br>A-2 | 40-55                           | 30-65                                | 25-60 | 20-55 | 10-45 | 20-25           | NP-5                 |
|                             | 43-47     | Unweathered<br>bedrock.   | ---            | ---              | ---                             | ---                                  | ---   | ---   | ---   | ---             | ---                  |
| Dollarhide-----             | 0-7       | Very gravelly<br>silt loam.   | GM             | A-2, A-4         | 0-25                            | 40-55                                | 35-50 | 30-50 | 25-45 | 20-25           | NP-5                 |
|                             | 7-16      | Extremely cobbly<br>fine sandy loam,<br>extremely cobbly<br>loam.                     | GM             | A-1, A-2         | 50-65                           | 40-50                                | 40-45 | 30-40 | 15-30 | 20-25           | NP-5                 |
|                             | 16-20     | Unweathered<br>bedrock.   | ---            | ---              | ---                             | ---                                  | ---   | ---   | ---   | ---             | ---                  |
| 63*:<br>Lavacreek-----      | 0-23      | Very gravelly<br>silt loam.   | GM             | A-4, A-2,<br>A-5 | 0-15                            | 45-60                                | 40-55 | 35-50 | 30-50 | 35-45           | NP-5                 |
|                             | 23-41     | Very gravelly<br>silt loam, very<br>cobbly loam,<br>extremely cobbly<br>loam.         | GM, ML         | A-4, A-2         | 30-55                           | 45-75                                | 40-70 | 30-65 | 25-65 | 25-35           | NP-5                 |
|                             | 41-49     | Very gravelly<br>loam, extremely<br>gravelly loam,<br>extremely cobbly<br>sandy loam. | GM             | A-1, A-4,<br>A-2 | 40-55                           | 30-65                                | 25-60 | 20-55 | 10-45 | 20-25           | NP-5                 |
|                             | 49        | Unweathered<br>bedrock.   | ---            | ---              | ---                             | ---                                  | ---   | ---   | ---   | ---             | ---                  |
| Vitale-----                 | 0-6       | Very gravelly<br>loam.  | GM-GC, GC      | A-2, A-1         | 10-15                           | 35-60                                | 30-55 | 25-45 | 20-35 | 25-35           | 5-15                 |
|                             | 6-15      | Very gravelly<br>clay loam, very<br>cobbly clay<br>loam.                              | GC             | A-6, A-2,<br>A-7 | 10-45                           | 35-65                                | 30-60 | 30-55 | 25-45 | 35-45           | 15-25                |
|                             | 15-23     | Very gravelly<br>loam, very<br>cobbly loam.   | GM-GC, GC      | A-2              | 15-45                           | 35-55                                | 35-50 | 30-45 | 25-35 | 25-35           | 5-15                 |
|                             | 23        | Unweathered<br>bedrock.   | ---            | ---              | ---                             | ---                                  | ---   | ---   | ---   | ---             | ---                  |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and<br>map symbol | Depth | USDA texture   | Classification          |          | Frag-<br>ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|-----------------------------|-------|--|-------------------------|----------|---------------------------------|--------------------------------------|-------|-------|-------|-----------------|--------------------------|
|                             |       |  | Unified                 | AASHTO   |                                 | 4                                    | 10    | 40    | 200   |                 |                          |
|                             | In    |  |                         |          | Pct                             |                                      |       |       |       | Pct             |                          |
| 64, 65-----<br>Little Wood  | 0-13  | Gravelly loam----  | GM, CL-ML,<br>ML, GM-GC | A-2, A-4 | 0                               | 55-80                                | 50-75 | 40-70 | 30-55 | 25-35           | 5-10                     |
|                             | 13-26 | Very gravelly<br>sandy clay loam,<br>very gravelly<br>loam, very<br>gravelly clay<br>loam. | GC                      | A-2      | 0-15                            | 45-55                                | 40-50 | 20-40 | 10-35 | 30-50           | 10-25                    |
|                             | 26-32 | Extremely<br>gravelly loamy<br>coarse sand,<br>extremely<br>gravelly coarse<br>sandy loam. | GM, GP-GM               | A-1      | 5-20                            | 25-35                                | 20-30 | 10-20 | 5-15  | 15-20           | NP-5                     |
|                             | 32-61 | Extremely<br>gravelly loamy<br>coarse sand,<br>extremely<br>gravelly coarse<br>sand.       | GP, GP-GM               | A-1      | 5-20                            | 20-35                                | 15-30 | 5-20  | 0-10  | ---             | NP                       |
| 66-----<br>Little Wood      | 0-10  | Very gravelly<br>loam.   | GM, GM-GC               | A-2, A-4 | 0-5                             | 45-55                                | 40-50 | 30-50 | 20-40 | 25-35           | 5-10                     |
|                             | 10-25 | Very gravelly<br>sandy clay loam,<br>very gravelly<br>loam, very<br>gravelly clay<br>loam. | GC                      | A-2      | 0-15                            | 45-55                                | 40-50 | 20-40 | 10-35 | 30-50           | 10-25                    |
|                             | 25-35 | Extremely<br>gravelly loamy<br>coarse sand,<br>extremely<br>gravelly coarse<br>sandy loam. | GM, GP-GM               | A-1      | 5-20                            | 25-35                                | 20-30 | 10-20 | 5-15  | 15-20           | NP-5                     |
|                             | 35-61 | Extremely<br>gravelly loamy<br>coarse sand,<br>extremely<br>gravelly coarse<br>sand.       | GP, GP-GM               | A-1      | 5-20                            | 20-35                                | 15-30 | 5-20  | 0-10  | ---             | NP                       |
| 67-----<br>Little Wood      | 0-10  | Very gravelly<br>loam.   | GM, GM-GC               | A-2, A-4 | 0-5                             | 45-55                                | 40-50 | 30-50 | 20-40 | 25-35           | 5-10                     |
|                             | 10-22 | Very gravelly<br>sandy clay loam,<br>very gravelly<br>loam, very<br>gravelly clay<br>loam. | GC                      | A-2      | 0-15                            | 45-55                                | 40-50 | 20-40 | 10-35 | 30-50           | 10-25                    |
|                             | 22-32 | Extremely<br>gravelly loamy<br>coarse sand,<br>extremely<br>gravelly coarse<br>sandy loam. | GM, GP-GM               | A-1      | 5-20                            | 25-35                                | 20-30 | 10-20 | 5-15  | 15-20           | NP-5                     |
|                             | 32-61 | Extremely<br>gravelly loamy<br>coarse sand,<br>extremely<br>gravelly coarse<br>sand.       | GP, GP-GM               | A-1      | 5-20                            | 20-35                                | 15-30 | 5-20  | 0-10  | ---             | NP                       |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture  | Classification |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|--------------------------|-----------|---|----------------|----------|-----------------------------|--------------------------------------|--------|--------|-------|------------------------|--------------------------|
|                          |           |   | Unified        | AASHTO   |                             | 4                                    | 10     | 40     | 200   |                        |                          |
|                          | <u>In</u> |   |                |          | <u>Pct</u>                  |                                      |        |        |       |                        |                          |
| 68-----<br>Little Wood   | 0-12      | Very gravelly loam.   | GC             | A-2      | 0                           | 40-55                                | 35-50  | 25-40  | 20-35 | 30-35                  | 10-15                    |
|                          | 12-16     | Very gravelly sandy clay loam.  | GC             | A-2      | 0-10                        | 35-55                                | 30-50  | 20-35  | 15-30 | 35-50                  | 15-25                    |
|                          | 16-24     | Extremely cobbly sandy clay loam.   | GP-GC, GC      | A-2      | 40-60                       | 20-40                                | 20-35  | 10-30  | 5-20  | 30-40                  | 10-20                    |
|                          | 24-31     | Extremely cobbly sandy loam.  | GP-GC, GM-GC   | A-2      | 45-65                       | 20-40                                | 20-35  | 15-25  | 5-20  | 25-30                  | 5-10                     |
|                          | 31-60     | Extremely cobbly loamy coarse sand, extremely cobbly coarse sand.           | GP             | A-1      | 55-70                       | 15-25                                | 10-20  | 5-10   | 0-5   | ---                    | NP                       |
| 69*:<br>Little Wood----- | 0-10      | Very gravelly loam.   | GM, GM-GC      | A-2, A-4 | 0-5                         | 45-55                                | 40-50  | 30-50  | 20-40 | 25-35                  | 5-10                     |
|                          | 10-25     | Very gravelly sandy clay loam, very gravelly loam, very gravelly clay loam. | GC             | A-2      | 0-15                        | 45-55                                | 40-50  | 20-40  | 10-35 | 30-50                  | 10-25                    |
|                          | 25-35     | Extremely gravelly loamy coarse sand, extremely gravelly coarse sandy loam. | GM, GP-GM      | A-1      | 5-20                        | 25-35                                | 20-30  | 10-20  | 5-15  | 15-20                  | NP-5                     |
|                          | 35-61     | Extremely gravelly loamy coarse sand, extremely gravelly coarse sand.       | GP, GP-GM      | A-1      | 5-20                        | 20-35                                | 15-30  | 5-20   | 0-10  | ---                    | NP                       |
|                          |           |   |                |          |                             |                                      |        |        |       |                        |                          |
| Balaam-----              | 0-10      | Gravelly sandy loam.  | SM, GM         | A-2, A-1 | 0-5                         | 55-80                                | 55-75  | 30-60  | 15-30 | 25-30                  | NP-5                     |
|                          | 10-24     | Very gravelly coarse sandy loam, very gravelly fine sandy loam.             | GM             | A-1, A-2 | 0-10                        | 45-60                                | 40-55  | 20-50  | 10-30 | ---                    | NP                       |
|                          | 24-63     | Extremely gravelly coarse sand, extremely gravelly loamy coarse sand.       | GP, GP-GM      | A-1      | 10-30                       | 20-35                                | 15-30  | 5-20   | 0-10  | ---                    | NP                       |
| 70-----<br>Manard        | 0-11      | Silt loam-----  | CL             | A-6      | 0-5                         | 90-100                               | 85-100 | 75-100 | 60-95 | 30-40                  | 10-20                    |
|                          | 11-36     | Silty clay, clay  | CH, CL         | A-7      | 0-5                         | 90-100                               | 85-100 | 75-100 | 65-95 | 45-60                  | 25-40                    |
|                          | 36-38     | Indurated-----  | ---            | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
|                          | 38-42     | Unweathered bedrock.  | ---            | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| 71-----<br>Marshdale     | 0-9       | Loam-----   | CL, CL-ML      | A-4, A-6 | 0                           | 90-100                               | 85-100 | 75-85  | 65-75 | 25-35                  | 5-15                     |
|                          | 9-52      | Loam, sandy clay loam, clay loam.   | CL-ML, CL      | A-4, A-6 | 0                           | 90-100                               | 85-100 | 70-80  | 50-70 | 25-35                  | 5-15                     |
|                          | 52-62     | Gravelly coarse sand, very gravelly coarse sand.                            | SP, SP-SM, SM  | A-1      | 5-20                        | 55-100                               | 55-75  | 30-50  | 0-15  | ---                    | NP                       |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture   | Classification       |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-------|--|----------------------|----------|-----------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |       |  | Unified              | AASHTO   |                             | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | In    |  |                      |          | Pct                         |                                      |        |        |       | Pct             |                          |
| 72*:<br>Marshdale-----   | 0-14  | Loam-----  | CL, CL-ML            | A-4, A-6 | 0                           | 90-100                               | 85-100 | 75-85  | 65-75 | 25-35           | 5-15                     |
|                          | 14-50 | Loam, sandy clay<br>loam, clay loam.   | CL-ML, CL            | A-4, A-6 | 0                           | 90-100                               | 85-100 | 70-80  | 50-70 | 25-35           | 5-15                     |
|                          | 50-65 | Gravelly coarse<br>sand, very<br>gravelly coarse<br>sand.  | SP, SP-SM, SM        | A-1      | 5-20                        | 55-100                               | 55-75  | 30-50  | 0-15  | ---             | NP                       |
| Bruneel-----             | 0-14  | Loam-----  | CL-ML, ML, CL        | A-4, A-6 | 0                           | 95-100                               | 85-100 | 80-95  | 60-75 | 20-35           | NP-15                    |
|                          | 14-27 | Stratified loam<br>to fine sandy<br>loam.  | ML, CL-ML            | A-4      | 0                           | 95-100                               | 80-100 | 75-90  | 50-75 | 20-30           | NP-10                    |
|                          | 27-61 | Very gravelly<br>loamy sand,<br>extremely<br>gravelly loamy<br>sand, extremely<br>gravelly sand. | GP, GP-GM            | A-1      | 10-30                       | 25-40                                | 20-40  | 5-30   | 0-10  | ---             | NP                       |
| 73-----<br>McBiggam      | 0-10  | Silt loam-----   | ML                   | A-4      | 0                           | 90-100                               | 85-100 | 85-100 | 80-90 | 20-25           | NP-5                     |
|                          | 10-26 | Silt loam, silty<br>clay loam.   | CL                   | A-6      | 0-10                        | 95-100                               | 95-100 | 95-100 | 75-90 | 30-40           | 10-20                    |
|                          | 26-46 | Silty clay-----  | CL, CH               | A-7      | 0                           | 100                                  | 95-100 | 95-100 | 80-95 | 45-60           | 30-40                    |
|                          | 46-80 | Silty clay loam,<br>clay loam.   | CL, ML               | A-6, A-7 | 0                           | 100                                  | 95-100 | 95-100 | 75-95 | 35-45           | 10-20                    |
| 74*:<br>McCarey-----     | 0-11  | Loam-----  | ML                   | A-4      | 0-5                         | 95-100                               | 90-100 | 85-100 | 60-90 | 20-35           | NP-10                    |
|                          | 11-23 | Clay loam, silty<br>clay loam, silt<br>loam.   | CL, CL-ML            | A-6, A-4 | 0-5                         | 85-100                               | 85-100 | 80-100 | 65-85 | 25-40           | 5-15                     |
|                          | 23-28 | Silt loam, loam  | ML                   | A-4      | 0-5                         | 85-100                               | 85-100 | 80-100 | 65-85 | 20-35           | NP-10                    |
|                          | 28-32 | Unweathered<br>bedrock.  | ---                  | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Justesen-----            | 0-14  | Loam-----  | CL-ML                | A-4      | 0                           | 100                                  | 95-100 | 80-95  | 55-75 | 25-30           | 5-10                     |
|                          | 14-31 | Loam, clay loam,<br>silty clay loam.   | CL                   | A-6, A-7 | 0                           | 100                                  | 95-100 | 85-100 | 65-85 | 35-45           | 15-25                    |
|                          | 31-64 | Fine sandy loam,<br>loam.  | CL-ML, ML, SM-SC, SM | A-4      | 0                           | 90-100                               | 85-100 | 60-90  | 45-75 | 25-35           | 5-10                     |
| 75*:<br>McCarey-----     | 0-11  | Loam-----  | ML                   | A-4      | 0-5                         | 95-100                               | 90-100 | 85-100 | 60-90 | 20-35           | NP-10                    |
|                          | 11-23 | Clay loam, silty<br>clay loam, silt<br>loam.   | CL, CL-ML            | A-6, A-4 | 0-5                         | 85-100                               | 85-100 | 80-100 | 65-85 | 25-40           | 5-15                     |
|                          | 23-28 | Silt loam, loam  | ML                   | A-4      | 0-5                         | 85-100                               | 85-100 | 80-100 | 65-85 | 20-35           | NP-10                    |
|                          | 28-32 | Unweathered<br>bedrock.  | ---                  | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Justesen-----            | 0-14  | Loam-----  | CL-ML                | A-4      | 0                           | 100                                  | 95-100 | 80-95  | 55-75 | 25-30           | 5-10                     |
|                          | 14-31 | Loam, clay loam,<br>silty clay loam.   | CL                   | A-6, A-7 | 0                           | 100                                  | 95-100 | 85-100 | 65-85 | 35-45           | 15-25                    |
|                          | 31-64 | Fine sandy loam,<br>loam.  | CL-ML, ML, SM-SC, SM | A-4      | 0                           | 90-100                               | 85-100 | 60-90  | 45-75 | 25-35           | 5-10                     |
| Rock outcrop.            |       |  |                      |          |                             |                                      |        |        |       |                 |                          |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture   | Classification            |                  | Frag-<br>ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit<br>Pct | Plas-<br>tic<br>inde |
|--------------------------|-----------|--|---------------------------|------------------|--|--------------------------------------|--------|--------|-------|------------------------|----------------------|
|                          |           |  | Unified                   | AASHTO           |  | 4                                    | 10     | 40     | 200   |                        |                      |
| 76*:<br>McCarey-----     | <u>In</u> |  |                           |                  |  |                                      |        |        |       |                        |                      |
|                          | 0-10      | Loam-----  | ML                        | A-4              | 0-5                                    | 95-100                               | 90-100 | 85-100 | 60-90 | 20-35                  | NP-1                 |
|                          | 10-22     | Clay loam, silty<br>clay loam, silt<br>loam.                       | CL, CL-ML                 | A-6, A-4         | 0-5                                    | 85-100                               | 85-100 | 80-100 | 65-85 | 25-40                  | 5-1                  |
|                          | 22-37     | Silt loam, loam  | ML                        | A-4              | 0-5                                    | 85-100                               | 85-100 | 80-100 | 65-85 | 20-35                  | NP-1                 |
|                          | 37-41     | Unweathered<br>bedrock.  | ---                       | ---              | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                  |
| Molyneux-----            | 0-13      | Loam-----  | CL-ML                     | A-4              | 0                                      | 95-100                               | 90-100 | 75-90  | 55-70 | 20-25                  | 5-1                  |
|                          | 13-50     | Clay loam, silt<br>loam, loam.                                     | CL                        | A-6, A-7         | 0                                      | 80-95                                | 75-90  | 70-90  | 55-75 | 35-45                  | 15-2                 |
|                          | 50-75     | Gravelly clay<br>loam, gravelly<br>sandy clay loam.                | CL, SC                    | A-2, A-6         | 0                                      | 70-85                                | 60-75  | 50-75  | 20-60 | 25-35                  | 10-1                 |
| 77*:<br>McCarey-----     | 0-10      | Loam-----  | ML                        | A-4              | 0-5                                    | 95-100                               | 90-100 | 85-100 | 60-90 | 20-35                  | NP-1                 |
|                          | 10-22     | Clay loam, silty<br>clay loam, silt<br>loam.                       | CL, CL-ML                 | A-6, A-4         | 0-5                                    | 85-100                               | 85-100 | 80-100 | 65-85 | 25-40                  | 5-1                  |
|                          | 22-37     | Silt loam, loam  | ML                        | A-4              | 0-5                                    | 85-100                               | 85-100 | 80-100 | 65-85 | 20-35                  | NP-1                 |
|                          | 37-41     | Unweathered<br>bedrock.  | ---                       | ---              | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                  |
| Pedleford-----           | 0-5       | Very stony loam  | SM, GM, ML                | A-2, A-4         | 40-50                                  | 50-85                                | 45-80  | 40-75  | 25-70 | 20-25                  | NP-5                 |
|                          | 5-13      | Very stony sandy<br>loam, very stony<br>loam, very<br>cobbly loam. | CL-ML,<br>SM-SC,<br>GM-GC | A-2, A-4         | 40-45                                  | 45-85                                | 40-80  | 25-75  | 10-60 | 25-30                  | 5-10                 |
|                          | 13-33     | Very stony silt<br>loam, very stony<br>loam, very<br>cobbly loam.  | SM, GM, ML                | A-1, A-2         | 30-45                                  | 45-75                                | 40-70  | 25-65  | 20-55 | 20-25                  | NP-5                 |
|                          | 33        | Unweathered<br>bedrock.  | ---                       | ---              | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                  |
| 78, 79-----<br>Molyneux  | 0-12      | Loam-----  | CL-ML                     | A-4              | 0                                      | 95-100                               | 90-100 | 75-90  | 55-70 | 20-25                  | 5-10                 |
|                          | 12-61     | Clay loam, silt<br>loam, loam.                                     | CL                        | A-6, A-7         | 0                                      | 80-95                                | 75-90  | 70-90  | 55-75 | 35-45                  | 15-25                |
| 80-----<br>Molyneux      | 0-13      | Loam-----  | CL-ML                     | A-4              | 0                                      | 95-100                               | 90-100 | 75-90  | 55-70 | 20-25                  | 5-10                 |
|                          | 13-50     | Clay loam, silt<br>loam, loam.                                     | CL                        | A-6, A-7         | 0                                      | 80-95                                | 75-90  | 70-90  | 55-75 | 35-45                  | 15-25                |
|                          | 50-75     | Gravelly clay<br>loam, gravelly<br>sandy clay loam.                | CL, SC                    | A-2, A-6         | 0                                      | 70-85                                | 60-75  | 50-75  | 20-60 | 25-35                  | 10-15                |
| 81*:<br>Moonstone-----   | 0-26      | Gravelly coarse<br>sandy loam.                                     | SM                        | A-1, A-2         | 0-5                                    | 70-80                                | 65-75  | 45-50  | 20-30 | 20-25                  | NP-5                 |
|                          | 26-34     | Coarse sandy<br>loam, gravelly<br>coarse sandy<br>loam.            | SM                        | A-1, A-2,<br>A-4 | 0-5                                    | 70-95                                | 65-90  | 45-70  | 20-50 | 20-25                  | NP-5                 |
|                          | 34        | Weathered bedrock  | ---                       | ---              | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                  |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture  | Classification  |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-------|---|-----------------|----------|-----------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |       |   | Unified         | AASHTO   |                             | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | In    |   |                 |          | Pct                         |                                      |        |        |       | Pct             |                          |
| 81*:<br>Bauscher-----    | 0-14  | Loam-----   | CL-ML           | A-4      | 0                           | 90-100                               | 85-95  | 65-85  | 50-70 | 20-30           | 5-10                     |
|                          | 14-37 | Loam, sandy clay<br>loam.   | CL, SC          | A-2, A-6 | 0                           | 90-100                               | 85-95  | 45-70  | 40-55 | 25-35           | 10-15                    |
|                          | 37-42 | Coarse sandy<br>loam, gravelly<br>coarse sandy<br>loam.                                     | SM              | A-2      | 0                           | 75-95                                | 65-85  | 40-60  | 25-30 | 20-25           | NP-5                     |
|                          | 42    | Weathered bedrock   | ---             | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| 82*:<br>Moonstone-----   | 0-21  | Gravelly coarse<br>sandy loam.  | SM              | A-1, A-2 | 0-5                         | 70-80                                | 65-75  | 45-50  | 20-30 | 20-25           | NP-5                     |
|                          | 21-32 | Coarse sandy<br>loam, gravelly<br>coarse sandy<br>loam.                                     | SM              | A-1, A-2 | 0-5                         | 70-95                                | 65-90  | 45-70  | 20-50 | 20-25           | NP-5                     |
|                          | 32-36 | Weathered bedrock   | ---             | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Earcree-----             | 0-37  | Gravelly coarse<br>sandy loam.  | SM              | A-1, A-2 | 0                           | 75-95                                | 65-75  | 35-45  | 20-35 | 20-25           | NP-5                     |
|                          | 37-52 | Gravelly coarse<br>sandy loam,<br>gravelly sandy<br>loam, gravelly<br>loamy coarse<br>sand. | SM, GM          | A-1, A-2 | 0                           | 60-80                                | 50-75  | 25-50  | 10-35 | 15-25           | NP-5                     |
|                          | 52-70 | Very gravelly<br>loamy coarse<br>sand.  | SM, GM          | A-1      | 0                           | 50-60                                | 40-50  | 20-30  | 10-20 | ---             | NP                       |
| 83*:<br>Muldoon-----     | 0-7   | Loam-----   | ML, CL-ML       | A-4      | 0-5                         | 90-100                               | 85-100 | 75-95  | 50-75 | 25-35           | 5-10                     |
|                          | 7-32  | Clay loam, silty<br>clay loam.  | CL              | A-6      | 0-5                         | 90-100                               | 90-100 | 85-100 | 70-95 | 30-40           | 10-20                    |
|                          | 32-45 | Clay loam, cobbly<br>clay loam.   | CL              | A-6      | 0-40                        | 85-95                                | 80-95  | 70-95  | 60-75 | 30-35           | 10-15                    |
|                          | 45    | Indurated-----  | ---             | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Peevywell-----           | 0-12  | Loam-----   | CL-ML           | A-4      | 0-10                        | 90-95                                | 85-95  | 75-90  | 50-65 | 25-30           | 5-10                     |
|                          | 12-22 | Clay loam-----  | CL              | A-6, A-7 | 0-10                        | 90-95                                | 85-95  | 75-90  | 60-75 | 35-50           | 15-25                    |
|                          | 22-30 | Silty clay, clay  | CL, CH          | A-7      | 0-10                        | 90-95                                | 85-95  | 70-90  | 70-90 | 40-60           | 20-35                    |
|                          | 30-44 | Indurated-----  | ---             | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 44-61 | Very gravelly<br>sandy loam,<br>gravelly loamy<br>sand.                                     | GM, SM          | A-1, A-2 | 10-30                       | 40-70                                | 35-70  | 25-55  | 10-25 | 20-25           | NP-5                     |
| 84*:<br>Mulshoe-----     | 0-10  | Very stony loam   | GM-GC,<br>CL-ML | A-4, A-2 | 30-60                       | 50-80                                | 50-75  | 45-70  | 30-60 | 25-30           | 5-10                     |
|                          | 10-23 | Very stony clay<br>loam, very<br>cobbly clay<br>loam, very<br>gravelly clay<br>loam.        | GC, CL          | A-6, A-2 | 15-65                       | 35-85                                | 30-80  | 25-75  | 20-65 | 30-40           | 10-15                    |
|                          | 23-28 | Weathered bedrock   | ---             | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 28    | Unweathered<br>bedrock.   | ---             | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and<br>map symbol | Depth     | USDA texture   | Classification             |                  | Frag-<br>ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|-----------------------------|-----------|--|----------------------------|------------------|--|--------------------------------------|-------|-------|-------|------------------------|--------------------------|
|                             |           |  | Unified                    | AASHTO           |  | 4                                    | 10    | 40    | 200   |                        |                          |
| 84*:<br>Gaib-----           | <u>In</u> |  |                            |                  |  |                                      |       |       |       |                        |                          |
|                             | 0-4       | Stony loam-----  | CL-ML, CL                  | A-4, A-6         | 10-25                                  | 85-95                                | 80-90 | 70-80 | 55-65 | 25-35                  | 5-15                     |
|                             | 4-12      | Very cobbly clay<br>loam, very stony<br>sandy clay loam.   | GC, SC                     | A-2, A-6,<br>A-7 | 30-50                                  | 55-70                                | 50-70 | 40-60 | 20-50 | 35-50                  | 15-25                    |
|                             | 12-16     | Unweathered<br>bedrock.  | ---                        | ---              | ---                                    | ---                                  | ---   | ---   | ---   | ---                    | ---                      |
| Rock outcrop.               |           |  |                            |                  |  |                                      |       |       |       |                        |                          |
| 85*:<br>Mulshoe-----        |           |  |                            |                  |  |                                      |       |       |       |                        |                          |
|                             | 0-12      | Very cobbly loam   | GM-GC,<br>CL-ML            | A-4, A-2         | 30-60                                  | 50-80                                | 50-75 | 45-70 | 30-60 | 25-30                  | 5-10                     |
|                             | 12-21     | Very stony clay<br>loam, very<br>cobbly clay<br>loam, very<br>gravelly clay<br>loam.                 | GC, CL                     | A-6, A-2         | 15-65                                  | 35-85                                | 30-80 | 25-75 | 20-65 | 30-40                  | 10-15                    |
|                             | 21-25     | Unweathered<br>bedrock.  | ---                        | ---              | ---                                    | ---                                  | ---   | ---   | ---   | ---                    | ---                      |
| Gaib-----                   |           |  |                            |                  |  |                                      |       |       |       |                        |                          |
|                             | 0-5       | Very gravelly<br>loam.   | GM-GC, GC                  | A-2, A-4,<br>A-6 | 0-25                                   | 30-55                                | 25-50 | 15-40 | 10-40 | 25-35                  | 5-15                     |
|                             | 5-13      | Very cobbly clay<br>loam, very stony<br>sandy clay loam.   | GC, SC                     | A-2, A-6,<br>A-7 | 30-50                                  | 55-70                                | 50-70 | 40-60 | 20-50 | 35-50                  | 15-25                    |
|                             | 13        | Unweathered<br>bedrock.  | ---                        | ---              | ---                                    | ---                                  | ---   | ---   | ---   | ---                    | ---                      |
| Winu-----                   |           |  |                            |                  |  |                                      |       |       |       |                        |                          |
|                             | 0-13      | Stony loam-----  | SM-SC,<br>CL-ML            | A-4              | 5-15                                   | 75-85                                | 70-80 | 65-75 | 45-55 | 20-30                  | 5-10                     |
|                             | 13-35     | Gravelly loam,<br>gravelly sandy<br>clay loam,<br>gravelly clay<br>loam.                             | GC, SC                     | A-6              | 5-10                                   | 65-75                                | 55-75 | 45-65 | 35-45 | 25-35                  | 10-20                    |
|                             | 35-39     | Unweathered<br>bedrock.  | ---                        | ---              | ---                                    | ---                                  | ---   | ---   | ---   | ---                    | ---                      |
| 86*:<br>Pagari-----         |           |  |                            |                  |  |                                      |       |       |       |                        |                          |
|                             | 0-11      | Very cobbly sandy<br>loam.   | SM                         | A-1, A-2,<br>A-4 | 40-65                                  | 80-90                                | 70-80 | 40-50 | 20-40 | 20-25                  | NP-5                     |
|                             | 11-17     | Very cobbly sandy<br>loam, very<br>cobbly loam.  | SM                         | A-1, A-2,<br>A-4 | 40-65                                  | 85-95                                | 70-80 | 40-55 | 20-40 | 20-25                  | NP-5                     |
|                             | 17-31     | Extremely cobbly<br>loam, extremely<br>cobbly sandy<br>clay loam,<br>extremely cobbly<br>clay loam.  | GC, GM-GC,<br>SC, SM-SC    | A-2              | 50-75                                  | 50-65                                | 45-60 | 25-40 | 15-35 | 25-40                  | 5-15                     |
|                             | 31-46     | Extremely cobbly<br>sandy loam,<br>extremely cobbly<br>sandy clay loam,<br>extremely cobbly<br>loam. | GM, SM,<br>GM-GC,<br>SM-SC | A-2              | 50-75                                  | 50-65                                | 45-60 | 25-35 | 10-25 | 25-35                  | 5-10                     |
|                             | 46        | Unweathered<br>bedrock.  | ---                        | ---              | ---                                    | ---                                  | ---   | ---   | ---   | ---                    | ---                      |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture  | Classification             |                  | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-----------|---|----------------------------|------------------|-----------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |           |   | Unified                    | AASHTO           |                             | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | <u>In</u> |   |                            |                  | <u>Pct</u>                  |                                      |        |        |       | <u>Pct</u>      |                          |
| 86*:<br>Rehfield-----    | 0-11      | Loamy sand-----   | SM                         | A-2, A-1         | 0                           | 90-100                               | 85-100 | 45-75  | 15-30 | ---             | NP                       |
|                          | 11-42     | Sandy loam, loam,<br>sandy clay loam.                               | SC, CL,<br>SM-SC,<br>CL-ML | A-4, A-6         | 0-5                         | 100                                  | 90-100 | 55-85  | 35-55 | 25-40           | 5-15                     |
|                          | 42-67     | Gravelly loamy<br>sand, loamy<br>sand, very fine<br>sandy loam.     | SM                         | A-1, A-2,<br>A-4 | 0-15                        | 75-100                               | 70-100 | 40-75  | 10-40 | 20-25           | NP-5                     |
| 87*:<br>Peevywell-----   | 0-5       | Loam-----   | CL-ML                      | A-4              | 0-10                        | 90-95                                | 85-95  | 75-90  | 50-65 | 25-30           | 5-10                     |
|                          | 5-10      | Clay loam-----  | CL                         | A-6, A-7         | 0-10                        | 90-95                                | 85-95  | 75-90  | 60-75 | 35-50           | 15-25                    |
|                          | 10-24     | Silty clay, clay  | CL, CH                     | A-7              | 0-10                        | 90-95                                | 85-95  | 70-90  | 70-90 | 40-60           | 20-35                    |
|                          | 24-46     | Indurated-----  | ---                        | ---              | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 46-61     | Very gravelly<br>sandy loam,<br>gravelly loamy<br>sand.             | GM, SM                     | A-1, A-2         | 10-30                       | 40-70                                | 35-70  | 25-55  | 10-25 | 20-25           | NP-5                     |
| Simonton-----            | 0-12      | Loam-----   | CL-ML,<br>SM-SC            | A-4              | 0                           | 85-100                               | 75-100 | 60-95  | 45-75 | 20-30           | 5-10                     |
|                          | 12-52     | Loam, clay loam,<br>sandy clay loam.                                | CL, SC                     | A-6, A-7         | 0                           | 85-100                               | 75-100 | 60-95  | 45-75 | 30-45           | 10-20                    |
|                          | 52-64     | Loamy coarse<br>sand, sandy<br>loam.                                | SM                         | A-2, A-1         | 0                           | 85-100                               | 75-100 | 40-65  | 15-30 | ---             | NP                       |
| 88*:<br>Peevywell-----   | 0-12      | Loam-----   | CL-ML                      | A-4              | 0-10                        | 90-95                                | 85-95  | 75-90  | 50-65 | 25-30           | 5-10                     |
|                          | 12-22     | Clay loam-----  | CL                         | A-6, A-7         | 0-10                        | 90-95                                | 85-95  | 75-90  | 60-75 | 35-50           | 15-25                    |
|                          | 22-30     | Silty clay, clay  | CL, CH                     | A-7              | 0-10                        | 90-95                                | 85-95  | 70-90  | 70-90 | 40-60           | 20-35                    |
|                          | 30-44     | Indurated-----  | ---                        | ---              | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 44-61     | Very gravelly<br>sandy loam,<br>gravelly loamy<br>sand.             | GM, SM                     | A-1, A-2         | 10-30                       | 40-70                                | 35-70  | 25-55  | 10-25 | 20-25           | NP-5                     |
| Simonton-----            | 0-11      | Silt loam-----  | CL-ML,<br>SM-SC            | A-4              | 0                           | 85-100                               | 75-100 | 60-95  | 45-75 | 20-30           | 5-10                     |
|                          | 11-61     | Loam, clay loam,<br>sandy clay loam.                                | CL, SC                     | A-6, A-7         | 0                           | 85-100                               | 75-100 | 60-95  | 45-75 | 30-45           | 10-20                    |
| 89-----<br>Picabo        | 0-9       | Silt loam-----  | ML                         | A-4              | 0                           | 95-100                               | 95-100 | 90-100 | 75-95 | ---             | NP                       |
|                          | 9-39      | Loam, silt loam   | ML                         | A-5              | 0                           | 95-100                               | 95-100 | 95-100 | 75-95 | 40-50           | NP-5                     |
|                          | 39-51     | Gravelly silt<br>loam.  | GM, SM, ML                 | A-5              | 0                           | 70-80                                | 65-75  | 55-70  | 45-60 | 40-50           | NP-5                     |
|                          | 51-61     | Very fine sandy<br>loam, silt loam.                                 | ML                         | A-4              | 0                           | 95-100                               | 95-100 | 90-95  | 65-90 | ---             | NP                       |
|                          | 61-72     | Stratified loamy<br>sand to<br>extremely<br>gravelly loamy<br>sand. | GM, SM                     | A-1              | 0-10                        | 35-65                                | 30-60  | 20-45  | 10-20 | ---             | NP                       |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth     | USDA texture   | Classification             |          | Frag-ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-----------|--|----------------------------|----------|-----------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |           |  | Unified                    | AASHTO   |                             | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | <u>In</u> |  |                            |          | <u>Pct</u>                  |                                      |        |        |       | <u>Pct</u>      |                          |
| 90-----<br>Picabo        | 0-11      | Gravelly loam----  | GM, ML                     | A-4      | 0                           | 65-75                                | 60-75  | 55-70  | 45-60 | 30-40           | NP-5                     |
|                          | 11-40     | Loam, silt loam  | ML                         | A-5      | 0                           | 95-100                               | 95-100 | 95-100 | 75-95 | 40-50           | NP-5                     |
|                          | 40-53     | Gravelly silt<br>loam.   | GM, SM, ML                 | A-5      | 0                           | 70-80                                | 65-75  | 55-70  | 45-60 | 40-50           | NP-5                     |
|                          | 53-61     | Very fine sandy<br>loam, silt loam.  | ML                         | A-4      | 0                           | 95-100                               | 95-100 | 90-95  | 65-90 | ---             | NP                       |
|                          | 61-72     | Stratified loamy<br>sand to<br>extremely<br>gravelly loamy<br>sand.                      | GM, SM                     | A-1      | 0-10                        | 35-65                                | 30-60  | 20-45  | 10-20 | ---             | NP                       |
| 91*.<br>Pits, gravel     |           |  |                            |          |                             |                                      |        |        |       |                 |                          |
| 92*:<br>Povey-----       | 0-14      | Gravelly loam----  | SM, GM,<br>SM-SC,<br>GM-GC | A-4      | 5-10                        | 60-85                                | 55-80  | 40-70  | 35-50 | 20-30           | NP-10                    |
|                          | 14-35     | Very gravelly<br>loam, very<br>cobbly loam,<br>extremely<br>gravelly fine<br>sandy loam. | GM, GM-GC                  | A-2, A-1 | 10-50                       | 30-60                                | 25-55  | 20-50  | 10-35 | 20-30           | NP-10                    |
|                          | 35-60     | Very cobbly loam,<br>extremely cobbly<br>sandy loam,<br>extremely cobbly<br>loam.        | GM                         | A-1, A-2 | 40-70                       | 50-60                                | 45-55  | 30-45  | 20-35 | 20-25           | NP-5                     |
|                          | 60        | Unweathered<br>bedrock.  | ---                        | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Dollarhide-----          | 0-7       | Very gravelly<br>silt loam.  | GM                         | A-2, A-4 | 0-25                        | 40-55                                | 35-50  | 30-50  | 25-45 | 20-25           | NP-5                     |
|                          | 7-16      | Extremely cobbly<br>fine sandy loam,<br>extremely cobbly<br>loam.                        | GM                         | A-1, A-2 | 50-65                       | 40-50                                | 40-45  | 30-40  | 15-30 | 20-25           | NP-5                     |
|                          | 16-20     | Unweathered<br>bedrock.  | ---                        | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| 93*:<br>Povey-----       | 0-14      | Gravelly loam----  | SM, GM,<br>SM-SC,<br>GM-GC | A-4      | 5-10                        | 60-85                                | 55-80  | 40-70  | 35-50 | 20-30           | NP-10                    |
|                          | 14-35     | Very gravelly<br>loam, very<br>cobbly loam,<br>extremely<br>gravelly fine<br>sandy loam. | GM, GM-GC                  | A-2, A-1 | 10-50                       | 30-60                                | 25-55  | 20-50  | 10-35 | 20-30           | NP-10                    |
|                          | 35-60     | Very cobbly loam,<br>extremely cobbly<br>sandy loam,<br>extremely cobbly<br>loam.        | GM                         | A-1, A-2 | 40-70                       | 50-60                                | 45-55  | 30-45  | 20-35 | 20-25           | NP-5                     |
|                          | 60        | Unweathered<br>bedrock.  | ---                        | ---      | ---                         | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Rock outcrop.            |           |  |                            |          |                             |                                      |        |        |       |                 |                          |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and<br>map symbol                      | Depth | USDA texture   | Classification             |          | Frag-<br>ments<br>> 3<br>inches<br><br>Pct | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit<br><br>Pct | Plas-<br>ticity<br>index |
|--|-------|--|----------------------------|----------|--|--------------------------------------|-------|-------|-------|----------------------------|--------------------------|
|  |       |  | Unified                    | AASHTO   |  | 4                                    | 10    | 40    | 200   |                            |                          |
| 94*:<br>Povey very<br>gravelly silt<br>loam----- | In    |  |                            |          |  |                                      |       |       |       |                            |                          |
|  | 0-12  | Very gravelly<br>silt loam.  | GM, GM-GC                  | A-4      | 0-10                                       | 50-60                                | 45-55 | 35-55 | 35-50 | 20-30                      | NP-10                    |
|  | 12-44 | Very gravelly<br>loam, very<br>cobbly loam,<br>extremely<br>gravelly fine<br>sandy loam. | GM, GM-GC                  | A-2, A-1 | 10-50                                      | 30-60                                | 25-55 | 20-50 | 10-35 | 20-30                      | NP-10                    |
|  | 44-52 | Very cobbly loam,<br>extremely cobbly<br>sandy loam,<br>extremely cobbly<br>loam.        | GM                         | A-1, A-2 | 40-70                                      | 50-60                                | 45-55 | 30-45 | 20-35 | 20-25                      | NP-5                     |
|  | 52-56 | Unweathered<br>bedrock.  | ---                        | ---      | ---  | ---                                  | ---   | ---   | ---   | ---                        | ---                      |
| Povey gravelly<br>loam-----                      | 0-14  | Gravelly loam----  | SM, GM,<br>SM-SC,<br>GM-GC | A-4      | 5-10                                       | 60-85                                | 55-80 | 40-70 | 35-50 | 20-30                      | NP-10                    |
|  | 14-35 | Very gravelly<br>loam, very<br>cobbly loam,<br>extremely<br>gravelly fine<br>sandy loam. | GM, GM-SC                  | A-2, A-1 | 10-50                                      | 30-60                                | 25-55 | 20-50 | 10-35 | 20-30                      | NP-10                    |
|  | 35-60 | Very cobbly loam,<br>extremely cobbly<br>sandy loam,<br>extremely cobbly<br>loam.        | GM                         | A-1, A-2 | 40-70                                      | 50-60                                | 45-55 | 30-45 | 20-35 | 20-25                      | NP-5                     |
|  | 60    | Unweathered<br>bedrock.  | ---                        | ---      | ---  | ---                                  | ---   | ---   | ---   | ---                        | ---                      |
| 95*:<br>Povey-----                               | 0-14  | Gravelly loam----  | SM, GM,<br>SM-SC,<br>GM-GC | A-4      | 5-10                                       | 60-85                                | 55-80 | 40-70 | 35-50 | 20-30                      | NP-10                    |
|  | 14-35 | Very gravelly<br>loam, very<br>cobbly loam,<br>extremely<br>gravelly fine<br>sandy loam. | GM, GM-SC                  | A-2, A-1 | 10-50                                      | 30-60                                | 25-55 | 20-50 | 10-35 | 20-30                      | NP-10                    |
|  | 35-60 | Very cobbly loam,<br>extremely cobbly<br>sandy loam,<br>extremely cobbly<br>loam.        | GM                         | A-1, A-2 | 40-70                                      | 50-60                                | 45-55 | 30-45 | 20-35 | 20-25                      | NP-5                     |
|  | 60    | Unweathered<br>bedrock.  | ---                        | ---      | ---  | ---                                  | ---   | ---   | ---   | ---                        | ---                      |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture   | Classification       |               | Frag-<br>ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|--------------------------|-------|--|----------------------|---------------|--|--------------------------------------|--------|--------|-------|------------------------|--------------------------|
|                          |       |  | Unified              | AASHTO        |  | 4                                    | 10     | 40     | 200   |                        |                          |
| 95*:<br>Vitale-----      | In    |  |                      |               |  |                                      |        |        |       |                        |                          |
|                          | 0-6   | Very gravelly loam.                                    | GM-GC, GC            | A-2, A-1      | 10-15                                  | 35-60                                | 30-55  | 25-45  | 20-35 | 25-35                  | 5-15                     |
|                          | 6-15  | Very gravelly clay loam, very cobbly clay loam.        | GC                   | A-6, A-2, A-7 | 10-45                                  | 35-65                                | 30-60  | 30-55  | 25-45 | 35-45                  | 15-25                    |
|                          | 15-23 | Very gravelly loam, very cobbly loam.                  | GM-GC, GC            | A-2           | 15-45                                  | 35-55                                | 35-50  | 30-45  | 25-35 | 25-35                  | 5-15                     |
|                          | 23    | Unweathered bedrock.                                   | ---                  | ---           | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| 96*:<br>Rehfield-----    | 0-11  | Sandy loam-----  | SM                   | A-2, A-4      | 0                                      | 90-100                               | 85-100 | 50-70  | 25-40 | 20-25                  | NP-5                     |
|                          | 11-42 | Sandy loam, loam, sandy clay loam.                     | SC, CL, SM-SC, CL-ML | A-4, A-6      | 0-5                                    | 100                                  | 90-100 | 55-85  | 35-55 | 25-40                  | 5-15                     |
|                          | 42-67 | Gravelly loamy sand, loamy sand, very fine sandy loam. | SM                   | A-1, A-2, A-4 | 0-15                                   | 75-100                               | 70-100 | 40-75  | 10-40 | 20-25                  | NP-5                     |
| Gooding-----             | 0-9   | Silt loam-----   | ML                   | A-4           | 0                                      | 95-100                               | 90-100 | 80-95  | 75-90 | 25-35                  | NP-10                    |
|                          | 9-34  | Silty clay, clay, silty clay loam.                     | CL, CH               | A-7           | 0                                      | 90-100                               | 90-100 | 85-100 | 75-95 | 45-65                  | 20-40                    |
|                          | 34-49 | Silty clay loam, clay loam.                            | CL, CH               | A-7           | 5-10                                   | 90-100                               | 90-100 | 80-95  | 75-90 | 40-55                  | 15-30                    |
|                          | 49-62 | Cemented-----  | ---                  | ---           | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
|                          | 62    | Unweathered bedrock.                                   | ---                  | ---           | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| 97*.<br>Riverwash        |       |  |                      |               |  |                                      |        |        |       |                        |                          |
| 98*:<br>Rock outcrop.    |       |  |                      |               |  |                                      |        |        |       |                        |                          |
| Adios-----               | 0-5   | Stony loam-----  | CL                   | A-6           | 5-10                                   | 85-100                               | 80-95  | 70-85  | 60-80 | 25-35                  | 10-15                    |
|                          | 5-23  | Clay, clay loam, gravelly clay.                        | CL, CH               | A-7           | 0-15                                   | 70-100                               | 65-100 | 60-90  | 55-80 | 40-60                  | 20-35                    |
|                          | 23-27 | Indurated-----   | ---                  | ---           | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
|                          | 27    | Weathered bedrock                                      | ---                  | ---           | ---                                    | ---                                  | ---    | ---    | ---   | ---                    | ---                      |
| 99-----<br>Rockybar      | 0-9   | Extremely cobbly loam.                                 | GM-GC                | A-2           | 60-75                                  | 40-60                                | 35-55  | 35-50  | 20-35 | 25-30                  | 5-10                     |
|                          | 9-31  | Extremely cobbly loam, extremely cobbly clay loam.     | GC, CL               | A-6, A-2      | 60-75                                  | 50-75                                | 45-70  | 45-65  | 25-55 | 30-35                  | 10-15                    |
|                          | 31-62 | Extremely cobbly sandy loam, extremely cobbly loam.    | GM-GC                | A-2, A-4      | 55-65                                  | 40-60                                | 30-55  | 20-50  | 10-40 | 25-30                  | 5-10                     |
| 100*.<br>Rubbleland      |       |  |                      |               |  |                                      |        |        |       |                        |                          |
| 101*:<br>Rubbleland.     |       |  |                      |               |  |                                      |        |        |       |                        |                          |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and<br>map symbol | Depth | USDA texture  | Classification  |                  | Frag-<br>ments<br>> 3<br>inches<br><br>Pct | Percentage passing<br>sieve number-- |        |       |       | Liquid<br>limit<br><br>Pct | Plas-<br>ticity<br>index |
|-----------------------------|-------|---|-----------------|------------------|--|--------------------------------------|--------|-------|-------|----------------------------|--------------------------|
|                             |       |   | Unified         | AASHTO           |  | 4                                    | 10     | 40    | 200   |                            |                          |
|                             | In    |   |                 |                  |  |                                      |        |       |       |                            |                          |
| 101*:<br>Milligan-----      | 0-8   | Very cobbly loam  | GM              | A-2, A-4         | 45-55                                      | 55-75                                | 50-70  | 45-65 | 30-50 | 20-25                      | NP-5                     |
|                             | 8-18  | Very gravelly<br>loam, extremely<br>cobbly loam,<br>extremely<br>gravelly loam. | GM, SM          | A-1, A-2         | 25-70                                      | 40-70                                | 35-45  | 20-45 | 20-35 | 20-25                      | NP-5                     |
|                             | 18-24 | Fragmental<br>material.   | GP              | A-1              | 60-80                                      | 5-15                                 | 0-10   | 0-5   | 0     | ---                        | NP                       |
|                             | 24    | Unweathered<br>bedrock.   | ---             | ---              | ---  | ---                                  | ---    | ---   | ---   | ---                        | ---                      |
| 102, 103-----<br>Simonton   | 0-12  | Loam-----   | CL-ML,<br>SM-SC | A-4              | 0  | 85-100                               | 75-100 | 60-95 | 45-75 | 20-30                      | 5-10                     |
|                             | 12-52 | Loam, clay loam,<br>sandy clay loam.  | CL, SC          | A-6, A-7         | 0  | 85-100                               | 75-100 | 60-95 | 45-75 | 30-45                      | 10-20                    |
|                             | 52-64 | Loamy coarse<br>sand, sandy<br>loam.  | SM              | A-2, A-1         | 0  | 85-100                               | 75-100 | 40-65 | 15-30 | ---                        | NP                       |
| 104*:<br>Simonton-----      | 0-11  | Silt loam-----  | CL-ML,<br>SM-SC | A-4              | 0  | 85-100                               | 75-100 | 60-95 | 45-75 | 20-30                      | 5-10                     |
|                             | 11-61 | Loam, clay loam,<br>sandy clay loam.  | CL, SC          | A-6, A-7         | 0  | 85-100                               | 75-100 | 60-95 | 45-75 | 30-45                      | 10-20                    |
| Bauscher-----               | 0-14  | Loam-----   | CL-ML           | A-4              | 0  | 90-100                               | 85-95  | 65-85 | 50-70 | 20-30                      | 5-10                     |
|                             | 14-37 | Loam, sandy clay<br>loam.   | CL, SC          | A-2, A-6         | 0  | 90-100                               | 85-95  | 45-70 | 40-55 | 25-35                      | 10-15                    |
|                             | 37-42 | Coarse sandy<br>loam, gravelly<br>coarse sandy<br>loam.                         | SM              | A-2              | 0  | 75-95                                | 65-85  | 40-60 | 25-30 | 20-25                      | NP-5                     |
|                             | 42    | Weathered bedrock   | ---             | ---              | ---  | ---                                  | ---    | ---   | ---   | ---                        | ---                      |
| 105*:<br>Starhope-----      | 0-9   | Loam-----   | CL-ML           | A-4              | 0  | 95-100                               | 75-95  | 65-90 | 50-70 | 25-30                      | 5-10                     |
|                             | 9-23  | Clay loam, cobbly<br>clay, gravelly<br>clay loam.                               | CH, CL          | A-7              | 0-45                                       | 70-100                               | 65-100 | 60-95 | 50-80 | 40-60                      | 20-40                    |
|                             | 23-26 | Clay loam,<br>gravelly clay<br>loam.  | CL              | A-6, A-7         | 0-10                                       | 70-100                               | 65-100 | 65-95 | 50-75 | 35-45                      | 15-25                    |
|                             | 26-30 | Unweathered<br>bedrock.   | ---             | ---              | ---  | ---                                  | ---    | ---   | ---   | ---                        | ---                      |
| Furshur-----                | 0-2   | Very channery<br>loam.  | GC, GM-GC       | A-2, A-6,<br>A-4 | 0-10                                       | 40-60                                | 35-55  | 25-50 | 20-40 | 20-30                      | 5-15                     |
|                             | 2-5   | Clay loam-----  | CL              | A-6              | 0-10                                       | 90-100                               | 85-95  | 60-85 | 50-65 | 30-40                      | 10-15                    |
|                             | 5-15  | Clay, gravelly<br>clay.   | CH              | A-7              | 0-10                                       | 70-90                                | 65-90  | 55-80 | 55-75 | 50-70                      | 30-45                    |
|                             | 15-20 | Indurated-----  | ---             | ---              | ---  | ---                                  | ---    | ---   | ---   | ---                        | ---                      |
|                             | 20    | Unweathered<br>bedrock.   | ---             | ---              | ---  | ---                                  | ---    | ---   | ---   | ---                        | ---                      |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and map symbol | Depth | USDA texture  | Classification |                  | Frag-<br>ments<br>> 3<br>inches | Percentage passing<br>sieve number-- |        |        |       | Liquid<br>limit | Plas-<br>ticity<br>index |
|--------------------------|-------|---|----------------|------------------|---------------------------------|--------------------------------------|--------|--------|-------|-----------------|--------------------------|
|                          |       |   | Unified        | AASHTO           |                                 | 4                                    | 10     | 40     | 200   |                 |                          |
|                          | In    |   |                |                  | Pct                             |                                      |        |        |       | Pct             |                          |
| 106*:<br>Starhope-----   | 0-10  | Loam-----   | CL-ML          | A-4              | 0                               | 95-100                               | 75-95  | 65-90  | 50-70 | 25-30           | 5-10                     |
|                          | 10-26 | Clay loam, cobbly<br>clay, gravelly<br>clay loam.                           | CH, CL         | A-7              | 0-45                            | 70-100                               | 65-100 | 60-95  | 50-80 | 40-60           | 20-40                    |
|                          | 26-30 | Clay loam,<br>gravelly clay<br>loam.  | CL             | A-6, A-7         | 0-10                            | 70-100                               | 65-100 | 65-95  | 50-75 | 35-45           | 15-25                    |
|                          | 30    | Unweathered<br>bedrock.   | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Peevywell-----           | 0-12  | Loam-----   | CL-ML          | A-4              | 0-10                            | 90-95                                | 85-95  | 75-90  | 50-65 | 25-30           | 5-10                     |
|                          | 12-22 | Clay loam-----  | CL             | A-6, A-7         | 0-10                            | 90-95                                | 85-95  | 75-90  | 60-75 | 35-50           | 15-25                    |
|                          | 22-30 | Silty clay, clay  | CL, CH         | A-7              | 0-10                            | 90-95                                | 85-95  | 70-90  | 70-90 | 40-60           | 20-35                    |
|                          | 30-44 | Indurated-----  | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
|                          | 44-61 | Very gravelly<br>sandy loam,<br>gravelly loamy<br>sand.                     | GM, SM         | A-1, A-2         | 10-30                           | 40-70                                | 35-70  | 25-55  | 10-25 | 20-25           | NP-5                     |
| Smelter-----             | 0-18  | Loam-----   | CL-ML          | A-4              | 0                               | 85-100                               | 85-100 | 75-95  | 55-75 | 25-30           | 5-10                     |
|                          | 18-35 | Clay loam, silty<br>clay loam.  | CL, CH         | A-7, A-6         | 0                               | 90-100                               | 90-100 | 90-100 | 80-95 | 35-55           | 15-30                    |
|                          | 35-61 | Clay loam, sandy<br>clay loam, loam.  | CL             | A-6, A-7         | 0-15                            | 80-95                                | 75-90  | 70-85  | 50-75 | 30-45           | 15-25                    |
| 107*:<br>Vitale-----     | 0-6   | Very gravelly<br>loam.  | GM-GC, GC      | A-2, A-1         | 10-15                           | 35-60                                | 30-55  | 25-45  | 20-35 | 25-35           | 5-15                     |
|                          | 6-15  | Very gravelly<br>clay loam, very<br>cobbly clay<br>loam.                    | GC             | A-6, A-2,<br>A-7 | 10-45                           | 35-65                                | 30-60  | 30-55  | 25-45 | 35-45           | 15-25                    |
|                          | 15-23 | Very gravelly<br>loam, very<br>cobbly loam.                                 | GM-GC, GC      | A-2              | 15-45                           | 35-55                                | 35-50  | 30-45  | 25-35 | 25-35           | 5-15                     |
|                          | 23    | Unweathered<br>bedrock.   | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| Blackspar-----           | 0-3   | Very cobbly loam  | GM, SM         | A-2, A-4         | 20-65                           | 45-85                                | 40-65  | 35-60  | 25-50 | 25-35           | NP-10                    |
|                          | 3-17  | Very cobbly loam,<br>extremely cobbly<br>loam, very<br>cobbly clay<br>loam. | GC             | A-2, A-6         | 25-65                           | 35-65                                | 30-65  | 25-65  | 20-50 | 30-40           | 10-20                    |
|                          | 17    | Unweathered<br>bedrock.   | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |
| 108*:<br>Vitale-----     | 0-6   | Very gravelly<br>loam.  | GM-GC, GC      | A-2, A-1         | 10-15                           | 35-60                                | 30-55  | 25-45  | 20-35 | 25-35           | 5-15                     |
|                          | 6-15  | Very gravelly<br>clay loam, very<br>cobbly clay<br>loam.                    | GC             | A-6, A-2,<br>A-7 | 10-45                           | 35-65                                | 30-60  | 30-55  | 25-45 | 35-45           | 15-25                    |
|                          | 15-23 | Very gravelly<br>loam, very<br>cobbly loam.                                 | GM-GC, GC      | A-2              | 15-45                           | 35-55                                | 35-50  | 30-45  | 25-35 | 25-35           | 5-15                     |
|                          | 23    | Unweathered<br>bedrock.   | ---            | ---              | ---                             | ---                                  | ---    | ---    | ---   | ---             | ---                      |

See footnote at end of table.

TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and<br>map symbol | Depth     | USDA texture   | Classification             |                  | Frag-<br>ments<br>> 3<br>inches<br><br>Pct | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit<br><br>Pct | Plas-<br>ticity<br>index |
|-----------------------------|-----------|--|----------------------------|------------------|--|--------------------------------------|-------|-------|-------|----------------------------|--------------------------|
|                             |           |  | Unified                    | AASHTO           |  | 4                                    | 10    | 40    | 200   |                            |                          |
|                             | <u>In</u> |  |                            |                  |  |                                      |       |       |       |                            |                          |
| 108*:<br>Milligan-----      | 0-8       | Very cobbly loam   | GM                         | A-2, A-4         | 45-55                                      | 55-75                                | 50-70 | 45-65 | 30-50 | 20-25                      | NP-5                     |
|                             | 8-18      | Very gravelly<br>loam, extremely<br>cobbly loam,<br>extremely<br>gravelly loam.          | GM, SM                     | A-1, A-2         | 25-70                                      | 40-70                                | 35-45 | 20-45 | 20-35 | 20-25                      | NP-5                     |
|                             | 18-24     | Fragmental<br>material.  | GP                         | A-1              | 60-80                                      | 5-15                                 | 0-10  | 0-5   | 0     | ---                        | NP                       |
|                             | 24        | Unweathered<br>bedrock.  | ---                        | ---              | ---  | ---                                  | ---   | ---   | ---   | ---                        | ---                      |
| 109*:<br>Vitale-----        | 0-6       | Very gravelly<br>loam.   | GM-GC, GC                  | A-2, A-1         | 10-15                                      | 35-60                                | 30-55 | 25-45 | 20-35 | 25-35                      | 5-15                     |
|                             | 6-15      | Very gravelly<br>clay loam, very<br>cobbly clay<br>loam.                                 | GC                         | A-6, A-2,<br>A-7 | 10-45                                      | 35-65                                | 30-60 | 30-55 | 25-45 | 35-45                      | 15-25                    |
|                             | 15-23     | Very gravelly<br>loam, very<br>cobbly loam.  | GM-GC, GC                  | A-2              | 15-45                                      | 35-55                                | 35-50 | 30-45 | 25-35 | 25-35                      | 5-15                     |
|                             | 23        | Unweathered<br>bedrock.  | ---                        | ---              | ---  | ---                                  | ---   | ---   | ---   | ---                        | ---                      |
| Povey-----                  | 0-14      | Gravelly loam----  | SM, GM,<br>SM-SC,<br>GM-GC | A-4              | 5-10                                       | 60-85                                | 55-80 | 40-70 | 35-50 | 20-30                      | NP-10                    |
|                             | 14-35     | Very gravelly<br>loam, very<br>cobbly loam,<br>extremely<br>gravelly fine<br>sandy loam. | GM, GM-GC                  | A-2, A-1         | 10-50                                      | 30-60                                | 25-55 | 20-50 | 10-35 | 20-30                      | NP-10                    |
|                             | 35-60     | Very cobbly loam,<br>extremely cobbly<br>sandy loam,<br>extremely cobbly<br>loam.        | GM                         | A-1, A-2         | 40-70                                      | 50-60                                | 45-55 | 30-45 | 20-35 | 20-25                      | NP-5                     |
|                             | 60        | Unweathered<br>bedrock.  | ---                        | ---              | ---  | ---                                  | ---   | ---   | ---   | ---                        | ---                      |
| 110*:<br>Winu-----          | 0-13      | Stony loam-----  | SM-SC,<br>CL-ML            | A-4              | 5-15                                       | 75-85                                | 70-80 | 65-75 | 45-55 | 20-30                      | 5-10                     |
|                             | 13-35     | Gravelly loam,<br>gravelly sandy<br>clay loam,<br>gravelly clay<br>loam.                 | GC, SC                     | A-6              | 5-10                                       | 65-75                                | 55-75 | 45-65 | 35-45 | 25-35                      | 10-20                    |
|                             | 35-39     | Unweathered<br>bedrock.  | ---                        | ---              | ---  | ---                                  | ---   | ---   | ---   | ---                        | ---                      |
| Rock outcrop.               |           |  |                            |                  |  |                                      |       |       |       |                            |                          |

See footnote at end of table.



TABLE 13.--ENGINEERING INDEX PROPERTIES--Continued

| Soil name and<br>map symbol | Depth     | USDA texture   | Classification  |                  | Frag-<br>ments<br>> 3<br>inches<br>Pct | Percentage passing<br>sieve number-- |       |       |       | Liquid<br>limit<br>Pct | Plas-<br>ticity<br>index |
|-----------------------------|-----------|--|-----------------|------------------|--|--------------------------------------|-------|-------|-------|------------------------|--------------------------|
|                             |           |  | Unified         | AASHTO           |  | 4                                    | 10    | 40    | 200   |                        |                          |
| 111*:<br>Winu-----          | <u>In</u> |  |                 |                  |  |                                      |       |       |       |                        |                          |
|                             | 0-13      | Stony loam-----  | SM-SC,<br>CL-ML | A-4              | 5-15                                   | 75-85                                | 70-80 | 65-75 | 45-55 | 20-30                  | 5-10                     |
|                             | 13-35     | Gravelly loam,<br>gravelly sandy<br>clay loam,<br>gravelly clay<br>loam. | GC, SC          | A-6              | 5-10                                   | 65-75                                | 55-75 | 45-65 | 35-45 | 25-35                  | 10-20                    |
|                             | 35-39     | Unweathered<br>bedrock.  | ---             | ---              | ---                                    | ---                                  | ---   | ---   | ---   | ---                    | ---                      |
| Gaib-----                   | 0-5       | Very gravelly<br>loam.   | GM-GC, GC       | A-2, A-4,<br>A-6 | 0-25                                   | 30-55                                | 25-50 | 15-40 | 10-40 | 25-35                  | 5-15                     |
|                             | 5-13      | Very cobbly clay<br>loam, very stony<br>sandy clay loam.                 | GC, SC          | A-2, A-6         | 30-50                                  | 55-70                                | 50-70 | 40-60 | 20-50 | 35-50                  | 15-25                    |
|                             | 13        | Unweathered<br>bedrock.  | ---             | ---              | ---                                    | ---                                  | ---   | ---   | ---   | ---                    | ---                      |

\* See description of the map unit for composition and behavior characteristics of the map unit.

TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS

(The symbol < means less than; > means more than. Entries under "Erosion factors--T" apply to the entire profile. Entries under "Wind erodibility group" and "Organic matter" apply only to the surface layer. Absence of an entry indicates that data were not available or were not estimated)

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               | K                  | T |                                   | Pct               |
| 1-----<br>Adamson           | 0-5   | 10-18 | 0.6-2.0      | 0.16-0.18                      | 6.6-7.8          | <2       | Low-----                      | 0.28               | 2 | 5                                 | 1-3               |
|                             | 5-28  | 8-18  | 0.6-2.0      | 0.11-0.18                      | 6.6-7.8          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 28-61 | 0-5   | >20          | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 2*:<br>Adios-----           | 0-5   | 20-27 | 0.6-2.0      | 0.16-0.19                      | 6.6-7.3          | <2       | Low-----                      | 0.20               | 1 | 8                                 | 1-3               |
|                             | 5-23  | 35-60 | <0.06        | 0.15-0.17                      | 6.6-8.4          | <2       | High-----                     | 0.28               |   |                                   |                   |
|                             | 23-27 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 27    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| Gooding-----                | 0-9   | 10-20 | 0.2-0.6      | 0.19-0.21                      | 6.6-7.3          | <2       | Low-----                      | 0.37               | 1 | 6                                 | 1-3               |
|                             | 9-34  | 35-59 | <0.06        | 0.14-0.21                      | 6.6-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 34-49 | 27-40 | 0.06-0.2     | 0.14-0.21                      | 7.4-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 49-62 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 62    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| Bostrum-----                | 0-4   | 15-25 | 0.2-0.6      | 0.14-0.18                      | 6.6-7.3          | <2       | Low-----                      | 0.28               | 2 | 6                                 | <1                |
|                             | 4-28  | 35-50 | <0.06        | 0.14-0.17                      | 6.6-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 28-32 | 30-40 | 0.06-0.2     | 0.19-0.21                      | 6.6-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 32-36 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 3*:<br>Adios-----           | 0-5   | 20-27 | 0.6-2.0      | 0.16-0.19                      | 6.6-7.3          | <2       | Low-----                      | 0.20               | 1 | 8                                 | 1-3               |
|                             | 5-23  | 35-60 | <0.06        | 0.16-0.17                      | 6.6-8.4          | <2       | High-----                     | 0.28               |   |                                   |                   |
|                             | 23-27 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 27    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| Adios, cool-----            | 0-7   | 20-27 | 0.6-2.0      | 0.16-0.18                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 1 | 6                                 | 1-3               |
|                             | 7-25  | 35-60 | <0.06        | 0.15-0.17                      | 6.6-8.4          | <2       | High-----                     | 0.28               |   |                                   |                   |
|                             | 25-28 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 28-32 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 4-----<br>Balaam            | 0-14  | 10-15 | 2.0-6.0      | 0.07-0.10                      | 6.1-7.3          | <2       | Low-----                      | 0.15               | 3 | 3                                 | 1-3               |
|                             | 14-21 | 5-10  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 21-61 | 0-5   | >20          | 0.01-0.03                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 5-----<br>Balaam            | 0-14  | 10-15 | 2.0-6.0      | 0.05-0.08                      | 6.1-7.3          | <2       | Low-----                      | 0.10               | 5 | 6                                 | 1-3               |
|                             | 14-21 | 5-10  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 21-61 | 0-5   | >20          | 0.01-0.03                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 6*:<br>Balaam-----          | 0-21  | 10-15 | 2.0-6.0      | 0.05-0.08                      | 6.1-7.3          | <2       | Low-----                      | 0.10               | 5 | 6                                 | 1-3               |
|                             | 21-35 | 5-10  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 35-63 | 0-5   | >20          | 0.01-0.03                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| Adamson-----                | 0-5   | 8-15  | 2.0-6.0      | 0.11-0.13                      | 6.6-7.8          | <2       | Low-----                      | 0.42               | 2 | 3                                 | 1-2               |
|                             | 5-28  | 8-18  | 0.6-2.0      | 0.11-0.18                      | 6.6-7.8          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 28-61 | 0-5   | >20          | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 7*:<br>Balaam-----          | 0-10  | 12-18 | 2.0-6.0      | 0.08-0.13                      | 5.1-6.0          | <2       | Low-----                      | 0.10               | 2 | 3                                 | 2-3               |
|                             | 10-17 | 7-12  | 2.0-6.0      | 0.06-0.08                      | 5.1-5.5          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 17-60 | 0-10  | >20          | 0.01-0.04                      | 5.1-5.5          | <2       | Low-----                      | 0.02               |   |                                   |                   |

See footnote at end of table.



TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 7*:                         |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Adamson-----                | 0-9   | 12-18 | 2.0-6.0      | 0.11-0.14                      | 6.1-6.5          | <2       | Low-----                      | 0.28               | 3 | 3                                 | 2-3               |
|                             | 9-22  | 14-18 | 0.6-2.0      | 0.14-0.16                      | 6.1-6.5          | <2       | Low-----                      | 0.32               |   |                                   |                   |
|                             | 22-48 | 0-5   | >20          | 0.01-0.03                      | 6.1-7.3          | <2       | Low-----                      | 0.02               |   |                                   |                   |
|                             | 48-60 | 0-5   | >20          | 0.01-0.03                      | 6.6-7.3          | <2       | Low-----                      | 0.02               |   |                                   |                   |
| 8*:                         |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Balaam-----                 | 0-10  | 12-18 | 2.0-6.0      | 0.08-0.13                      | 5.1-6.0          | <2       | Low-----                      | 0.10               | 2 | 3                                 | 2-3               |
|                             | 10-17 | 5-12  | 2.0-6.0      | 0.06-0.08                      | 5.1-5.5          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 17-60 | 0-10  | >20          | 0.01-0.03                      | 5.1-5.5          | <2       | Low-----                      | 0.02               |   |                                   |                   |
| Adamson-----                | 0-9   | 12-18 | 2.0-6.0      | 0.11-0.14                      | 6.1-6.5          | <2       | Low-----                      | 0.28               | 3 | 3                                 | 2-3               |
|                             | 9-22  | 14-18 | 0.6-2.0      | 0.14-0.16                      | 6.1-6.5          | <2       | Low-----                      | 0.32               |   |                                   |                   |
|                             | 22-48 | 0-5   | >20          | 0.01-0.03                      | 6.1-7.3          | <2       | Low-----                      | 0.02               |   |                                   |                   |
|                             | 48-60 | 0-5   | >20          | 0.01-0.03                      | 6.6-7.3          | <2       | Low-----                      | 0.02               |   |                                   |                   |
| Riverwash.                  |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 9, 10-----                  | 0-11  | 15-20 | 0.6-2.0      | 0.19-0.21                      | 6.1-7.3          | <2       | Low-----                      | 0.43               | 5 | 5                                 | 2-3               |
| Bancroft                    | 11-42 | 18-32 | 0.6-2.0      | 0.19-0.21                      | 6.1-8.4          | <2       | Low-----                      | 0.43               |   |                                   |                   |
|                             | 42-80 | 5-18  | 0.6-2.0      | 0.06-0.16                      | 7.4-8.4          | <2       | Low-----                      | 0.24               |   |                                   |                   |
| 11-----                     | 0-6   | ---   | 0.6-2.0      | 0.22-0.30                      | 6.6-7.8          | <2       | Low-----                      | ---                | 5 | 8                                 | 60-85             |
| Bickett                     | 6-11  | ---   | 0.6-2.0      | 0.22-0.30                      | 7.4-7.8          | <2       | Low-----                      | ---                |   |                                   |                   |
|                             | 11-40 | 24-35 | 0.2-0.6      | 0.19-0.21                      | 7.4-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 40-61 | 20-30 | 0.6-2.0      | 0.15-0.18                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
| 12*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Blackspar-----              | 0-3   | 10-20 | 0.6-2.0      | 0.05-0.07                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 1 | 8                                 | 1-2               |
|                             | 3-17  | 20-30 | 0.6-2.0      | 0.04-0.06                      | 6.6-7.3          | <2       | Low-----                      | 0.20               |   |                                   |                   |
|                             | 17    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 13*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Blackspot-----              | 0-7   | 10-18 | 2.0-6.0      | 0.06-0.10                      | 7.4-8.4          | <2       | Low-----                      | 0.17               | 1 | 5                                 | 1-2               |
|                             | 7-14  | 10-18 | 2.0-6.0      | 0.06-0.10                      | 7.9-9.0          | <2       | Low-----                      | 0.20               |   |                                   |                   |
|                             | 14-19 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 19    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Prudy-----                  | 0-10  | 18-24 | 0.6-2.0      | 0.15-0.17                      | 6.6-7.8          | <2       | Low-----                      | 0.28               | 4 | 5                                 | 3-5               |
|                             | 10-42 | 18-27 | 0.6-2.0      | 0.10-0.17                      | 7.4-9.0          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 42-50 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 50    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 14*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Bostrum-----                | 0-4   | 15-25 | 0.2-0.6      | 0.14-0.18                      | 6.6-7.3          | <2       | Low-----                      | 0.28               | 2 | 6                                 | <1                |
|                             | 4-32  | 35-50 | <0.06        | 0.14-0.17                      | 6.6-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 32-36 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Yuttrue-----                | 0-7   | 40-60 | <0.06        | 0.14-0.16                      | 6.6-7.3          | <2       | High-----                     | 0.37               | 5 | 4                                 | .5-1              |
|                             | 7-35  | 40-60 | <0.06        | 0.14-0.16                      | 6.6-7.8          | <2       | High-----                     | 0.28               |   |                                   |                   |
|                             | 35-63 | 30-40 | 0.06-0.2     | 0.19-0.21                      | 7.4-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |

See footnote at end of table.

TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 14*:<br>Hamrub-----         | 0-10  | 16-20 | 0.6-2.0      | 0.19-0.21                      | 6.6-7.3          | <2       | Low-----                      | 0.43               | 4 | 6                                 | 1-2               |
|                             | 10-41 | 20-32 | 0.2-0.6      | 0.19-0.21                      | 6.6-8.4          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 41-43 | 16-20 | ---          | 0.14-0.18                      | 7.4-8.4          | <2       | Low-----                      | 0.37               |   |                                   |                   |
|                             | 43-48 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 48    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 15, 16, 17-----<br>Bringmee | 0-7   | 15-25 | 0.6-2.0      | 0.13-0.19                      | 5.6-7.3          | <2       | Moderate                      | 0.32               | 5 | 5                                 | 1-4               |
|                             | 7-47  | 20-35 | 0.2-0.6      | 0.14-0.20                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 47-61 | 0-15  | 2.0-20       | 0.02-0.08                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 18*:<br>Bringmee-----       | 0-7   | 15-25 | 0.6-2.0      | 0.13-0.19                      | 5.6-7.3          | <2       | Moderate                      | 0.32               | 5 | 5                                 | 1-4               |
|                             | 7-47  | 20-35 | 0.2-0.6      | 0.14-0.20                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 47-61 | 0-15  | 2.0-20       | 0.02-0.08                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| Hutton-----                 | 0-4   | 27-35 | 0.2-0.6      | 0.18-0.20                      | 6.6-7.3          | <2       | Moderate                      | 0.32               | 5 | 6                                 | 2-4               |
|                             | 4-19  | 28-40 | 0.2-0.6      | 0.16-0.18                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 19-62 | 40-60 | <0.06        | 0.12-0.16                      | 6.6-7.8          | <2       | High-----                     | 0.24               |   |                                   |                   |
| 19*:<br>Bringmee-----       | 0-11  | 15-25 | 0.6-2.0      | 0.09-0.12                      | 5.6-7.3          | <2       | Moderate                      | 0.24               | 5 | 5                                 | 1-4               |
|                             | 11-33 | 20-35 | 0.2-0.6      | 0.14-0.20                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 33-61 | 0-15  | 2.0-20       | 0.02-0.08                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| Little Wood-----            | 0-13  | 15-25 | 2.0-6.0      | 0.09-0.11                      | 6.1-6.5          | <2       | Low-----                      | 0.17               | 2 | 5                                 | 2-4               |
|                             | 13-26 | 20-35 | 0.6-2.0      | 0.10-0.12                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 26-32 | 5-15  | 6.0-20       | 0.04-0.06                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 32-61 | 0-5   | >20          | 0.02-0.04                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 20-----<br>Bruneel          | 0-14  | 10-25 | 0.6-2.0      | 0.16-0.18                      | 6.6-8.4          | <2       | Low-----                      | 0.28               | 2 | 5                                 | 2-3               |
|                             | 14-23 | 10-18 | 0.6-2.0      | 0.11-0.18                      | 6.6-7.8          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 23-61 | 0-5   | >20          | 0.02-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 21, 22-----<br>Carey Lake   | 0-12  | 12-18 | 0.6-2.0      | 0.16-0.18                      | 6.6-7.3          | <2       | Low-----                      | 0.32               | 5 | 5                                 | 2-3               |
|                             | 12-20 | 22-33 | 0.2-0.6      | 0.14-0.20                      | 6.6-7.3          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 20-42 | 15-28 | 0.6-2.0      | 0.12-0.18                      | 6.6-7.8          | <2       | Low-----                      | 0.32               |   |                                   |                   |
|                             | 42-72 | 10-18 | 0.6-2.0      | 0.12-0.19                      | 6.6-8.4          | <2       | Low-----                      | 0.28               |   |                                   |                   |
| 23*:<br>Cox-----            | 0-3   | 8-15  | 2.0-6.0      | 0.07-0.09                      | 6.1-7.3          | <2       | Low-----                      | 0.24               | 1 | 3                                 | 1-2               |
|                             | 3-12  | 10-18 | 2.0-6.0      | 0.05-0.08                      | 6.1-7.8          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 12-16 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rehfield-----               | 0-3   | 4-10  | 6.0-20       | 0.07-0.10                      | 6.6-7.3          | <2       | Low-----                      | 0.20               | 5 | 2                                 | 1-2               |
|                             | 3-42  | 18-31 | 0.6-2.0      | 0.13-0.17                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 42-67 | 8-13  | 0.6-6.0      | 0.06-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 24*:<br>Deerhorn-----       | 0-9   | 10-15 | 2.0-6.0      | 0.13-0.15                      | 6.1-7.8          | <2       | Low-----                      | 0.24               | 2 | 3                                 | 1-3               |
|                             | 9-21  | 18-30 | 0.2-0.6      | 0.14-0.18                      | 7.4-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 21-24 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 24-28 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rehfield-----               | 0-11  | 10-17 | 2.0-6.0      | 0.09-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.28               | 5 | 3                                 | 1-2               |
|                             | 11-42 | 18-31 | 0.6-2.0      | 0.13-0.17                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 42-67 | 8-13  | 0.6-6.0      | 0.06-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |

See footnote at end of table.



TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 25*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Deerhorn-----               | 0-9   | 10-15 | 2.0-6.0      | 0.13-0.15                      | 6.1-7.8          | <2       | Low-----                      | 0.24               | 2 | 3                                 | 1-3               |
|                             | 9-21  | 18-30 | 0.2-0.6      | 0.14-0.18                      | 7.4-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 21-24 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 24-28 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Wildors-----                | 0-9   | 10-17 | 2.0-6.0      | 0.05-0.07                      | 6.6-7.3          | <2       | Low-----                      | 0.10               | 2 | 3                                 | 1-2               |
|                             | 9-21  | 11-20 | 0.6-2.0      | 0.05-0.11                      | 7.4-8.4          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 21-24 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 24-28 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 26*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Deerhorn-----               | 0-8   | 10-15 | 2.0-6.0      | 0.13-0.15                      | 6.1-7.8          | <2       | Low-----                      | 0.24               | 2 | 3                                 | 1-3               |
|                             | 8-21  | 18-30 | 0.2-0.6      | 0.14-0.18                      | 7.4-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 21-28 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 28-32 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Wildors-----                | 0-10  | 10-17 | 2.0-6.0      | 0.05-0.07                      | 6.6-7.3          | <2       | Low-----                      | 0.10               | 2 | 3                                 | 1-2               |
|                             | 10-22 | 11-20 | 0.6-2.0      | 0.05-0.11                      | 7.4-8.4          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 22-24 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 24-28 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Trevino-----                | 0-12  | 12-18 | 0.6-2.0      | 0.08-0.10                      | 6.6-8.4          | <2       | Low-----                      | 0.15               | 1 | 5                                 | 1-2               |
|                             | 12-16 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 27*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Dollarhide-----             | 0-7   | 8-18  | 2.0-6.0      | 0.06-0.11                      | 6.6-7.8          | <2       | Low-----                      | 0.17               | 1 | 8                                 | 1-3               |
|                             | 7-13  | 8-18  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 13    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 28, 29-----                 | 0-14  | 15-25 | 0.6-2.0      | 0.10-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.20               | 5 | 6                                 | 1-3               |
| Drage                       | 14-20 | 28-35 | 0.2-0.6      | 0.08-0.12                      | 6.6-7.8          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 20-61 | 10-25 | 0.6-2.0      | 0.04-0.06                      | 7.4-8.4          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 30-----                     | 0-14  | 15-25 | 0.6-2.0      | 0.10-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.20               | 5 | 6                                 | 1-3               |
| Drage                       | 14-30 | 28-35 | 0.2-0.6      | 0.08-0.12                      | 6.6-7.8          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 30-61 | 10-25 | 0.6-2.0      | 0.04-0.06                      | 7.4-8.4          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 31-----                     | 0-16  | 15-25 | 0.6-2.0      | 0.08-0.10                      | 6.6-7.8          | <2       | Low-----                      | 0.15               | 5 | 6                                 | 1-3               |
| Drage                       | 16-41 | 28-35 | 0.2-0.6      | 0.08-0.12                      | 6.6-7.8          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 41-61 | 10-25 | 0.6-2.0      | 0.04-0.06                      | 7.4-8.4          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 32*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Earcree-----                | 0-37  | 10-18 | 2.0-6.0      | 0.10-0.13                      | 5.6-7.3          | <2       | Low-----                      | 0.10               | 5 | 3                                 | 3-6               |
|                             | 37-52 | 5-15  | 2.0-6.0      | 0.05-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 52-70 | 5-10  | 2.0-6.0      | 0.05-0.07                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| Lockman-----                | 0-15  | 5-15  | 2.0-6.0      | 0.13-0.15                      | 5.6-7.3          | <2       | Low-----                      | 0.20               | 3 | 5                                 | 2-4               |
|                             | 15-23 | 5-15  | 2.0-6.0      | 0.11-0.13                      | 5.6-7.3          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 23-44 | 3-12  | 2.0-6.0      | 0.09-0.11                      | 5.6-7.3          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 44-58 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 58    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 33*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Earcree-----                | 0-37  | 10-18 | 2.0-6.0      | 0.10-0.13                      | 5.6-7.3          | <2       | Low-----                      | 0.10               | 5 | 3                                 | 3-6               |
|                             | 37-52 | 5-15  | 2.0-6.0      | 0.05-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 52-70 | 5-10  | 2.0-6.0      | 0.05-0.07                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |

See footnote at end of table.

TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 33*:<br>Moonstone-----      | 0-26  | 10-15 | 2.0-6.0      | 0.07-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.10               | 2 | 4                                 | 1-3               |
|                             | 26-34 | 10-15 | 2.0-6.0      | 0.08-0.13                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 34    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 34*:<br>Earcree-----        | 0-37  | 10-18 | 2.0-6.0      | 0.10-0.13                      | 5.6-7.3          | <2       | Low-----                      | 0.10               | 5 | 3                                 | 3-6               |
|                             | 37-52 | 5-15  | 2.0-6.0      | 0.05-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 52-70 | 5-15  | 2.0-6.0      | 0.05-0.07                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| Moonstone-----              | 0-21  | 10-15 | 2.0-6.0      | 0.07-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.10               | 2 | 4                                 | 1-3               |
|                             | 21-32 | 10-15 | 2.0-6.0      | 0.08-0.13                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 32-36 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 35*:<br>Elkcreek-----       | 0-11  | 15-25 | 0.6-2.0      | 0.16-0.18                      | 6.1-7.3          | <2       | Low-----                      | 0.32               | 2 | 6                                 | 1-3               |
|                             | 11-34 | 20-35 | 0.2-0.6      | 0.12-0.17                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 34-38 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Gaib-----                   | 0-4   | 15-25 | 0.6-2.0      | 0.05-0.07                      | 5.6-6.0          | <2       | Low-----                      | 0.24               | 1 | 6                                 | 1-3               |
|                             | 4-12  | 24-35 | 0.2-0.6      | 0.10-0.16                      | 6.1-7.3          | <2       | Moderate                      | 0.20               |   |                                   |                   |
|                             | 12-16 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 36*:<br>Elkcreek-----       | 0-11  | 15-25 | 0.6-2.0      | 0.16-0.18                      | 6.1-7.3          | <2       | Low-----                      | 0.32               | 2 | 6                                 | 1-3               |
|                             | 11-34 | 20-35 | 0.2-0.6      | 0.12-0.17                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 34-38 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Polecreek-----              | 0-4   | 20-26 | 0.6-2.0      | 0.08-0.11                      | 6.1-7.3          | <2       | Low-----                      | 0.15               | 1 | 8                                 | 2-3               |
|                             | 4-6   | 35-60 | 0.06-0.2     | 0.07-0.10                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 6-13  | 40-60 | <0.06        | 0.07-0.10                      | 6.1-7.3          | <2       | Moderate                      | 0.05               |   |                                   |                   |
|                             | 13    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 37*:<br>Elksel-----         | 0-10  | 22-27 | 0.2-0.6      | 0.08-0.11                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 2 | 8                                 | 2-5               |
|                             | 10-33 | 35-55 | 0.06-0.2     | 0.07-0.09                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 33-45 | 35-45 | 0.06-0.2     | 0.04-0.06                      | 6.6-7.3          | <2       | High-----                     | 0.28               |   |                                   |                   |
|                             | 45    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Friedman-----               | 0-5   | 16-25 | 0.6-2.0      | 0.11-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.17               | 4 | 8                                 | 3-5               |
|                             | 5-24  | 16-30 | 0.6-2.0      | 0.11-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 24-47 | 35-45 | 0.06-0.2     | 0.09-0.11                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 47-54 | 15-25 | 0.6-2.0      | 0.07-0.09                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 54    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Starhope-----               | 0-3   | 28-38 | 0.2-0.6      | 0.04-0.06                      | 6.1-7.3          | <2       | Moderate                      | 0.24               | 2 | 8                                 | 1-3               |
|                             | 3-19  | 35-50 | 0.06-0.2     | 0.09-0.15                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 19-22 | 35-40 | 0.06-0.2     | 0.09-0.15                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 22-26 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 38*:<br>Elksel-----         | 0-12  | 15-27 | 0.6-2.0      | 0.13-0.15                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 5                                 | 2-5               |
|                             | 12-42 | 35-55 | 0.06-0.2     | 0.08-0.11                      | 6.6-7.3          | <2       | High-----                     | 0.20               |   |                                   |                   |
|                             | 42-54 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 54    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Peevywell-----              | 0-5   | 18-27 | 0.6-2.0      | 0.14-0.16                      | 6.6-7.3          | <2       | Low-----                      | 0.28               | 2 | 5                                 | 2-5               |
|                             | 5-13  | 20-30 | 0.2-0.6      | 0.14-0.16                      | 6.6-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 13-31 | 35-55 | 0.06-0.2     | 0.14-0.16                      | 6.6-7.3          | <2       | High-----                     | 0.20               |   |                                   |                   |
|                             | 31-40 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 40    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |

See footnote at end of table.



TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               | K                  | T |                                   | Pct               |
| 38*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Furshur-----                | 0-2   | 19-25 | 0.6-2.0      | 0.11-0.14                      | 6.6-7.3          | <2       | Low-----                      | 0.10               | 1 | 6                                 | 1-3               |
|                             | 2-5   | 27-32 | 0.2-0.6      | 0.18-0.21                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 5-15  | 50-60 | <0.06        | 0.11-0.15                      | 6.6-7.8          | <2       | High-----                     | 0.17               |   |                                   |                   |
|                             | 15-20 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 20    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 39*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Elksel-----                 | 0-10  | 22-27 | 0.2-0.6      | 0.08-0.11                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 8                                 | 2-5               |
|                             | 10-33 | 35-55 | 0.06-0.2     | 0.07-0.09                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 33-45 | 35-45 | 0.06-0.2     | 0.04-0.06                      | 6.6-7.3          | <2       | High-----                     | 0.28               |   |                                   |                   |
|                             | 45    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Starhope-----               | 0-3   | 28-38 | 0.2-0.6      | 0.04-0.06                      | 6.1-7.3          | <2       | Moderate                      | 0.24               | 2 | 8                                 | 1-3               |
|                             | 3-19  | 35-50 | 0.06-0.2     | 0.09-0.15                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 19-22 | 35-40 | 0.06-0.2     | 0.09-0.15                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 22-26 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 40*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Friedman-----               | 0-5   | 16-25 | 0.6-2.0      | 0.11-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.17               | 4 | 8                                 | 3-5               |
|                             | 5-24  | 16-30 | 0.6-2.0      | 0.11-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 24-47 | 35-45 | 0.06-0.2     | 0.09-0.11                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 47-54 | 15-25 | 0.6-2.0      | 0.07-0.09                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 54    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Elksel-----                 | 0-10  | 22-27 | 0.2-0.6      | 0.08-0.11                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 8                                 | 2-5               |
|                             | 10-33 | 35-55 | 0.06-0.2     | 0.07-0.09                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 33-45 | 35-45 | 0.06-0.2     | 0.04-0.06                      | 6.6-7.3          | <2       | High-----                     | 0.28               |   |                                   |                   |
|                             | 45    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Winridge-----               | 0-4   | 27-35 | 0.2-0.6      | 0.17-0.18                      | 6.1-7.3          | <2       | Moderate                      | 0.24               | 2 | 6                                 | 2-4               |
|                             | 4-16  | 40-60 | <0.06        | 0.10-0.16                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 16-23 | 27-40 | 0.2-0.6      | 0.10-0.18                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 23    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 41*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Gaib-----                   | 0-5   | 15-25 | 0.6-2.0      | 0.05-0.07                      | 5.6-6.0          | <2       | Low-----                      | 0.24               | 1 | 6                                 | 1-3               |
|                             | 5-13  | 24-35 | 0.2-0.6      | 0.10-0.16                      | 6.1-7.3          | <2       | Moderate                      | 0.20               |   |                                   |                   |
|                             | 13    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 42-----                     |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Gimlett                     | 0-3   | 13-17 | 0.6-2.0      | 0.05-0.08                      | 5.6-7.3          | <2       | Low-----                      | 0.15               | 5 | 6                                 | 1-3               |
|                             | 3-27  | 14-19 | 0.6-2.0      | 0.05-0.10                      | 5.6-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 27-49 | 8-15  | >20          | 0.02-0.05                      | 5.6-7.3          | <2       | Low-----                      | 0.02               |   |                                   |                   |
|                             | 49-63 | 0-8   | >20          | 0.02-0.03                      | 5.6-7.3          | <2       | Low-----                      | 0.02               |   |                                   |                   |
| 43*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Gooding-----                | 0-9   | 10-20 | 0.2-0.6      | 0.19-0.21                      | 6.6-7.3          | <2       | Low-----                      | 0.37               | 1 | 6                                 | 1-3               |
|                             | 9-34  | 35-59 | <0.06        | 0.14-0.21                      | 6.6-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 34-49 | 27-40 | 0.06-0.2     | 0.14-0.21                      | 7.4-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 49-62 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 62    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Gooding, eroded             | 0-2   | 28-35 | 0.2-0.6      | 0.12-0.16                      | 6.6-7.8          | <2       | Moderate                      | 0.24               | 3 | 8                                 | 1-3               |
|                             | 2-42  | 35-59 | <0.06        | 0.14-0.21                      | 6.6-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 42-62 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 62-66 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |

See footnote at end of table.

TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 43*:<br>Hamrub-----         | 0-10  | 16-20 | 0.6-2.0      | 0.19-0.21                      | 6.6-7.3          | <2       | Low-----                      | 0.43               | 4 | 6                                 | 1-2               |
|                             | 10-41 | 20-32 | 0.2-0.6      | 0.19-0.21                      | 6.6-8.4          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 41-43 | 16-20 | 0.6-2.0      | 0.14-0.18                      | 7.4-8.4          | <2       | Low-----                      | 0.37               |   |                                   |                   |
|                             | 43-48 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 48    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 44-----<br>Goodington       | 0-10  | 15-25 | 0.2-0.6      | 0.18-0.22                      | 6.1-7.3          | <2       | Low-----                      | 0.43               | 2 | 5                                 | 1-3               |
|                             | 10-26 | 40-55 | <0.06        | 0.16-0.18                      | 6.6-7.8          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 26-56 | 25-40 | 0.2-0.6      | 0.16-0.18                      | 7.4-8.4          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 56    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 45*:<br>Goodington-----     | 0-15  | 15-25 | 0.2-0.6      | 0.18-0.22                      | 6.1-7.3          | <2       | Low-----                      | 0.43               | 2 | 5                                 | 1-3               |
|                             | 15-28 | 40-55 | <0.06        | 0.16-0.18                      | 6.6-7.8          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 28-48 | 25-40 | 0.2-0.6      | 0.16-0.18                      | 7.4-8.4          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 48-52 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| Manard-----                 | 0-11  | 20-27 | 0.2-0.6      | 0.18-0.20                      | 6.1-7.3          | <2       | Moderate                      | 0.20               | 2 | 6                                 | 2-4               |
|                             | 11-26 | 40-50 | <0.06        | 0.14-0.16                      | 6.6-7.8          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 26-28 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 28-32 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 46-----<br>Hapur            | 0-3   | 19-26 | 0.6-2.0      | 0.19-0.21                      | 7.4-9.0          | 2-4      | Low-----                      | 0.37               | 4 | 4                                 | 3-6               |
|                             | 3-30  | 20-35 | 0.2-0.6      | 0.16-0.21                      | 6.6-9.0          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 30-44 | 8-17  | 2.0-6.0      | 0.11-0.15                      | 6.6-7.8          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 44-51 | 3-9   | 6.0-20       | 0.08-0.10                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 51-63 | 0-8   | >20          | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 47*:<br>Hapur-----          | 0-3   | 19-26 | 0.6-2.0      | 0.19-0.21                      | 7.4-9.0          | 2-4      | Low-----                      | 0.37               | 4 | 4                                 | 3-6               |
|                             | 3-30  | 20-35 | 0.2-0.6      | 0.16-0.21                      | 6.6-9.0          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 30-44 | 8-17  | 2.0-6.0      | 0.11-0.15                      | 6.6-7.8          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 44-51 | 3-9   | 6.0-20       | 0.08-0.10                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 51-63 | 0-8   | >20          | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| Bickett-----                | 0-6   | ---   | 0.6-2.0      | 0.22-0.30                      | 6.6-7.8          | <2       | Low-----                      | ---                | 5 | 8                                 | 60-85             |
|                             | 6-11  | ---   | 0.6-2.0      | 0.22-0.30                      | 7.4-7.8          | <2       | Low-----                      | ---                |   |                                   |                   |
|                             | 11-40 | 24-35 | 0.2-0.6      | 0.19-0.21                      | 7.4-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 40-61 | 20-30 | 0.6-2.0      | 0.15-0.18                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
| 48*:<br>Hapur-----          | 0-3   | 19-26 | 0.6-2.0      | 0.19-0.21                      | 7.4-9.0          | 2-4      | Low-----                      | 0.37               | 4 | 4                                 | 3-6               |
|                             | 3-30  | 20-35 | 0.2-0.6      | 0.16-0.21                      | 6.6-9.0          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 30-44 | 8-17  | 2.0-6.0      | 0.11-0.15                      | 6.6-7.8          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 44-51 | 3-9   | 6.0-20       | 0.08-0.10                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 51-63 | 0-8   | >20          | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| Picabo-----                 | 0-9   | 5-10  | 0.6-2.0      | 0.19-0.21                      | 8.5-9.0          | 2-8      | Low-----                      | 0.37               | 5 | 4                                 | 7-9               |
|                             | 9-39  | 5-12  | 0.6-2.0      | 0.16-0.20                      | 7.9-8.4          | <2       | Low-----                      | 0.37               |   |                                   |                   |
|                             | 39-51 | 6-12  | 0.6-2.0      | 0.13-0.17                      | 7.9-8.4          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 51-61 | 5-10  | 0.6-2.0      | 0.15-0.20                      | 7.9-8.4          | <2       | Low-----                      | 0.64               |   |                                   |                   |
|                             | 61-72 | 4-8   | 6.0-20       | 0.03-0.05                      | 7.9-8.4          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 49-----<br>Hutton           | 0-4   | 25-35 | 0.2-0.6      | 0.18-0.20                      | 6.6-7.3          | <2       | Moderate                      | 0.32               | 5 | 6                                 | 2-4               |
|                             | 4-19  | 28-40 | 0.2-0.6      | 0.16-0.18                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 19-62 | 40-60 | <0.06        | 0.12-0.16                      | 6.6-7.8          | <2       | High-----                     | 0.24               |   |                                   |                   |

See footnote at end of table.



TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 50-----<br>Hutton Variant   | 0-8   | 27-36 | 0.2-0.6      | 0.19-0.21                      | 5.1-6.0          | <2       | Moderate                      | 0.24               | 3 | 6                                 | 2-3               |
|                             | 8-24  | 40-55 | <0.06        | 0.13-0.16                      | 5.6-6.5          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 24-39 | 28-42 | 0.06-0.6     | 0.07-0.10                      | 6.1-6.5          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 39-66 | 2-10  | >20          | 0.02-0.06                      | 6.1-6.5          | <2       | Low-----                      | 0.02               |   |                                   |                   |
| 51-----<br>Isknat           | 0-2   | 27-33 | 0.2-0.6      | 0.17-0.20                      | 5.6-6.0          | <2       | Moderate                      | 0.10               | 3 | 6                                 | 2-3               |
|                             | 2-11  | 32-40 | 0.06-0.2     | 0.16-0.20                      | 5.6-6.0          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 11-26 | 35-45 | 0.06-0.2     | 0.07-0.12                      | 5.6-6.0          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 26-35 | 20-32 | 0.2-0.6      | 0.06-0.12                      | 5.6-6.0          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 35-61 | 0-10  | >6.0         | 0.02-0.06                      | 5.6-6.0          | <2       | Low-----                      | 0.02               |   |                                   |                   |
| 52, 53-----<br>Justesen     | 0-7   | 12-18 | 0.6-2.0      | 0.13-0.19                      | 6.6-7.3          | <2       | Low-----                      | 0.32               | 5 | 5                                 | 1-3               |
|                             | 7-24  | 23-34 | 0.2-0.6      | 0.13-0.20                      | 6.6-7.8          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 24-62 | 15-20 | 0.6-2.0      | 0.10-0.19                      | 7.9-8.4          | <2       | Low-----                      | 0.28               |   |                                   |                   |
| 54, 55-----<br>Justesen     | 0-14  | 12-18 | 0.6-2.0      | 0.13-0.19                      | 6.6-7.3          | <2       | Low-----                      | 0.32               | 5 | 5                                 | 1-3               |
|                             | 14-31 | 23-34 | 0.2-0.6      | 0.13-0.20                      | 6.6-7.8          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 31-64 | 15-20 | 0.6-2.0      | 0.10-0.19                      | 7.9-8.4          | <2       | Low-----                      | 0.28               |   |                                   |                   |
| 56*:<br>Ketchum-----        | 0-3   | 15-25 | 2.0-6.0      | 0.08-0.11                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 5 | 8                                 | 1-2               |
|                             | 3-48  | 10-20 | 2.0-6.0      | 0.06-0.11                      | 6.6-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 48-61 | 5-15  | 2.0-6.0      | 0.04-0.06                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| Dollarhide-----             | 0-7   | 8-18  | 2.0-6.0      | 0.06-0.11                      | 6.6-7.8          | <2       | Low-----                      | 0.17               | 1 | 8                                 | 1-3               |
|                             | 7-13  | 8-18  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 13    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 57*:<br>Ketchum-----        | 0-3   | 15-25 | 2.0-6.0      | 0.08-0.11                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 5 | 8                                 | 1-2               |
|                             | 3-48  | 10-20 | 2.0-6.0      | 0.06-0.11                      | 6.6-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 48-61 | 5-15  | 2.0-6.0      | 0.04-0.06                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| Povey-----                  | 0-4   | 10-20 | 0.6-2.0      | 0.07-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 5                                 | 2-3               |
|                             | 4-25  | 10-20 | 0.6-2.0      | 0.06-0.08                      | 6.6-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 25-50 | 8-15  | 0.6-2.0      | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 50-54 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 58*:<br>Laurentzen-----     | 0-13  | 18-27 | 0.6-2.0      | 0.19-0.21                      | 6.1-7.3          | <2       | Low-----                      | 0.43               | 5 | 6                                 | 2-4               |
|                             | 13-63 | 22-35 | 0.2-0.6      | 0.16-0.21                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 63    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| Mulshoe-----                | 0-10  | 15-25 | 0.6-2.0      | 0.08-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.24               | 2 | 5                                 | 1-3               |
|                             | 10-23 | 28-35 | 0.2-0.6      | 0.08-0.10                      | 6.6-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 23-28 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 28    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 59*.<br>Lava flows          |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 60*:<br>Lava flows.         |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Cinderhurst-----            | 0-3   | 15-20 | 0.6-2.0      | 0.06-0.09                      | 6.1-7.3          | <2       | Low-----                      | 0.15               | 1 | 8                                 | 2-4               |
|                             | 3-8   | 18-25 | 0.6-2.0      | 0.06-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 8     | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |

See footnote at end of table.

TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               | K                  | T |                                   | Pct               |
| 61*:<br>Lavacreek-----      | 0-23  | ---   | 0.6-2.0      | 0.09-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.28               | 3 | 8                                 | 1-3               |
|                             | 23-41 | 10-20 | 0.6-2.0      | 0.08-0.11                      | 6.1-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 41-49 | 10-20 | 2.0-6.0      | 0.05-0.08                      | 5.6-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 49    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Dollarhide-----             | 0-7   | 8-18  | 2.0-6.0      | 0.08-0.13                      | 6.6-7.8          | <2       | Low-----                      | 0.20               | 1 | 8                                 | 1-3               |
|                             | 7-16  | 8-18  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 16-20 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 62*:<br>Lavacreek-----      | 0-9   | ---   | 0.6-2.0      | 0.09-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.28               | 3 | 8                                 | 1-3               |
|                             | 9-38  | 10-20 | 0.6-2.0      | 0.08-0.11                      | 6.1-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 38-43 | 10-20 | 2.0-6.0      | 0.05-0.08                      | 5.6-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 43-47 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Dollarhide-----             | 0-7   | 8-18  | 2.0-6.0      | 0.08-0.13                      | 6.6-7.8          | <2       | Low-----                      | 0.20               | 1 | 8                                 | 1-3               |
|                             | 7-16  | 8-18  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 16-20 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 63*:<br>Lavacreek-----      | 0-23  | ---   | 0.6-2.0      | 0.09-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.28               | 3 | 8                                 | 1-3               |
|                             | 23-41 | 10-20 | 0.6-2.0      | 0.08-0.11                      | 6.1-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 41-49 | 10-20 | 2.0-6.0      | 0.05-0.08                      | 5.6-7.3          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 49    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Vitale-----                 | 0-6   | 15-25 | 2.0-6.0      | 0.12-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.20               | 2 | 8                                 | 1-3               |
|                             | 6-15  | 28-35 | 0.6-2.0      | 0.14-0.17                      | 6.6-7.8          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 15-23 | 15-25 | 0.6-2.0      | 0.10-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 23    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 64, 65-----<br>Little Wood  | 0-13  | 15-25 | 2.0-6.0      | 0.11-0.14                      | 6.1-6.5          | <2       | Low-----                      | 0.20               | 2 | 5                                 | 2-4               |
|                             | 13-26 | 20-35 | 0.6-2.0      | 0.10-0.12                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 26-32 | 5-15  | 6.0-20       | 0.04-0.06                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 32-61 | 0-5   | >20          | 0.02-0.04                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 66-----<br>Little Wood      | 0-10  | 15-25 | 2.0-6.0      | 0.09-0.11                      | 6.1-6.5          | <2       | Low-----                      | 0.17               | 2 | 5                                 | 2-4               |
|                             | 10-25 | 20-35 | 0.6-2.0      | 0.10-0.12                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 25-35 | 5-15  | 6.0-20       | 0.04-0.06                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 35-61 | 0-5   | >20          | 0.02-0.04                      | 6.6-7.3          | <2       | -----                         | 0.05               |   |                                   |                   |
| 67-----<br>Little Wood      | 0-10  | 15-25 | 2.0-6.0      | 0.09-0.11                      | 6.1-6.5          | <2       | Low-----                      | 0.17               | 2 | 5                                 | 2-4               |
|                             | 10-22 | 20-35 | 0.6-2.0      | 0.10-0.12                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 22-32 | 5-15  | 6.0-20       | 0.04-0.06                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 32-61 | 0-5   | >20          | 0.02-0.04                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 68-----<br>Little Wood      | 0-12  | 17-25 | 0.6-2.0      | 0.09-0.11                      | 5.6-6.5          | <2       | Low-----                      | 0.10               | 3 | 5                                 | 1-2               |
|                             | 12-16 | 25-35 | 0.6-2.0      | 0.08-0.10                      | 6.1-6.5          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 16-24 | 22-30 | 0.6-2.0      | 0.05-0.07                      | 6.1-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 24-31 | 16-20 | 2.0-6.0      | 0.03-0.05                      | 6.1-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 31-60 | 0-6   | >6.0         | 0.02-0.03                      | 6.6-7.3          | <2       | Low-----                      | 0.02               |   |                                   |                   |
| 69*:<br>Little Wood-----    | 0-10  | 15-25 | 2.0-6.0      | 0.09-0.11                      | 6.1-6.5          | <2       | Low-----                      | 0.17               | 2 | 5                                 | 2-4               |
|                             | 10-25 | 20-35 | 0.6-2.0      | 0.10-0.12                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 25-35 | 5-15  | 6.0-20       | 0.04-0.06                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
|                             | 35-61 | 0-5   | >20          | 0.02-0.04                      | 6.6-7.3          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| Balaam-----                 | 0-10  | 10-15 | 2.0-6.0      | 0.07-0.10                      | 6.1-7.3          | <2       | Low-----                      | 0.15               | 3 | 3                                 | 1-3               |
|                             | 10-24 | 5-10  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 24-63 | 0-5   | >20          | 0.01-0.03                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |

See footnote at end of table.



TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 70-----<br>Manard           | 0-11  | 20-27 | 0.2-0.6      | 0.19-0.21                      | 6.1-7.3          | <2       | Moderate                      | 0.43               | 2 | 6                                 | 1-2               |
|                             | 11-36 | 40-50 | <0.06        | 0.14-0.17                      | 6.6-7.8          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 36-38 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 38-42 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 71-----<br>Marshdale        | 0-9   | 18-27 | 0.6-2.0      | 0.16-0.20                      | 6.6-8.4          | <2       | Moderate                      | 0.28               | 3 | 4                                 | 5-10              |
|                             | 9-52  | 18-30 | 0.6-2.0      | 0.14-0.18                      | 7.4-8.4          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 52-62 | 0-5   | >20          | 0.03-0.06                      | 7.4-8.4          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 72*:<br>Marshdale-----      | 0-14  | 18-27 | 0.6-2.0      | 0.16-0.20                      | 6.6-8.4          | <2       | Moderate                      | 0.28               | 3 | 4                                 | 5-10              |
|                             | 14-50 | 18-30 | 0.6-2.0      | 0.14-0.18                      | 7.4-8.4          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 50-65 | 0-5   | >20          | 0.03-0.06                      | 7.4-8.4          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| Bruneel-----                | 0-14  | 10-25 | 0.6-2.0      | 0.16-0.18                      | 6.6-8.4          | <2       | Low-----                      | 0.28               | 2 | 5                                 | 2-3               |
|                             | 14-27 | 10-18 | 0.6-2.0      | 0.11-0.18                      | 6.6-7.8          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 27-61 | 0-5   | >20          | 0.02-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 73-----<br>McBiggam         | 0-10  | 10-15 | 0.6-2.0      | 0.18-0.22                      | 6.1-7.3          | <2       | Low-----                      | 0.43               | 5 | 6                                 | 1-2               |
|                             | 10-26 | 22-32 | 0.2-0.6      | 0.16-0.18                      | 6.6-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 26-46 | 40-50 | 0.06-0.2     | 0.13-0.17                      | 6.6-7.8          | <2       | High-----                     | 0.32               |   |                                   |                   |
|                             | 46-80 | 30-40 | 0.2-0.6      | 0.15-0.19                      | 7.4-8.4          | <2       | Moderate                      | 0.37               |   |                                   |                   |
| 74*:<br>McCarey-----        | 0-11  | 10-20 | 0.6-2.0      | 0.16-0.21                      | 6.1-7.8          | <2       | Low-----                      | 0.43               | 2 | 5                                 | 1-3               |
|                             | 11-23 | 20-34 | 0.2-0.6      | 0.19-0.21                      | 6.6-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 23-28 | 15-25 | 0.6-2.0      | 0.16-0.21                      | 6.6-8.4          | <2       | Low-----                      | 0.43               |   |                                   |                   |
|                             | 28-32 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Justesen-----               | 0-14  | 12-18 | 0.6-2.0      | 0.13-0.19                      | 6.6-7.3          | <2       | Low-----                      | 0.32               | 5 | 5                                 | 1-3               |
|                             | 14-31 | 23-34 | 0.2-0.6      | 0.13-0.20                      | 6.6-7.8          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 31-64 | 15-20 | 0.6-2.0      | 0.10-0.19                      | 7.9-8.4          | <2       | Low-----                      | 0.28               |   |                                   |                   |
| 75*:<br>McCarey-----        | 0-11  | 10-20 | 0.6-2.0      | 0.16-0.21                      | 6.1-7.8          | <2       | Low-----                      | 0.43               | 2 | 5                                 | 1-3               |
|                             | 11-23 | 20-34 | 0.2-0.6      | 0.19-0.21                      | 6.6-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 23-28 | 15-25 | 0.6-2.0      | 0.16-0.21                      | 6.6-8.4          | <2       | Low-----                      | 0.43               |   |                                   |                   |
|                             | 28-32 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Justesen-----               | 0-14  | 12-18 | 0.6-2.0      | 0.13-0.19                      | 6.6-7.3          | <2       | Low-----                      | 0.32               | 2 | 5                                 | 1-3               |
|                             | 14-31 | 23-34 | 0.2-0.6      | 0.13-0.20                      | 6.6-7.8          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 31-64 | 15-20 | 0.6-2.0      | 0.10-0.19                      | 7.9-8.4          | <2       | Low-----                      | 0.28               |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 76*:<br>McCarey-----        | 0-10  | 10-20 | 0.6-2.0      | 0.16-0.21                      | 6.1-7.8          | <2       | Low-----                      | 0.43               | 2 | 5                                 | 1-3               |
|                             | 10-22 | 20-34 | 0.2-0.6      | 0.19-0.21                      | 6.6-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 22-37 | 15-25 | 0.6-2.0      | 0.16-0.21                      | 6.6-8.4          | <2       | Low-----                      | 0.43               |   |                                   |                   |
|                             | 37-41 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Molyneux-----               | 0-13  | 10-20 | 0.6-2.0      | 0.13-0.19                      | 6.1-7.3          | <2       | Low-----                      | 0.32               | 5 | 4                                 | 1-3               |
|                             | 13-50 | 25-35 | 0.2-0.6      | 0.14-0.20                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 50-75 | 20-30 | 0.2-0.6      | 0.13-0.15                      | 6.1-7.8          | <2       | Moderate                      | 0.28               |   |                                   |                   |
| 77*:<br>McCarey-----        | 0-10  | 10-20 | 0.6-2.0      | 0.16-0.21                      | 6.1-7.8          | <2       | Low-----                      | 0.43               | 2 | 5                                 | 1-3               |
|                             | 10-22 | 20-34 | 0.2-0.6      | 0.19-0.21                      | 6.6-8.4          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 22-37 | 15-25 | 0.6-2.0      | 0.16-0.21                      | 6.6-8.4          | <2       | Low-----                      | 0.43               |   |                                   |                   |
|                             | 37-41 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |

See footnote at end of table.

TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 77*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Pedleford-----              | 0-5   | 10-16 | 0.6-2.0      | 0.06-0.08                      | 6.6-7.3          | <2       | Low-----                      | 0.17               | 2 | 8                                 | 1-2               |
|                             | 5-13  | 13-19 | 0.6-2.0      | 0.08-0.12                      | 6.6-8.4          | <2       | Low-----                      | 0.24               |   |                                   |                   |
|                             | 13-33 | 10-16 | 0.6-2.0      | 0.06-0.08                      | 7.9-9.0          | <2       | Low-----                      | 0.28               |   |                                   |                   |
|                             | 33    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 78, 79-----                 | 0-12  | 10-20 | 0.6-2.0      | 0.13-0.19                      | 6.1-7.3          | <2       | Low-----                      | 0.32               | 5 | 4                                 | 1-3               |
| Molyneux                    | 12-61 | 25-35 | 0.2-0.6      | 0.14-0.20                      | 6.1-7.3          | <2       | Moderate--                    | 0.32               |   |                                   |                   |
| 80-----                     | 0-13  | 10-20 | 0.6-2.0      | 0.13-0.19                      | 6.1-7.3          | <2       | Low-----                      | 0.32               | 5 | 4                                 | 1-3               |
| Molyneux                    | 13-50 | 25-35 | 0.2-0.6      | 0.14-0.20                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 50-75 | 20-30 | 0.2-0.6      | 0.13-0.15                      | 6.1-7.8          | <2       | Moderate                      | 0.28               |   |                                   |                   |
| 81*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Moonstone-----              | 0-26  | 10-15 | 2.0-6.0      | 0.07-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.10               | 2 | 4                                 | 1-3               |
|                             | 26-34 | 10-15 | 2.0-6.0      | 0.08-0.13                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 34    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Bauscher-----               | 0-14  | 12-20 | 0.6-2.0      | 0.16-0.18                      | 5.6-7.3          | <2       | Low-----                      | 0.32               | 5 | 5                                 | 2-5               |
|                             | 14-37 | 18-30 | 0.2-0.6      | 0.12-0.18                      | 5.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 37-42 | 10-15 | 2.0-6.0      | 0.09-0.13                      | 5.6-7.3          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 42    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 82*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Moonstone-----              | 0-21  | 10-15 | 2.0-6.0      | 0.07-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.10               | 2 | 4                                 | 1-3               |
|                             | 21-32 | 10-15 | 2.0-6.0      | 0.08-0.13                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 32-36 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Earcree-----                | 0-37  | 10-18 | 2.0-6.0      | 0.10-0.13                      | 5.6-7.3          | <2       | Low-----                      | 0.10               | 5 | 3                                 | 3-6               |
|                             | 37-52 | 5-15  | 2.0-6.0      | 0.05-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 52-70 | 5-10  | 2.0-6.0      | 0.05-0.07                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 83*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Muldoon-----                | 0-7   | 20-27 | 0.6-2.0      | 0.17-0.18                      | 6.1-6.5          | <2       | Low-----                      | 0.32               | 3 | 5                                 | 2-6               |
|                             | 7-32  | 27-35 | 0.2-0.6      | 0.16-0.18                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 32-45 | 27-33 | 0.2-0.6      | 0.13-0.18                      | 6.6-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 45    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Peevywell-----              | 0-12  | 15-20 | 0.6-2.0      | 0.16-0.18                      | 6.1-7.3          | <2       | Low-----                      | 0.37               | 2 | 5                                 | 1-3               |
|                             | 12-22 | 30-40 | 0.2-0.6      | 0.17-0.19                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 22-30 | 40-55 | 0.06-0.2     | 0.15-0.17                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 30-44 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 44-61 | 5-12  | 6.0-20       | ---                            | 7.4-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 84*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Mulshoe-----                | 0-10  | 15-25 | 0.6-2.0      | 0.08-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.24               | 2 | 5                                 | 1-3               |
|                             | 10-23 | 28-35 | 0.2-0.6      | 0.08-0.10                      | 6.6-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 23-28 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 28    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Gaib-----                   | 0-4   | 15-25 | 0.6-2.0      | 0.05-0.07                      | 5.6-6.0          | <2       | Low-----                      | 0.24               | 1 | 6                                 | 1-3               |
|                             | 4-12  | 24-35 | 0.2-0.6      | 0.10-0.16                      | 6.1-7.3          | <2       | Moderate                      | 0.20               |   |                                   |                   |
|                             | 12-16 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 85*:                        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Mulshoe-----                | 0-12  | 15-25 | 0.6-2.0      | 0.08-0.12                      | 6.1-7.3          | <2       | Low-----                      | 0.24               | 2 | 5                                 | 1-3               |
|                             | 12-21 | 28-35 | 0.2-0.6      | 0.08-0.10                      | 6.6-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 21-25 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |

See footnote at end of table.



TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 85*:<br>Gaib-----           | 0-5   | 15-25 | 0.6-2.0      | 0.05-0.07                      | 5.6-6.0          | <2       | Low-----                      | 0.24               | 1 | 6                                 | 1-3               |
|                             | 5-13  | 24-35 | 0.2-6.0      | 0.10-0.16                      | 6.1-7.3          | <2       | Moderate                      | 0.20               |   |                                   |                   |
|                             | 13    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| Winu-----                   | 0-13  | 15-25 | 0.6-2.0      | 0.08-0.10                      | 5.6-7.3          | <2       | Low-----                      | 0.28               | 3 | 5                                 | 4-5               |
|                             | 13-35 | 20-30 | 0.2-0.6      | 0.10-0.13                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 35-39 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| 86*:<br>Pagari-----         | 0-11  | 10-15 | 2.0-6.0      | 0.06-0.10                      | 6.6-7.3          | <2       | Low-----                      | 0.17               | 3 | 8                                 | 1-2               |
|                             | 11-17 | 10-17 | 2.0-6.0      | 0.06-0.10                      | 6.6-7.3          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 17-31 | 18-30 | 0.6-2.0      | 0.07-0.12                      | 7.4-7.8          | <2       | Moderate                      | 0.20               |   |                                   |                   |
|                             | 31-46 | 14-25 | 0.6-2.0      | 0.06-0.10                      | 7.4-7.8          | <2       | Low-----                      | 0.28               |   |                                   |                   |
|                             | 46    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
| Rehfield-----               | 0-11  | 4-10  | 6.0-20       | 0.07-0.10                      | 6.6-7.3          | <2       | Low-----                      | 0.20               | 2 | 2                                 | 1-2               |
|                             | 11-42 | 18-31 | 0.6-2.0      | 0.13-0.17                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 42-67 | 8-13  | 0.6-6.0      | 0.06-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
| 87*:<br>Peevywell-----      | 0-5   | 15-20 | 0.6-2.0      | 0.16-0.18                      | 6.1-7.3          | <2       | Low-----                      | 0.37               | 2 | 5                                 | 1-3               |
|                             | 5-10  | 30-40 | 0.2-0.6      | 0.17-0.19                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 10-24 | 40-55 | 0.06-0.2     | 0.15-0.17                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 24-46 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 46-61 | 5-12  | 6.0-20       | ---                            | 7.4-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| Simonton-----               | 0-12  | 10-20 | 0.6-2.0      | 0.16-0.18                      | 5.6-7.3          | <2       | Low-----                      | 0.28               | 5 | 6                                 | 1-2               |
|                             | 12-52 | 18-32 | 0.2-0.6      | 0.14-0.21                      | 5.6-7.3          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 52-64 | 5-10  | 2.0-6.0      | 0.06-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.20               |   |                                   |                   |
| 88*:<br>Peevywell-----      | 0-12  | 15-20 | 0.6-2.0      | 0.16-0.18                      | 6.1-7.3          | <2       | Low-----                      | 0.37               | 2 | 5                                 | 1-3               |
|                             | 12-22 | 30-40 | 0.2-0.6      | 0.17-0.19                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 22-30 | 40-55 | 0.06-0.2     | 0.15-0.17                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 30-44 | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |
|                             | 44-61 | 5-12  | 6.0-20       | ---                            | 7.4-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| Simonton-----               | 0-11  | 10-20 | 0.6-2.0      | 0.16-0.18                      | 5.6-7.3          | <2       | Low-----                      | 0.28               | 5 | 6                                 | 1-2               |
|                             | 11-61 | 18-32 | 0.2-0.6      | 0.14-0.21                      | 5.6-7.3          | <2       | Moderate                      | 0.37               |   |                                   |                   |
| 89-----<br>Picabo           | 0-9   | 5-10  | 0.6-2.0      | 0.19-0.21                      | 8.5-9.0          | <2       | Low-----                      | 0.37               | 5 | 4                                 | 7-9               |
|                             | 9-39  | 5-12  | 0.6-2.0      | 0.16-0.20                      | 7.9-8.4          | <2       | Low-----                      | 0.37               |   |                                   |                   |
|                             | 39-51 | 6-12  | 0.6-2.0      | 0.13-0.17                      | 7.9-8.4          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 51-61 | 5-10  | 0.6-2.0      | 0.15-0.20                      | 7.9-8.4          | <2       | Low-----                      | 0.64               |   |                                   |                   |
|                             | 61-72 | 4-8   | 6.0-20       | 0.03-0.05                      | 7.9-8.4          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 90-----<br>Picabo           | 0-11  | 8-13  | 0.6-2.0      | 0.11-0.14                      | 8.5-9.0          | 2-8      | Low-----                      | 0.20               | 5 | 8                                 | 7-9               |
|                             | 11-40 | 5-12  | 0.6-2.0      | 0.16-0.20                      | 7.9-8.4          | <2       | Low-----                      | 0.37               |   |                                   |                   |
|                             | 40-53 | 6-12  | 0.6-2.0      | 0.13-0.17                      | 7.9-8.4          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 53-61 | 5-10  | 0.6-2.0      | 0.15-0.20                      | 7.9-8.4          | <2       | Low-----                      | 0.64               |   |                                   |                   |
|                             | 61-72 | 4-8   | 6.0-20       | 0.03-0.05                      | 7.9-8.4          | <2       | Low-----                      | 0.05               |   |                                   |                   |
| 91*.<br>Pits, gravel        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 92*:<br>Povey-----          | 0-14  | 10-20 | 0.6-2.0      | 0.07-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 5                                 | 2-3               |
|                             | 14-35 | 10-20 | 0.6-2.0      | 0.06-0.08                      | 6.6-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 35-60 | 8-15  | 0.6-2.0      | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 60    | ---   | ---          | ---                            | ---              | ---      | ---                           | ---                |   |                                   |                   |

See footnote at end of table.

TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol                      | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|--|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|  |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|  | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 92*:<br>Dollarhide-----                          | 0-7   | 8-18  | 2.0-6.0      | 0.08-0.13                      | 6.6-7.8          | <2       | Low-----                      | 0.20               | 1 | 8                                 | 1-3               |
|  | 7-16  | 8-18  | 2.0-6.0      | 0.05-0.09                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|  | 16-20 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 93*:<br>Povey-----                               | 0-14  | 10-20 | 0.6-2.0      | 0.07-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 5                                 | 2-3               |
|  | 14-35 | 10-20 | 0.6-2.0      | 0.06-0.08                      | 6.6-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|  | 35-60 | 8-15  | 0.6-2.0      | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|  | 60    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rock outcrop.                                    |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 94*:<br>Povey very<br>gravelly silt<br>loam----- | 0-12  | 10-20 | 0.6-2.0      | 0.07-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.20               | 3 | 5                                 | 2-3               |
|  | 12-44 | 10-20 | 0.6-2.0      | 0.06-0.08                      | 6.6-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|  | 44-52 | 8-15  | 0.6-2.0      | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|  | 52-56 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Povey gravelly<br>loam-----                      | 0-14  | 10-20 | 0.6-2.0      | 0.07-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 5                                 | 2-3               |
|  | 14-35 | 10-20 | 0.6-2.0      | 0.06-0.08                      | 6.6-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|  | 35-60 | 8-15  | 0.6-2.0      | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|  | 60    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 95*:<br>Povey-----                               | 0-14  | 10-20 | 0.6-2.0      | 0.07-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 5                                 | 2-3               |
|  | 14-35 | 10-20 | 0.6-2.0      | 0.06-0.08                      | 6.6-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|  | 35-60 | 8-15  | 0.6-2.0      | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|  | 60    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Vitale-----                                      | 0-6   | 15-25 | 2.0-6.0      | 0.12-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.20               | 2 | 8                                 | 1-3               |
|  | 6-15  | 28-35 | 0.6-2.0      | 0.14-0.17                      | 6.6-7.8          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|  | 15-23 | 15-25 | 0.6-2.0      | 0.10-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|  | 23    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 96*:<br>Rehfield-----                            | 0-11  | 10-17 | 2.0-6.0      | 0.09-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.28               | 5 | 3                                 | 1-2               |
|  | 11-42 | 18-31 | 0.6-2.0      | 0.13-0.17                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|  | 42-67 | 8-13  | 0.6-6.0      | 0.06-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
| Gooding-----                                     | 0-9   | 10-20 | 0.2-0.6      | 0.19-0.21                      | 6.6-7.3          | <2       | Low-----                      | 0.37               | 1 | 6                                 | 1-3               |
|  | 9-34  | 35-59 | <0.06        | 0.14-0.21                      | 6.6-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|  | 34-49 | 27-40 | 0.06-0.2     | 0.14-0.21                      | 7.4-8.4          | <2       | High-----                     | 0.32               |   |                                   |                   |
|  | 49-62 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|  | 62    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 97*:<br>Riverwash                                |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 98*:<br>Rock outcrop.                            |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Adios-----                                       | 0-5   | 20-27 | 0.6-2.0      | 0.16-0.19                      | 6.6-7.3          | <2       | Low-----                      | 0.20               | 1 | 8                                 | 1-3               |
|  | 5-23  | 35-60 | <0.06        | 0.15-0.17                      | 6.6-8.4          | <2       | High-----                     | 0.28               |   |                                   |                   |
|  | 23-27 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|  | 27    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |

See footnote at end of table.



TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 99-----<br>Rockybar         | 0-9   | 15-25 | 0.6-2.0      | 0.05-0.07                      | 6.1-7.3          | <2       | Low-----                      | 0.05               | 2 | 8                                 | 1-2               |
|                             | 9-31  | 25-33 | 0.6-2.0      | 0.07-0.12                      | 6.1-7.3          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 31-62 | 15-27 | 2.0-6.0      | 0.05-0.07                      | 6.1-7.3          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| 100*.<br>Rubbleland         |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 101*:<br>Rubbleland.        |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| Milligan-----               | 0-8   | 8-15  | 2.0-6.0      | 0.08-0.13                      | 6.1-7.3          | <2       | Low-----                      | 0.24               | 2 | 7                                 | 1-3               |
|                             | 8-18  | 8-15  | 2.0-6.0      | 0.08-0.10                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 18-24 | 0-1   | >20          | 0.01-0.02                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 24    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 102, 103-----<br>Simonton   | 0-12  | 10-20 | 0.6-2.0      | 0.16-0.18                      | 5.6-7.3          | <2       | Low-----                      | 0.28               | 5 | 6                                 | 1-2               |
|                             | 12-52 | 18-32 | 0.2-0.6      | 0.14-0.21                      | 5.6-7.3          | <2       | Moderate                      | 0.37               |   |                                   |                   |
|                             | 52-64 | 5-10  | 2.0-6.0      | 0.06-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.20               |   |                                   |                   |
| 104*:<br>Simonton-----      | 0-11  | 10-20 | 0.6-2.0      | 0.16-0.18                      | 5.6-7.3          | <2       | Low-----                      | 0.28               | 5 | 6                                 | 1-2               |
|                             | 11-61 | 18-32 | 0.2-0.6      | 0.14-0.21                      | 5.6-7.3          | <2       | Moderate                      | 0.37               |   |                                   |                   |
| Bauscher-----               | 0-14  | 12-20 | 0.6-2.0      | 0.16-0.18                      | 5.6-7.3          | <2       | Low-----                      | 0.32               | 5 | 5                                 | 2-5               |
|                             | 14-37 | 18-30 | 0.2-0.6      | 0.12-0.18                      | 5.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 37-42 | 10-15 | 2.0-6.0      | 0.09-0.13                      | 5.6-7.3          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 42    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 105*:<br>Starhope-----      | 0-9   | 20-25 | 0.2-0.6      | 0.17-0.19                      | 6.1-7.3          | <2       | Low-----                      | 0.28               | 2 | 5                                 | 1-3               |
|                             | 9-23  | 35-50 | 0.06-0.2     | 0.09-0.15                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 23-26 | 35-40 | 0.06-0.2     | 0.09-0.15                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 26-30 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Furshur-----                | 0-2   | 19-25 | 0.6-2.0      | 0.11-0.14                      | 6.6-7.3          | <2       | Low-----                      | 0.10               | 1 | 6                                 | 1-3               |
|                             | 2-5   | 27-32 | 0.2-0.6      | 0.18-0.21                      | 6.6-7.3          | <2       | Moderate                      | 0.28               |   |                                   |                   |
|                             | 5-15  | 50-60 | <0.06        | 0.11-0.15                      | 6.6-7.8          | <2       | High-----                     | 0.17               |   |                                   |                   |
|                             | 15-20 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 20    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 106*:<br>Starhope-----      | 0-10  | 20-25 | 0.2-0.6      | 0.17-0.19                      | 6.1-7.3          | <2       | Low-----                      | 0.28               | 2 | 5                                 | 1-3               |
|                             | 10-26 | 35-50 | 0.06-0.2     | 0.09-0.15                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 26-30 | 35-40 | 0.06-0.2     | 0.09-0.15                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 30    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Peevywell-----              | 0-12  | 15-20 | 0.6-2.0      | 0.16-0.18                      | 6.1-7.3          | <2       | Low-----                      | 0.37               | 2 | 5                                 | 1-3               |
|                             | 12-22 | 30-40 | 0.2-0.6      | 0.17-0.19                      | 6.1-7.3          | <2       | Moderate                      | 0.32               |   |                                   |                   |
|                             | 22-30 | 40-55 | 0.06-0.2     | 0.15-0.17                      | 6.1-7.3          | <2       | High-----                     | 0.24               |   |                                   |                   |
|                             | 30-44 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
|                             | 44-61 | 5-12  | 6.0-20       | ---                            | 7.4-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
| Smelter-----                | 0-18  | 20-27 | 0.2-0.6      | 0.16-0.19                      | 6.1-7.3          | <2       | Low-----                      | 0.28               | 5 | 5                                 | 2-4               |
|                             | 18-35 | 27-35 | 0.06-0.2     | 0.18-0.20                      | 6.1-7.3          | <2       | Moderate                      | 0.17               |   |                                   |                   |
|                             | 35-61 | 20-32 | 0.2-0.6      | 0.16-0.18                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
| 107*:<br>Vitale-----        | 0-6   | 15-25 | 2.0-6.0      | 0.12-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.20               | 2 | 8                                 | 1-3               |
|                             | 6-15  | 28-35 | 0.6-2.0      | 0.14-0.17                      | 6.6-7.8          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 15-23 | 15-25 | 0.6-2.0      | 0.10-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 23    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |

See footnote at end of table.

TABLE 14.--PHYSICAL AND CHEMICAL PROPERTIES OF THE SOILS--Continued

| Soil name and<br>map symbol | Depth | Clay  | Permeability | Available<br>water<br>capacity | Soil<br>reaction | Salinity | Shrink-<br>swell<br>potential | Erosion<br>factors |   | Wind<br>erodi-<br>bility<br>group | Organic<br>matter |
|-----------------------------|-------|-------|--------------|--------------------------------|------------------|----------|-------------------------------|--------------------|---|-----------------------------------|-------------------|
|                             |       |       |              |                                |                  |          |                               | K                  | T |                                   |                   |
|                             | In    | Pct   | In/hr        | In/in                          | pH               | mmhos/cm |                               |                    |   |                                   | Pct               |
| 107*:<br>Blackspar-----     | 0-3   | 10-20 | 0.6-2.0      | 0.05-0.07                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 1 | 8                                 | 1-2               |
|                             | 3-17  | 20-30 | 0.6-2.0      | 0.04-0.06                      | 6.6-7.3          | <2       | Low-----                      | 0.20               |   |                                   |                   |
|                             | 17    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 108*:<br>Vitale-----        | 0-6   | 15-25 | 2.0-6.0      | 0.12-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.20               | 2 | 8                                 | 1-3               |
|                             | 6-15  | 28-35 | 0.6-2.0      | 0.14-0.17                      | 6.6-7.8          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 15-23 | 15-25 | 0.6-2.0      | 0.10-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 23    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Milligan-----               | 0-8   | 8-15  | 2.0-6.0      | 0.08-0.13                      | 6.1-7.3          | <2       | Low-----                      | 0.24               | 2 | 7                                 | 1-3               |
|                             | 8-18  | 8-15  | 2.0-6.0      | 0.08-0.10                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 18-24 | 0-1   | >20          | 0.01-0.02                      | 6.6-7.8          | <2       | Low-----                      | 0.10               |   |                                   |                   |
|                             | 24    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 109*:<br>Vitale-----        | 0-6   | 15-25 | 2.0-6.0      | 0.12-0.14                      | 6.1-7.3          | <2       | Low-----                      | 0.20               | 2 | 8                                 | 1-3               |
|                             | 6-15  | 28-35 | 0.6-2.0      | 0.14-0.17                      | 6.6-7.8          | <2       | Moderate                      | 0.10               |   |                                   |                   |
|                             | 15-23 | 15-25 | 0.6-2.0      | 0.10-0.12                      | 6.6-7.8          | <2       | Low-----                      | 0.17               |   |                                   |                   |
|                             | 23    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Povey-----                  | 0-14  | 10-20 | 0.6-2.0      | 0.07-0.13                      | 6.6-7.3          | <2       | Low-----                      | 0.24               | 3 | 5                                 | 2-3               |
|                             | 14-35 | 10-20 | 0.6-2.0      | 0.06-0.08                      | 6.6-7.3          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 35-60 | 8-15  | 0.6-2.0      | 0.03-0.05                      | 6.6-7.8          | <2       | Low-----                      | 0.15               |   |                                   |                   |
|                             | 60    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| 110*:<br>Winu-----          | 0-13  | 15-25 | 0.6-2.0      | 0.08-0.10                      | 5.6-7.3          | <2       | Low-----                      | 0.28               | 3 | 5                                 | 4-5               |
|                             | 13-35 | 20-30 | 0.2-0.6      | 0.10-0.13                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 35-39 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Rock outcrop.               |       |       |              |                                |                  |          |                               |                    |   |                                   |                   |
| 111*:<br>Winu-----          | 0-13  | 15-25 | 0.6-2.0      | 0.08-0.10                      | 5.6-7.3          | <2       | Low-----                      | 0.28               | 3 | 5                                 | 4-5               |
|                             | 13-35 | 20-30 | 0.2-0.6      | 0.10-0.13                      | 6.1-7.3          | <2       | Moderate                      | 0.24               |   |                                   |                   |
|                             | 35-39 | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |
| Gaib-----                   | 0-5   | 15-25 | 0.6-2.0      | 0.05-0.07                      | 5.6-6.0          | <2       | Low-----                      | 0.24               | 1 | 6                                 | 1-3               |
|                             | 5-13  | 24-35 | 0.2-0.6      | 0.10-0.16                      | 6.1-7.3          | <2       | Moderate                      | 0.20               |   |                                   |                   |
|                             | 13    | ---   | ---          | ---                            | ---              | ---      | -----                         | ---                |   |                                   |                   |

\* See description of the map unit for composition and behavior characteristics of the map unit.



TABLE 15.--WATER FEATURES

("Flooding" and "water table" and terms such as "rare," "brief," and "apparent" are explained in the text.  
The symbol < means less than; > means more than. Absence of an entry indicates that the feature is not a concern or that data were not estimated)

| Soil name and<br>map symbol | Hydrologic<br>group | Flooding        |               |         | High water table |          |         |
|-----------------------------|---------------------|-----------------|---------------|---------|------------------|----------|---------|
|                             |                     | Frequency       | Duration      | Months  | Depth*           | Kind     | Months  |
|                             |                     |                 |               |         | <u>Ft</u>        |          |         |
| 1-----<br>Adamson           | B                   | Rare-----       | ---           | ---     | >6.0             | ---      | ---     |
| 2**:<br>Adios-----          | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Gooding-----                | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Bostrum-----                | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 3**:<br>Adios-----          | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Adios, cool-----            | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 4, 5-----<br>Balaam         | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 6**:<br>Balaam-----         | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Adamson-----                | B                   | Rare-----       | ---           | ---     | >6.0             | ---      | ---     |
| 7**:<br>Balaam-----         | B                   | Rare-----       | ---           | ---     | >6.0             | ---      | ---     |
| Adamson-----                | B                   | Rare-----       | ---           | ---     | >6.0             | ---      | ---     |
| 8**:<br>Balaam-----         | B                   | Occasional----- | Brief-----    | May-Jun | >5.0             | Apparent | Apr-Jun |
| Adamson-----                | B                   | Occasional----- | Brief-----    | May-Jun | >4.0             | Apparent | Apr-Jun |
| Riverwash.                  |                     |                 |               |         |                  |          |         |
| 9, 10-----<br>Bancroft      | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 11-----<br>Bickett          | D                   | Frequent-----   | Very long---- | Dec-May | + .5-0.5         | Apparent | Jan-Dec |
| 12**:<br>Blackspar-----     | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Rock outcrop.               |                     |                 |               |         |                  |          |         |
| 13**:<br>Blackspot-----     | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Prudy-----                  | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 14**:<br>Bostrum-----       | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Yutru-----                  | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |

See footnotes at end of table.

TABLE 15.--WATER FEATURES--Continued

| Soil name and<br>map symbol  | Hydrologic<br>group | Flooding        |            |         | High water table |          |         |
|------------------------------|---------------------|-----------------|------------|---------|------------------|----------|---------|
|                              |                     | Frequency       | Duration   | Months  | Depth*<br>Ft     | Kind     | Months  |
| 14**:<br>Hamrub-----         | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 15, 16, 17-----<br>Bringmee  | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 18**:<br>Bringmee-----       | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Hutton-----                  | D                   | Frequent-----   | Brief----- | Apr-Jun | 1.0-2.5          | Apparent | Apr-Jun |
| 19**:<br>Bringmee-----       | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Little Wood-----             | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 20-----<br>Bruneel           | D                   | Occasional----- | Brief----- | Mar-Jun | 1.0-1.5          | Apparent | Mar-Jun |
| 21, 22-----<br>Carey Lake    | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 23**:<br>Cox-----            | D                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Rehfield-----                | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Rock outcrop.                |                     |                 |            |         |                  |          |         |
| 24**:<br>Deerhorn-----       | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Rehfield-----                | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Rock outcrop.                |                     |                 |            |         |                  |          |         |
| 25**:<br>Deerhorn-----       | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Wildors-----                 | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 26**:<br>Deerhorn-----       | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Wildors-----                 | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Trevino-----                 | D                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 27**:<br>Dollarhide-----     | D                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Rock outcrop.                |                     |                 |            |         |                  |          |         |
| 28, 29, 30, 31-----<br>Drage | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 32**:<br>Earcree-----        | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Lockman-----                 | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |

See footnotes at end of table.



TABLE 15.--WATER FEATURES--Continued

| Soil name and<br>map symbol | Hydrologic<br>group | Flooding  |          |        | High water table |      |        |
|-----------------------------|---------------------|-----------|----------|--------|------------------|------|--------|
|                             |                     | Frequency | Duration | Months | Depth*           | Kind | Months |
|                             |                     |           |          |        | <u>Ft</u>        |      |        |
| 33**, 34**:<br>Earcree----- | B                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Moonstone-----              | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 35**:<br>Elkcreek-----      | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Gaib-----                   | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 36**:<br>Elkcreek-----      | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Polecreek-----              | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 37**:<br>Elksel-----        | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Friedman-----               | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Starhope-----               | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 38**:<br>Elksel-----        | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Peevywell-----              | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Furshur-----                | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 39**:<br>Elksel-----        | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Starhope-----               | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Rock outcrop.               |                     |           |          |        |                  |      |        |
| 40**:<br>Friedman-----      | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Elksel-----                 | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Winridge-----               | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 41**:<br>Gaib-----          | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Rock outcrop.               |                     |           |          |        |                  |      |        |
| 42-----<br>Gimlett          | B                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 43**:<br>Gooding-----       | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Gooding, eroded----         | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Hamrub-----                 | B                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 44-----<br>Goodington       | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |

See footnotes at end of table.

TABLE 15.--WATER FEATURES--Continued

| Soil name and<br>map symbol     | Hydrologic<br>group | Flooding        |               |         | High water table |          |         |
|---------------------------------|---------------------|-----------------|---------------|---------|------------------|----------|---------|
|                                 |                     | Frequency       | Duration      | Months  | Depth*           | Kind     | Months  |
|                                 |                     |                 |               |         | <u>Ft</u>        |          |         |
| 45**:<br>Goodington-----        | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Manard-----                     | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 46-----<br>Hapur                | D                   | Frequent-----   | Brief-----    | Mar-Jun | 0.5-1.0          | Apparent | Sep-May |
| 47**:<br>Hapur-----             | D                   | Frequent-----   | Brief-----    | Mar-Jun | 0.5-1.0          | Apparent | Sep-May |
| Bickett-----                    | D                   | Frequent-----   | Very long---- | Dec-May | +5-0.5           | Apparent | Jan-Dec |
| 48**:<br>Hapur-----             | D                   | Frequent-----   | Brief-----    | Mar-Jun | 0.5-1.0          | Apparent | Sep-May |
| Picabo-----                     | C                   | Occasional----- | Long-----     | Feb-May | 2.0-4.0          | Apparent | Oct-May |
| 49-----<br>Hutton               | D                   | Frequent-----   | Brief-----    | Apr-Jun | 1.0-2.5          | Apparent | Apr-Jun |
| 50-----<br>Hutton Variant       | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 51-----<br>Isknat               | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 52, 53, 54, 55-----<br>Justesen | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 56**:<br>Ketchum-----           | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Dollarhide-----                 | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 57**:<br>Ketchum-----           | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Povey-----                      | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 58**:<br>Laurentzen-----        | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Mulshoe-----                    | C                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 59**.<br>Lava flows             |                     |                 |               |         |                  |          |         |
| 60**:<br>Lava flows.            |                     |                 |               |         |                  |          |         |
| Cinderhurst-----                | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 61**, 62**:<br>Lavacreek-----   | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| Dollarhide-----                 | D                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |
| 63**:<br>Lavacreek-----         | B                   | None-----       | ---           | ---     | >6.0             | ---      | ---     |

See footnotes at end of table.



TABLE 15.--WATER FEATURES--Continued

| Soil name and<br>map symbol         | Hydrologic<br>group | Flooding        |            |         | High water table |          |         |
|-------------------------------------|---------------------|-----------------|------------|---------|------------------|----------|---------|
|                                     |                     | Frequency       | Duration   | Months  | Depth*<br>Ft     | Kind     | Months  |
| 63**:<br>Vitale-----                | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 64, 65, 66, 67, 68--<br>Little Wood | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 69**:<br>Little Wood-----           | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Balaam-----                         | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 70-----<br>Manard                   | D                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 71-----<br>Marshdale                | D                   | Frequent-----   | Long-----  | Apr-Jul | 0.5-1.5          | Apparent | Apr-Aug |
| 72**:<br>Marshdale-----             | D                   | Frequent-----   | Long-----  | Apr-Jul | 0.5-1.5          | Apparent | Apr-Aug |
| Bruneel-----                        | D                   | Occasional----- | Brief----- | Mar-Jun | 1.0-1.5          | Apparent | Mar-Jun |
| 73-----<br>McBiggam                 | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 74**:<br>McCarey-----               | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Justesen-----                       | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 75**:<br>McCarey-----               | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Justesen-----                       | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Rock outcrop.                       |                     |                 |            |         |                  |          |         |
| 76**:<br>McCarey-----               | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Molyneux-----                       | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 77**:<br>McCarey-----               | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Pedleford-----                      | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 78, 79, 80-----<br>Molyneux         | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 81**:<br>Moonstone-----             | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Bauscher-----                       | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| 82**:<br>Moonstone-----             | C                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |
| Earcree-----                        | B                   | None-----       | ---        | ---     | >6.0             | ---      | ---     |

See footnotes at end of table.

TABLE 15.--WATER FEATURES--Continued

| Soil name and<br>map symbol                    | Hydrologic<br>group | Flooding        |           |         | High water table |          |         |
|--|---------------------|-----------------|-----------|---------|------------------|----------|---------|
|  |                     | Frequency       | Duration  | Months  | Depth*           | Kind     | Months  |
|  |                     |                 |           |         | <u>Ft</u>        |          |         |
| 83**:<br>Muldoon-----                          | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Peevywell-----                                 | C                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| 84**:<br>Mulshoe-----                          | C                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Gaib-----                                      | D                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Rock outcrop.                                  |                     |                 |           |         |                  |          |         |
| 85**:<br>Mulshoe-----                          | C                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Gaib-----                                      | D                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Winu-----                                      | C                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| 86**:<br>Pagari-----                           | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Rehfield-----                                  | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| 87**, 88**:<br>Peevywell-----                  | C                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Simonton-----                                  | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| 89, 90-----<br>Picabo                          | C                   | Occasional----- | Long----- | Feb-May | 2.0-4.0          | Apparent | Oct-May |
| 91**:<br>Pits, gravel                          |                     |                 |           |         |                  |          |         |
| 92**:<br>Povey-----                            | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Dollarhide-----                                | D                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| 93**:<br>Povey-----                            | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Rock outcrop.                                  |                     |                 |           |         |                  |          |         |
| 94**:<br>Povey very gravelly<br>silt loam----- | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Povey gravelly<br>loam-----                    | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| 95**:<br>Povey-----                            | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Vitale-----                                    | C                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| 96**:<br>Rehfield-----                         | B                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |
| Gooding-----                                   | D                   | None-----       | ---       | ---     | >6.0             | ---      | ---     |

See footnotes at end of table.



TABLE 15.--WATER FEATURES--Continued

| Soil name and<br>map symbol | Hydrologic<br>group | Flooding  |          |        | High water table |      |        |
|-----------------------------|---------------------|-----------|----------|--------|------------------|------|--------|
|                             |                     | Frequency | Duration | Months | Depth*           | Kind | Months |
|                             |                     |           |          |        | <u>Ft</u>        |      |        |
| 97**.<br>Riverwash          |                     |           |          |        |                  |      |        |
| 98**:<br>Rock outcrop.      |                     |           |          |        |                  |      |        |
| Adios-----                  | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 99-----<br>Rockybar         | B                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 100**.<br>Rubbleland        |                     |           |          |        |                  |      |        |
| 101**:<br>Rubbleland.       |                     |           |          |        |                  |      |        |
| Milligan-----               | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 102, 103-----<br>Simonton   | B                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 104**:<br>Simonton-----     | B                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Bauscher-----               | B                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 105**:<br>Starhope-----     | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Furshur-----                | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 106**:<br>Starhope-----     | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Peevywell-----              | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Smelter-----                | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 107**:<br>Vitale-----       | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Blackspar-----              | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 108**:<br>Vitale-----       | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Milligan-----               | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 109**:<br>Vitale-----       | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Povey-----                  | B                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| 110**:<br>Winu-----         | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Rock outcrop.               |                     |           |          |        |                  |      |        |

See footnotes at end of table.

TABLE 15.--WATER FEATURES--Continued

| Soil name and<br>map symbol | Hydrologic<br>group | Flooding  |          |        | High water table |      |        |
|-----------------------------|---------------------|-----------|----------|--------|------------------|------|--------|
|                             |                     | Frequency | Duration | Months | Depth*           | Kind | Months |
|                             |                     |           |          |        | <u>Ft</u>        |      |        |
| 111**:<br>Winu-----         | C                   | None----- | ---      | ---    | >6.0             | ---  | ---    |
| Gaib-----                   | D                   | None----- | ---      | ---    | >6.0             | ---  | ---    |

\* A plus sign preceding the range in depth indicates that the water table is above the surface of the soil. The first numeral in the range indicates how high the water table rises above the surface. The second numeral indicates the depth below the surface.

\*\* See description of the map unit for composition and behavior characteristics of this map unit.



TABLE 16.--SOIL FEATURES

(The symbol < means less than; > means more than. Absence of an entry indicates that the feature is not a concern or that data were not estimated)

| Soil name and<br>map symbol | Bedrock   |          | Cemented<br>pan |           | Subsidence |           | Potential<br>frost<br>action | Risk of corrosion |           |
|-----------------------------|-----------|----------|-----------------|-----------|------------|-----------|------------------------------|-------------------|-----------|
|                             | Depth     | Hardness | Depth           | Thickness | Initial    | Total     |                              | Uncoated<br>steel | Concrete  |
|                             |           |          |                 |           |            |           |                              |                   |           |
|                             | <u>In</u> |          | <u>In</u>       |           | <u>In</u>  | <u>In</u> |                              |                   |           |
| 1-----<br>Adamson           | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | High-----         | Low.      |
| 2*:<br>Adios-----           | 26-36     | Hard     | 22-31           | Thick     | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Gooding-----                | 48-72     | Hard     | 40-60           | Thin      | ---        | ---       | Moderate                     | High-----         | Low.      |
| Bostrum-----                | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | High-----         | Low.      |
| 3*:<br>Adios-----           | 26-36     | Hard     | 22-31           | Thick     | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Adios, cool-----            | 26-36     | Hard     | 22-31           | Thick     | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 4, 5-----<br>Balaam         | >60       | ---      | ---             | ---       | ---        | ---       | Low-----                     | Moderate          | Low.      |
| 6*:<br>Balaam-----          | >60       | ---      | ---             | ---       | ---        | ---       | Low-----                     | Moderate          | Low.      |
| Adamson-----                | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | High-----         | Low.      |
| 7*:<br>Balaam-----          | >60       | ---      | ---             | ---       | ---        | ---       | Low-----                     | Moderate          | Moderate  |
| Adamson-----                | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 8*:<br>Balaam-----          | >60       | ---      | ---             | ---       | ---        | ---       | Low-----                     | Moderate          | Moderate. |
| Adamson-----                | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Riverwash.                  |           |          |                 |           |            |           |                              |                   |           |
| 9, 10-----<br>Bancroft      | >60       | ---      | ---             | ---       | ---        | ---       | High-----                    | High-----         | Low.      |
| 11-----<br>Bickett          | >60       | ---      | ---             | ---       | 5-8        | 8-15      | High-----                    | Moderate          | Low.      |
| 12*:<br>Blackspar-----      | 10-20     | Hard     | ---             | ---       | ---        | ---       | Low-----                     | Moderate          | Low.      |
| Rock outcrop.               |           |          |                 |           |            |           |                              |                   |           |
| 13*:<br>Blackspot-----      | 19-22     | Soft     | 13-17           | Thick     | ---        | ---       | Moderate                     | High-----         | Low.      |
| Prudy-----                  | 50-60     | Soft     | 40-48           | Thick     | ---        | ---       | Moderate                     | High-----         | Low.      |
| 14*:<br>Bostrum-----        | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | High-----         | Low.      |
| Yutruue-----                | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | High-----         | Low.      |
| Hamrub-----                 | 45-60     | Hard     | 40-50           | Thick     | ---        | ---       | Moderate                     | High-----         | Low.      |

See footnote at end of table.

TABLE 16.--SOIL FEATURES--Continued

| Soil name and<br>map symbol  | Bedrock   |          | Cemented<br>pan |           | Subsidence |           | Potential<br>frost<br>action | Risk of corrosion |           |
|------------------------------|-----------|----------|-----------------|-----------|------------|-----------|------------------------------|-------------------|-----------|
|                              | Depth     | Hardness | Depth           | Thickness | Initial    | Total     |                              | Uncoated<br>steel | Concrete  |
|                              |           |          |                 |           |            |           |                              |                   |           |
|                              | <u>In</u> |          | <u>In</u>       |           | <u>In</u>  | <u>In</u> |                              |                   |           |
| 15, 16, 17-----<br>Bringmee  | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| 18*:<br>Bringmee-----        | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| Hutton-----                  | >60       | ---      | ---             | ---       | ---        | ---       | High-----                    | Moderate          | Low.      |
| 19*:<br>Bringmee-----        | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| Little Wood-----             | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 20-----<br>Bruneel           | >60       | ---      | ---             | ---       | ---        | ---       | High-----                    | High-----         | Low.      |
| 21, 22-----<br>Carey Lake    | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 23*:<br>Cox-----             | 10-20     | Hard     | ---             | ---       | ---        | ---       | Low-----                     | Moderate          | Low.      |
| Rehfield-----                | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Rock outcrop.                |           |          |                 |           |            |           |                              |                   |           |
| 24*:<br>Deerhorn-----        | 22-35     | Hard     | 20-30           | Thin      | ---        | ---       | Moderate                     | High-----         | Low.      |
| Rehfield-----                | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Rock outcrop.                |           |          |                 |           |            |           |                              |                   |           |
| 25*:<br>Deerhorn-----        | 22-35     | Hard     | 20-30           | Thin      | ---        | ---       | Moderate                     | High-----         | Low.      |
| Wildors-----                 | 23-30     | Hard     | 21-28           | Thin      | ---        | ---       | Moderate                     | High-----         | Low.      |
| 26*:<br>Deerhorn-----        | 22-35     | Hard     | 20-30           | Thin      | ---        | ---       | Moderate                     | High-----         | Low.      |
| Wildors-----                 | 23-30     | Hard     | 21-28           | Thin      | ---        | ---       | Moderate                     | High-----         | Low.      |
| Trevino-----                 | 10-20     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | High-----         | Low.      |
| 27*:<br>Dollarhide-----      | 10-20     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Rock outcrop.                |           |          |                 |           |            |           |                              |                   |           |
| 28, 29, 30, 31-----<br>Drage | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | High-----         | Low.      |
| 32*:<br>Earcree-----         | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| Lockman-----                 | 40-60     | Soft     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| 33*, 34*:<br>Earcree-----    | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |

See footnote at end of table.



TABLE 16.--SOIL FEATURES--Continued

| Soil name and<br>map symbol | Bedrock |          | Cemented<br>pan |           | Subsidence |       | Potential<br>frost<br>action | Risk of corrosion |           |
|-----------------------------|---------|----------|-----------------|-----------|------------|-------|------------------------------|-------------------|-----------|
|                             | Depth   | Hardness | Depth           | Thickness | Initial    | Total |                              | Uncoated<br>steel | Concrete  |
|                             | In      |          | In              |           | In         | In    |                              |                   |           |
| 33*, 34*:<br>Moonstone----- | 20-40   | Soft     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 35*:<br>Elkcreek-----       | 26-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Gaib-----                   | 10-20   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Moderate. |
| 36*:<br>Elkcreek-----       | 26-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Polecreek-----              | 10-20   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 37*:<br>Elksel-----         | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Friedman-----               | 40-60   | Soft     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Starhope-----               | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 38*:<br>Elksel-----         | 45-60   | Hard     | 40-50           | Thick     | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Peevywell-----              | 40-55   | Hard     | 24-35           | Thick     | ---        | ---   | High-----                    | Moderate          | Low.      |
| Furshur-----                | 18-24   | Hard     | 14-20           | Thick     | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 39*:<br>Elksel-----         | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Starhope-----               | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Rock outcrop.               |         |          |                 |           |            |       |                              |                   |           |
| 40*:<br>Friedman-----       | 40-60   | Soft     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Elksel-----                 | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Winridge-----               | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 41*:<br>Gaib-----           | 10-20   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Moderate. |
| Rock outcrop.               |         |          |                 |           |            |       |                              |                   |           |
| 42-----<br>Gimlett          | >60     | ---      | ---             | ---       | ---        | ---   | Low-----                     | Moderate          | Moderate. |
| 43*:<br>Gooding-----        | 48-72   | Hard     | 40-60           | Thin      | ---        | ---   | Moderate                     | High-----         | Low.      |
| Gooding, eroded-----        | 48-72   | Hard     | 40-60           | Thin      | ---        | ---   | Moderate                     | High-----         | Low.      |
| Hamrub-----                 | 45-60   | Hard     | 40-50           | Thick     | ---        | ---   | Moderate                     | High-----         | Low.      |
| 44-----<br>Goodington       | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |
| 45*:<br>Goodington-----     | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |

See footnote at end of table.

TABLE 16.--SOIL FEATURES--Continued

| Soil name and<br>map symbol     | Bedrock   |          | Cemented<br>pan |           | Subsidence |           | Potential<br>frost<br>action | Risk of corrosion |           |
|---------------------------------|-----------|----------|-----------------|-----------|------------|-----------|------------------------------|-------------------|-----------|
|                                 | Depth     | Hardness | Depth           | Thickness | Initial    | Total     |                              | Uncoated<br>steel | Concrete  |
|                                 |           |          |                 |           |            |           |                              |                   |           |
|                                 | <u>In</u> |          | <u>In</u>       |           | <u>In</u>  | <u>In</u> |                              |                   |           |
| 45*:<br>Manard-----             | 21-38     | Hard     | 20-37           | Thick     | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 46-----<br>Hapur                | >60       | ---      | ---             | ---       | ---        | ---       | High-----                    | High-----         | Low.      |
| 47*:<br>Hapur-----              | >60       | ---      | ---             | ---       | ---        | ---       | High-----                    | High-----         | Low.      |
| Bickett-----                    | >60       | ---      | ---             | ---       | 5-8        | 8-15      | High-----                    | Moderate          | Low.      |
| 48*:<br>Hapur-----              | >60       | ---      | ---             | ---       | ---        | ---       | High-----                    | High-----         | Low.      |
| Picabo-----                     | >60       | ---      | ---             | ---       | ---        | ---       | High-----                    | High-----         | Low.      |
| 49-----<br>Hutton               | >60       | ---      | ---             | ---       | ---        | ---       | High-----                    | Moderate          | Low.      |
| 50-----<br>Hutton Variant       | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| 51-----<br>Isknat               | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| 52, 53, 54, 55-----<br>Justesen | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | High-----         | Low.      |
| 56*:<br>Ketchum-----            | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Dollarhide-----                 | 10-20     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 57*:<br>Ketchum-----            | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Povey-----                      | 40-60     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 58*:<br>Laurentzen-----         | >40       | Hard     | ---             | ---       | ---        | ---       | High-----                    | Moderate          | Low.      |
| Mulshoe-----                    | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 59*.<br>Lava flows              |           |          |                 |           |            |           |                              |                   |           |
| 60*.<br>Lava flows              |           |          |                 |           |            |           |                              |                   |           |
| Cinderhurst-----                | 4-10      | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 61*, 62*:<br>Lavacreek-----     | 40-60     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| Dollarhide-----                 | 10-20     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 63*:<br>Lavacreek-----          | 40-60     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| Vitale-----                     | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |

See footnote at end of table.



TABLE 16.--SOIL FEATURES--Continued

| Soil name and<br>map symbol            | Bedrock |          | Cemented<br>pan |           | Subsidence |       | Potential<br>frost<br>action | Risk of corrosion |           |
|--|---------|----------|-----------------|-----------|------------|-------|------------------------------|-------------------|-----------|
|  | Depth   | Hardness | Depth           | Thickness | Initial    | Total |                              | Uncoated<br>steel | Concrete  |
|  | In      |          | In              |           | In         | In    |                              |                   |           |
| 64, 65, 66, 67, 68-----<br>Little Wood | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 69*:<br>Little Wood-----               | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Balaam-----                            | >60     | ---      | ---             | ---       | ---        | ---   | Low-----                     | Moderate          | Low.      |
| 70-----<br>Manard                      | 21-38   | Hard     | 20-37           | Thin      | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 71-----<br>Marshdale                   | >60     | ---      | ---             | ---       | ---        | ---   | Low-----                     | High-----         | Moderate. |
| 72*:<br>Marshdale-----                 | >60     | ---      | ---             | ---       | ---        | ---   | Low-----                     | High-----         | Moderate. |
| Bruneel-----                           | >60     | ---      | ---             | ---       | ---        | ---   | High-----                    | High-----         | Low.      |
| 73-----<br>McBiggam                    | >60     | ---      | ---             | ---       | ---        | ---   | High-----                    | High-----         | Low.      |
| 74*:<br>McCarey-----                   | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |
| Justesen-----                          | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |
| 75*:<br>McCarey-----                   | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |
| Justesen-----                          | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |
| Rock outcrop.                          |         |          |                 |           |            |       |                              |                   |           |
| 76*:<br>McCarey-----                   | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |
| Molyneux-----                          | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 77*:<br>McCarey-----                   | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |
| Pedleford-----                         | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | High-----         | Low.      |
| 78, 79, 80-----<br>Molyneux            | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 81*:<br>Moonstone-----                 | 20-40   | Soft     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Bauscher-----                          | 40-60   | Soft     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Moderate. |
| 82*:<br>Moonstone-----                 | 20-40   | Soft     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Earcree-----                           | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Moderate. |
| 83*:<br>Muldoon-----                   | >60     | ---      | 40-60           | Thick     | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Peevywell-----                         | >60     | ---      | 24-35           | Thick     | ---        | ---   | Moderate                     | Moderate          | Low.      |

See footnote at end of table.

TABLE 16.--SOIL FEATURES--Continued

| Soil name and<br>map symbol                   | Bedrock |          | Cemented<br>pan |           | Subsidence |       | Potential<br>frost<br>action | Risk of corrosion |           |
|---|---------|----------|-----------------|-----------|------------|-------|------------------------------|-------------------|-----------|
|   | Depth   | Hardness | Depth           | Thickness | Initial    | Total |                              | Uncoated<br>steel | Concrete  |
|   | In      |          | In              |           | In         | In    |                              |                   |           |
| 84*:<br>Mulshoe-----                          | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Gaib-----                                     | 10-20   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Moderate. |
| Rock outcrop.                                 |         |          |                 |           |            |       |                              |                   |           |
| 85*:<br>Mulshoe-----                          | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Gaib-----                                     | 10-20   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Moderate. |
| Winu-----                                     | 24-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Moderate. |
| 86*:<br>Pagari-----                           | 40-60   | Soft     | ---             | ---       | ---        | ---   | Low-----                     | High-----         | Low.      |
| Rehfield-----                                 | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 87*, 88*:<br>Peewywell-----                   | >60     | ---      | 24-35           | Thick     | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Simonton-----                                 | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Moderate. |
| 89, 90-----<br>Picabo                         | >60     | ---      | ---             | ---       | ---        | ---   | High-----                    | High-----         | Low.      |
| 91*.<br>Pits, gravel                          |         |          |                 |           |            |       |                              |                   |           |
| 92*:<br>Povey-----                            | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Dollarhide-----                               | 10-20   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 93*:<br>Povey-----                            | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Rock outcrop.                                 |         |          |                 |           |            |       |                              |                   |           |
| 94*:<br>Povey very gravelly<br>silt loam----- | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Povey gravelly loam----                       | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 95*:<br>Povey-----                            | 40-60   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Vitale-----                                   | 20-40   | Hard     | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| 96*:<br>Rehfield-----                         | >60     | ---      | ---             | ---       | ---        | ---   | Moderate                     | Moderate          | Low.      |
| Gooding-----                                  | 40-72   | Hard     | 40-60           | Thin      | ---        | ---   | Moderate                     | High-----         | Low.      |
| 97*.<br>Riverwash                             |         |          |                 |           |            |       |                              |                   |           |
| 98*:<br>Rock outcrop.                         |         |          |                 |           |            |       |                              |                   |           |
| Adios-----                                    | 26-36   | Hard     | 22-31           | Thick     | ---        | ---   | Moderate                     | Moderate          | Low.      |

See footnote at end of table.



TABLE 16.--SOIL FEATURES--Continued

| Soil name and<br>map symbol | Bedrock   |          | Cemented<br>pan |           | Subsidence |           | Potential<br>frost<br>action | Risk of corrosion |           |
|-----------------------------|-----------|----------|-----------------|-----------|------------|-----------|------------------------------|-------------------|-----------|
|                             | Depth     | Hardness | Depth           | Thickness | Initial    | Total     |                              | Uncoated<br>steel | Concrete  |
|                             | <u>In</u> |          | <u>In</u>       |           | <u>In</u>  | <u>In</u> |                              |                   |           |
| 99-----<br>Rockybar         | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 100*:<br>Rubbleland         |           |          |                 |           |            |           |                              |                   |           |
| 101*:<br>Rubbleland.        |           |          |                 |           |            |           |                              |                   |           |
| Milligan-----               | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 102, 103-----<br>Simonton   | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| 104*:<br>Simonton-----      | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| Bauscher-----               | 40-60     | Soft     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| 105*:<br>Starhope-----      | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Furshur-----                | 18-24     | Hard     | 14-20           | Thick     | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 106*:<br>Starhope-----      | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Peevywell-----              | >60       | ---      | 24-35           | Thick     | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Smelter-----                | >60       | ---      | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 107*:<br>Vitale-----        | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Blackspar-----              | 10-20     | Hard     | ---             | ---       | ---        | ---       | Low-----                     | Moderate          | Low.      |
| 108*:<br>Vitale-----        | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Milligan-----               | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 109*:<br>Vitale-----        | 20-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| Povey-----                  | 40-60     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Low.      |
| 110*:<br>Winu-----          | 24-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| Rock outcrop.               |           |          |                 |           |            |           |                              |                   |           |
| 111*:<br>Winu-----          | 24-40     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |
| Gaib-----                   | 10-20     | Hard     | ---             | ---       | ---        | ---       | Moderate                     | Moderate          | Moderate. |

\* See description of the map unit for composition and behavior characteristics of the map unit.

TABLE 17.--CLASSIFICATION OF THE SOILS

(An asterisk in the first column indicates that the soil is a taxadjunct to the series. See text for a description of those characteristics of the soil that are outside the range of the series)

| Soil name           | Family or higher taxonomic class  |
|---------------------|---|
| Adamson-----        | Coarse-loamy over sandy or sandy-skeletal, mixed, frigid Calcic Pachic Haploxerolls |
| Adios-----          | Fine, montmorillonitic, mesic Aridic Durixerolls                                    |
| Balaam-----         | Sandy-skeletal, mixed, frigid Entic Ultic Haploxerolls                              |
| Bancroft-----       | Fine-silty, mixed, frigid Calcic Argixerolls  |
| Bauscher-----       | Fine-loamy, mixed, frigid Pachic Ultic Argixerolls                                  |
| Bickett-----        | Fine-silty, mixed (calcareous), frigid Histic Humaquepts                            |
| Blackspar-----      | Loamy-skeletal, mixed, frigid Lithic Mollic Haploxeralfs                            |
| Blackspot-----      | Loamy-skeletal, mixed, frigid (shallow) Haplic Durixerolls                          |
| Bostrum-----        | Fine, montmorillonitic, mesic Typic Palexeralfs                                     |
| Bringmee-----       | Fine-loamy, mixed, frigid Pachic Ultic Argixerolls                                  |
| Bruneel-----        | Coarse-loamy over sandy or sandy-skeletal, mixed, frigid Typic Haplaquolls          |
| Carey Lake-----     | Fine-loamy, mixed, frigid Pachic Argixerolls  |
| Cinderhurst-----    | Loamy-skeletal, mixed, frigid Lithic Mollic Haploxeralfs                            |
| Cox-----            | Loamy-skeletal, mixed, mesic Lithic Ultic Haploxerolls                              |
| Deerhorn-----       | Fine-loamy, mixed, mesic Argic Durixerolls  |
| Dollarhide-----     | Loamy-skeletal, mixed Lithic Cryoborolls  |
| Drage-----          | Loamy-skeletal, mixed, frigid Calcic Argixerolls                                    |
| Earcree-----        | Coarse-loamy, mixed Pachic Cryoborolls  |
| Elkcreek-----       | Fine-loamy, mixed, frigid Ultic Argixerolls   |
| Elksel-----         | Clayey-skeletal, montmorillonitic, frigid Ultic Argixerolls                         |
| Friedman-----       | Clayey-skeletal, montmorillonitic Argic Pachic Cryoborolls                          |
| Furshur-----        | Clayey, montmorillonitic, frigid, shallow Abruptic Durixeralfs                      |
| Gaib-----           | Loamy-skeletal, mixed, frigid Lithic Ultic Argixerolls                              |
| Gimlett-----        | Loamy-skeletal, mixed, frigid Pachic Ultic Haploxerolls                             |
| Gooding-----        | Fine, montmorillonitic, mesic Xerollic Paleargids                                   |
| Goodington-----     | Fine, montmorillonitic, frigid Typic Palexerolls                                    |
| Hamrub-----         | Fine-silty, mixed, mesic Aridic Calcic Argixerolls                                  |
| Hapur-----          | Fine-loamy, frigid Typic Calciaquolls   |
| Hutton-----         | Fine, montmorillonitic, frigid Cumulic Haplaquolls                                  |
| Hutton Variant----- | Fine, montmorillonitic, frigid Pachic Ultic Argixerolls                             |
| Isknat-----         | Clayey-skeletal, montmorillonitic, frigid Pachic Ultic Argixerolls                  |
| Justesen-----       | Fine-loamy, mixed, frigid Calcic Argixerolls  |
| Ketchum-----        | Loamy-skeletal, mixed Typic Cryochrepts   |
| Laurentzen-----     | Fine-silty, mixed, frigid Pachic Ultic Argixerolls                                  |
| Lavacreek-----      | Loamy-skeletal, mixed Andeptic Cryoborolls  |
| Little Wood-----    | Loamy-skeletal, mixed, frigid Ultic Argixerolls                                     |
| Lockman-----        | Coarse-loamy, mixed Typic Cryoborolls   |
| Manard-----         | Fine, montmorillonitic, frigid Typic Durixerolls                                    |
| Marshdale-----      | Fine-loamy, mixed, frigid Cumulic Haplaquolls                                       |
| McBiggam-----       | Fine-silty, mixed, frigid Typic Palexerolls   |
| McCarey-----        | Fine-loamy, mixed, frigid Calcic Argixerolls  |
| Milligan-----       | Loamy-skeletal over fragmental, mixed, frigid Typic Haploxerolls                    |
| Molyneux-----       | Fine-loamy, mixed, frigid Ultic Argixerolls   |
| Moonstone-----      | Coarse-loamy, mixed, frigid Pachic Ultic Haploxerolls                               |
| Muldoon-----        | Fine-loamy, mixed, frigid Ultic Argixerolls   |
| Mulshoe-----        | Loamy-skeletal, mixed, frigid Ultic Argixerolls                                     |
| Pagari-----         | Loamy-skeletal, mixed, mesic Aridic Calcic Argixerolls                              |
| Pedleford-----      | Loamy-skeletal, mixed, frigid Calcic Haploxerolls                                   |
| Peevywell-----      | Fine, montmorillonitic, frigid Typic Durixerolls                                    |
| Picabo-----         | Coarse-silty, carbonatic, frigid Aquic Calcixerolls                                 |
| Polecreek-----      | Clayey-skeletal, montmorillonitic, frigid Lithic Ultic Argixerolls                  |
| Povey-----          | Loamy-skeletal, mixed Pachic Cryoborolls  |
| Prudy-----          | Fine-loamy, mixed Calcic Cryoborolls  |
| Rehfield-----       | Fine-loamy, mixed, mesic Ultic Argixerolls  |
| Rockybar-----       | Loamy-skeletal, mixed, frigid Mollic Haploxeralfs                                   |
| Simonton-----       | Fine-loamy, mixed, frigid Ultic Argixerolls   |
| Smelter-----        | Fine-silty, mixed, frigid Pachic Argixerolls  |
| Starhope-----       | Fine, montmorillonitic, frigid Ultic Argixerolls                                    |
| *Trevino-----       | Loamy, mixed, mesic Lithic Xerollic Camborthids                                     |
| Vitale-----         | Loamy-skeletal, mixed, frigid Typic Argixerolls                                     |




TABLE 17.--CLASSIFICATION OF THE SOILS--Continued

| Soil name     | Family or higher taxonomic class                  |
|---------------|---|
| Wildors-----  | Loamy-skeletal, mixed, mesic Orthidic Durixerolls |
| Winridge----- | Fine, montmorillonitic Argic Vertic Cryoborolls   |
| Winu-----     | Fine-loamy, mixed Argic Pachic Cryoborolls        |
| *Yutru-----   | Fine, montmorillonitic, mesic Vertic Xerochrepts  |







# LEGEND

WELL DRAINED SOILS ON MOUNTAINSIDES  
AND FOOTHILLS

- 1 POVEY-VITALE-MILLIGAN: Moderately deep and deep soils that formed in colluvium derived from metasedimentary rock; on slopes of 15 to 75 percent
- 2 FRIEDMAN-ELKSEL-STARHOPE: Moderately deep and deep soils that formed in colluvium and residuum derived from volcanic rock; on slopes of 4 to 60 percent
- 3 MOONSTONE-EARCREE: Moderately deep and very deep soils that formed in colluvium, alluvium, and residuum derived from granite; on slopes of 8 to 60 percent
- 4 VITALE-LAVACREEK-BLACKSPAR: Shallow to deep soils that formed in colluvium and in tephra over colluvium; on slopes of 15 to 75 percent
- 5 ELKCREEK-GAIB-WINU: Shallow and moderately deep soils that formed in colluvium and residuum derived from volcanic rock; on slopes of 4 to 60 percent

WELL DRAINED SOILS ON BASALT PLAINS

- 6 LAVA FLOWS-CINDERHURST: Lava flows, and very shallow soils that formed in tephra; on slopes of 2 to 15 percent
- 7 DEERHORN-REHFELD-ROCK OUTCROP: Moderately deep and very deep soils that formed in eolian material over basalt and in eolian-influenced alluvium, and Rock outcrop; on slopes of 2 to 15 percent
- 8 GOODING-HAMRUB: Deep soils that formed in alluvium over basalt and in loess over alluvium; on slopes of 2 to 20 percent
- 9 MCCAREY-McBIGGAM-BANCROFT: Moderately deep and very deep soils that formed in loess over residuum and in silty alluvium; on slopes of 1 to 30 percent
- 10 MCCAREY-JUSTESEN-ROCK OUTCROP: Moderately deep and very deep soils that formed in loess over residuum and in alluvium, and Rock outcrop; on slopes of 2 to 15 percent

WELL DRAINED AND SOMEWHAT  
EXCESSIVELY DRAINED SOILS ON FAN  
TERRACES AND STREAM TERRACES

- 11 LITTLE WOOD-BALAAM-ADAMSON: Very deep, well drained and somewhat excessively drained soils that formed in alluvium; on slopes of 0 to 4 percent
- 12 PEEVYWELL-MULDOON-SIMONTON: Moderately deep to very deep, well drained soils that formed in alluvium; on slopes of 2 to 30 percent
- 13 CAREY LAKE-BRINGMEE: Very deep, well drained soils that formed in alluvium; on slopes of 0 to 8 percent
- 14 SOMEWHAT POORLY DRAINED TO VERY POORLY DRAINED SOILS ON STREAM TERRACES AND FLOOD PLAINS
- 14 PICABO-HAPUR-BICKETT: Very deep, somewhat poorly drained to very poorly drained soils that formed in alluvium; on slopes of 0 to 2 percent



Compiled 1986

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE  
U. S. DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
STATE OF IDAHO  
SOIL CONSERVATION COMMISSION  
UNIVERSITY OF IDAHO  
COLLEGE OF AGRICULTURE

## GENERAL SOIL MAP

BLAINE COUNTY AREA, IDAHO

Scale 1:316,800




Each area outlined on this map consists of more than one kind of soil. The map is thus meant for general planning rather than a basis for decisions on the use of specific tracts.




SECTIONALIZED  
TOWNSHIP

|    |    |    |    |    |    |
|----|----|----|----|----|----|
| 6  | 5  | 4  | 3  | 2  | 1  |
| 7  | 8  | 9  | 10 | 11 | 12 |
| 18 | 17 | 16 | 15 | 14 | 13 |
| 19 | 20 | 21 | 22 | 23 | 24 |
| 30 | 29 | 28 | 27 | 26 | 25 |
| 31 | 32 | 33 | 34 | 35 | 36 |



INDEX TO MAP SHEETS  
BLAINE COUNTY AREA, IDAHO





SOIL LEGEND

| SYMBOL | NAME   | SYMBOL | NAME   |
|--------|--|--------|--|
| 1      | Adamson loam, 0 to 2 percent slopes                            | 56     | Ketchum-Dollarhide complex, 30 to 60 percent slopes                          |
| 2      | Adios-Gooding-Bostrum complex, 4 to 20 percent slopes          | 57     | Ketchum-Povey complex, 30 to 60 percent slopes                               |
| 3      | Adios association, 8 to 25 percent slopes                      |        |  |
| 4      | Balaam gravelly sandy loam, 0 to 2 percent slopes              | 58     | Laurentzen-Mulshoe complex, 4 to 30 percent slopes                           |
| 5      | Balaam very gravelly sandy loam, 2 to 4 percent slopes         | 59     | Lava flows   |
| 6      | Balaam-Adamson complex, 0 to 2 percent slopes                  | 60     | Lava flows-Cinderhurst complex, 2 to 15 percent slopes                       |
| 7      | Balaam-Adamson complex, cool, 0 to 2 percent slopes            | 61     | Lavacreek-Dollarhide very gravelly silt loams, 30 to 60 percent slopes       |
| 8      | Balaam-Adamson-Riverwash complex, 0 to 2 percent slopes        | 62     | Lavacreek-Dollarhide very gravelly silt loams, cold, 15 to 60 percent slopes |
| 9      | Bancroft silt loam, 1 to 4 percent slopes                      | 63     | Lavacreek-Vitale association, 30 to 60 percent slopes                        |
| 10     | Bancroft silt loam, 4 to 8 percent slopes                      | 64     | Little Wood gravelly loam, 0 to 2 percent slopes                             |
| 11     | Bickett mucky peat, 0 to 2 percent slopes                      | 65     | Little Wood gravelly loam, 2 to 4 percent slopes                             |
| 12     | Blackspat-Rock outcrop complex, 45 to 75 percent slopes        | 66     | Little Wood very gravelly loam, 0 to 2 percent slopes                        |
| 13     | Blackspot-Prudy association, 30 to 60 percent slopes           | 67     | Little Wood very gravelly loam, 2 to 4 percent slopes                        |
| 14     | Bostrum-Yutru-Hamrub complex, 2 to 12 percent slopes           | 68     | Little Wood very gravelly loam, cool, 1 to 4 percent slopes                  |
| 15     | Bringmee loam, 0 to 2 percent slopes                           | 69     | Little Wood-Balaam complex, 0 to 2 percent slopes                            |
| 16     | Bringmee loam, 2 to 4 percent slopes                           |        |  |
| 17     | Bringmee loam, 4 to 8 percent slopes                           | 70     | Manard silt loam, 1 to 4 percent slopes                                      |
| 18     | Bringmee-Hutton complex, 1 to 4 percent slopes                 | 71     | Marshdale loam, 0 to 2 percent slopes  |
| 19     | Bringmee-Little Wood complex, 1 to 4 percent slopes            | 72     | Marshdale-Bruneel loams, 0 to 2 percent slopes                               |
| 20     | Bruneel loam, 0 to 2 percent slopes                            | 73     | McBigger silt loam, 2 to 8 percent slopes                                    |
| 21     | Carey Lake loam, 0 to 2 percent slopes                         | 74     | McCarey-Justesen loams, 2 to 8 percent slopes                                |
| 22     | Carey Lake loam, 2 to 4 percent slopes                         | 75     | McCarey-Justesen-Rock outcrop complex, 2 to 15 percent slopes                |
| 23     | Cox-Rehfield-Rock outcrop complex, 2 to 15 percent slopes      | 76     | McCarey-Molyneux loams, 2 to 8 percent slopes                                |
| 24     | Deerhorn-Rehfield-Rock outcrop complex, 2 to 15 percent slopes | 77     | McCarey-Pedleford complex, 2 to 30 percent slopes                            |
| 25     | Deerhorn-Wildors complex, 2 to 8 percent slopes                | 78     | Molyneux loam, 2 to 4 percent slopes   |
| 26     | Deerhorn-Wildors-Trevino complex, 2 to 15 percent slopes       | 79     | Molyneux loam, 4 to 8 percent slopes   |
| 27     | Dollarhide-Rock outcrop complex, 60 to 75 percent slopes       | 80     | Molyneux loam, cool, 2 to 15 percent slopes                                  |
| 28     | Drage gravelly loam, 4 to 8 percent slopes                     | 81     | Moonstone-Bauscher complex, 8 to 30 percent slopes                           |
| 29     | Drage gravelly loam, 8 to 12 percent slopes                    | 82     | Moonstone-Earcree association, 30 to 60 percent slopes                       |
| 30     | Drage gravelly loam, cool, 2 to 15 percent slopes              | 83     | Muldoon-Peevywell loams, 2 to 15 percent slopes                              |
| 31     | Drage very gravelly loam, cool, 0 to 3 percent slopes          | 84     | Mulshoe-Gaib-Rock outcrop complex, 4 to 30 percent slopes                    |
| 32     | Earcree-Lockman complex, 30 to 60 percent slopes               | 85     | Mulshoe-Gaib-Winu complex, 30 to 60 percent slopes                           |
| 33     | Earcree-Moonstone association, 8 to 30 percent slopes          |        |  |
| 34     | Earcree-Moonstone association, 30 to 60 percent slopes         | 86     | Pagari-Rehfield complex, 2 to 15 percent slopes                              |
| 35     | Elkcreek-Gaib complex, 30 to 60 percent slopes                 | 87     | Peevywell-Simonton loams, 2 to 8 percent slopes                              |
| 36     | Elkcreek-Polecreek complex, 4 to 30 percent slopes             | 88     | Peevywell-Simonton complex, 8 to 30 percent slopes                           |
| 37     | Elksel-Friedman-Starhope complex, 30 to 60 percent slopes      | 89     | Picabo silt loam, 0 to 2 percent slopes                                      |
| 38     | Elksel-Peevywell-Furshur complex, 30 to 60 percent slopes      | 90     | Picabo gravelly loam, 0 to 2 percent slopes                                  |
| 39     | Elksel-Starhope-Rock outcrop complex, 30 to 60 percent slopes  | 91     | Pits, gravel   |
| 40     | Friedman-Elksel-Winridge complex, 30 to 60 percent slopes      | 92     | Povey-Dollarhide complex, 30 to 60 percent slopes                            |
| 41     | Gaib-Rock outcrop complex, 30 to 60 percent slopes             | 93     | Povey-Rock outcrop complex, 30 to 60 percent slopes                          |
| 42     | Gimlett very gravelly sandy loam, 0 to 2 percent slopes        | 94     | Povey association, cold, 15 to 60 percent slopes                             |
| 43     | Gooding-Gooding eroded-Hamrub complex, 2 to 12 percent slopes  | 95     | Povey-Vitale association, 30 to 60 percent slopes                            |
| 44     | Goodington silt loam, 2 to 4 percent slopes                    |        |  |
| 45     | Goodington-Manard complex, 2 to 8 percent slopes               | 96     | Rehfield-Gooding complex, 2 to 15 percent slopes                             |
| 46     | Hapur silt loam, 0 to 2 percent slopes                         | 97     | Riverwash  |
| 47     | Hapur-Bickett complex, 0 to 2 percent slopes                   | 98     | Rock outcrop-Adios complex, 25 to 60 percent slopes                          |
| 48     | Hapur-Picabo silt loams, 0 to 2 percent slopes                 | 99     | Rockybar extremely cobbly loam, 2 to 30 percent slopes                       |
| 49     | Hutton clay loam, 0 to 2 percent slopes                        | 100    | Rubbleland   |
| 50     | Hutton Variant clay loam, 0 to 2 percent slopes                | 101    | Rubbleland-Milligan complex, 60 to 75 percent slopes                         |
| 51     | Isknot gravelly clay loam, 0 to 2 percent slopes               | 102    | Simonton loam, 2 to 4 percent slopes   |
| 52     | Justesen loam, 2 to 4 percent slopes                           | 103    | Simonton loam, 4 to 8 percent slopes   |
| 53     | Justesen loam, 4 to 8 percent slopes                           | 104    | Simonton-Bauscher complex, 4 to 15 percent slopes                            |
| 54     | Justesen loam, 8 to 12 percent slopes                          | 105    | Starhope-Furshur complex, 4 to 15 percent slopes                             |
| 55     | Justesen loam, 12 to 30 percent slopes                         | 106    | Starhope-Peevywell-Smelter loams, 4 to 30 percent slopes                     |
|        |  | 107    | Vitale-Blackspat complex, 30 to 60 percent slopes                            |
|        |  | 108    | Vitale-Milligan complex, 30 to 60 percent slopes                             |
|        |  | 109    | Vitale-Povey association, 30 to 60 percent slopes                            |
|        |  | 110    | Winu-Rock outcrop complex, 30 to 60 percent slopes                           |
|        |  | 111    | Winu-Gaib association, 30 to 60 percent slopes                               |
|        |  | W      | Water  |

CONVENTIONAL AND SPECIAL  
SYMBOLS LEGEND

CULTURAL FEATURES

BOUNDARIES

|  |  |
|--|--|
| National, state or province  |  |
| County or parish   |  |
| Minor civil division   |  |
| Reservation (national forest or park, state forest or park, and large airport) |  |
| Land grant   |  |
| Limit of soil survey (label)   |  |
| Field sheet matchline and neatline   |  |
| AD HOC BOUNDARY (label)  |  |
| Small airport, airfield, park, oilfield, cemetery, or flood pool               |  |
| STATE COORDINATE TICK  |  |
| LAND DIVISION CORNER (sections and land grants)                                |  |
| ROADS  |  |
| Divided (median shown if scale permits)  |  |
| Improved motor road  |  |
| Poor motor road  |  |
| ROAD EMBLEM & DESIGNATIONS   |  |
| Interstate   |  |
| Federal  |  |
| State  |  |
| County, farm or ranch  |  |
| RAILROAD   |  |
| POWER TRANSMISSION LINE (normally not shown)                                   |  |
| PIPE LINE (normally not shown)   |  |
| FENCE (normally not shown)   |  |
| LEVEES   |  |
| Without road   |  |
| With road  |  |
| With railroad  |  |
| DAMS   |  |
| Large (to scale)   |  |
| Medium or Small  |  |
| PITS   |  |
| Gravel pit   |  |
| Mine or quarry   |  |

MISCELLANEOUS CULTURAL FEATURES

|  |  |
|--|--|
| Farmstead, house (omit in urban areas) |  |
| Church                                 |  |
| School                                 |  |
| Indian mound (label)                   |  |
| Located object (label)                 |  |
| Tank (label)                           |  |
| Wells, oil or gas                      |  |
| Windmill                               |  |
| Kitchen midden                         |  |

WATER FEATURES

DRAINAGE

|                            |  |
|----------------------------|--|
| Perennial, double line     |  |
| Perennial, single line     |  |
| Intermittent               |  |
| Drainage end               |  |
| Canals or ditches          |  |
| Double-line (label)        |  |
| Drainage and/or irrigation |  |

LAKES, PONDS AND RESERVOIRS

|              |  |
|--------------|--|
| Perennial    |  |
| Intermittent |  |

MISCELLANEOUS WATER FEATURES

|                  |  |
|------------------|--|
| Marsh or swamp   |  |
| Spring           |  |
| Well, artesian   |  |
| Well, irrigation |  |
| Wet spot         |  |

SPECIAL SYMBOLS FOR  
SOIL SURVEY

SOIL DELINEATIONS AND SYMBOLS

ESCARPMENTS

|  |  |
|--|--|
| Bedrock (points down slope)            |  |
| Other than bedrock (points down slope) |  |

SHORT STEEP SLOPE

GULLY


DEPRESSION OR SINK

|                                  |  |
|----------------------------------|--|
| SOIL SAMPLE (normally not shown) |  |
|----------------------------------|--|


MISCELLANEOUS

|   |  |
|---|--|
| Blowout                                     |  |
| Clay spot                                   |  |
| Gravelly spot                               |  |
| Gumbo, slick or scabby spot (sodic)         |  |
| Dumps and other similar non soil areas      |  |
| Prominent hill or peak                      |  |
| Rock outcrop (includes sandstone and shale) |  |
| Saline spot                                 |  |
| Sandy spot                                  |  |
| Severely eroded spot                        |  |
| Slide or slip (tips point upslope)          |  |
| Stony spot, very stony spot                 |  |






























6





BLAINE COUNTY AREA, IDAHO NO. 6







114°00'00"  
43°37'30"

R. 21 E. | R. 22 E.  
530 000 FEET





114°22'30" R. 17 E. | R. 18 E.  
43°35'00"




(Joins inset B, sheet 4)

T. 2 N. | T. 3 N.

(Joins sheet 5)

(Joins sheet 10)

(Joins sheet 16)




43°32'30"  
114°15'00"


BLAINE COUNTY AREA, IDAHO NO. 8



10










N












BLAINE COUNTY AREA, IDAHO NO. 12












BLAINE COUNTY AREA, IDAHO NO. 14

This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating











BLAINE COUNTY AREA, IDAHO NO. 16












































BLAINE COUNTY AREA, IDAHO NO. 24  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating








This soil survey map was compiled by the U.S. Department of Agriculture Soil Conservation Service and cooperating







N  
↑




































This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating












BLAINE COUNTY AREA, IDAHO NO. 36  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating












BLAINE COUNTY AREA, IDAHO NO. 38















BLAINE COUNTY AREA, IDAHO NO. 40  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating










BLAINE COUNTY AREA, IDAHO NO. 42  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating




































BLAINE COUNTY AREA, IDAHO NO. 48  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating









BLAINE COUNTY AREA, IDAHO NO. 50  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating









BLAINE COUNTY AREA, IDAHO NO. 52


This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating agencies. It is based on aerial photographs, ground surveys, and other data. The map is not to be used for legal purposes. The U.S. Government is authorized to reproduce and distribute reprints for government purposes, not withstanding any copyright notation that may appear hereon.






BLAINE COUNTY AREA, IDAHO NO. 52  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating











BLAINE COUNTY AREA, IDAHO NO. 54  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating









BLAINE COUNTY AREA, IDAHO NO. 56

This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating agencies. Data were prepared from 1978 aerial photography, coordinate grid, and field and laboratory data.










BLAINE COUNTY AREA, IDAHO NO. 58

This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating agencies. The map was prepared from 1972 aerial photography. Coordinates are in decimal degrees and are based on the North American Datum of 1983. The map is not to be used for any purpose other than that for which it was prepared.




BLAINE COUNTY AREA, IDAHO NO. 58

This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating





N







BLAINE COUNTY AREA, IDAHO NO. 60

This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating












BLAINE COUNTY AREA, IDAHO NO. 62

This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating












This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating






















This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating agencies, including the following:























BLAINE COUNTY AREA, IDAHO NO. 73
























BLAINE COUNTY AREA, IDAHO NO. 76  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating agencies. It is based on the information furnished by the U.S. Department of the Interior, Bureau of Land Management, and the U.S. Geological Survey. It is not to be used for any purpose other than that for which it was prepared.









BLAINE COUNTY AREA, IDAHO NO. 78  
This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating agencies, using data from 1978 aerial photography, coordinate grid ticks and land division corners, if available, and other available data.





This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating agencies. Base maps are derived from 1970 aerial photography. Coordinates are land-tie and land division corners. If growth, are approximately positioned. BLAINE COUNTY AREA, IDAHO No. 79





2000 AND 5000-FOOT GRID TICKS











BLAINE COUNTY AREA, IDAHO NO. 80

This soil survey map was compiled by the U.S. Department of Agriculture, Soil Conservation Service, and cooperating agencies. Base maps are prepared from 1978 aerial photography. Coordinate grid ticks and land division corners, if shown, are approximately positioned.

BLAINE COUNTY AREA, IDAHO NO. 81



BLM Library  
Denver Federal Center  
Bldg. 50, OC-521  
P.O. Box 25047  
Denver, CO 80225





